

NOTE: This Page to be added.

FIGURE D-1B
NEW DRUM MANAGEMENT BUILDING LAYOUT

CALCULATION SHEET

PAGE 1 OF 13**EnSol, Inc.**

Environmental Solutions

PROJECT NO.: 09-7011


CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse Prepared By: JCD Date: 6/22/2012
 SUBJECT: Secondary Containment Calculations Reviewed By: BDS Date: 6/22/2012

NEW DRUM BUILDING WAREHOUSE**TASK:**

Calculate the total available and required volumes within the secondary containment areas. All dimensions are interior.

CALCULATIONS:**AREA 1 – FLAMMABLE LIQUID STORAGE AREA:**

Dimensions:



There are 4 *sections* in Area 1.

A *section* is defined as 2 *drums* side by side (4.0 feet total) with approximately 11-foot aisle space, and minimum 4-foot from wall; 63 *drums* each row x 2 rows of *drums* (126 *drums* total, Single-Stacked).

4 *sections* x 126 *drums/section* = 504 *drums*

Required Secondary Containment per Area 1:

504 *drums* x 55 *gallons/drum* = 27,720 *gallons* x 10% = 2,772 *gallons*

CALCULATION SHEET

EnSol, Inc.

Environmental Solutions

PROJECT NO.: 09-7011

CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse Prepared By: JCD Date: 6/22/2012
SUBJECT: Secondary Containment Calculations Reviewed By: BDS Date: 6/22/2012

Available Secondary Containment per Area 1:

Gross Dimensions and Volume (less floor trench volume):

57' x 144.34' x 0.167' (2-inches curb height)

 $57' \times 144.34' \times 0.167' = 1374 \text{ ft}^3$ 7.48 gallons / ft^3 $7.48 \text{ gallons/ft}^3 \times 1374 \text{ ft}^3 \cong 10,277.5 \text{ gallons}$

Floor Trench System Volume:

 $126' L \times 1.0' W \times 0.75' D = 94.5 \text{ ft}^3$ $7.48 \text{ gallons/ft}^3 \times 94.5 \text{ ft}^3 \cong 706.9 \text{ gallons}$

Total Secondary Containment Volume:

 $10,277.5 \text{ gallons} + 706.9 \text{ gallons} = 10,984.4 \text{ gallons}$ Reduction in Gross Available Volume Due to Presence of Drums (assume 1 drum leaks): $503 \text{ drums} \times [3.14 \times (2')^2 / 4 \times 0.167'] = 263.8 \text{ ft}^3$ 7.48 gallons / ft^3 $7.48 \text{ gallons/ft}^3 \times 263.8 \text{ ft}^3 \cong 1973.2 \text{ gallons}$ Net Available Secondary Containment Volume: $10,984.4 \text{ gallons} - 1973.2 \text{ gallons} = 9,011.2 \text{ gallons}$ **CONCLUSIONS:**Area 1 has sufficient secondary containment for the flammable liquid storage capacity of 504 55-gallon drums.

CALCULATION SHEET

EnSol, Inc.


Environmental Solutions

PROJECT NO.: 09-7011

CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse Prepared By: JCD Date: 6/22/2012
 SUBJECT: Secondary Containment Calculations Reviewed By: BDS Date: 6/22/2012

NEW DRUM BUILDING WAREHOUSE (continued)**AREA 2 – ACIDS LIQUID STORAGE AREA:**

Dimensions:

There are 4 *sections* in Area 2.

A *section* is defined as 2 drums side by side (4.0 feet total) with approximately 11-foot aisle space and 2-foot minimum from wall; 63 drums each row x 2 rows of drums (126 drums total, Single-Stacked; 252 drums total, Double-Stacked).

$$4 \text{ sections} \times 126 \text{ drums/section} \times 2 \text{ drums/stack} = 1,008 \text{ drums}$$

Required Secondary Containment per Area 2:

$$1,008 \text{ drums} \times 55 \text{ gallons/drum} = 55,440 \text{ gallons} \times 10\% = \underline{5,544 \text{ gallons}}$$

Available Secondary Containment per Area 2 :

Gross Dimensions and Volume (less floor trench volume):

$$44' \times 144.34' \times 0.167' \text{ (2-inches curb height)}$$

$$44' \times 144.34' \times 0.167' = 1,060.6 \text{ ft}^3$$

CALCULATION SHEET

EnSol, Inc.

Environmental Solutions

PROJECT NO.: 09-7011

CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse Prepared By: JCD Date: 6/22/2012
 SUBJECT: Secondary Containment Calculations Reviewed By: BDS Date: 6/22/2012

$$7.48 \text{ gallons} / \text{ft}^3$$

$$7.48 \text{ gallons/ft}^3 \times 1,060.6 \text{ ft}^3 \cong 7,933.3 \text{ gallons}$$

Floor Trench System Volume:

$$126' L \times 1.0' W \times 0.75' D = 94.5 \text{ ft}^3$$

$$7.48 \text{ gallons/ft}^3 \times 94.5 \text{ ft}^3 \cong 706.9 \text{ gallons}$$

Total Secondary Containment Volume:

$$7,933.3 \text{ gallons} + 706.9 \text{ gallons} = \underline{8,640.2 \text{ gallons}}$$

Reduction in Gross Available Volume Due to Presence of Drums (assume 1 drum leaks):

$$503 \text{ drums} \times [3.14 \times (2')^2 / 4 \times 0.167'] = 263.8 \text{ ft}^3$$

$$7.48 \text{ gallons} / \text{ft}^3$$

$$7.48 \text{ gallons/ft}^3 \times 263.8 \text{ ft}^3 \cong \underline{1973.2 \text{ gallons}}$$

Net Available Secondary Containment Volume:

$$8,640.2 \text{ gallons} - 1973.2 \text{ gallons} = \underline{6,667 \text{ gallons}}$$

CONCLUSIONS:

Area 2 has sufficient secondary containment for the acids liquid storage capacity of 1,008 55-gallon drums.

CALCULATION SHEET

EnSol, Inc.

Environmental Solutions

PROJECT NO.: 09-7011

CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse


Prepared By: JCD Date: 6/22/2012

SUBJECT: Secondary Containment Calculations

Reviewed By: BDS Date: 6/22/2012

NEW DRUM BUILDING WAREHOUSE (continued)**AREA 3 – CAUSTICS STORAGE AREA:**

Dimensions:



There are 4 sections in Area 3.

A section is defined as 2 drums side by side (4.0 feet total) with approximately 11-foot aisle space and 2-foot minimum from wall; 63 drums each row x 2 rows of drums (126 drums total, Single-Stacked; 252 drums total, Double-Stacked).

$$4 \text{ sections} \times 126 \text{ drums/section} \times 2 \text{ drums/stack} = 1,008 \text{ drums}$$

Required Secondary Containment per Area 3:

$$1,008 \text{ drums} \times 55 \text{ gallons/drum} = 55,440 \text{ gallons} \times 10\% = \underline{5,544 \text{ gallons}}$$

Available Secondary Containment per Area 3:

Gross Dimensions and Volume (less floor trench volume):

$$44' \times 148.84' \times 0.167' \text{ (2-inches curb height)}$$

$$44' \times 148.84' \times 0.167' = 1,093.7 \text{ ft}^3$$

CALCULATION SHEET

EnSol, Inc.

Environmental Solutions

PROJECT NO.: 09-7011

CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse Prepared By: JCD Date: 6/22/2012
 SUBJECT: Secondary Containment Calculations Reviewed By: BDS Date: 6/22/2012

$$7.48 \text{ gallons} / \text{ft}^3$$

$$7.48 \text{ gallons/ft}^3 \times 1,093.7 \text{ ft}^3 \cong 8,180.9 \text{ gallons}$$

Floor Trench System Volume:

$$126' L \times 1.0' W \times 0.75' D = 94.5 \text{ ft}^3$$

$$7.48 \text{ gallons/ft}^3 \times 94.5 \text{ ft}^3 \cong 706.9 \text{ gallons}$$

Total Secondary Containment Volume:

$$8,180.9 \text{ gallons} + 706.9 \text{ gallons} = \underline{8,887.8 \text{ gallons}}$$

Reduction in Gross Available Volume Due to Presence of Drums (assume 1 drum leaks):

$$503 \text{ drums} \times [3.14 \times (2')^2 / 4 \times 0.167'] = 263.8 \text{ ft}^3$$

$$7.48 \text{ gallons} / \text{ft}^3$$

$$7.48 \text{ gallons/ft}^3 \times 263.8 \text{ ft}^3 \cong \underline{1973.2 \text{ gallons}}$$

Net Available Secondary Containment Volume:

$$8,887.8 \text{ gallons} - 1973.2 \text{ gallons} = \underline{6,914.6 \text{ gallons}}$$

CONCLUSIONS:

Area 3 has sufficient secondary containment for the caustics storage capacity of 1,008 55-gallon drums.

CALCULATION SHEET

EnSol, Inc.

Environmental Solutions

PROJECT NO.: 09-7011

CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse


Prepared By: JCD Date: 6/22/2012

SUBJECT: Secondary Containment Calculations

Reviewed By: BDS Date: 6/22/2012

NEW DRUM BUILDING WAREHOUSE (continued)**AREA 4 – POISONS STORAGE AREA:**

Dimensions:



There are 4 sections in Area 4.

A section is defined as 2 drums side by side (4.0 feet total) with approximately 11-foot aisle space and 2-foot minimum from wall or curb; 6 drums each row x 2 rows of drums (12 drums total, Single-Stacked, 24 drums total Double Stacked).

$$4 \text{ sections} \times 12 \text{ drums/section} \times 2 \text{ drums/stack} = 96 \text{ drums}$$

Required Secondary Containment per Area 4:

$$96 \text{ Drums} \times 55 \text{ gallons/Drum} = 5,280 \text{ gallons} \times 10\% = \underline{528 \text{ gallons}}$$

Available Secondary Containment per Area 4:

Gross Dimensions and Volume:

$$44' \times 26' \times 0.167' \text{ (2-inches curb height)}$$

$$44' \times 26' \times 0.167' = 191 \text{ ft}^3$$

$$7.48 \text{ gallons} / \text{ft}^3$$

$$7.48 \text{ gallons/ft}^3 \times 191 \text{ ft}^3 \cong \underline{1,428.7 \text{ gallons}}$$

Reduction in Gross Available Volume Due to Presence of Drums (assume 1 drum leaks):

$$47 \text{ drums} \times [3.14 \times (2')^2 / 4 \times 0.167'] = 24.6 \text{ ft}^3$$

$$7.48 \text{ gallons} / \text{ft}^3$$

$$7.48 \text{ gallons/ft}^3 \times 24.6 \text{ ft}^3 \cong \underline{184 \text{ gallons}}$$

CALCULATION SHEET

EnSol, Inc.

Environmental Solutions

PROJECT NO.: 09-7011

CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse

Prepared By: JCD Date: 6/22/2012

SUBJECT: Secondary Containment Calculations


Reviewed By: BDS Date: 6/22/2012

Net Available Secondary Containment Volume:

$$1,428.7 \text{ gallons} - 184 \text{ gallons} = \underline{1,244.7 \text{ gallons}}$$

CONCLUSIONS:Area 4 has sufficient secondary containment for the poisons storage capacity of 96 55-gallon drums.**AREA 5 - OXIDIZER STORAGE AREA:**

Dimensions:



There are 3 sections in Area 5.

A section is defined as 2 drums side by side (4.0 feet total) with approximately 11-foot aisle space and 2-foot minimum from wall or curb; 8 drums each row x 2 rows of drums (16 drums total, Single-Stacked, 32 drums total Double Stacked).

$$3 \text{ sections} \times 16 \text{ drums/section} \times 2 \text{ drums/stack} = 96 \text{ drums}$$

Required Secondary Containment per Area 5:

$$96 \text{ Drums} \times 55 \text{ gallons/Drum} = 5,280 \text{ gallons} \times 10\% = \underline{528 \text{ gallons}}$$

Available Secondary Containment per Area 5:

Gross Dimensions and Volume:

$$20' \times 38' \times 0.167' \text{ (2-inches curb height)}$$

$$20' \times 38' \times 0.167' = 126.9 \text{ ft}^3$$

$$7.48 \text{ gallons} / \text{ft}^3$$

$$7.48 \text{ gallons/ft}^3 \times 126.9 \text{ ft}^3 \cong \underline{949.2 \text{ gallons}}$$

CALCULATION SHEET

EnSol, Inc.

Environmental Solutions

PROJECT NO.: 09-7011

CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse

Prepared By: JCD Date: 6/22/2012

SUBJECT: Secondary Containment Calculations

Reviewed By: BDS Date: 6/22/2012

Reduction in Gross Available Volume Due to Presence of Drums (assume 1 drum leaks):

$$47 \text{ drums} \times [3.14 \times (2')^2 / 4 \times 0.167'] = 24.6 \text{ ft}^3$$

$$7.48 \text{ gallons} / \text{ft}^3$$



$$7.48 \text{ gallons/ft}^3 \times 24.6 \text{ ft}^3 \cong 184 \text{ gallons}$$

Net Available Secondary Containment Volume:

$$949.2 \text{ gallons} - 184 \text{ gallons} = 765.2 \text{ gallons}$$

CONCLUSIONS:Area 5 has sufficient secondary containment for the oxidizer storage capacity of 96 55-gallon drums.AREA 6 – QA/QC STORAGE AREA:

Dimensions:



There are 4 sections in Area 6.

A section is defined as 2 drums side by side (4.0 feet total) with a minimum of 11-foot aisle space and 12-foot from closest wall; 21 drums each row x 2 rows of drums (42 drums total, Single-Stacked, 84 drums total, Double Stacked).

CALCULATION SHEET

EnSol, Inc.

Environmental Solutions

PROJECT NO.: 09-7011

CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse Prepared By: JCD Date: 6/22/2012
 SUBJECT: Secondary Containment Calculations Reviewed By: BDS Date: 6/22/2012

4 sections x 42 drums/section x 2 drums/stack = 336 drums

Required Secondary Containment per Area 6:

336 drums x 55 gallons/drum = 18,480 gallons x 10% = 1,848 gallons

Available Secondary Containment per Area 6:

Gross Dimensions and Volume (less floor trench volumes):

A1 + A4 + A3:

$(0.5 \times 20.5' \times 138.67' \times 0.21') + (0.5 \times 15.33' \times 138.67' \times 0.21') + (0.21' \times 1' \times 138.67')$

$(298.49 \text{ ft}^3) + (223.21 \text{ ft}^3) + (29.12 \text{ ft}^3) = 550.82 \text{ ft}^3$

7.48 gallons / ft³

7.48 gallons/ft³ x 550.86 ft³ \cong 4,120.1 gallons

Floor Trench System Volume:

A2: $2 \times 42' L \times 1.0' W \times 0.75' D = 63 \text{ ft}^3$

7.48 gallons/ft³ x 63 ft³ \cong 471.2 gallons

Total Secondary Containment Volume:

4120.1 gallons + 471.2 gallons = 4,591.3 gallons

Reduction in Gross Available Volume Due to Presence of Drums (assume 1 drum leaks):

$167 \text{ drums} \times [3.14 \times (2')^2 / 4 \times 0.21'] = 110.1 \text{ ft}^3$

7.48 gallons / ft³

7.48 gallons/ft³ x 110.1 ft³ \cong 823.7 gallons

Net Available Secondary Containment Volume:

4591.3 gallons – 823.7 gallons = 3,768 gallons

CONCLUSIONS:

Area 6 has sufficient secondary containment for the QA/QC storage capacity of 336 55-gallon drums.


CALCULATION SHEET

EnSol, Inc.

Environmental Solutions

PROJECT NO.: 09-7011

CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse Prepared By: JCD Date: 6/22/2012
 SUBJECT: Secondary Containment Calculations Reviewed By: BDS Date: 6/22/2012

AREA 7 - DRUM BUILDING FUELS TRANSFER RAMP:Dimensions:

32' x 65' x 2'-9" (Deep End)

Available Secondary Containment:

$$0.50 \times (32' \times 65' \times 2.75') = 2,860 \text{ ft}^3 \cong \underline{21,392 \text{ gallons}}$$

Required Secondary Containment:

2 tankers; 5,500 gallons each:
 Largest single container equals 5,500 gallons.

25 Year, 24 Hour Precipitation Event:

$$32' \times 65' \times 0.333' = 692.6 \text{ ft}^3 \cong 5,181 \text{ gallons}$$

0.333 feet is equivalent to 4.0 inches of precipitation (i.e., rain).

Required Secondary Containment Including Precipitation Event:

$$5,500 \text{ gallons} + 5,181 \text{ gallons} = \underline{10,681 \text{ gallons}}$$

CONCLUSIONS:

Area 7, the Fuels Transfer Ramp/Drum Building North Ramp, has sufficient secondary containment capacity for (2) 5,500-gallon tankers.


CALCULATION SHEET

EnSol, Inc.

Environmental Solutions

PROJECT NO.: 09-7011

CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building Warehouse Prepared By: JCD Date: 6/22/2012
 SUBJECT: Secondary Containment Calculations Reviewed By: BDS Date: 6/22/2012

NEW DRUM BUILDING WAREHOUSE (continued)**AREA 8 – TRANSFORMER FLUSH AREA:**Dimensions:

$$29'W \times 57'L \times 0.167'D$$

Available Secondary Containment:

$$(29' \times 57' \times 0.167') = 276.1 \text{ ft}^3 \cong \underline{2,065.2 \text{ gallons}}$$

CONCLUSIONS:

The Transformer Flush Area has secondary containment capacity of 2,065.2 gallons.


CALCULATION SHEET

EnSol, Inc.

Environmental Solutions

PROJECT NO.: 09-7011CLIENT: CWM Chem. Svcs. PROJECT: New Drum Building WarehousePrepared By: JCD Date: 6/22/2012SUBJECT: Secondary Containment CalculationsReviewed By: BDS Date: 6/22/2012AREA 9 – TRUCK LOADING AND UNLOADING RAMP:Dimensions:

= 177'-11"

58'-2" x 175'-11" x 2'-6" (*Deep End*)Available Secondary Containment:

$$0.50 \times (58.17' \times 175.92' \times 2.5') = 12,792 \text{ ft}^3 \cong \underline{95,681 \text{ gallons}}$$

Required Secondary Containment:

13 flatbeds or trailers x 80 drums per trailer = 1,040 drums

$$1,040 \text{ drums} \times 55 \text{ gallons} = 57,200 \text{ gallons} \times 10\% = \underline{5,720 \text{ gallons}}$$

CONCLUSIONS:

The Truck Loading and Unloading Ramp, has sufficient secondary containment capacity of a minimum of 10% of the total volume of all containers.

NOTE: This Page to be added.

FIGURE D-3A
NEW FULL TRAILER PARKING AREA





NOTE: This Page to be added.

Imagine the result

Calculation Sheet

Client: CWM Chemical Services, LLC**Project Location:** Model City, New York**Project:** RMU-2 Design Calculations**Project No.:** B0023725.2011**Subject:** New Full Trailer Parking Area – Secondary Containment Calculations**Prepared By:** GNG**Date:** August 2013**Reviewed By:** BMS**Date:** August 2013**Checked By:** BMS**Date:** August 2013**OBJECTIVE:**

Determine the capacity of the new Full Trailer Parking Area (new Parking Area) for solids and liquid storage containers. Demonstrate that adequate secondary containment volume exists for management of free liquids anticipated within the new Parking Area including precipitation.

REFERENCES:

1. Permit Drawing No. D-3A entitled "Full Trailer Parking Area," contained in Attachment D-1 of the Overall Site/RMU-1 Part 373 Permit, ARCADIS, August 2013.
2. New York State Department of Environmental Conservation Regulations, Subpart 373.2.9 (f).

ASSUMPTIONS:

1. The new Parking Area is wide enough (55 ft from the entrance to the back wall) to contain roll-offs (for solids), semi tanker trailers (for liquids), or some combination of these containers. Because roll-offs sit much closer to the pavement, they consume secondary containment volume, whereas semi tanker trailers consume only negligible volume. Thus, when calculating the available secondary containment volume, this analysis assumes that the new Parking Area is filled to capacity with roll-offs. When calculating the required secondary containment volume, this analysis assumes that the new Parking Area is filled to capacity with semi tanker trailers. Although this combination cannot physically occur, it provides the most extreme case in terms of assessing secondary containment volume. Any physically possible combination of roll-offs and semi tanker trailers can therefore be accommodated with adequate secondary containment volume.
2. The secondary containment system must have sufficient capacity to contain 10 percent of the total volume of liquid storage containers or the volume of the largest liquid container, whichever is greater.
3. The precipitation volume considered in this calculation is based on the 25-year, 24-hour storm event which contributes 4-inches or 0.333 feet of runoff.
4. The liquid storage container volume is 5,500 gallons (gal) per container.
5. Roll-offs are assumed to rest on approximately 6-inch-diameter rollers and thus sit 6 inches off the pavement.



NOTE: This Page to be added.

Imagine the result

Calculation Sheet

CALCULATIONS:

1. Capacity for Solids and Liquid Storage Containers

The capacity of the new Parking Area for solids and liquid storage containers is based on the geometry of the parking area and the typical size of individual storage containers and is calculated as follows:

Solids Storage Container Dimensions

- Width of a typical container = 8 ft
- Aisle space requirement between containers = 2 ft
- Adjusted width of a typical container = 10 ft (8 ft + 2 ft)
- Length of a typical solids container = 22 ft

Maximum Number of Solids Storage Containers

- Adjusted row length taking into account a required 2 ft distance between the last container in the end row to the edge of the containment area = $250 \text{ ft} - 2 \text{ ft} = 248 \text{ ft}$
- Maximum number of rows = $248 \text{ ft} \div 10 \text{ ft} = 24.8 \approx 24 \text{ rows}$
- Maximum number of solids storage containers end-to-end in each row = $50 \text{ ft} \div 22 \text{ ft}$ (solids storage container length) = $2.3 \approx 2 \text{ containers}$
- Maximum number of solids storage containers = $24 \text{ rows} \times 2 \text{ containers per row} = 48 \text{ containers}$

Liquid Storage Container Dimensions

- Width of a typical container = 8 ft
- Aisle space requirement between containers = 2 ft
- Adjusted width of a typical container = 10 ft (8 ft + 2 ft)
- Length of a typical liquid container = 50 ft

Maximum Number of Liquid Storage Containers

- Adjusted row length taking into account a required 2 ft distance between the last container in the end row to the edge of the containment area = $250 \text{ ft} - 2 \text{ ft} = 248 \text{ ft}$
- Maximum number of rows = $248 \text{ ft} \div 10 \text{ ft} = 24.8 \approx 24 \text{ rows}$
- Maximum number of liquid storage containers end-to-end in each row = $50 \text{ ft} \div 50 \text{ ft}$ (liquid storage container length) = 1 container
- Maximum number of liquid storage containers = $24 \text{ rows} \times 1 \text{ containers per row} = 24 \text{ containers}$

2. Secondary Containment Analysis

Total Available Secondary Containment Volume

The new Parking Area consists of a sloped, reinforced concrete pad that measures 55ft wide by 250 ft long. Access to the new Parking Area is from the full length of the southern edge (250 ft) where the concrete pad is approximately flush with surrounding grade. The reinforced concrete pad is sloped toward the center and back of the two drain areas within the new Parking Area. Reinforced concrete curbing and the slope of the reinforced concrete pad provide the secondary containment for the new Parking Area. Due to its complex dimensions, the total available secondary containment volume of the new Parking Area was determined based on 3-dimensional surface computations performed using computer aided design software (Terramodel).



NOTE: This Page to be added.

Imagine the result

Calculation Sheet

As discussed in Assumption 1, the new Parking Area is assumed to be filled to capacity with roll-offs for the purposes of determining available secondary containment volume. Because the roll-offs sit approximately 6 inches off the pavement, liquid can spread across the pavement for the first 6 inches within the entire footprint of the new Parking Area, except near the entrance edge where the liquid cannot have an elevation greater than the entrance elevation. This volume was modeled with Terramodel and determined to be 47,380 gal. As confirmation, one can multiply 6 inches by the plan dimensions of the new Parking Area (55 ft by 250 ft) to yield 51429 gal. This slightly larger volume is attributable to the loss at the entrance where liquid cannot be 6 inches above the entrance elevation.

The volume available between rows of containers and above the aforementioned 6-inch-thick layer of storage is calculated manually based on an average depth of 1.63 ft at the back wall, an aisle width of 2 ft, a length of 43 ft, and 25 aisles. Using the area formula for a triangle multiplied by the aisle width and the number of aisles, this volume is estimated to be 13,107 gal. Similarly, the volume available along the back wall and above the 6-inch-thick layer of storage is calculated manually based on an average depth of 1.63 ft at the back wall, an aisle width of 2 ft, and a length of 250 ft. Using the area formula for a rectangle multiplied by the aisle width, this volume is estimated to be 6,096 gal.

Summing the above components, a worst-case available secondary containment volume of 66,583 gal is calculated.

Required Secondary Containment Volume

As discussed in Assumption 1, the new Parking Area is assumed to be filled to capacity with semi tanker trailers for the purposes of determining required secondary containment volume. The required secondary containment volume for liquid storage containers is based on one of two possible conditions. The first condition (Condition 1) provides storage for 10 percent of the total liquid volume of containers stored within the new Parking Area plus the runoff volume resulting from a 25-year, 24-hour storm event. The second condition (Condition 2) provides storage for the entire volume of the single largest liquid container stored within the new Parking Area plus the runoff volume resulting from a 25-year, 24-hour storm event. Calculations for both conditions are presented below.

Condition 1

Total Container Volume (assuming all containers store liquid)

- Total Container Volume: Maximum number of containers x volume per container (Assumption 4) x 0.10 (10 percent) = 24 containers x 5,500 gal/container x 0.10 = 13,200 gal

Precipitation Runoff Volume

- Runoff Volume: 55 ft x 250 ft x 0.333 ft = 4,579 cf or 34,249 gal

Required Secondary Containment Volume

- Total Container Volume + Precipitation Runoff Volume = 13,200 gal + 34,249gal = 47,449gal



NOTE: This Page to be added.

Imagine the result

Calculation Sheet

Condition 2

Single Largest Liquid Storage Container Volume

- The volume of the largest liquid storage container stored within the secondary containment area = 5,500 gal

Required Secondary Containment Volume

- Largest Liquid Storage Container Volume + Precipitation Runoff Volume (from Condition 1 above) = 5,500 gal + 34,249gal = 39,749 gal

Based on a comparison of the required secondary containment volumes calculated for Conditions 1 and 2 above, the greatest required secondary containment volume is 47,449 gal (Condition 1).

Excess Secondary Containment Volume

The excess secondary containment volume condition is based on the total secondary volume available within the new Parking Area compared with the greatest required secondary containment volume. The resultant volume condition is as follows:

Total Secondary Containment Volume: 66,583 gal
 Required Secondary Containment Volume: 47,449 gal
 Excess Volume: 66,583 gal – 47,449 gal = 19,134 gal

It is noted that this is a worst-case scenario because it is based on extremes of all roll-offs for available volume and all semi tanker trailers for required volume. Any physically possible combination of roll-offs and semi tanker trailers will yield additional reserve capacity beyond this calculated minimum.

SUMMARY:

The new Parking Area has a worst-case secondary containment volume of 66,583 gal. Based on the required secondary containment volume of 47,449 gal, which accounts for 10 percent of the maximum volume in all liquid storage containers within the new Parking Area plus the runoff volume resulting from a 25-year, 24-hour storm event, the new Parking Area provides adequate secondary containment. A maximum of 48 solids storage containers or 24 liquid containers or any combination of the two container types may be stored in the new Parking Area assuming the required aisle spaces considered herein are maintained.

NOTE: This Page to be added.


FIGURE D-4A

NEW STABILIZATION FACILITY FULL TRAILER PARKING AREA

NOTE: This Figure to be added.

NOTES:


1. CONCRETE MIX SHALL BE 4000 PSI AT 28 DAYS WITH AIR ENTRAINING ADMIXTURE 6±1%. STEEL FIBER REINFORCEMENT SHALL BE ADDED TO MIX AS MANUFACTURED BY MITCHELL FIBERCON, INC., MEETING ASTM A820 TYPE II SPECIFICATIONS.
2. ALL EXPOSED CONCRETE SURFACES TO RECEIVE CHEMTEC ONE CONCRETE PROTECTION SEALANT, OR APPROVED EQUAL.
3. REINFORCED CONCRETE BARS OF NEW BILLET STEEL CONFORMING TO ASTM A615, GRADE 60. LAP REINFORCING BARS MINIMUM 44 BAR DIAMETERS.
4. DESIGN ELEVATIONS ARE RELATIVE. EXISTING GROUND SURFACE IS ASSUMED TO BE ELEVATION 0.0 FOR REFERENCE PURPOSES.
5. STEEL ANGLE SHALL BE FABRICATED IN LENGTHS CORRESPONDING TO JOINT LOCATIONS. STEEL ANGLE SHALL NOT SPAN ANY SLAB JOINT. STRUCTURAL STEEL SHALL CONFORM TO ASTM A36 AND BE GALVANIZED IN ACCORDANCE WITH ASTM A123. WELDING SHALL BE IN ACCORDANCE WITH AWS D1.1.
6. SUBBASE SHALL BE PROOF-ROLLED AND INSPECTED BY ENGINEER PRIOR TO PLACING CRUSHED STONE. IF SOFT SOILS OR AREAS OF PUMPING ARE OBSERVED, SOIL WITHIN THESE AREAS SHALL BE REMOVED AND REPLACED WITH CRUSHED STONE OR STRUCTURAL FILL AND PROOF ROLLED.
7. CRUSHED STONE SHALL BE COMPACTED TO A MINIMUM 95% OF MAXIMUM DRY DENSITY BASED ON MODIFIED PROCTOR.
8. WATERSTOP SHALL BE WESTEC'S ENVIROSTOP™ TPE-R (THERMOPLASTIC ELASTOMERIC RUBBER) 600 SERIES OR APPROVED EQUAL.



STABILIZATION FACILITY FULL TRAILER PARKING AREA

1


SCALE: 1/16"=1'-0"



SECTION

2


SCALE: 1/2"=1'-0"



SECTION

8


SCALE: 1/4"=1'-0"



WALL CONTRACTION JOINT DETAIL

6


SCALE: 1/2"=1'-0"



SECTION

9


SCALE: 1/4"=1'-0"



SECTION

3


SCALE: 1/2"=1'-0"



SLAB EXPANSION JOINT

4


SCALE: 1"=1'-0"



SLAB CONTRACTION JOINT

5

SCALE: 1"=1'-0"



SECTIONAL PLAN

WALL EXPANSION JOINT

7

SCALE: 1"=1'-0"

CITY: SYRACUSE DIV/GROUP: EN/CAD DE: K. DAVIS G. STOWELL L. FORAKER LD: P.C. W. POPHAM PM: W. RANKIN TM: B. STONE LVR: ON=OFF=REF= G:\ENVCAD\SYRACUSE\ENVCAD\201100003\DWG\FULL TRAILER PARKING\23725D04.dwg LAYOUT: D-4A SAVED: 7/8/2013 12:42 PM ACADVER: 18.15 (LMS TECH) PAGES: 1 OF 1 PLOT: 7/8/2013 12:42 PM BY: SARTORI, KATHERINE

SCALE(S) AS INDICATED		Professional Engineer's Name JOSEPH MOLINA		Professional Engineer's No. 072644	
THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.		State NY		Date Signed	Project Mgr. WAR
USE TO VERIFY FIGURE REPRODUCTION SCALE		Designed by LAB		Drawn by SJK	Checked by BMS
7/2013		GENERAL REVISIONS		Revisions	
No.		Date		By	
1		7/2013		NWF	
2				BMS	
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					



ARCADIS OF NEW YORK, INC.

CWM CHEMICAL SERVICES, LLC • MODEL CITY, NEW YORK
FULL TRAILER PARKING AREA AND LEACHATE TRANSFER RAMP PERMIT DRAWINGS

STABILIZATION FACILITY FULL TRAILER PARKING AREA

GENERAL

ARCADIS Project No.
80023725.2009.00006

Date
FEBRUARY 2013

ARCADIS of New York, Inc.
6723 Towpath Road
P.O. Box 66
Syracuse, New York
TEL: 315.446.9120

D-4A



NOTE: This Page to be added.

Imagine the result

Calculation Sheet

Client: CWM Chemical Services, LLCProject Location: Model City, New YorkProject: RMU-2 Design CalculationsProject No.: B0023725.2011Subject: New Stabilization Full Trailer Parking Area – Secondary Containment CalculationsPrepared By: NWFDate: August 2013Reviewed By: BMSDate: August 2013Checked By: BMSDate: August 2013

OBJECTIVE:

Determine the capacity of the new Stabilization Full Trailer Parking Area (new Parking Area) for solids and liquid storage containers. Demonstrate that adequate secondary containment volume exists for management of precipitation within the new Parking Area.

REFERENCES:

1. RMU-2 Permit Drawing No. D-4A entitled "Stabilization Facility Full Trailer Parking Area," contained in Attachment D-1 of the Overall Site/RMU-1 Part 373 Permit, ARCADIS, August 2013.
2. New York State Department of Environmental Conservation Regulations, Subpart 373.2.9 (f).

ASSUMPTIONS:

1. The new Parking Area may contain roll-offs (for solids), tanker trucks (for liquid), or some combination of these containers. Because roll-offs sit much closer to the pavement, they consume secondary containment volume, whereas tankers consume only negligible volume. Thus, when calculating the available secondary containment volume, this analysis assumes that the new Parking Area is filled to capacity with roll-offs. When calculating the required secondary containment volume, this analysis assumes that the new Parking Area is filled to capacity with tankers. Although this scenario cannot physically occur, it provides the most extreme case in terms of assessing secondary containment volume. Any physically possible combination of roll-offs and tankers can therefore be accommodated with adequate secondary containment volume.
2. The secondary containment system must have sufficient capacity to contain 10 percent of the total volume of liquid storage containers or the volume of the largest liquid container, whichever is greater.
3. The precipitation volume considered in this calculation is based on the 25-year, 24-hour storm event which contributes 4-inches or 0.333 feet of runoff.
4. The liquid storage container volume is 2,500 gallons (gal) per container.
5. Roll-offs are assumed to rest on approximately 6-inch-diameter rollers and thus sit 6 inches off the pavement.



NOTE: This Page to be added.

Imagine the result

Calculation Sheet

CALCULATIONS:

1. Capacity for Solids and Liquid Storage Containers

The capacity of the new Parking Area for solids and liquid storage containers is based on the geometry of the parking area and the typical size of individual storage containers and is calculated as follows:

Solids Storage Container Dimensions

- Width of a typical container = 8 ft
- Aisle space requirement between containers = 2 ft
- Adjusted width of a typical container = 10 ft (8 ft + 2 ft)
- Length of a typical liquid container = 22 ft

Maximum Number of Solids Storage Containers

- Adjusted row length taking into account a required 2 ft distance between the last container in the end row to the edge of the containment area = $375 \text{ ft} - 2 \text{ ft} = 373 \text{ ft}$
- Maximum number of rows = $373 \text{ ft} \div 10 \text{ ft} = 37.3 \approx 37 \text{ rows}$
- Maximum number of solids storage containers end-to-end in each row = $35 \text{ ft} \div 22 \text{ ft}$ (solids storage container length) = $1.6 \approx 1 \text{ container}$
- Maximum number of solids storage containers = 37 rows x 1 container per row = 37 containers

Liquid Storage Container Dimensions

- Width of a typical container = 8 ft
- Aisle space requirement between containers = 2 ft
- Adjusted width of a typical container = 10 ft (8 ft + 2 ft)
- Length of a typical liquid container = variable (less than 35 ft), thus only one liquid container per row is assumed

Maximum Number of Liquid Storage Containers

- Adjusted row length taking into account a required 2 ft distance between the last container in the end row to the edge of the containment area = $375 \text{ ft} - 2 \text{ ft} = 373 \text{ ft}$
- Maximum number of rows = $373 \text{ ft} \div 10 \text{ ft} = 37.3 \approx 37 \text{ rows}$
- Maximum number of liquid storage containers end-to-end in each row = 1 container
- Maximum number of liquid storage containers = 37 rows x 1 container per row = 37 containers

2. Secondary Containment Analysis

Total Available Secondary Containment Volume

The new Parking Area consists of a sloped, reinforced concrete pad that measures 35 feet (ft) wide by 375 ft long. Access to the new Parking Area is from the full length of the southern edge (375 ft) where the concrete pad is approximately flush with surrounding grade. The reinforced concrete pad is sloped toward the center and back of the two drain areas within the new Parking Area. Reinforced concrete curbing and the slope of the reinforced concrete pad provide the secondary containment for the new Parking Area. Due to its complex dimensions, the total available secondary containment volume of the new Parking Area was determined based on 3-dimensional surface computations performed using computer aided design software (Terramodel).



NOTE: This Page to be added.

Imagine the result

Calculation Sheet

As discussed in Assumption 1, the new Parking Area is assumed to be filled to capacity with roll-offs for the purposes of determining available secondary containment volume. Because the roll-offs sit approximately 6 inches off the pavement, liquid can spread across the pavement for the first 6 inches within the entire footprint of the new Parking Area, except near the entrance edge where the liquid cannot have an elevation greater than the entrance elevation. This volume was modeled with Terramodel and determined to be 43,020 gal. As confirmation, one can multiply 6 inches by the plan dimensions of the new Parking Area (35 ft by 375 ft) to yield 49,091 gal. This slightly larger volume is attributable to the loss at the entrance where liquid cannot be 6 inches above the entrance elevation.

The volume available between rows of containers and above the aforementioned 6-inch-thick layer of storage is calculated manually based on an average depth of 1.00 ft at the back wall, an aisle width of 2 ft, a length of 26.3 ft, and 38 aisles. Using the area formula for a triangle multiplied by the aisle width and the number of aisles, this volume is estimated to be 7,476 gal. Similarly, the volume available along the back wall and above the 6-inch-thick layer of storage is calculated manually based on an average depth of 1.00 ft at the back wall, an aisle width of 2 ft, and a length of 375 ft. Using the area formula for a rectangle multiplied by the aisle width, this volume is estimated to be 5,610 gal.

Summing the above components, a worst-case available secondary containment volume of 56,106 gal is calculated.

Required Secondary Containment Volume

As discussed in Assumption 1, the new Parking Area is assumed to be filled to capacity with tankers for the purposes of determining required secondary containment volume. The required secondary containment volume for liquid storage containers is based on one of two possible conditions. The first condition (Condition 1) provides storage for 10 percent of the total liquid volume of containers stored within the new Parking Area plus the runoff volume resulting from a 25-year, 24-hour storm event. The second condition (Condition 2) provides storage for the entire volume of the single largest liquid container stored within the new Parking Area plus the runoff volume resulting from a 25-year, 24-hour storm event. Calculations for both conditions are presented below.

Condition 1

Total Container Volume (assuming all containers store liquid)

- Total Container Volume: Maximum number of containers x volume per container (Assumption 4) x 0.10 (10 percent) = 37 containers x 2,500 gal/container x 0.10 = 9,250 gal

Precipitation Runoff Volume

- Runoff Volume: 35 ft x 375 ft x 0.333 ft = 4,375 cf or 32,727 gal

Required Secondary Containment Volume

- Total Container Volume + Precipitation Runoff Volume = 9,250 gal + 32,727 gal = 41,977 gal



NOTE: This Page to be added.

Imagine the result

Calculation Sheet

Condition 2

Single Largest Liquid Storage Container Volume

- The volume of the largest liquid storage container stored within the secondary containment area = 2,500 gal

Required Secondary Containment Volume

- Largest Liquid Storage Container Volume + Precipitation Runoff Volume (from Condition 1 above) = 2,500 gal + 32,727 gal = 35,227 gal

Based on a comparison of the required secondary containment volumes calculated for Conditions 1 and 2 above, the greatest required secondary containment volume is 41,977 gal (Condition 1).

Excess Secondary Containment Volume

The excess secondary containment volume condition is based on the worst-case total secondary volume available within the new Parking Area compared with the required secondary containment volume. The resultant volume condition is as follows:

Total Secondary Containment Volume: 56,106 gal
 Required Secondary Containment Volume: 41,977 gal
 Excess Volume: 56,106 gal – 41,977 gal = 14,129 gal

It is noted that this is a worst-case scenario because it is based on extremes of all roll-offs for available volume and all tankers for required volume. Any physically possible combination of roll-offs and tankers will yield additional reserve capacity beyond this calculated minimum.


SUMMARY:

The new Parking Area has a worst-case secondary containment volume of 56,106 gal. Based on the required secondary containment volume of 41,977 gal, which accounts for 10 percent of the maximum volume in all liquid storage containers within the new Parking Area plus the runoff volume resulting from a 25-year, 24-hour storm event, the new Parking Area provides adequate secondary containment. A maximum of 37 solids storage containers or 37 liquid storage containers or any combination of the two container types may be stored in the new Parking Area assuming the required aisle spaces considered herein are maintained.

NOTE: This Page to be added.

FIGURE D-12A
NEW TANK T-109 (SLF 10)
LEACHATE LOADING/UNLOADING PAD

CITY: SYRACUSE DIV:GROUP: ENV:CAD DB:K DAVIS L FORAKER K DAVIS ID: PIC:W POPHAM PM:W RANKIN TM:B STONE LVR:ON:OFF=REF: G:\ENV\CAD\SYRACUSE\SELECT\180023725\201100003\DWG\FULL TRAILER PARKING\23725D12A.dwg LAYOUT: D-12A SAVED: 7/8/2013 12:43 PM ACADVER: 18.1S (LMS TECH) PAGES: 18 PAGES: 18 PLOT: 7/8/2013 12:43 PM BY: SARTORI, KATHERINE



SCALE AS NOTED						Professional Engineer's Name					
						JOSEPH MOLINA					
						Professional Engineer's No.					
						072644					
						State		Date Signed		Project Mgr.	
						NY				WAR	
						Designed by		Drawn by		Checked by	
						LAB		SJK		BMS	
THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.		USE TO VERIFY FIGURE REPRODUCTION SCALE									
				</							



NOTE: This Page to be added.

Imagine the result

Calculation Sheet

Client: CWM Chemical Services, LLC

Project Location: Model City, New York

Project: RMU-2 Design Calculations

Project No.: B0023725.2011

Subject: New SLF 10 Leachate Loading/Unloading Ramp – Secondary Containment Calculations

Prepared By: NWF

Date: August 2013

Reviewed By: BMS

Date: August 2013

Checked By: BMS

Date: August 2013

OBJECTIVE:

Calculate the total secondary containment volume for the new SLF 10 Leachate Loading/Unloading Ramp and demonstrate that adequate capacity exists for the anticipated storage quantities.

REFERENCES:

1. Permit Drawing No. D-12A entitled "SLF 10 Holding Tank Building Leachate Transfer Ramp," contained in Attachment D-1 of the Overall Site/RMU-1 Part 373 Permit, ARCADIS, August 2013.
2. SLF 10 Leachate Building Secondary Containment Calculations, Sitewide 6 NYCRR Part 373 Permit, February 2001.
3. New York State Department of Environmental Conservation Regulations, Subpart 373.2.9 (f).

ASSUMPTIONS:

1. The secondary storage volume consumed by the semi tanker trailer tires and landing gear is assumed to be negligible and is not considered in this analysis.
2. The secondary containment must have sufficient capacity to contain the entire volume of the largest liquid container that will be stored on the ramp (Reference 3).
3. The precipitation volume considered in this calculation is based on the 25-year, 24-hour design storm, which contributes 4 inches of 0.333 feet (ft) of runoff.
4. One tanker truck can be located on the ramp at any one time. The largest liquid storage container volume that will be stored on the ramp is 5,500 gallons (gal).

CALCULATIONS:

The new ramp has interior dimensions of 13-feet-wide by 55.33-feet-long. Access to the ramp is from one end where the concrete is approximately flush with surrounding grade. The ramp slopes downward into the ground, such that the ramp is 2.25 feet lower at the deep end.

The available secondary containment volume within the ramp can be calculated manually using the area of a triangle multiplied by the ramp width as follows:



NOTE: This Page to be added.

Imagine the result

Calculation Sheet

$$[\frac{1}{2} (13 \text{ ft} \times 55.33 \text{ ft} \times 2.25 \text{ ft})] = 809 \text{ cubic feet} = 6,053 \text{ gal}$$

The new ramp is connected to the SLF 10 Holding Tank Building by a 3 inch pipe. A valve on this pipe is opened whenever liquid containers are on the ramp. As such, an additional 15,709 gallons of secondary containment volume within the SLF 10 Holding Tank Building (Reference 2) is also available. A total secondary containment volume of 21,762 gal is thus provided by the ramp itself and the building.

The required secondary containment volume for the new ramp is equal to the sum of the largest liquid storage container volume (5,500 gal) and the runoff from the design storm. The stormwater runoff volume is calculated as follows:

$$13 \text{ ft} \times 55.33 \text{ ft} \times 0.333 \text{ ft} = 240 \text{ cubic feet} = 1,794 \text{ gal}$$

Thus, the required secondary containment volume is 7,294 gal


SUMMARY:

The available secondary containment volume for the new SLF 10 Leachate Loading/Unloading Ramp (including the volume provided both by the ramp itself and the SLF 10 Holding Tank Building) exceeds the required secondary containment volume and is therefore acceptable.

NOTE: This Page to be added.


FIGURE D-14A
NEW TANK T-158 (SLF 1-11 OWS)
BUILDING LOADING/UNLOADING PAD

NOTE: This Figure to be added.




RAMP PLAN 1

SCALE: 1/4"=1'-0"




SECTION 2

SCALE: 1/4"=1'-0"




SECTION 3

SCALE: 1/2"=1'-0"




SLAB EXPANSION JOINT DETAIL 6

SCALE: 1/2"=1'-0"




WALL EXPANSION JOINT DETAIL 7

SCALE: 1/2"=1'-0"




BUILDING WALL/RAMP DETAIL 4

SCALE: 1/2"=1'-0"



PIPE PENETRATION DETAIL 5

SCALE: 1"=1'-0"



SECTION 8

SCALE: 1/2"=1'-0"

GENERAL NOTES:

- CONCRETE MIX SHALL BE 4000 PSI AT 28 DAYS WITH AIR ENTRAINING ADMIXTURE 6±1%. STEEL REINFORCEMENT SHALL BE ADDED TO MIX AS MANUFACTURED BY MITCHELL FIBERCON, INC., MEETING ASTM A820 TYPE II SPECIFICATIONS.
- ALL EXPOSED CONCRETE CONTAINMENT SURFACES TO RECEIVE CHEMTEC ONE CONCRETE PROTECTION SEALANT, OR APPROVED EQUAL.
- 5" SCHEDULE 40 STEEL SLEEVE SHALL BE INSTALLED AS SHOWN THROUGH CONTAINMENT RAMP WALL. CORRESPONDING 5" CORE DRILLED OPENING SHALL BE PROVIDED IN FOUNDATION WALL OF EXISTING SLF 1-11 OIL/WATER SEPARATOR BUILDING.
- 3" PIPE TO EXTEND INTO EXISTING SLF 1-11 OIL/WATER SEPARATOR BUILDING AND BE EQUIPPED WITH VALVE ACCESSIBLE FROM INTERIOR.
- REINFORCED CONCRETE BARS OF NEW BILLET STEEL CONFORMING TO ASTM A615, GRADE 60. LAP REINFORCING BARS MINIMUM 36 BAR DIAMETERS.
- DESIGN ELEVATIONS ARE RELATIVE. EXISTING GROUND SURFACE IS ASSUMED TO BE ELEVATION 0.0 FOR REFERENCE PURPOSES.
- STEEL ANGLE SHALL BE FABRICATED IN LENGTHS CORRESPONDING TO JOINT LOCATIONS. STEEL ANGLE SHALL NOT SPAN ANY SLAB JOINT. STRUCTURAL STEEL SHALL CONFORM TO ASTM A36 AND BE GALVANIZED IN ACCORDANCE WITH ASTM A123. WELDING SHALL BE IN ACCORDANCE WITH AWS D1.1.
- SUBBASE SHALL BE PROOF-ROLLED AND INSPECTED BY ENGINEER PRIOR TO PLACING CRUSHED STONE. IF SOFT SOILS OR AREAS OF PUMPING ARE OBSERVED, SOIL WITHIN THESE AREAS SHALL BE REMOVED AND REPLACED WITH CRUSHED STONE OR STRUCTURAL FILL AND PROOF ROLLED.
- CRUSHED STONE SHALL BE COMPACTED TO A MINIMUM 95% OF MAXIMUM DRY DENSITY BASED ON MODIFIED PROCTOR.
- WATERSTOP SHALL BE WESTEC'S ENVIROSTOP™ TPE-R (THERMOPLASTIC ELASTOMERIC RUBBER) 600 SERIES OR APPROVED EQUAL.

SCALE AS NOTED

THIS BAR REPRESENTS ONE INCH ON THE ORIGINAL DRAWING.

USE TO VERIFY FIGURE REPRODUCTION SCALE

7/2013 GENERAL REVISIONS

THIS DRAWING IS THE PROPERTY OF THE ARCADIS ENTITY IDENTIFIED IN THE TITLE BLOCK AND MAY NOT BE REUSED OR ALTERED IN WHOLE OR IN PART WITHOUT THE EXPRESS WRITTEN PERMISSION OF SAME

Professional Engineer's Name

JOSEPH MOLINA

Professional Engineer's No.

072644

State

NY

Designed by

LAB

Drawn by

SJK

Checked by

BMS

Project Mgr.

WAR

ARCADIS

ARCADIS OF NEW YORK, INC.

CWM CHEMICAL SERVICES, LLC • MODEL CITY, NEW YORK
FULL TRAILER PARKING AREA AND LEACHATE TRANSFER RAMP PERMIT DRAWINGS
SLF 1-11 OIL/WATER SEPARATOR BUILDING
LEACHATE TRANSFER RAMP

GENERAL

ARCADIS Project No.

80023725.2009.00006

Date

FEBRUARY 2013

ARCADIS of New York, Inc.

6723 Towpath Road

P.O. Box 66

Syracuse, New York

TEL: 315.446.9120

D-14A



NOTE: This Page to be added.

Imagine the result

Calculation Sheet

Client: CWM Chemical Services, LLC

Project Location: Model City, New York

Project: RMU-2 Design Calculations

Project No.: B0023725.2011

Subject: New SLF 1-11 OWS Loading/Unloading Ramp – Secondary Containment Calculations

Prepared By: NWF

Date: August 2013

Reviewed By: BMS

Date: August 2013

Checked By: BMS

Date: August 2013

OBJECTIVE:

Calculate the total secondary containment volume for the new SLF 1-11 Oil/Water Separator (OWS) Loading/Unloading Ramp (ramp) and demonstrate that adequate capacity exists for the anticipated storage quantities.

REFERENCES:

1. Permit Drawing No. D-14A entitled "SLF 1-11 Oil/Water Separator Building Leachate Transfer Ramp," contained in Attachment D-1 of the Overall Site/RMU-1 Part 373 Permit, ARCADIS, August 2013.
2. SLF 1-11 OWS Building Secondary Containment Calculations, Sitewide 6 NYCRR Part 373 Permit, February 2001.
3. New York State Department of Environmental Conservation Regulations, Subpart 373.2.9 (f).

ASSUMPTIONS:

1. The secondary storage volume consumed by the semi tanker trailer tires and landing gear is assumed to be negligible and is not considered in this analysis.
2. The secondary containment must have sufficient capacity to contain the entire volume of the largest liquid container that will be stored on the ramp (Reference 3).
3. The precipitation volume considered in this calculation is based on the 25-year, 24-hour design storm, which contributes 4 inches of 0.333 feet (ft) of runoff.
4. One tanker truck can be located on the ramp at any one time. The largest liquid storage container volume that will be stored on the ramp is 5,500 gallons (gal).

CALCULATIONS:

The new ramp has interior dimensions of 13-feet-wide by 55.33-feet-long. Access to the ramp is from one end where the concrete is approximately flush with surrounding grade. The ramp slopes downward into the ground, such that the ramp is 2.25 feet lower at the deep end.



NOTE: This Page to be added.

Imagine the result

Calculation Sheet

The available secondary containment volume within the ramp can be calculated manually using the area of a triangle multiplied by the ramp width as follows:

$$[\frac{1}{2} (13 \text{ ft} \times 55.33 \text{ ft} \times 2.25 \text{ ft})] = 809 \text{ cubic feet} = 6,053 \text{ gal}$$

The new ramp is connected to the SLF 1-11 OWS Building by a 3 inch pipe. A valve on this pipe is opened whenever liquid containers are on the ramp. As such, an additional 24,876 gallons of secondary containment volume within the SLF 1-11 OWS Building (Reference 2) is also available. A total secondary containment volume of 30,929 gal is thus provided by the ramp itself and the building.

The required secondary containment volume for the new ramp is equal to the sum of the largest liquid storage container volume (5,500 gal) and the runoff from the design storm. The stormwater runoff volume is calculated as follows:

$$13 \text{ ft} \times 55.33 \text{ ft} \times 0.333 \text{ ft} = 240 \text{ cubic feet} = 1,794 \text{ gal}$$

Thus, the required secondary containment volume is 7,294 gal

SUMMARY:

The available secondary containment volume for the new SLF 1-11 OWS Loading/Unloading Ramp (including the volume provided both by the ramp itself and the SLF 1-11 OWS Building) exceeds the required secondary containment volume and is therefore acceptable.

APPENDIX D-2

SURFACE IMPOUNDMENTS

APPENDIX D-2 SURFACE IMPOUNDMENTS

TABLE OF CONTENTS

I.	Introduction.....	1
II.	Background.....	1
III.	Description of Active Facultative Ponds 1, 2, 3 and 8	2
IV.	Facultative Pond Construction	3
IV.	Land Disposal Regulations.....	24
VI.	Operation	34
VII.	Maintenance.....	35
	A. Control of Overtopping and Maintenance of Dikes	35
	1. Inspections	35
	2. Erosion Protection	46
VIII.	Air Emission Standards.....	46

Facultative Pond 5 Construction Drawings

1. Title and Index
2. Site Plan
3. Fac Pond Grading Plans
4. Fac Pond Sections and Details
5. Fac Pond Transfer Pipeline
6. Fac Pond Transfer Pipeline
7. Fac Pond Transfer Pipeline
8. Fac Pond Transfer Pipeline Details
9. Site Electrical Feed Relocation Plan
10. Site Water Supply Relocation Plan
11. Fac Pond Riser House Mechanical Installation Details
12. Fac Pond Riser House Electrical Installation Details
13. Valve House Details
14. Fac Pond Transfer Pipeline Details

Fac Pond 5 Response Action Plan

SURFACE IMPOUNDMENTS

I. Introduction

The active surface impoundments, i.e., facultative ponds (FAC Ponds), are comprised of FAC Ponds 1, 2, 3 and 8. These surface impoundments are utilized for biological treatment using aeration and storage of treated wastewater prior to discharge into the Niagara River in accordance with the Model City Facility SPDES Permit.

The FAC ponds receive treated effluent from the Aqueous Wastewater Treatment System only. There are no other inputs to these impoundments with the exception of direct precipitation into the impoundments. Precipitation that accumulates in FAC Pond 8 may be transferred to FAC Pond 1 / 2.

Fac Ponds 3 and 8 will be closed in accordance with the Sitewide Closure Plan as part of site preparation for the construction of the Residuals Management Unit No. 2 (RMU-2) landfill. Fac Ponds 3 and 8 lie within the footprint of RMU-2 and upon closure will be filled with structural (as required) and general soil fill to the RMU-2 excavation grades. It should be noted that Fac Pond 8 will be closed in accordance with the Compliance Schedule in Schedule 1 of Module I of the Permit. Fac Pond 3 will be closed after the construction of Fac Pond 5 because of the need to continuously provide storage of treated wastewater prior to discharge.

New Fac Pond 5 will be constructed to compensate for the storage capacity lost due to closure of Fac Ponds 3 and 8. Fac Pond 5 will be constructed to the north of proposed RMU-2 between SLF 12 and SLF 7. Fac Pond 5 will include a double liner system with leak detection.

II. Background

The RCRA Hazardous and Solid Waste Amendments of 1984 (HSWA) specify that surface impoundments which treat or store hazardous waste must have two or more liners, a leachate collection system between these liners, and appropriate groundwater monitoring.

Owners and operators of facilities with interim status surface impoundments were given four years to retrofit impoundments to meet these minimum technology requirements (November 8, 1988). Chemical Waste Management, Inc. applied to the USEPA Region II for a variance to the HSWA double liner requirements for Facultative Ponds No. 1, 2, 3, 8, 9, Fire Pond and the Aggressive Biological Treatment Unit (ABTU) No. 58. On February 17, 1989 CWM was notified by the USEPA of the approval of its request for a variance. In the approval, the USEPA stated that CWM still qualifies for the exemption should the

composition of waste streams handled by CWM change or in the event that a new SPDES Permit was issued.

Moreover, during August of 1993, CWM requested verification from the NYSDEC that its exemption was still valid even though the AWTs had been upgraded and CWM's SPDES Permit had been renewed. In its 1993 request for verification, CWM demonstrated that the conditions upon which the exemption was based had not changed. In December of 1993, the NYSDEC informed CWM that its exemption from minimum technology requirements for the facultative pond system was still valid.¹

Consequently, the active surface impoundments described herein (FAC Ponds 1, 2, 3 and 8) do not meet the minimum technology requirements and are not double lined impoundments.

The Fire Pond was removed from service, clean closed and certified on March 1, 1990. Fac Pond 9 was removed from service, clean closed and certified on August 7, 1992. These two Fac Ponds no longer exist. ABTU 58 was converted to a RCRA tank in 1993.

III. Description of ~~Active~~ Facultative Ponds 1, 2, 3, 5 and 8

Active Fac Ponds 1, 2, 3 and 8 are clay lined surface impoundments of the following approximate sizes:

<u>Fac Pond</u>	<u>Capacity (gallons)</u>	<u>Area in Acres</u>
1 and 2	22,880,700	7.1
3	51,355,300	13.2
8	43,413,500	6.6

New Fac Pond 5 will be constructed as a double-lined surface impoundment with the following approximate size:

<u>Fac Pond</u>	<u>Capacity (gallons)</u>	<u>Area in Acres</u>
5	24,700,000	7.5

¹Paul R. Counterman, P.E. to Ms. Jill Knickerbocker, "Aggressive Biological Treatment Exemption", New York State Department of Environmental Conservation letter dated December 21, 1993.

Fac Ponds 1 and 2 were originally two separate adjacent ponds separated by a berm. In recent years, however, the internal berm was encroached. Now Fac Pond 1 and 2 are considered a single surface impoundment with common exterior berms.

The historical purpose of the Fac Ponds was to provide the final step for treated wastewater prior to discharge. This was accomplished by mechanical aeration allowing the continued reduction in TOC, BOD and COD, plus an increase in dissolved oxygen content. Since the inception of Land Disposal Regulations (LDRs), however, the levels of organic and other contaminants in the treated wastewater entering the Fac Ponds are greatly reduced. Aeration is currently used mainly for odor control.

IV. Facultative Pond 5 Construction

Material that is excavated from the floor area of Fac Pond 5 will be used to initiate construction of the eastern perimeter berm. This will allow a channel to be built between Fac Pond 5 and SLF 7 to divert runoff from SLF 7 around the Fac Pond 5 footprint. Additional fill material will be obtained from on-site stockpiles or be imported from pre-screened off-site sources.

A new liner system will be installed in Fac Pond 5, as described in Section 3.5.2 of the Engineering Report for RMU-2/Fac Ponds. A sideslope riser pipe will allow for monitoring of liquid levels in the sump of the leak detection system and for removal of accumulated liquids. A pre-fabricated weather proof riser house will be installed near the top of the perimeter berm at the sideslope riser pipe location. The sideslope riser pipe will penetrate the wall of the riser house so that transfer piping from the ponds leak detection system submersible pump may discharge into a tank. The riser house will contain a double-walled tank for storage of liquids pumped from the leak detection system. Access to the riser house will be provided by a ramp from an access road on the adjacent SLF 7.

A new at grade transfer line will be installed between Fac Ponds 1 and 2 and Fac Pond 5. The transfer line will include two parallel 6-inch-diameter in 10-inch diameter double-wall HDPE pipes at grade with soil protection cover. Each forcemain (two, in total) will be constructed of double-contained HDPE pipe. The inner carrier pipe will be 6-inches and the outer containment pipe will be 10-inches. The outer, secondary containment pipe will terminate at the penetration into HDPE manholes to allow for leak detection. The treated wastewater forcemains will be sloped so that any liquid in the secondary containment pipe will gravity drain back to a junction or transfer manhole.

As indicated on Drawing Nos. 5, 6 and 7 in this appendix, the pipeline will be sloped towards leak detection manholes. At Fac Pond 5, the pipeline will terminate above ground at the riser house. Connective piping will be installed to allow either of the two parallel lines to be used to fill or drain the pond. At Fac Ponds 1 and 2, the pipeline will terminate

in a valve house as indicated on Drawing Nos. 3, 5, and 13 in this appendix. Piping from the valve house will lead to Fac Ponds 1 and 2, Fac Pond 5, and the existing discharge manhole to the north of the Fac Pond perimeter berm that discharges to the Niagara River. Piping will be installed in the new valve house to allow either of the two parallel lines to be used to transfer liquid from Fac Ponds 1 and 2 to Fac Pond 5 or vice versa, fill Fac Pond 5 with effluent from the site's treatment plant and to discharge liquid from Fac Pond 5 to the existing discharge piping leading to the Niagara River. The existing discharge filter system will be relocated from its current location at Fac Pond 3 to an area north of Fac Ponds 1 and 2.

The Action Leakage Rate (ALR) for Fac Pond 5 was calculated and a Response Action Plan (RAP) is included in this appendix.

IV. Land Disposal Regulations

LDRs have established treatment standards for wastewater discharged to surface impoundments. In November 1998, NYSDEC updated the 6NYCRR Part 376 regulations to adopt recently promulgated USEPA LDRs. The CWM Waste Analysis Plan describes the test procedures and frequency employed to assure that the treated effluent meets established LDRs under the multi-source leachate Waste Code F039.

VI. Operation

After treatment in the carbon adsorption system of the AWTs, the wastewater effluent is discharged into an effluent holding tank. Following qualification, the effluent is transferred to FAC Pond 1 and 2.

Periodically, this volume of treated effluent is pumped from Fac Pond 1 and 2 into Fac Pond 3 to accumulate sufficient quantities for discharge. The final step of the qualification process occurs in Fac Pond 3 where samples are collected and analyzed for comparison to the SPDES Permit limits. Once the effluent qualifies under the SPDES Permit, the wastewater is discharged via the facility's pipeline to the Niagara River. Generally, one batch is qualified and discharged per year. A typical volume is 15-25 million gallons per year.

Fac Ponds 1, 2 and 3 are equipped with mechanical aerators whose main purpose is to minimize odorous emissions from the pond by maintaining a high dissolved oxygen content. Aerators are operated on an as needed basis. The liquid level in each Fac Pond is visually inspected to maintain a freeboard of at least two feet.

Fac Pond 8 was taken out of service in 2004 and emptied in anticipation of closure. Prior to that time, Fac Pond 8 was used as the final qualification pond. Closure of Fac Pond 8 is currently in progress.

Development of the first phase of RMU-2 (Cell 20) will be at the location of current Fac Pond 8. During the development of the first phase of RMU-2 Fac Ponds 1 / 2 and 3 will operate as described above and Fac Pond 5 will be constructed. Fac Pond 3 will be closed in accordance with the Sitewide Closure Plan prior to the development of the second phase of RMU-2 after the final discharge from the pond.

The existing influent and effluent piping will be modified, as necessary, to accommodate the Fac pond construction and reconstruction. Piping will be installed in a new valve house to allow either of the two parallel lines to be used to transfer liquid from Fac Ponds 1 and 2 to Fac Pond 5 or vice versa, fill Fac Pond 5 with effluent from the site's treatment plant and to discharge liquid from Fac Pond 5 to the existing discharge piping leading to the Niagara River.

Periodically, a volume of treated effluent will be pumped from Fac Pond 1 and 2 into Fac Pond 5 to accumulate sufficient quantities for discharge. The final step of the qualification process will occur in Fac Pond 5 where samples will be collected and analyzed for comparison to the SPDES Permit limits. Once the effluent qualifies under the SPDES Permit, the wastewater will be discharged via the facility's pipeline to the Niagara River. Generally, one batch is qualified and discharged per year, however additional batches may be discharged within a calendar year.

Fac Ponds 1, 2 and 5 will be equipped with mechanical aerators whose main purpose is to minimize odorous emissions from the ponds by maintaining a high dissolved oxygen content. Aerators will be operated on an as needed basis. The liquid level in each Fac Pond will be visually inspected to maintain a freeboard of at least two feet.

Liquids will be pumped from the leak detection system of Fac Pond 5 to the riser house constructed on the berm. The amount of liquids removed from the leak detection system sump will be recorded at least once each week during the active life and will compared to the Response Rate in the RAP and the ALR.

VII. Maintenance

Erosion protection is predominately provided for the exterior surfaces of all above grade impoundments in the form of a vegetative growth. Inspections of all active surface impoundment embankments are performed at least once each operating day.

A. Control of Overtopping and Maintenance of Dikes

1. Inspections

Specific inspection criteria are described in the facility's Inspection Plan for the following criteria:

- 1) measurement devices;
- 2) liquid level in the impoundment (indication whether two feet of freeboard is present);
- 3) no sudden drop in level of contents not associated with pumping;
- 4) no signs of severe erosion, deterioration, or instability of dikes;
- 5) aerators are operable when in use.

The inspections are designed to detect any evidence of deterioration, malfunction or improper operation which would compromise the efficiency of the overtopping control. Level control is accomplished by visual inspections of the measuring device affixed near each impoundment. This will assure that sudden changes in liquid level will be quickly detected.

Liquid losses, due to berm failure, from the FAC Ponds would be contained in the facility surface water drainage collection system until contingency measures were implemented.

Moreover, most of the Fac Ponds are below ground level, **with the exception of new Fac Pond 5**, making losses very minimal in the event of berm failure.

2. Erosion Protection

The exterior of the containment berms for the surface impoundments are vegetated to reduce the potential for erosion due to precipitation and runoff.

Inspections which indicate a problem with erosion will be handled by initiating the Environmental Work Order System. Restorative construction will consist of removal or reshaping the eroded soils, reseeding and adding additional material with compaction. The area will be monitored during subsequent inspections to ensure its viability.

VIII. Air Emission Standards

Air emission standards for surface impoundments are specified in 6NYCRR 373-2.29 and 40 CFR 264/265.1080-1091 (Subpart CC), which became effective on December 6, 1996. RCRA Subpart CC is applicable to owners and operators of a TSDF which treats, stores or disposes of hazardous waste containing greater than 500 ppmw volatile organics in tanks, surface impoundments and containers. If Subpart CC wastes are managed in a surface impoundment, a floating membrane continuous barrier or a cover vented through a closed vent system to a control device must be installed, unless specified exemptions apply. All surface impoundments at the CWM Model City Facility are exempt from these requirements as described below.

Fac Ponds 1, 2, 3, 5 and 8 are exempt since the treated wastewater placed in these impoundments meets the applicable numerical organic limits for F039, as specified by the LDR regulations. In addition, all wastewaters are exempt after being treated at the AWTS, and so the effluent from AWTS is exempt.