



29 July 2022

Mr. Scott Sokolowski
Remedial Project Manager
Naval Facilities Engineering Systems Command, Mid Atlantic
9324 Virginia Avenue, Building Z-144
Norfolk, VA 23511-3095

**Subject: US NAVY CONTRACT NO. N40085-16-D-2288
CONTRACT TASK ORDER NO. 0005
2022 FIRST QUARTER OPERATIONS REPORT
GWTP GM-38 AREA REMEDIATION
NAVAL WEAPONS INDUSTRIAL RESERVE PLANT, BETHPAGE, NY**

Dear Mr. Sokolowski:

An electronic copy of the *2022 First Quarter Operations Report, Groundwater Treatment Plant, GM-38 Area Groundwater Remediation, Naval Weapons Industrial Reserve Plant, Bethpage, New York*, has been submitted to your attention via email.

Please contact me at rgregory@komangs.com or 610.400.0636 if you have any questions or comments regarding this submittal.

Sincerely,
KOMAN Government Solutions, LLC (KGS)

A handwritten signature in black ink that reads 'Robert G. Gregory'.

Robert G. Gregory
Project Manager

Cc: Mr. Jason Pelton (NYSDEC) – electronic only
Ms. Kristin Granzen (NYSDEC) – electronic only
Mr. Matthew Travis (NYSDEC) – electronic only
Mr. Steven Scharf (NYSDEC) – electronic only
Mr. William Cords (NAVAIR) – electronic only
Mr. James Sullivan (NYSDOH) – electronic only
Ms. Monica Marrow (Jacobs - NIRIS) – 1 hard copy, 1 CD
Mr. Vin Varricchio (NWIRP Bethpage) – 2 hard copies, 2 CDs
Mr. Ed Hannon (Northrop Grumman) – electronic only
Mr. David Stern (ARCADIS) – electronic only
Mr. David Brayack (Tetra Tech) – electronic only
Mr. Patrick Schauble (KGS) – electronic only

**Quarterly Operations Report
First Quarter 2022**

**Groundwater Treatment Plant
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant
Bethpage, New York**

**Contract No. N40085-16-D-2288
Contract Task Order No. 0005**

July 2022

Prepared for:



Naval Facilities Engineering Systems Command Mid-Atlantic
9324 Virginia Avenue
Norfolk, VA 23511

Prepared by:



**KOMAN Government Solutions, LLC
180 Gordon Drive, Suite 110
Exton, Pennsylvania 19341
(610) 363-3000**

**Quarterly Operations Report
First Quarter 2022**

**Groundwater Treatment Plant
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant
Bethpage, New York**

**Contract No. N40085-16-D-2288
Contract Task Order No. 0005**

July 2022

Prepared for:

Naval Facilities Engineering Systems Command Mid-Atlantic
9324 Virginia Avenue
Norfolk, VA 23511



Patrick Schauble
Program Manager

07/06/2022

Date

Robert Gregory
Project Manager

07/06/2022

Date

TABLE OF CONTENTS

1.0	INTRODUCTION.....	1-1
1.1	Background.....	1-1
1.2	GWTP Overview	1-1
2.0	GWTP OPERATIONS AND MAINTENANCE	2-1
2.1	Routine Maintenance Activities.....	2-1
2.2	Non-routine Maintenance / Site Activities	2-1
3.0	GWTP MONITORING	3-1
3.1	Process Water Quality Monitoring	3-1
3.2	Air Quality Monitoring.....	3-1
3.3	Groundwater Quality Monitoring.....	3-1
3.3.1	Groundwater Quality Results.....	3-2
3.3.2	Quality Assurance/Quality Control Sampling.....	3-3
3.3.3	Groundwater Concentration Trends	3-3
4.0	CONCLUSIONS AND RECOMMENDATIONS	4-1
5.0	REFERENCES.....	5-1

FIGURES

FIGURE 1	Site Location Map
FIGURE 2	Process Flow Diagram
FIGURE 3	Site Map
FIGURE 4	Recovery Well Locations
FIGURE 5a	First Quarter 2022 Groundwater Analytical Map – Select VOC Concentrations (RW-1 and RW-4)
FIGURE 5b	First Quarter 2022 Groundwater Analytical Map – Select VOC Concentrations - Monitoring Wells
FIGURE 6	Groundwater Concentrations Trends of Select VOCs – RW-1
FIGURE 7	Groundwater Concentrations Trends of Select VOCs – RW-4 (PCE, TCE, cis-1,2-DCE)
FIGURE 8	Groundwater Concentrations Trends of Select VOCs – RW-4 (PCE, cis-1,2-DCE)
FIGURE 9	Groundwater Concentrations Trends of Select VOCs – RW1-MW1
FIGURE 10	Groundwater Concentrations Trends of Select VOCs – RW1-MW3
FIGURE 11	Groundwater Concentrations Trends of Select VOCs – RW2-MW1
FIGURE 12	Groundwater Concentrations Trends of Select VOCs – RW3-MW1
FIGURE 13	Groundwater Concentrations Trends of Select VOCs – RW3-MW2
FIGURE 14	Groundwater Concentrations Trends of Select VOCs – RW3-MW3
FIGURE 15	Groundwater Concentrations Trends of Select VOCs – RW3-MW4
FIGURE 16	Groundwater Concentrations Trends of Select VOCs – TP-01

TABLES

TABLE 1	Discharge Monitoring Results – First Quarter 2022
TABLE 2	Air Sampling Results – First Quarter 2022
TABLE 3	Stack Emissions – First Quarter 2022
TABLE 4	Groundwater Level Measurements – First Quarter 2022
TABLE 5	Summary of Groundwater Chemistry Results – First Quarter 2022
TABLE 6	Summary of Detected Groundwater Analytical Results – First Quarter 2022
TABLE 7	Summary of Historical Groundwater Analytical Results through First Quarter 2022

APPENDICES

APPENDIX A	NYSDEC Effluent Limitations and Monitoring Requirements and January 2022 – March 2022 DMRs
APPENDIX B	NYSDEC Air Discharge Limit Documentation
APPENDIX C	Field Logs and Chain of Custody Documentation – First Quarter 2022
APPENDIX D	Data Validation Reports

Acronyms and Abbreviations

%	percent
AOP	Advanced Oxidation Process
ARAR	Applicable or Relevant and Appropriate Requirement
AS	air stripper
ASE	air stripper effluent
BFE	bag filter effluent
bgs	below ground surface
CERCLA	Comprehensive Environmental Response Compensation and Liability Act
DAR	Division of Air Resources
DCA	dichloroethane
DCE	dichloroethene
DMR	Discharge Monitoring Report
DO	dissolved oxygen
DoD	Department of Defense
DTW	depth to water
EB	equipment blank
ECL	Environmental Conservation Law
ELAP	Environmental Laboratory Accreditation Program
EQ	equalization
GOCO	Government Owned Contractor Operated
gpm	gallon per minute
GWTP	groundwater treatment plant
KGS	KOMAN Government Solutions, LLC
HMI	human-machine interface
IRP	Installation Restoration Program
L	liter
lb	pound
LGAC	liquid-phase granular activated carbon
MS/MSD	matrix spike/matrix spike duplicate
NAVFAC	Naval Facilities Engineering Systems Command
Navy	United States Department of the Navy
NELAC	National Environmental Laboratory Accreditation Conference
NG	Northrop Grumman

NWIRP	Naval Weapons Industrial Reserve Plant
NYSDEC	New York State Department of Environmental Conservation
O&M	Operation and Maintenance
ORP	oxidation-reduction potential
OU	operable unit
PCE	tetrachloroethene
PLC	programmable logic controller
QA/QC	quality assurance/quality control
ROD	Record of Decision
RPD	relative percent difference
SC	specific conductivity
scfm	standard cubic feet per minute
SIM	selective ion monitoring
SPDES	State Pollution Discharge Elimination System
TB	trip blank
TCE	trichloroethene
TE	treated effluent
Tetra Tech	Tetra Tech, Inc.
TICs	tentatively identified compounds
TtEC	Tetra Tech EC, Inc.
TSS	total suspended solids
µg/L	micrograms per liter
USEPA	United States Environmental Protection Agency
UV	ultraviolet
VC	vinyl chloride
VFD	variable frequency drive
VGAC	vapor phase granular activated carbon
VOC	volatile organic compound

1.0 INTRODUCTION

KOMAN Government Solutions, LLC (KGS) has prepared this Quarterly Operations Report for the GM-38 Area Groundwater Treatment Plant (GWTP) at the Naval Weapons Industrial Reserve Plant (NWIRP) in Bethpage, New York. This report has been prepared for the United States Department of the Navy (Navy), Naval Facilities Engineering Systems Command (NAVFAC), Mid-Atlantic, under Contract No. N40085-16-D-2288, Contract Task Order No. 0005. This First Quarter 2022 Operations Report details activities that occurred from January to March 2022. Data were collected and operational activities were performed by KGS in accordance with the following documents:

- *Final Operation, Maintenance & Monitoring Plan for Groundwater Treatment Plant GM-38 Area Groundwater Remediation, Naval Weapons Industrial Reserve Plant, Bethpage, New York* prepared by Tetra Tech EC, Inc. (TtEC) in 2010, hereafter referred to as the “O&M Manual.”
- *Final Sampling and Analysis Plan (Field Sampling Plan and Quality Assurance Project Plan), UFP-SAP for Operations, Maintenance, and Monitoring of the Groundwater Treatment Plant, GM-38 Area, Naval Weapons Industrial Reserve Plant, Bethpage, New York* prepared by TtEC in 2010.

1.1 Background

NWIRP Bethpage is located in east central Nassau County, Long Island, New York, approximately 30 miles east of New York City (**Figure 1**) and is currently listed by New York State Department of Environmental Conservation (NYSDEC) as an “inactive hazardous waste site” (#1-30-003B). In the late 1990s, the Navy’s property totaled approximately 109.5 acres and was a Government Owned Contractor Operated (GOCO) facility that was operated by Northrop Grumman (NG) until September 1998. NWIRP Bethpage was bordered on the north, west, and south by property owned, or formerly owned, by NG that covered approximately 550 acres, and on the east by a residential neighborhood.

The GM-38 Area refers to a cluster of monitoring wells installed in the 1990s by NG. The GM-38 Area is approximately 8,500 feet south, southeast, and hydraulically downgradient of NWIRP Bethpage. The GWTP is located within a utility easement with a street address of 100 Broadway, Bethpage, New York.

The “hot spot” cleanup remedy for the GM-38 Area groundwater was originally set forth in Record of Decision (ROD) documents for Operable Unit (OU) 2 Groundwater for the NG and NWIRP Sites (New York State Registry Site Numbers 1-30-003A & 1-30-003B, respectively) issued by NYSDEC Division of Environmental Remediation in March 2001 and for the NWIRP Bethpage Site by NAVFAC in April 2003 (Revision 1). The selected remedy was chosen in accordance with the New York State Environmental Conservation Law (ECL) and the Navy’s Installation Restoration Program (IRP). It is also consistent with the Comprehensive Environmental Response Compensation and Liability Act (CERCLA), as amended, 42 U.S.C. §§ 9601-9675.

1.2 GWTP Overview

Currently, groundwater is extracted from recovery wells RW-1 and RW-4. Pumping at RW-3 was suspended from July 2015 to June 2018, and then again in April 2021 when the new recovery well RW-4 was brought online. All extracted groundwater is treated in the GWTP. The treatment process consists of flow equalization, air stripping and vapor-phase carbon treatment, bag filtration, and liquid-phase carbon treatment. In addition, an Advanced Oxidation Process (AOP) system has been installed at the GWTP and is intended to remove residual concentrations of 1,4-dioxane from the GWTP effluent prior to discharge. The AOP commissioning process began in April 2021.

The GWTP was originally equipped with a pH adjustment system utilizing sodium hydroxide; however, it was subsequently determined that pH adjustment was not necessary. The equipment has been taken off-line and sodium hydroxide sent off site for beneficial reuse. A process flow diagram is presented as

Figure 2. The treated water is either re-injected into injection well IW-1 or discharged into the Nassau County Recharge Basin #495. Under CERCLA, the Navy is required to meet the effluent requirement in the NYSDEC State Pollution Discharge Elimination System (SPDES) Permit Equivalent Application as an Applicable or Relevant and Appropriate Requirement (ARAR).

The GWTP was designed to operate at an average flow rate of 1,100 gallons per minute (gpm), as measured by the average discharge flow rate. It was determined that this flow rate would be optimal with respect to effective containment of the higher concentration of contamination in the GM-38 Area groundwater. During the current reporting period, both the AOP system and recovery well RW-4 have been online full time but at a reduced capacity while operations continue to be evaluated by the Navy team. RW-1 has been operating at approximately 660 gpm, 506 gpm, and 498 gpm during January, February, and March 2022; and RW-4 has been operating at approximately 266 gpm, 368 gpm, and 395 gpm throughout the First Quarter, respectively.

Volatile Organic Compounds (VOCs) in the influent groundwater consist of trichloroethene (TCE), tetrachloroethene (PCE), vinyl chloride (VC), cis-1,2-dichloroethene (DCE), 1,2-dichloroethane (DCA), benzene, toluene, total xylenes, and 1,4-dioxane.

The air stripper (AS) is a structural aluminum tower that is packed with 3.5-inch diameter polypropylene Jaeger Tripack. Groundwater is pumped to the AS distribution port and sprayed over the column of Jaeger Tripack at a design flow rate of approximately 1,100 gpm. Previously, 100 gpm of recirculated water was also rerouted through the AS, but as of October 2010, recirculation was no longer deemed necessary to the operation of the system. An induced draft countercurrent flow of air enters the AS below the base of the packing material at a rate of 8,000 standard cubic feet per minute (scfm). The large surface area of the packing material allows for a mass transfer of the VOCs from the groundwater into the air stream. The VOCs in the off-gas, except for VC, are removed via two 20,000-pound (lb) vapor phase granular activated carbon (VGAC) units (VGAC-1 and VGAC-2). VC is oxidized into potassium chloride and carbon dioxide via treatment in a 20,000-lb vessel (VGAC-3) containing zeolite impregnated with potassium permanganate. The potassium chloride remains in the pore structure of the zeolite substrate. The treated off-gas is discharged from the stack.

Water treated by the AS is subsequently processed through the AOP unit, followed by processing through three 8,000-lb liquid phase granular activated carbon (LGAC) units in parallel prior to discharge in the recovery basin (or injection well, if necessary).

The GWTP is controlled by a programmable logic controller (PLC)-based digital and analog control system, with instrumentation that monitors pH, pressure, tank level, flow and differential pressure transmitters, water level in recovery wells, and motor operational status. The information in the PLC is made available to an operator via a human-machine interface (HMI) program. By using this program, the status of the GWTP can be displayed in real time and adjusted, if necessary, by the operator. The AOP unit has a standalone PLC to control its internal functions. The GWTP and AOP control systems are interlocked such that shut down of the AOP unit will result in shut down of the GWTP, and vice versa, to ensure that effluent is fully treated prior to discharge.

A 2014 evaluation of the GM-38 Area, conducted in order to better determine the capture zone of the recovery wells, recommended that use of recovery well RW-3 be discontinued (“*Capture Zone Evaluation and Path Forward, GM-38 Area Groundwater Treatment Plant*” [Tetra Tech, Inc. [Tetra Tech], 2014]). The report was sent to NYSDEC in March 2014 and recommended ceasing operation of recovery well RW-3 and increasing the pumping rate of recovery well RW-1. These system modifications would maintain the existing GWTP pumping rate of 1,000 to 1,100 gpm while maintaining the desired capture zone of the GWTP (Tetra Tech, 2014). NYSDEC concurred with the implementation of this path forward and associated system modifications on 20 April 2015. On 1 July 2015, in accordance with the approved path forward, recovery well RW-3 was taken off-line. The flowrate of recovery well RW-1 was increased from approximately 800 gpm to approximately 1,000 gpm. Pumping

at RW-3 was once again resumed in June 2018 to address persistent VOC concentrations at this well. Pumping at RW-3 was suspended in April 2021 to facilitate startup and integration of RW-4 into the system.

2.0 GWTP OPERATIONS AND MAINTENANCE

While designed to run autonomously, the GWTP requires regular visits by an operator to record and adjust operational parameters and to perform scheduled maintenance. The GWTP is equipped with telemetry that will alert an on-call operator in the event of a plant shutdown.

2.1 Routine Maintenance Activities

Routine maintenance activities at the GWTP were performed during the operator's visits. These activities include general site inspections, collection of operational data (water and vapor flowrates, differential pressures across the AS, carbon units, bag filter units and blower discharge pressures, tank levels, and totalizer readings), measurement of water levels in the recovery wells, adjustment of pump signal settings, collection of vapor and process water samples, changing bag filters, switching lead/lag pump assignments, and preventive maintenance of system equipment.

In addition, the following maintenance tasks were also performed during this reporting period:

- 7 February – Annual certification for backflow prevention device.
- 13 February – Operator replaced the AS intake filters.

2.2 Non-routine Maintenance / Site Activities

During previous routine maintenance tasks at GWTP, the operator observed that both LGAC backwashing and bag filter changes were required more frequently than usual to maintain the desired process flowrate. In addition, the backwash water from the LGACs in the plant sump was increasingly turbid. Following pumping of the water to the equalization (EQ) tank, a light gray coating was observed on the walls of the sump and on the sump pump and associated piping. In addition, the operation of the sump pump was compromised by the accumulation of solids from the backwash water. Collection and investigation of solids from the floor of the sump identified dark gray clay-sized material that dried and hardened to a light gray solid. Chemical analysis of the solid identified inorganics and elements typical of clay materials. This material was presumed to be accumulating within the LGAC vessels resulting in the required increase in backwash frequency and damage to the sump pump. Discussions between Navy and the project team resulted in a phased approach to determine if one or both of the active recovery wells (RW-1 and RW-3) was the source of the solids observed in the plant influent as discussed below. Following investigative activities in the Fourth Quarter of 2020, it was determined that RW-1 was the apparent source of the solids. RW-1 was rehabilitated and re-developed and a new pump installed in the Fourth Quarter 2020. Pumping rates for RW-1 were increased sequentially while the frequency of bag filter changeouts was assessed. It was determined that a pumping rate within the range of 650-700 gpm could be sustained while not exceeding the typical bag filter changeout frequency of one changeout per week. The flow from RW-1 will continue to be assessed.

During the Fourth Quarter 2021, efforts continued, under separate contract, to integrate the AOP into the existing treatment system. Operational issues related to low flow alarms from the hydrogen peroxide feed line and inconsistent function of the ultraviolet (UV) light transmittance monitor persisted through the reporting period. Intermittent plant shutdowns associated with the low flow alarms in the AOP unit resulted in surging of flow from RW-4 that caused an additional brown-colored sediment load in the plant influent. It is unclear whether the source of the sediment is from RW-4 itself or possibly from the pipeline to the GWTP. The source of the additional sediment load is currently under investigation by others under a separate contract. The frequency of bag filter changes resulting from this additional sediment load has increased and has varied from once a day to once every four days during the current reporting period.

Various non-routine maintenance tasks associated with adjustments to the AOP unit and startup of RW-4 in the current reporting period were performed. Recording and reporting of these tasks specific to AOP

unit itself are being conducted by others under a separate contract and are not itemized in this report. AOP-related events that impacted operation of the GWTP are listed in the following text.

The following non-routine activities occurred at the GWTP during the current reporting period:

- 3 January – Operator increased RW-4 to 300 gpm.
- 2 February – Operator increased RW-4 to 400 gpm.
- 17 February – Vapor-phase GAC replaced in Unit #1.
- 3 March – Installation of upgraded plant PLC alarm call-out equipment.

3.0 GWTP MONITORING

The objective of the GWTP is to remove contaminant mass and reduce elevated VOC levels to levels similar to those in the surrounding aquifer. It is anticipated that GWTP operation will minimize contaminant impacts on water supply wells and currently unaffected portions of the groundwater aquifer. The GWTP is not intended to remediate groundwater contamination in the local aquifer to non-detectable levels (TtEC, 2010). Various process samples (water and vapor) are collected on a monthly basis to monitor GWTP efficiency and to ensure compliance with Federal and State effluent discharge and air emission requirements. In addition, groundwater samples are collected semi-annually to monitor water quality and determine the effectiveness of the remediation activities and monitor the hydraulic containment and capture of impacted groundwater by the recovery wells.

3.1 Process Water Quality Monitoring

Processed groundwater is analyzed to comply with calculations submitted by the Navy and documented in the NYSDEC SPDES Permit Equivalent Application for applicable effluent limitations and monitoring requirements. These results are also submitted to NYSDEC on a monthly basis in the form of a Discharge Monitoring Report (DMR). A copy of the current NYSDEC effluent limitations, monitoring constituents, and the reporting forms are included in **Appendix A**.

Monthly aqueous samples are collected from the active recovery wells (RW-1 and RW-4), and the treated effluent (TE) discharge line. In addition, various intermediary process system samples are collected monthly, consisting of air stripper effluent (ASE), bag filter effluent (BFE), and effluent samples (LC1, LC2, and LC3) of each of the three LGAC units. The analytical results of monthly aqueous samples collected during the First Quarter are presented in Table 1.

3.2 Air Quality Monitoring

Treated off-gas discharged at the stack of the GWTP is subject to emissions limitations. Original discharge goals were derived from calculations submitted by the Navy and approved by the NYSDEC Division of Air Resources (DAR) in July 2009. In November 2011, the Navy submitted an evaluation proposing revised discharge goals, which NYSDEC approved in October 2013. A copy of this documentation is included as **Appendix B**.

Sampling of the stack emissions is required for NYSDEC compliance; however, process vapor samples are also collected using 6-liter (L) summa canisters at various locations to monitor for breakthrough of the VGAC units. The analytical results of monthly influent and effluent vapor samples as well as midfluent samples (VC12 and VC23) collected during the First Quarter are presented in **Table 2**. Air emissions calculations using the stack vapor concentrations along with discharge flowrates are presented in **Table 3**. The calculations demonstrate that all constituents were within the regulatory requirements during the First Quarter, based on the calculated emission rates.

3.3 Groundwater Quality Monitoring

The groundwater monitoring well system at the GM-38 Groundwater Remediation Area consists of 14 monitoring wells, four recovery wells (RW-1, RW-2, RW-3, and RW-4), and one injection well (IW-1). Well locations are depicted on **Figure 3**. Recovery well RW-4, brought on-line in April 2021, is located approximately one mile to the west of the GWTP (**Figure 4**). Although RW-2 was installed in 2005, a pump was never installed in this well and the well is not operated as a recovery well in response to concerns expressed by the Bethpage Water District. As mentioned in Section 1.2, pumping at RW-3 was suspended between July 2015 and June 2018. RW-3 was reactivated on 1 June 2018 to address persistent VOC concentrations at this location and was subsequently replaced with Well RW-4 in April 2021. Well RW-1 was offline during the months of October and November 2020 as a result of a rehabilitation and redevelopment effort conducted at that time. Groundwater level measurements were collected from the current groundwater monitoring well system in early March 2022 and are summarized in **Table 4**.

Depth to water (DTW) measurements are collected from 12 of the monitoring wells on a quarterly basis. Prior to 2014, water quality samples were collected from eight of the monitoring wells on a quarterly basis; beginning in 2014, the sample collection frequency was reduced to semi-annually, with sample collection generally in the March (annual/First Quarter) and September (semi-annual/Third Quarter) timeframes. The monitoring network includes well clusters located near the recovery wells RW-1 and RW-3 and injection well IW-1 as described below and as shown on **Figure 3**. Two additional wells, GM-38D and GM-38D2, located at the corner of Arthur Avenue and Broadway, are monitored by others.

Annual groundwater samples for March 2022 were collected from eight monitoring wells (RW1-MW1, RW1-MW3, RW2-MW1, RW3-MW1, RW3-MW2, RW3-MW3, RW3-MW4, and TP-01) and from two recovery wells (RW-1 and RW-4). Samples are collected from monitoring wells using bladder pumps in accordance with USEPA low-flow sampling methodologies. Samples were collected from recovery wells RW-1 and RW-4 using the dedicated extraction pump as it is normally done during routine O&M sampling. Results of the groundwater sampling for the first semi-annual event are presented in Section 3.3.1 below. Descriptions of monitoring well locations are as follows:

Recovery Well 1 (RW-1) Monitoring Wells

The RW-1 cluster consists of three monitoring wells screened between 395 and 435 feet below ground surface (bgs). RW1-MW1 is located approximately 140 feet northwest of RW-1 and RW1-MW2 is located approximately 50 feet north of RW-1. RW1-MW3 is located approximately 400 feet northeast of RW-1, on the eastern side of Seaford Oyster Bay Expressway. All three wells are hydraulically monitored while only RW1-MW1 and RW1-MW3 are also monitored for water quality.

Recovery Well 2 (RW-2) Monitoring Wells

The RW-2 cluster consists of three monitoring wells screened between 470 and 510 feet bgs. RW2-MW1 is located approximately 60 feet northwest of RW-2, RW2-MW2 is located approximately 100 feet west of RW-2, and RW2-MW3 is located approximately 20 feet west of RW-2. All three wells are hydraulically monitored while only RW2-MW1 is monitored for water quality.

Recovery Well 3 (RW-3) Monitoring Wells

The RW-3 cluster consists of four monitoring wells. RW3-MW2 and RW3-MW4 are screened between 475 and 495 feet bgs. RW3-MW1 and RW3-MW3 are screened between 330 and 350 feet bgs and 320 and 340 feet bgs, respectively. RW3-MW1 and RW3-MW2 are located approximately 280 feet west of RW-3, at the intersection of Arthur Avenue and Leroy Avenue. RW3-MW3 and RW3-MW4 are located approximately 400 feet north of the intersection of Sophia Street and Broadway. All four wells are both hydraulically monitored and monitored for water quality.

TP-01

TP-01 is screened between 450 and 470 feet bgs and is located approximately 25 feet north of the GWTP building, inside the fenced area. It is hydraulically monitored to observe the change in water levels associated with the influence from the pumping rates at the neighboring public water supply well field adjacent to the hot spot area and is also monitored for water quality.

Injection Well 1 (IW-1) Monitoring Well

There is one monitoring well associated with injection well IW-1. IW1-MW1 is screened between 20 and 150 feet bgs, is located approximately 20 feet south of IW-1 and is only hydraulically monitored on a quarterly basis.

3.3.1 Groundwater Quality Results

Annual groundwater samples for the March 2022 sampling event were collected on 9 and 10 March 2022. DTW measurements were used to calculate the groundwater elevations shown on **Table 4**. Field parameters measured during the well purging, which consisted of pH, specific conductivity (SC),

temperature, oxidation-reduction potential (OPR), dissolved oxygen (DO), and turbidity, are summarized in **Table 5**. Following stabilization of field parameters, groundwater samples were collected. Copies of the field logs and chain of custody documentation are presented in **Appendix C**.

Groundwater samples were submitted to a laboratory in accordance with National Environmental Laboratory Accreditation Conference (NELAC) requirements and the Department of Defense (DoD) Environmental Laboratory Accreditation Program (ELAP). The samples were analyzed for VOCs (including tentatively identified compounds [TICs] via USEPA Method 624, mercury via USEPA Method 7470A, and total suspended solids (TSS) via USEPA Method SM20 2450D. The general chemistry samples (TSS) were analyzed at the SGS Laboratory, located in Orlando Florida, and the VOC and mercury samples were analyzed at the subcontracted Pace Analytical National Laboratory, located in Mt. Juliet, Tennessee. Validated analytical sampling results for the First Quarter monitoring event are summarized in **Table 6** and are shown on **Figures 5a and 5b**. Data validation reports are presented in **Appendix D**. Raw analytical data are provided under a separate cover.

3.3.2 Quality Assurance/Quality Control Sampling

Quality assurance/quality control (QA/QC) samples were collected during the annual groundwater monitoring event in accordance with the Final Sampling and Analysis Plan (TtEC, 2010a). These samples consisted of field duplicates (collected from RW3-MW3), matrix spike/matrix spike duplicate (MS/MSD) samples, equipment rinsate blank (EB) collected at a rate one per sampling event, and trip blanks (TB) submitted at a rate of one per cooler.

The TB sample contained trace amounts of bromodichloromethane, chloroform, and methylene chloride. Results for bromodichloromethane and methylene chloride were non-detect in the field samples and no qualifications were required. Results for chloroform were qualified as non-detect in field samples GM-38-GW-RW3-MW4-0322, GM-38-GW-RW3-MW3-0322, GM-38-GW-RW3-MW3-DUP-0322, GM-38-GW-TP01-0322, GM-38-GW-RW1-MW1-0322, and GM-38-GW-RW1-MW3-0322, and in the QA/QC sample GM-38-EB-0322. Neither mercury nor TSS were detected in either the EB or the laboratory method blank; no qualification was required.

The MS/MSD recoveries for analyses were within the laboratory QC limits, but the percent recovery for the compounds carbon disulfide, cyclohexane, 1,2-dichloropropane, naphthalene, toluene, VC, total xylenes, and m&p-xylene were outside of the control limits. These eight compounds were non-detect in the parent sample, and no qualifications were required.

The result for 1,1-dichloroethene in sample GM-38-GW-RW3-MW4-0322 was qualified as estimated (J), the non-detect result for methyl cyclohexane was qualified as estimated (UJ), and the non-detect result for 2-chloroethyl vinyl ether was qualified as "X" (exclusion of data recommended because of no recovery for the MS/MSD samples).

For field duplicate samples, the precision between the original sample and its duplicate is evaluated by calculating the relative percent difference (RPD). RPDs for the First Quarter sampling event are presented in the data validation report in **Appendix D**. RPDs for VOC compounds were all less than 50% and did not require any qualification; neither mercury nor TSS were detected in the parent/duplicate pairs, no qualification was required.

3.3.3 Groundwater Concentration Trends

Historical groundwater analytical results through the First Quarter 2022 are presented in **Table 7**. Groundwater analytical results of select VOCs (cis-1,2-DCE, PCE, TCE, and VC) for recovery wells RW-1 and RW-4 for the First Quarter 2022 are presented on **Figures 6 through 8**.

The concentration trends of select VOCs (cis-1,2-DCE, TCE, PCE, and VC) for the eight monitoring wells sampled during the 2022 annual monitoring events are presented on **Figures 9 through 16** and discussed below.

Figure 6 presents concentrations measured at recovery well RW-1. No samples were collected from RW-1 in October and November 2020 because of the rehabilitation and redevelopment of the well, and the replacement of the pump conducted during that time period. TCE concentrations have decreased from initial concentrations in early 2010 [747 micrograms per liter ($\mu\text{g/L}$) measured in April 2010], remaining below 300 $\mu\text{g/L}$ since the latter half of 2012, decreasing to a minimum concentration of 49.3 $\mu\text{g/L}$ in September 2021. TCE concentrations remained stable in in the First Quarter 2022 ranging between concentrations of 54.0 $\mu\text{g/L}$ in February 2022 to 54.4 $\mu\text{g/L}$ in March 2022. Concentrations of cis-1,2-DCE have followed a similar trend, decreasing from a maximum of 160 $\mu\text{g/L}$ in February 2010 to a minimum concentration of 3.1 $\mu\text{g/L}$ in January and February 2022 and have remained below 5.0 $\mu\text{g/L}$ since February 2019. PCE concentrations have also exhibited a decreasing trend over time, with concentrations decreasing from 180 $\mu\text{g/L}$ in February 2010 to a minimum of 14.5 $\mu\text{g/L}$ in July 2021 and have remained below 20 $\mu\text{g/L}$ since April 2020. Concentrations of VC have decreased below initial concentrations in 2010. After reaching a maximum concentration of 61 $\mu\text{g/L}$ in February 2010, VC concentrations have remained below 5.0 $\mu\text{g/L}$ since the final quarter of 2011 and below 1.0 $\mu\text{g/L}$ since June 2013. VC was not detected during the current reporting period.

Figure 7 and **Figure 8** present concentrations measured at recovery well RW-4. Well RW-4 was brought online in place of well RW-3 in April 2021. Sampling of the well was initiated in May 2021 following stabilization of the pumping rate via the wireless communication with the GWTP. Measured TCE concentrations in the First Quarter 2022 ranged from 752 $\mu\text{g/L}$ in January 2022 to a maximum of 784 $\mu\text{g/L}$ in February 2022. Measured PCE concentrations in the First Quarter 2022 ranged from 5.2 $\mu\text{g/L}$ in January to 6.3 $\mu\text{g/L}$ in February. Measured cis-1,2-DCE concentrations ranged from non-detect in February to 1.4 $\mu\text{g/L}$ in January. VC was not detected during the current reporting period.

Figure 9 presents concentrations measured at RW1-MW1. TCE concentrations have varied widely since the initial sampling in May 2005 (53.6 $\mu\text{g/L}$). The concentration of TCE in March 2022 (73.2 $\mu\text{g/L}$) was higher than the concentration reported in May 2005, but less than the maximum concentration observed in September 2013 (175 $\mu\text{g/L}$). Concentrations of cis-1,2-DCE have remained consistently below 5.0 $\mu\text{g/L}$ since September 2018 until September 2021, when a slightly increased concentration of 7.06 $\mu\text{g/L}$ was measured; this concentration is well below the initial concentration observed in May 2005 (78.6 $\mu\text{g/L}$) and has since decreased for the March 2022 sampling event (4.33 $\mu\text{g/L}$). PCE concentrations have remained consistently below 1.0 $\mu\text{g/L}$; PCE was not detected in March 2022. VC has not been detected since the September 2011 sampling event.

Figure 10 presents concentrations measured at RW1-MW3. TCE concentrations have consistently remained below 5.0 $\mu\text{g/L}$ since monitoring was initiated in January 2010; TCE was not detected in September 2021 but was detected again in March 2022 at a concentration (3.42 $\mu\text{g/L}$) less than 5.0 $\mu\text{g/L}$. Concentrations of cis-1,2-DCE and PCE have consistently remained below 1.0 $\mu\text{g/L}$ since January 2010. VC has not been detected during any sampling event.

Figure 11 presents concentrations measured at RW2-MW1. TCE concentrations have varied since the initial sampling in May 2005 (37.6 $\mu\text{g/L}$). TCE was detected at a concentration of 2.45 $\mu\text{g/L}$ in March 2022. The concentration of cis-1,2-DCE measured in March 2022 (3.90 $\mu\text{g/L}$) was above the initial concentration observed in May 2005 (non-detect) but below the maximum concentration observed in the March 2016 (15.3 $\mu\text{g/L}$). PCE and VC have not been detected during any sampling events.

Figure 12 presents concentrations measured at RW3-MW1. TCE concentrations have decreased since reaching a maximum in November 2010 (77.6 $\mu\text{g/L}$). The TCE concentration in March 2022 (16.9 $\mu\text{g/L}$) was also below the initial concentration observed in January 2010 (35.0 $\mu\text{g/L}$) and is the lowest measured concentration to date. Cis-1,2-DCE has not been detected since September 2014. PCE concentrations have remained consistently near or below 2.0 $\mu\text{g/L}$ since May 2005, with a concentration of 2.50 $\mu\text{g/L}$ measured in October 2020, equal to the previous maximum in March 2016. The measured concentration of PCE in March 2022 was 1.44 $\mu\text{g/L}$.

Figure 13 presents concentrations measured at RW3-MW2. The TCE concentration observed in March 2022 (69.2 µg/L) was below the initial concentration observed in January 2010 (160 µg/L), below the maximum concentration observed in April 2010 (211 µg/L), and represents the minimum value measured since June 2012. A steadily decreasing trend in the measured concentration of TCE from 131 µg/L (September 2019) to 69.2 µg/L in March 2022 is noted. Concentrations of cis-1,2-DCE at this location have consistently remained below 2.0 µg/L. PCE has been detected at this location at trace levels throughout most of the period of record, with concentrations ranging from non-detect in March 2022 to 0.66 J µg/L in March 2016.

Figure 14 presents concentrations measured at RW3-MW3. TCE concentrations have decreased since the maximum concentration was observed in June 2013 (410 µg/L). The TCE concentration observed in March 2022 (146 J µg/L) was well below both the initial concentration observed in January 2010 (350 µg/L) and the maximum concentration measured in June 2013 (410 µg/L). Concentrations of cis-1,2-DCE have remained near or below 2.0 µg/L since March 2012. PCE has remained below 1.0 µg/L for all events.

Figure 15 presents concentrations measured at RW3-MW4. TCE concentrations have decreased since the initial sampling event in January 2010 (21 µg/L), with a concentration of 5.24 µg/L in March 2022. PCE was detected for the first time in September 2015 at a concentration of 0.31 J µg/L but has not been detected since the March 2016 sampling event. Cis-1,2-DCE has been detected infrequently since the initial sampling event in January 2010 (0.46 µg/L) and was detected in March 2022 at an estimated concentration of 0.243 J µg/L.

Figure 16 presents concentrations measured at TP-01. TCE concentrations have steadily decreased since the sampling event in March 2018. The TCE concentration observed in March 2022 (12.4 µg/L) was well below the initial and maximum concentration observed in January 2010 (65 µg/L). Concentrations of cis-1,2-DCE have generally decreased from an initial value of 190 µg/L in January 2010 to the current concentration measured in March 2022 (1.99 µg/L). PCE has remained below 1.0 µg/L since September 2013 and had not been detected since March 2017 until a detection of 0.680 J µg/L in March 2021 and the most current measurement of 1.84 J µg/L in March 2022.

4.0 CONCLUSIONS AND RECOMMENDATIONS

The objective of the groundwater treatment system at GM-38 is to remove contaminant mass and reduce elevated VOC concentrations to levels similar to those in the surrounding aquifer, and in doing so minimize the impacts on downgradient water supply wells and currently unaffected portions of the aquifer. Based on the removal of VOCs by the GWTP and decreasing contaminant concentration trends observed in the recovery wells and several of the monitoring wells, progress toward these goals is indicated. Based on the concentrations in the groundwater wells, the GWTP should continue to be operated. Groundwater sampling frequency for the eight monitoring wells is currently performed on a semi-annual basis in accordance with the O&M Manual. Water levels for the 14 monitoring wells continue to be measured on a quarterly basis.


5.0 REFERENCES

Tetra Tech, Inc. (Tetra Tech), 2014. *Capture Zone Evaluation and Path Forward, GM-38 Area Groundwater Treatment Plant, Naval Weapons Industrial Reserve Plant, Bethpage, New York.* March.


Tetra Tech EC, Inc. (TtEC), 2010. *Final Operation, Maintenance & Monitoring Plan for Groundwater Treatment Plant GM-38 Area Groundwater Remediation, Naval Weapons Industrial Reserve Plant, Bethpage, New York.* April.

Tetra Tech EC, Inc. (TtEC), 2010a. *Final Sampling and Analysis Plan (Field Sampling Plan and Quality Assurance Project Plan), UFP-SAP for Operations, Maintenance, and Monitoring of the Groundwater Treatment Plant, GM-38 Area, Naval Weapons Industrial Reserve Plant, Bethpage, New York.* September.

FIGURES




GM-38 AREA



Source: U.S.G.S. Topographic Maps (7.5 Minute)
Amityville, Freeport, Hicksville, Huntington, NY Quadrangles

U.S. Navy RAC Engineering Field Activity, Northeast GM-38 Area (Offsite) NWIRP Bethpage Bethpage, NY
Figure 1 Site Location Map




LEGEND
 - - - - - VAPOR PIPING
 _____ LIQUID PIPING

SOURCE:
 TETRA TECH ENGINEERING CORPORATION, PC, 2006
 UPDATED BY KGS, JANUARY 2022.


PROCESS FLOW DIAGRAM			
NWIRP BETHPAGE GM-38 AREA BETHPAGE, NEW YORK			
KOMAN Government Solutions, LLC 180 Gordon Drive, Suite 110, Exton, PA 19341			
SCALE NOT TO SCALE	DATE 1/27/2022	FIGURE 2	

Legend


- Monitoring Well (Monitored by Navy)
- Monitoring Well (Monitored by Northrop Grumman)
- ⊠ Recovery Well
- ⊠ Injection Well




(SEAFORD-OYSTER BAY EXPRESSWAY - RTE 135)



SITE MAP			
NWIRP BETHPAGE GM-38 AREA BETHPAGE, NEW YORK			
KOMAN Government Solutions, LLC 180 Gordon Drive, Suite 110, Exton, PA 19341			
SCALE	DATE	FIGURE	
SEE BARSCALE	01/15/2018	3	





RW-4	1/6/22	2/11/22	3/18/22
cis 1,2-Dichloroethene	1.4 J	ND	1.38 J
Tetrachloroethene	5.2	6.3	6.20 J
Trichloroethene	752 D	784	781
Vinyl Chloride	ND	ND	ND

RW-1	1/6/22	2/11/22	3/18/22
cis 1,2-Dichloroethene	3.1	3.1	3.16 J
Tetrachloroethene	14.9	15.4	15.5
Trichloroethene	54.2	54.0	54.4
Vinyl Chloride	ND	ND	ND

Legend



☒ Recovery Well

Notes:

All results in µg/L

J - Estimated result between laboratory method detection limit and reporting limit

ND - Not detected above laboratory method detection limit.


0 350
APPROXIMATE SCALE IN FEET

**1st QUARTER 2022
GROUNDWATER ANALYTICAL MAP
SELECT VOC CONCENTRATIONS**

**NWIRP BETHPAGE GM-38 AREA
BETHPAGE, NEW YORK**

KOMAN Government Solutions, LLC
180 Gordon Drive, Suite 110, Exton, PA 19341

SCALE	DATE	FIGURE
SEE BARSCALE	6/30/2022	5a



- Legend**
- Monitoring Well (Monitored by Navy)
 - Monitoring Well (Monitored by Northrop Grumman)
 - ⊠ Recovery Well
 - ⊞ Injection Well
 - J Estimated value
 - ND Not Detected above laboratory method detection limit
 - NS Not Sampled
 - DCE Dichloroethene
 - PCE Tetrachloroethane
 - TCE Trichloroethane
 - VC Vinyl Chloride

Notes:
 All concentrations reported in µg/L.

Monitoring wells were sampled on a semi-annual basis. Recovery well RW-1 was sampled on a monthly basis. Recovery well RW-3, previously an active extraction well sampled on a monthly basis, was off-line from July 2015 until June 2018. RW-3 is now sampled on a monthly basis.

RW3-MW2	3/10/2022
cis-1,2-DCE	0.774 J
PCE	ND
TCE	69.2
VC	ND

RW3-MW1	3/9/2022
cis-1,2-DCE	ND
PCE	1.44 J
TCE	16.9
VC	ND

RW3-MW4	3/9/2022
cis-1,2-DCE	0.243 J
PCE	ND
TCE	5.24
VC	ND

RW3-MW3	3/9/2022	3/9/2022 Dup
cis-1,2-DCE	0.595 J	0.581 J
PCE	0.336 J	0.302 J
TCE	146 J	149 J
VC	ND	ND




RW2-MW1	3/9/2022
cis-1,2-DCE	3.90
PCE	ND
TCE	2.45
VC	ND

TP-01	3/10/2022
cis-1,2-DCE	1.99
PCE	1.84 J
TCE	12.4
VC	ND

RW1-MW3	3/10/2022
cis-1,2-DCE	0.273 J
PCE	0.343 J
TCE	3.42
VC	ND

RW1-MW1	3/10/2022
cis-1,2-DCE	4.33
PCE	ND
TCE	73.2
VC	ND

RW-1	1/6/2022	2/11/2022	3/18/2022
cis-1,2-DCE	3.10	3.10	3.16 J
PCE	14.9	15.4	15.5
TCE	54.2	54.0	54.4
VC	ND	ND	ND



1st QUARTER 2022 GROUNDWATER ANALYTICAL MAP SELECT VOC CONCENTRATIONS

NWIRP BETHPAGE GM-38 AREA BETHPAGE, NEW YORK

KOMAN Government Solutions, LLC
 180 Gordon Drive, Suite 110, Exton, PA 19341

SCALE	DATE	FIGURE	
SEE BARSCALE	06/24/2022	5b	

Figure 6
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Concentration Trends of Select VOCs
RW1




Figure 7
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Concentration Trends of Select VOCs
RW4




Figure 8
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Concentration Trends of Select VOCs

RW4




Figure 9
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Concentration Trends of Select VOCs
RW1-MW1




Figure 10
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Concentration Trends of Select VOCs
RW1-MW3




Figure 11
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Concentration Trends of Select VOCs
RW2-MW1




Figure 12
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Concentration Trends of Select VOCs
RW3-MW1




Figure 13
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Concentration Trends of Select VOCs
RW3-MW2




Figure 14
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Concentration Trends of Select VOCs
RW3-MW3




Figure 15
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Concentration Trends of Select VOCs
RW3-MW4





Figure 16
GM-38 Area Groundwater Remediation
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Concentration Trends of Select VOCs
TP-01



TABLES

Table 1
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Discharge Monitoring Results
First Quarter 2022

SPDES Parameters ¹	Daily Maximum Goal	Units	January 2022										
			RW-1	RW-3	RW-4	Combined Influent	Treated Effluent	Treated Effluent DUPLICATE	Air Stripper Effluent (ASE)	Bag Filter Effluent (BFE)	Liquid Carbon 1 Effluent (LC1)	Liquid Carbon 2 Effluent (LC2)	Liquid Carbon 3 Effluent (LC3)
Process Stream													
Well Depth		ft	445	530	655*	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Screened Interval		ft	335-395 410-430	392-412 442-504	550-650*	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Sampling Date	N/A		1/6/22										
Average Flowrate	1100	GPM	660	0	266	925	986	NR	NR	936	NR	NR	NR
Total Flow	N/A	gallons	26,405,666	0	10,626,279	37,031,944	39,461,845	NR	NR	37,443,331	NR	NR	NR
pH	5.5 - 8.5	SU	5.55	NS	6.23	5.75	7.13	7.11	6.83	6.94	7.11	7.10	7.09
Chloroform	5	µg/L	ND (0.90)	NS	ND (2.3)	--	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
1,1-Dichloroethane	5	µg/L	0.97 J	NS	ND (2.3)	0.69	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
1,2-Dichloroethane	0.6	µg/L	ND (0.75)	NS	ND (1.9)	--	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)
1,1-Dichloroethene	5	µg/L	0.60 J	NS	1.9 J	0.973 J	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)
cis 1,2-Dichloroethene	5	µg/L	3.1	NS	1.4 J	2.61	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)
trans 1,2-Dichloroethene	5	µg/L	ND (0.90)	NS	ND (2.3)	--	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
Tetrachloroethene	5	µg/L	14.9	NS	5.2	12.12	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
1,1,1-Trichloroethane	5	µg/L	ND (0.90)	NS	ND (2.3)	--	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
Trichloroethene	5	µg/L	54.2	NS	752 D	254.4	ND (0.90)	ND (0.90)	2.9	2.4	ND (0.90)	ND (0.90)	ND (0.90)
1,1,2-Trichlorotrifluoroethane	5	µg/L	ND (0.90)	NS	3.1 J	0.89	ND (1.5)	ND (1.5)	ND (1.5)	ND (1.5)	ND (1.5)	ND (1.5)	ND (1.5)
Vinyl Chloride	2	µg/L	ND (0.90)	NS	ND (2.3)	--	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
1,4-Dioxane	--	µg/L	0.747	NS	4.49	1.82	ND (0.20)	ND (0.20)	NS	NS	NS	NS	NS
Mercury	0.00025	mg/L	ND (0.00015)	NS	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)
Total Suspended Solids (TSS)	N/A	mg/L	ND (2.0)	NS	13.5	ND (2.0)	ND (2.0)	ND (2.0)	ND (2.0)	ND (2.0)	ND (2.0)	ND (2.0)	ND (2.0)

Table 1
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Discharge Monitoring Results
First Quarter 2022

SPDES Parameters ¹	Daily Maximum Goal	Units	February 2022										
			RW-1	RW-3	RW-4	Combined Influent	Treated Effluent	Treated Effluent DUPLICATE	Air Stripper Effluent (ASE)	Bag Filter Effluent (BFE)	Liquid Carbon 1 Effluent (LC1)	Liquid Carbon 2 Effluent (LC2)	Liquid Carbon 3 Effluent (LC3)
Process Stream													
Well Depth		ft	445	530	655*	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Screened Interval		ft	335-395 410-430	392-412 442-504	550-650*	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Sampling Date	N/A		2/11/22										
Average Flowrate	1100	GPM	506	0	368	874	923	NR	NR	864	NR	NR	NR
Total Flow	N/A	gallons	19,932,300	0	14,512,800	34,445,100	36,375,000	NR	NR	34,040,700	NR	NR	NR
pH	5.5 - 8.5	SU	5.42	NS	6.37	5.82	7.16	7.15	6.87	6.90	7.15	7.15	7.16
Chloroform	5	µg/L	ND (0.90)	NS	8.3	3.50	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
1,1-Dichloroethane	5	µg/L	1.0	NS	ND (4.5)	0.58	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
1,2-Dichloroethane	0.6	µg/L	ND (0.75)	NS	ND (3.8)	--	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)
1,1-Dichloroethene	5	µg/L	0.750 J	NS	ND (3.8)	0.43 J	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)
cis 1,2-Dichloroethene	5	µg/L	3.1	NS	ND (3.8)	1.79	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)	ND (0.75)
trans 1,2-Dichloroethene	5	µg/L	ND (0.90)	NS	ND (4.5)	--	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
Tetrachloroethene	5	µg/L	15.4	NS	6.3	11.57	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
1,1,1-Trichloroethane	5	µg/L	ND (0.90)	NS	ND (4.5)	--	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
Trichloroethene	5	µg/L	54.0	NS	784	361.6	ND (0.90)	ND (0.90)	3.4	3.3	ND (0.90)	ND (0.90)	ND (0.90)
1,1,2-Trichlorotrifluoroethane	5	µg/L	ND (1.5)	NS	ND (7.5)	--	ND (1.5)	ND (1.5)	ND (1.5)	ND (1.5)	ND (1.5)	ND (1.5)	ND (1.5)
Vinyl Chloride	2	µg/L	ND (0.90)	NS	ND (4.5)	--	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)	ND (0.90)
1,4-Dioxane	--	µg/L	0.28 J	NS	3.3	1.55	ND (0.20)	ND (0.20)	NS	NS	NS	NS	NS
Mercury	0.00025	mg/L	ND (0.00015)	NS	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)	ND (0.00015)
Total Suspended Solids (TSS)	N/A	mg/L	ND (2.5)	NS	ND (2.5)	ND (2.0)	ND (2.5)	ND (2.5)	ND (2.5)	ND (2.5)	ND (2.5)	ND (2.5)	ND (2.5)

Table 1
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Discharge Monitoring Results
First Quarter 2022

SPDES Parameters ¹	Daily Maximum Goal	Units	March 2022											
			RW-1	RW-3	RW-4	Combined Influent	Treated Effluent	Treated Effluent DUPLICATE	Air Stripper Effluent (ASE)	Bag Filter Effluent (BFE)	Liquid Carbon 1 Effluent (LC1)	Liquid Carbon 2 Effluent (LC2)	Liquid Carbon 3 Effluent (LC3)	
Process Stream														
Well Depth		ft	445	530	655*	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Screened Interval		ft	335-395 410-430	392-412 442-504	550-650*	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A	N/A
Sampling Date	N/A		3/18/22											
Average Flowrate	1100	GPM	498	0	395	894	942	NR	NR	882	NR	NR	NR	NR
Total Flow	N/A	gallons	20,634,100	0	16,374,600	37,008,700	39,014,300	NR	NR	36,509,200	NR	NR	NR	NR
pH	5.5 - 8.5	SU	NS	NS	6.28	6.28	6.77	6.75	7.07	7.07	6.74	6.72	6.67	6.67
Chloroform	5	µg/L	0.248 J	NS	ND (5.0)	0.14	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)
1,1-Dichloroethane	5	µg/L	0.958 J	NS	ND (5.0)	0.53	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)
1,2-Dichloroethane	0.6	µg/L	ND (1.0)	NS	ND (5.0)	--	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)
1,1-Dichloroethene	5	µg/L	0.523 J	NS	1.84 J	1.11 J	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)
cis 1,2-Dichloroethene	5	µg/L	3.16 J	NS	1.38 J	2.37	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)
trans 1,2-Dichloroethene	5	µg/L	ND (1.0)	NS	ND (5.0)	--	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)
Tetrachloroethene	5	µg/L	15.5	NS	6.20 J	11.39	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)
1,1,1-Trichloroethane	5	µg/L	0.371 J	NS	ND (5.0)	0.207 J	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)
Trichloroethene	5	µg/L	54.4	NS	781	375.9	ND (1.0)	ND (1.0)	3.90 J	3.80 J	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)
1,1,2-Trichlorotrifluoroethane	5	µg/L	ND (1.0)	NS	4.92 J	2.2 J	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)
Vinyl Chloride	2	µg/L	ND (1.0)	NS	ND (5.0)	--	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)
1,4-Dioxane	--	µg/L	2.2 J	NS	16	8.31	0.17	0.14	NS	NS	NS	NS	NS	NS
Mercury	0.00025	mg/L	ND (0.00010)	NS	ND (0.00010)	ND (0.00010)	ND (0.00010)	ND (0.00010)	ND (0.00010)	ND (0.00010)	ND (0.00010)	ND (0.00010)	ND (0.00010)	ND (0.00010)
Total Suspended Solids (TSS)	N/A	mg/L	ND (1.0)	NS	ND (1.0)	ND (1.0)	ND (1.0)	ND (1.0)	13.4	ND (1.0)	1.2	ND (1.0)	ND (1.0)	ND (1.0)

Notes:

J - Estimated result between laboratory method detection limit and reporting limit
 NA - Not Applicable
 ND - Not detected above laboratory method detection limit. Limit of detection (LOD) given in parentheses.
 NR - Not Recorded
 NS - Not Sampled
 gpm - gallons per minute
 * Design Depths
 -- LOD for non-detect combined well influent not applicable; RW-4 sample required dilution.

(1) Wastewater discharge equivalence permit renewed on 18 August 2017. Discharge limits established for 10 years. Chloroform, 1,4-dioxane and 1,1,2-trichlorotrifluoroethane are now monitored under the new permit.

Table 2
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Air Sampling Results
First Quarter 2022

DAR Parameters	Discharge Goal ⁽³⁾	Units	January 2022				
			Influent (VC11)	Effluent	Effluent Duplicate	VC12	VC23
Process Stream							
Sampling Date			1/6/22				
Average Flowrate	N/A	CFM	NR	9,228			
Total Flow ⁽¹⁾	N/A	ft ³	NR	369,271,758	NR	NR	NR
Total Flow ⁽²⁾	N/A	m ³	NR	10,456,612	NR	NR	NR
1,2-Dichloroethane	N/A	µg/m ³	ND	ND	ND	2.2 J	ND
cis 1,2-Dichloroethene	≤ 100,000 ⁽⁴⁾	µg/m ³	14	40	41	40	40
trans 1,2-Dichloroethene		µg/m ³	ND	ND	ND	ND	ND
1,2-Dichloroethene (total)	≤ 100,000	µg/m ³	14	40	40	40	40
Toluene	N/A	µg/m ³	2.5 J	ND	ND	ND	ND
Total Xylene	N/A	µg/m ³	ND	ND	ND	ND	ND
1,1,2-Trichloroethane	N/A	µg/m ³	ND	ND	ND	ND	ND
Trichloroethene	≤ 2600	µg/m ³	1500	ND	ND	1800	ND
Vinyl Chloride	≤ 560	µg/m ³	ND	ND	ND	ND	ND
Tetrachloroethene	≤ 5100	µg/m ³	64	ND	8.4	4.6 J	ND

Notes:

NA - Not applicable

ND - Not detected

NR - Not recorded

SGC - Short-term Guideline Concentration

µg/m³ - micrograms per cubic meter

CFM - cubic feet per minute

DAR - Division of Air Resources

(1) Total Flow (ft³) = avg flowrate (cfm) * operational time (min)

(2) Total Flow (m³) = total flow (ft³) * (0.3048³)m³/ft³

(3) Discharge goal approved by NYSDEC's letter dated 10/31/2013.

(4) Discharge goal is for total 1,2-Dichloroethene.

Table 2
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Air Sampling Results
First Quarter 2022

DAR Parameters	Discharge Goal ⁽³⁾	Units	February 2022				
			Influent (VCI1)	Effluent	Effluent Duplicate	VC12	VC23
Process Stream							
Sampling Date			2/11/22				
Average Flowrate	N/A	CFM	NR	9,397			
Total Flow ⁽¹⁾	N/A	ft ³	NR	370,348,287	NR	NR	NR
Total Flow ⁽²⁾	N/A	m ³	NR	10,487,096	NR	NR	NR
1,2-Dichloroethane	N/A	µg/m ³	ND	ND	ND	2.7 J	ND
cis 1,2-Dichloroethene	≤ 100,000 ⁽⁴⁾	µg/m ³	36	55	51	45	56
trans 1,2-Dichloroethene		µg/m ³	ND	ND	ND	ND	ND
1,2-Dichloroethene (total)	≤ 100,000	µg/m ³	36	56	52	44	56
Toluene	N/A	µg/m ³	2.0 J	ND	ND	ND	ND
Total Xylene	N/A	µg/m ³	ND	ND	ND	ND	ND
1,1,2-Trichloroethane	N/A	µg/m ³	ND	ND	ND	ND	ND
Trichloroethene	≤ 2600	µg/m ³	5500	ND	ND	2300	2.0 J
Vinyl Chloride	≤ 560	µg/m ³	ND	ND	ND	ND	ND
Tetrachloroethene	≤ 5100	µg/m ³	150	ND	ND	4.8 J	ND

Notes:

NA - Not applicable

ND - Not detected

NR - Not recorded

SGC - Short-term Guideline Concentration

µg/m³ - micrograms per cubic meter

CFM - cubic feet per minute

DAR - Division of Air Resources

(1) Total Flow (ft³) = avg flowrate (cfm) * operational time (min)

(2) Total Flow (m³) = total flow (ft³) * (0.3048³)m³/ft³

(3) Discharge goal approved by NYSDEC's letter dated 10/31/2013.

(4) Discharge goal is for total 1,2-Dichloroethene.

Table 2
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Air Sampling Results
First Quarter 2022

DAR Parameters	Discharge Goal ⁽³⁾	Units	March 2022					
			Influent (VCI1)	Effluent	Effluent Duplicate	VC12	VC23	
Process Stream								
Sampling Date					3/18/22			
Average Flowrate	N/A	CFM	NR	9,211				
Total Flow ⁽¹⁾	N/A	ft ³	NR	381,473,565	NR	NR	NR	
Total Flow ⁽²⁾	N/A	m ³	NR	10,802,128	NR	NR	NR	
1,2-Dichloroethane	N/A	µg/m ³	ND	ND	ND	ND	ND	
cis 1,2-Dichloroethene	≤ 100,000 ⁽⁴⁾	µg/m ³	27	40	38	ND	40	
trans 1,2-Dichloroethene		µg/m ³	ND	ND	ND	ND	ND	
1,2-Dichloroethene (total)	≤ 100,000	µg/m ³	27	40	38	ND	40	
Toluene	N/A	µg/m ³	ND	ND	ND	ND	ND	
Total Xylene	N/A	µg/m ³	ND	ND	ND	ND	ND	
1,1,2-Trichloroethane	N/A	µg/m ³	ND	ND	ND	ND	ND	
Trichloroethene	≤ 2600	µg/m ³	4900	ND	ND	43	2.2	J
Vinyl Chloride	≤ 560	µg/m ³	ND	ND	ND	ND	ND	
Tetrachloroethene	≤ 5100	µg/m ³	140	ND	ND	5.2	2.1	J

Notes:

NA - Not applicable

ND - Not detected

NR - Not recorded

SGC - Short-term Guideline Concentration

µg/m³ - micrograms per cubic meter

CFM - cubic feet per minute

DAR - Division of Air Resources

(1) Total Flow (ft³) = avg flowrate (cfm) * operational time (min)

(2) Total Flow (m³) = total flow (ft³) * (0.3048³)m³/ft³

(3) Discharge goal approved by NYSDEC's letter dated 10/31/2013.

(4) Discharge goal is for total 1,2-Dichloroethene.

Table 3
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Stack Emissions
First Quarter 2022

DAR Parameters	Discharge Goal ⁽¹⁾	Units	January 2022	February 2022	March 2022
Sampling Date			1/6/22	2/11/22	3/18/22
Average Flowrate	N/A	CFM	9,228	9,397	9,211
Total Flow	N/A	ft ³	369,271,758	370,348,287	381,473,565
Total Flow	N/A	m ³	10,456,612	10,487,096	10,802,128
Trichloroethene	≤ 0.09	lb/hr	0.00000	0.00000	0.00000
Vinyl Chloride	≤ 0.02	lb/hr	0.00000	0.00000	0.00000
1,2 Dichloroethene	≤ 11	lb/hr	0.00124	0.00193	0.00128
1,2-Dichloroethane	N/A	lb/hr	0.00000	0.00000	0.00000
Toluene	N/A	lb/hr	0.00000	0.00000	0.00000
Total Xylene	N/A	lb/hr	0.00000	0.00000	0.00000
1,1,2-Trichloroethane	N/A	lb/hr	0.00000	0.00000	0.00000
Tetrachloroethene	≤ 0.18	lb/hr	0.00000	0.00000	0.00000

Notes:

NA - Not applicable

lb/hr - pounds per hour

DAR - Division of Air Resources

CFM - Cubic feet per minute

Stack Emissions (lb/hr) = average flowrate (cfm) * (0.3048^{^3})m³/ft³ * conc.(ug/m³) * 1 lb/453592370 ug *
60 min/hr

(1) Discharge goal as approved by NYSDEC's letter dated 31 October 2013.

Table 4
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Groundwater Level Measurements
First Quarter 2022

Monitoring Well ID	Date	Well Elevation (ft amsl)	Total Depth (ft)	Screen Interval (ft)	Depth to Water (ft)	Groundwater Elevation (ft amsl)
RW1-MW1	3/10/2022	85.86	435	395-435	32.71	53.15
RW1-MW2	3/11/2022	87.35	435	395-435	38.72	48.63
RW1-MW3	3/10/2022	80.34	435	395-435	26.55	53.79
RW2-MW1	3/9/2022	90.75	510	470-510	36.44	54.31
RW2-MW2	3/10/2022	90.15	510	470-510	36.11	54.04
RW2-MW3	3/10/2022	89.75	510	470-510	35.75	54.00
RW3-MW1	3/9/2022	92.22	350	330-350	35.94	56.28
RW3-MW2	3/10/2022	91.98	495	475-495	36.68	55.30
RW3-MW3	3/9/2022	92.98	340	320-340	36.45	56.53
RW3-MW4	3/9/2022	92.92	495	475-495	36.90	56.02
TP-01	3/10/2022	85.91	470	450-470	31.47	54.44
IW1-MW1	3/11/2022	89.41	150	20-150	44.81	44.60
RW-1	NA	91.37	340	320-340	NA	NA
RW-3	NA	91.57	495	475-495	NA	NA
RW-4	NA	NA	655*	550-650*	NA	NA

Notes:

amsl - above mean sea level

ft - feet

NA - Not Applicable

* - Design Depths

Table 5
Summary of Final Groundwater Chemistry Data
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Groundwater Chemistry Results
First Quarter 2022

Location	Temp (°C)	pH (SU)	S.C. (uS/cm ³)	DO (mg/L)	ORP (mV)	Turbidity (NTU)	Color (Visual)
RW1-MW1	14.3	5.06	153	0.81	29.5	2.75	Clear
RW1-MW3	13.3	5.31	185	0.22	245.8	3.95	Clear
RW2-MW1	21.3	8.86	155	0.06	149.7	3.24	Clear
RW3-MW1	10.0	4.51	170	3.20	390.5	0.72	Clear
RW3-MW2	10.8	5.08	87	0.71	302.9	1.31	Clear
RW3-MW3	12.5	4.88	128	1.54	343.0	6.70	Clear
RW3-MW4	13.0	4.50	137	0.32	315.2	1.25	Clear
TP-01	12.7	5.99	253	3.56	296.1	0.85	Clear

Notes:

S.C. = Specific Conductance
mS/cm = milliSiemens per centimeter
NTU = nephelometric turbidity units
mg/L = milligrams per liter
°C = degrees celsius
mV = millivolts
SU = standard units
ORP = oxidation/reduction potential

Table 6
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Detected Groundwater Analytical Results
First Quarter 2022

Sample ID	RW1-MW1	RW1-MW3	RW2-MW1	RW3-MW1	RW3-MW2	RW3-MW3	RW3-MW3	RW3-MW4	TP-01	RW-1	RW-4
Sample Date	3/10/2022	3/10/2022	3/9/2022	3/9/2022	3/10/2022	3/9/2022	3/9/2022	3/9/2022	3/10/2022	3/18/2022	3/18/2022
Comments							Duplicate				
VOCS (EPA 624.1) ug/L ⁽¹⁾											
Chloroform	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.248 J	ND
1,1-dichloroethane	4.18	3.83	2.26	ND	0.371 J	1.56	1.61	3.81	0.895 J	0.958 J	ND
1,2-dichloroethane	0.119 J	0.17 J	0.356 J	0.107 J	ND	0.159 J	0.150 J	0.109 J	ND	ND	ND
1,1-dichloroethene	1.39	1.06	0.413 J	ND	ND	0.925 J	1.01	1.00 J	0.339 J	0.523 J	1.84 J
cis-1,2-dichloroethene	4.33	0.273 J	3.90	ND	0.774 J	0.595 J	0.581 J	0.243 J	1.99	3.16 J	1.38 J
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Tetrachloroethene	ND	0.343 J	ND	1.44 J	ND	0.336 J	0.302 J	ND	1.84 J	15.5	6.20 J
1,1,1-trichloroethane	0.673 J	0.767 J	ND	ND	ND	0.320 J	0.302 J	0.686 J	ND	0.371 J	ND
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	73.2	3.42	2.45	16.9	69.2	146 J	149 J	5.24	12.4	54.4	781
Vinyl Chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-Dioxane (EPA 8270D) ug/L	NS	NS	NS	NS	NS	NS	NS	NS	NS	2.2 J	16
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	1.4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Notes:

J = estimated value

J- =biased low estimated value

ND = Not detected above laboratory method detection limit

mg/L = milligrams per liter

µg/L = micrograms per liter

NS = Not Sampled

(1) Samples were analyzed for TCL VOCs (including tentatively identified compounds [TICs]). Only those VOCs detected are presented above.

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW1-MW1															
Sample Date	5/4/2005	7/22/2005	5/27/2009	1/21/2010	4/21/2010	7/28/2010	11/10/2010	3/25/2011	6/14/2011 ⁽¹⁾	6/14/2011	9/28/2011	11/30/2011	3/8/2012	6/6/2012	6/6/2012	8/21/2012
Comments										Duplicate					Duplicate	
Well Depth (Ft)	435															
Screened Interval (Ft)	395-435															
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	30 R
Acrylonitrile	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND
Acetone	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
2-butanone	R	R	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	0.32J	ND	ND	ND	0.17J	ND	NR	NR	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
Dibromochloromethane	NR	NR	ND	NR	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND
Chloroform	ND	0.7J	1.1	ND	0.70J	0.65J	0.56J	0.55J	NR	NR	ND	ND	ND	ND	ND	ND
Chloromethane	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	0.74J	0.79J	3.3	2.9J	2.8	2.8	3.0	3.6	1.6 J	4.2 J	4.0 J	4.1	5.2	4.8	4.3	5.3
1,2-dichloroethane	ND	ND	0.29J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-dichloroethene	1.3	2.8	3.1	1.7J	1.9	1.7	1.7	1.9	0.85 J	2.1 J	2.3 J	2.1	2.7	2.5	2.3	2.8
cis-1,2-dichloroethene	78.6	80.4	180D	130	121	118	108	121	55.8 J	145 J	164	132	179	165	145	167
trans-1,2-dichloroethene	2.0	1.3J	2.8	4J	2.9	2.1	1.3	4.2	0.71 J	2.0 J	2.0 J	1.7	3.0	3.7	2.6	2.4
1,2-dichloropropane	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
1,4-dioxane	1.75J	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
2-hexanone	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
isopropylbenzene	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
styrene	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	ND	ND	0.72J	ND	0.42J	ND	ND	ND	ND	ND	0.36 J	ND	ND	ND	ND	ND
Toluene	ND	0.33J	0.68	ND	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	ND	ND	0.71J	ND	0.52J	0.43J	0.53J	0.79J	ND	0.63 J	1.1 J	0.66 J	0.96 J	0.98 J	0.89 J	0.99 J
1,1,2-trichloroethane	ND	ND	0.58J	NR	ND	ND	ND	ND	NR	NR	ND	0.33 J	ND	ND	ND	ND
Trichloroethene	53.6	52.7	140.0	79.0	116	95.4	84.2	97.6	26.6 J	73.8 J	129	84.5	115	107	102	126
Vinyl chloride	ND	ND	1.6	ND	ND	ND	0.17J	ND	ND	0.38 J	0.29 J	ND	ND	ND	ND	ND
xlenes (total)	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	NR	NR	ND	0.20	<0.20	<0.20	<0.20	<0.20	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	NR	NR	2.8	2.8	6.0	4.0	4.0	4.0	ND	6	ND	11	16	9	5	6

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW1-MW1															
	12/4/2012	3/13/2013	6/19/2013 ⁽²⁾	9/17/2013	12/16/2013	3/24/2014	3/24/2014	9/22/2014	3/25/2015	9/15/2015	3/22/2016	9/14/2016	3/1/2017	9/12/2017	3/5/2018	9/11/2018
Comments							Duplicate									
Well Depth (Ft)	435															
Screened Interval (Ft)	395-435															
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acrylonitrile	ND	ND	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acetone	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	NR	ND	ND	2.0 R	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroform	ND	ND	ND	ND	ND	ND	0.55 J	0.39 J	ND	ND	0.48 J	0.48 J	0.50 J	0.58 J	0.55 J	0.500 J
Chloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND
1,3-dichlorobenzene	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	4.9	5.3	4.8 J	4.7 J	5.2	5.3	5.3	4.1 J	5.1	5.1	6.5	7.0	6.6	7.7	7.5	7.67
1,2-dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.35 J	0.26 J	0.220 J
1,1-dichloroethene	2.0	2.8	ND	2.5	2.6	2.8	2.7	2.2 J	2.2 J	1.9	2.2	1.8	1.6	2.1	2.4	2.16
cis-1,2-dichloroethene	108	91.7	64	86.2 J	84.4	92.6 J	94.2	49.8	39.5	22.0	20.0	16	11	9.8	7.1	3.00
trans-1,2-dichloroethene	1.8	1.7	ND	ND	1.4	1.4	1.4	1.0	0.79 J	0.50 J	0.51 J	0.42 J	0.26 J	0.35 J	0.20 J	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
styrene	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1,1,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	ND	ND	ND	0.35 J	0.67 J	0.33 J	0.37 J	0.76 J	0.30 J	0.62 J	0.67 J	0.45 J	0.46 J	0.59 J	0.50 J	0.300 J
Toluene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	0.88 J	1.1	ND	1.2	1.5	ND	ND	ND	ND	ND	ND	1.0	0.94 J	1	1.2	0.920 J
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	85	101	78	175	128	101	103	94.3	99.5	98.9	114	110	86	110	170	118
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	ND	ND	ND	ND	11	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW1-MW1						
	3/7/2019	9/26/2019	3/11/2020	10/6/2020	3/11/2021	9/29/2021	3/10/2022
Sample Date							
Comments							
Well Depth (Ft)	435						
Screened Interval (Ft)	395-435						
VOCS (EPA 624) ug/L ⁽⁴⁾							
Acrolein	NR	NR	NR	NR	NR	NR	NR
Acrylonitrile	ND	ND	ND	ND	ND	ND	NR
Acetone	NR	NR	NR	NR	NR	NR	ND
Benzene	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	ND
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	NR
Chloroethane	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	NR	NR	NR	NR	NR	NR	NR
Chloroform	0.573 J	ND	0.476 J	0.454 J	0.480 J	ND	ND
Chloromethane	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	ND
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	ND
1,1-dichloroethane	7.89	6.30	6.26	5.54	4.23 J	4.90 J	4.18
1,2-dichloroethane	ND	0.227 J	ND	ND	ND	ND	0.119 J
1,1-dichloroethene	2.19 J	1.79 J	1.76 J	1.81 J	1.44 J	1.25 J	1.39
cis-1,2-dichloroethene	3.86 J	4.70 J	3.86 J	4.33 J	4.77 J	7.06 J	4.33
trans-1,2-dichloroethene	ND	ND	ND	ND	0.228 J	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	NR	NR	NR	NR	NR	ND
isopropylbenzene	NR	NR	NR	NR	NR	NR	ND
methyl acetate	NR	NR	NR	NR	NR	NR	ND
Methylene chloride	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	NR	NR	NR	NR	ND
styrene	NR	NR	NR	NR	NR	NR	ND
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	0.323 BJ	0.401 J	0.308 J	0.395 J	ND	ND	ND
Toluene	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	1.16 J	0.988 J	0.841 J	0.819 J	0.674 J	0.649 J	0.673 J
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	110	95.4	74.1	86.8	82.8	86.2	73.2
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	NR	NR	NR	ND
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	ND	ND	ND	3.7	ND	1.5	1.4

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW1-MW2				RW1-MW3												
	5/4/2005	7/22/2005	5/28/2009	6/18/2013 ⁽²⁾	1/20/2010	4/21/2010	7/29/2010	11/10/2010	3/25/2011	6/14/2011	9/28/2011	11/30/2011	3/8/2012	6/7/2012	8/22/2012	12/7/2012	
Comments																	
Well Depth (Ft)	435				435												
Screened Interval (Ft)	395-435				395-435												
VOCS (EPA 624) ug/L ⁽⁴⁾																	
Acrolein	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	30 R	ND	
Acrylonitrile	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	
Acetone	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
Bromodichloromethane	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
Bromoform	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
Bromomethane	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
2-butanone	R	R	ND	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	
carbon disulfide	ND	ND	ND	NR	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
Dibromochloromethane	NR	NR	ND	ND	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	
Chloroethane	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
2-chloroethylvinyl ether	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	
Chloroform	ND	1.4	ND	ND	0.67J	0.80J	0.47J	0.69J	0.73J	NR	0.97 J	ND	0.73 J	0.64 J	ND	1.2 J	
Chloromethane	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
cyclohexane	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
1,2-dibromo-3-chloro-propane	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
1,2-dibromomethane	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
1,2-dichlorobenzene	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	
1,3-dichlorobenzene	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	
1,4-dichlorobenzene	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	
dichlorodifluoromethane	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
1,1-dichloroethane	4.6	5.5	3.4	3.9	2.4	4.6	1.5	2.3	2.4	9.3	10.1 J	2.1	8.4	5.7	9.4	9.3	
1,2-dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,1-dichloroethene	3.2	12.3	ND	ND	0.42J	1.10	ND	0.28J	ND	1.8	2.2 J	ND	1.8	0.86 J	2.4	2.2	
cis-1,2-dichloroethene	181.0	47.6	160.0	120	0.54J	0.48J	0.36J	0.55J	0.58J	0.59 J	0.43 J	0.55 J	0.68 J	0.33 J	0.56 J	0.46 J	
trans-1,2-dichloroethene	2.5	7.6	2.5	1.9 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,2-dichloropropane	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
cis-1,3-dichloropropene	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
trans-1,3-dichloropropene	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
1,4-dioxane	4.01	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
2-hexanone	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	
isopropylbenzene	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
methyl acetate	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Methylene chloride	1.0	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
4-methyl-2-pentanone	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
styrene	ND	ND	ND	NR	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	0.23 J	ND	ND	
1,2,4-trichlorobenzene	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Tetrachloroethene	ND	134.0	19.0	5.9	ND	049J	ND	ND	ND	0.33 J	0.62 J	ND	0.65 J	0.30 J	0.97 J	0.40 J	
Toluene	0.32J	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
1,1,1-trichloroethane	1.3	1.0	ND	ND	0.41J	0.98J	ND	0.26J	0.33J	1.6	2.7 J	ND	ND	1.1 J	1.9	1.7	
1,1,2-trichloroethane	ND	0.65J	ND	ND	0.62J	0.60J	0.36J	0.55J	0.41J	NR	0.57 J	0.63 J	0.70 J	0.61 J	0.56 J	0.54 J	
Trichloroethene	158.0	198.0	200.0	64	1.2	1.6	0.58J	0.91J	1.0	1.4	1.8 J	1.0 J	2.2	1.3	2.3	1.6	
Vinyl chloride	12.9	187.0	4.1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
xylenes (total)	ND	ND	ND	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	
Mercury (EPA 245.1) ug/L	NR	NR	0.20	NR	NR	<0.20	<0.20	<0.20	<0.20	ND	ND	ND	ND	ND	ND	ND	
TSS (SM20 2540D) mg/L	NR	NR	4.0	NR	NR	8.0	<4.0	<4.0	<4.0	ND	ND	ND	5	ND	ND	ND	

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW1-MW3															
Sample Date	3/14/2013	6/19/2013 ⁽²⁾	9/17/2013	12/17/2013	3/25/2014	9/23/2014	3/25/2015	9/14/2015	3/21/2016	9/14/2016	3/1/2017	9/13/2017	3/5/2018	9/12/2018	3/7/2019	9/26/2019
Comments																
Well Depth (Ft)	435															
Screened Interval (Ft)	395-435															
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR
Acrylonitrile	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acetone	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	0.41 J	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	NR	NR
Chloroform	ND	0.82	ND	ND	0.74 J	0.67 J	0.79 J	ND	0.79 J	0.80 J	0.61 J	0.69 J	0.67 J	0.720 J	0.725 J	ND
Chloromethane	ND	ND	ND	ND	ND	ND	0.29 J	ND	ND	ND	ND	ND	ND	D	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	8.5	10	9.7 J	8.1	8.6	6.1 J	8.1	7.7	7.4	7.0	4.5	4.4	4.1	3.47	4.14 J	2.86 J
1,2-dichloroethane	ND	0.18 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-dichloroethene	1.7	1.8	1.6	1.9	2.1	1.6 J	2.3 J	2.3	2.5	1.7	1.1	1.2	0.97 J	0.950 J	1.08 J	0.888 J
cis-1,2-dichloroethene	0.53 J	0.46 J	0.72 J	0.60 J	0.57 J	0.44 J	0.54 J	0.49 J	0.58 J	0.44 J	0.29 J	0.37 J	0.36 J	0.310 J	0.398 J	0.363 J
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND
2-hexanone	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
styrene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	ND	0.20 J	ND	ND	ND	ND	ND	ND	0.25 J	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	ND	ND	ND	ND	ND	ND	ND	0.50 J	ND	0.35 J	ND	0.22 J	0.23 J	0.290 J	ND	0.397 J
Toluene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	1.4	1.8	1.5	2.0	1.7	1.2 J	1.5	1.6	2.1	1.6	1	1.1	0.87 J	0.810 J	1.27 J	0.711 J
1,1,2-trichloroethane	0.61 J	0.46 J	ND	0.55 J	0.46 J	0.46 J	0.43 J	0.44 J	0.47 J	0.41 J	0.51 J	0.35 J	0.37 J	0.400 J	0.296 J	0.284 J
Trichloroethene	1.9	1.7	2.5	3.2	2.5	1.9	2.0	2.4	4.5	3.5	2.3	2.8	2.2	2.24	4.49 J	3.34 J
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	ND	ND	ND	ND	5	ND	ND	ND	ND	1.8	2.1	5.6	7.1	2.7	8.6	2.2

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW1-MW3					RW2-MW1													
	3/12/2020	10/6/2020	3/11/2021	9/29/2021	3/10/2022	5/4/2005	7/20/2005	5/27/2009	1/18/2010	4/21/2010	7/28/2010	11/3/2010	3/24/2011	6/14/2011	9/27/2011	11/29/2011	3/7/2012	6/6/2012	
Comments																			
Well Depth (Ft)	435					510													
Screened Interval (Ft)	395-435					470-510													
VOCS (EPA 624) ug/L ⁽⁴⁾																			
Acrolein	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND
Acrylonitrile	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND
Acetone	NR	NR	NR	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.15J	0.69J	0.58J	0.30J	NR	0.22 J	0.27 J	0.22 J	ND	
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
2-butanone	NR	NR	NR	NR	NR	R	R	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	
carbon disulfide	NR	NR	NR	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	
Dibromochloromethane	ND	ND	ND	ND	NR	NR	NR	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
2-chloroethylvinyl ether	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	
Chloroform	0.631 J	0.623 J	0.590 J	0.308 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	0.38 J	
Chloromethane	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
1,2-dibromomethane	NR	NR	NR	NR	NR	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
1,2-dichlorobenzene	ND	ND	ND	ND	ND	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	
1,3-dichlorobenzene	ND	ND	ND	ND	ND	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	
1,4-dichlorobenzene	ND	ND	ND	ND	ND	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	
dichlorodifluoromethane	NR	NR	NR	NR	ND	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
1,1-dichloroethane	4.03 J	4.00 J	3.69 J	3.87 J	3.83	0.53J	0.93J	1.2J	0.82J	0.60J	0.58J	0.42J	ND	0.61 J	0.64 J	ND	0.50 J	4.2	
1,2-dichloroethane	ND	ND	ND	0.205 J	0.170 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,1-dichloroethene	1.1 J	1.22 J	1.13 J	1.02 J	1.06	ND	0.58J	0.55J	0.63J	ND	ND	ND	ND	ND	ND	ND	ND	0.55 J	
cis-1,2-dichloroethene	0.39 J	0.275 J	0.377 J	0.295 J	0.273 J	ND	0.55J	1.9	1.0	0.78J	0.80J	0.55J	0.43J	0.56 J	0.32 J	0.39 J	0.34 J	0.32 J	
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
1,4-dioxane	NR	NR	NR	NR	NR	5.34	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	
2-hexanone	NR	NR	NR	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	
isopropylbenzene	NR	NR	NR	NR	ND	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
methyl acetate	NR	NR	NR	NR	ND	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Methylene chloride	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
4-methyl-2-pentanone	NR	NR	NR	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	
styrene	NR	NR	NR	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	NR	NR	NR	NR	
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	ND	NR	ND	ND	ND	ND	NR	ND	ND	ND	ND	
Tetrachloroethene	0.295 J	0.324 J	0.407 J	0.406 J	0.343 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
Toluene	ND	ND	ND	ND	ND	ND	0.85J	1.0	ND	0.52J	0.49J	0.50J	ND	NR	0.24 J	0.29 J	0.19 J	ND	
1,1,1-trichloroethane	0.754 J	0.817 J	0.641 J	0.753 J	0.767 J	ND	0.37J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
1,1,2-trichloroethane	0.312 J	0.346 J	0.381 J	0.429 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	
Trichloroethene	3.21 J	3.13 J	3.06 J	ND	3.42	37.6	34.6	12.0	15.0	0.42J	ND	ND	1.7	1.6	0.89 J	0.67 J	0.67 J	9.0	
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	
xylenes (total)	NR	NR	NR	NR	ND	ND	1.4J	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	NR	NR	0.05J	NR	<0.20	<0.20	<0.20	<0.20	ND	ND	ND	ND	ND	
TSS (SM20 2540D) mg/L	ND	2.3	3.9	3.8	ND	NR	NR	2260.0	NR	58.0	<4.0	<4.0	<4.0	181	5	36	6	25	

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW2-MW1															
Sample Date	8/21/2012	12/7/2012	3/13/2013	6/17/2013 ⁽²⁾	9/17/2013	12/17/2013	12/17/2013	3/25/2014	9/23/2014	3/26/2015	9/14/2015	3/21/2016	3/21/2016	9/15/2016	3/1/2017	9/13/2017
Comments							Duplicate						Duplicate			
Well Depth (Ft)	510															
Screened Interval (Ft)	470-510															
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	30 R	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acrylonitrile	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acetone	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Benzene	ND	0.68 J	0.54 J	ND	0.59 J	ND	ND	0.21 J	0.21 J	0.56 J	ND	ND	0.18 J	ND	0.51 J	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	1.8 J	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	7.0 J	1.6 J	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	ND	NR	ND	2.0 R	2.0 R	ND	ND	ND	ND	ND	ND	ND	NR	ND
Chloroform	ND	ND	ND	2.9	ND	ND	ND	2.8 J	1.5	0.46 J	2.2	3.4	3.5	2.4	0.25 J	2
Chloromethane	ND	ND	ND	ND	ND	ND	ND	0.68 J	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	4.8	0.58 J	0.52 J	7.0	ND	5.8	6.4	5.1	ND	2.1	6.3	8.7	8.5	6.4	1.7	6.6
1,2-dichloroethane	ND	ND	ND	1.3	ND	1.9 J	1.7 J	1.3	0.69 J	0.41 J	1.4	1.4	1.3	0.93 J	ND	0.71 J
1,1-dichloroethene	0.95 J	0.19 J	ND	1.9	ND	2.6	2.6	1.8	1.3 J	0.61 J	2.6	3.7	3.4	1.6	0.27 J	1.3
cis-1,2-dichloroethene	0.39 J	0.33 J	0.29 J	7.7	0.77 J	11.0 J	11.1 J	8.0	4.0	2.6	13.3	15.3	15.0	6.1	1.3	2.6
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND
2-hexanone	NR	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
styrene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Toluene	ND	0.27 J	ND	ND	0.31 J	ND	ND	ND	ND	0.26 J	ND	0.20 J	ND	ND	ND	ND
1,1,1-trichloroethane	0.33 J	ND	ND	0.84	ND	0.94 J	0.94 J	ND	0.39 J	ND	ND	ND	ND	0.56 J	ND	0.49 J
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	20.8	0.73 J	0.67 J	14	1.5	34.6	33.5	23.4	18.3	4.3	27.5	43.9	44.2	18	2.1	8.6
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	12	10	ND	13	12	30	24	12	6	17	11	24	26	3.8	13.8	8.7

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW2-MW1									RW2-MW2			RW2-MW3			
	3/5/2018	9/11/2018	3/7/2019	9/25/2019	3/12/2020	10/6/2020	3/11/2021	9/29/2021	3/9/2022	5/4/2005	7/21/2005	6/17/2013 ⁽²⁾	5/3/2005	7/20/2005	5/28/2009	6/18/2013 ⁽²⁾
Sample Date																
Comments																
Well Depth (Ft)	510									510			510			
Screened Interval (Ft)	470-510									470-510			470-510			
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	30 R	NR
Acrylonitrile	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
Acetone	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND
Benzene	ND	0.250 J	ND	ND	0.233 J	0.208 J	ND	ND	0.113 J	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	R	R	ND	R	R	ND	ND
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	NR	ND	ND	ND	NR
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Chloroform	1.0	0.550 J	2.03 J	ND	ND	ND	ND	ND	ND	ND	ND	0.55	ND	ND	ND	ND
Chloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	NR	ND	ND	ND	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	NR	ND	ND	ND	NR
1,2-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	ND	NR
1,3-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	ND	NR
1,4-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	ND	NR
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	ND	NR	NR	NR	NR	NR	ND	NR
1,1-dichloroethane	6.5	2.75	7.81	6.03	2.18 J	2.38	2.36 J	2.31 J	2.26	ND	0.78J	4.9	0.68J	0.31J	1.4	7.4
1,2-dichloroethane	0.39 J	0.330 J	0.552 J	0.627 J	0.26 J	0.393 J	0.372 J	0.474 J	0.356 J	ND	ND	0.32 J	ND	ND	ND	ND
1,1-dichloroethene	1.5	0.470 J	1.67 J	1.87 J	0.269 J	0.532 J	0.479 J	0.554 J	0.413 J	ND	0.41J	0.72	ND	ND	0.42J	ND
cis-1,2-dichloroethene	1.2	1.09	2.42 J	7.18	1.66 J	4.01 J	4.56 J	3.77 J	3.90	0.33J	0.41J	4.6	0.40J	0.66J	2.3	ND
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	7.45J	NR	NR	7.42J	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	NR	NR	NR	NR	ND	NR
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	NR	NR	NR	NR	ND	NR
Methylene chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND
styrene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	NR	ND	ND	ND	NR
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	NR
Tetrachloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Toluene	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.33J	0.53J	ND	ND	0.50J	0.39J	ND
1,1,1-trichloroethane	0.43 J	ND	0.761 J	0.712 J	ND	ND	ND	ND	ND	ND	ND	0.34 J	ND	ND	ND	ND
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	D	ND	ND	ND	ND	ND	ND
Trichloroethene	7.1	2.61	9.65	15.7	1.49 J	2.82 J	2.86 J	ND	2.45	7.8	13.8	12	16.2	20.6	18.0	60
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	NR	ND	ND	ND	NR
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	ND	NR
TSS (SM20 2540D) mg/L	12.1	7.6	24.2	14	36.2	116	2.7	18.3	ND	NR	NR	NR	NR	NR	14.8	NR

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW3-MW1															
Sample Date	1/19/2010	4/22/2010	7/29/2010	11/9/2010	3/25/2011	3/25/2011	6/14/2011	9/27/2011	11/30/2011	11/30/2011	3/7/2012	6/7/2012	8/22/2012	12/6/2012	3/14/2013	6/20/2013 ⁽²⁾
Comments						Duplicate				Duplicate						
Well Depth (Ft)	350															
Screened Interval (Ft)	330-350															
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	30 R	ND	ND	NR
Acrylonitrile	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	NR
Acetone	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Benzene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
carbon disulfide	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	ND	0.19J	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	NR
Chloroform	ND	ND	ND	0.20J	ND	ND	NR	ND	ND	ND	ND	ND	ND	0.63 J	ND	ND
Chloromethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	NR
1,3-dichlorobenzene	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	NR
1,4-dichlorobenzene	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	NR
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	1.6	1.5	1.7	1.4	1.3	1.3	1.1	1.0 J	0.96 J	0.93 J	0.90 J	0.80 J	0.87 J	0.98 J	1.2	ND
1,2-dichloroethane	0.27J	ND	ND	ND	ND	ND	ND	0.57 J	ND	ND	0.43 J	ND	ND	0.50 J	ND	ND
1,1-dichloroethene	1.2	1.3	1.2	1.2	1.2	1.1	0.85 J	0.65 J	0.64 J	0.66 J	0.47 J	0.19 J	0.54 J	0.65 J	0.68 J	ND
cis-1,2-dichloroethene	0.37J	ND	0.32J	0.45J	0.47J	0.45J	0.48 J	0.31 J	0.36 J	0.43 J	0.37 J	0.39 J	0.36 J	0.44 J	0.38 J	ND
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
styrene	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	0.49J	0.81J	0.73J	1.5	1.4	1.6	1.2	1.3 J	1.0	1.1	1.0	0.33 J	ND	0.44 J	1.6	1.8 J
Toluene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	0.26 J	ND	ND	ND	ND
1,1,1-trichloroethane	ND	0.98J	0.84J	1.2	1.1	1.1	0.78 J	1.0 J	0.59 J	0.63 J	0.58 J	0.54 J	0.42 J	0.34 J	0.49 J	ND
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	35.0	53.2	52.3	77.6	76.2	77.9	63.1	72.4 J	51.0	55.2	59.0	42.5	37.7	42.8	46.6	49
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	NR	<0.20	<0.20	<0.20	<0.20	<0.20	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	NR	<4.0	<4.0	<4.0	<4.0	<4.0	5160	ND	ND	ND	NR	17	ND	ND	16	ND

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW3-MW1															
Sample Date	6/20/2013 ⁽²⁾	9/18/2013	12/17/2013	3/25/2014	9/23/2014	3/25/2015	9/15/2015	3/22/2016	9/14/2016	3/2/2017	9/12/2017	3/6/2018	9/11/2018	3/5/2019	9/25/2019	3/11/2020
Comments	Duplicate															
Well Depth (Ft)	350															
Screened Interval (Ft)	330-350															
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	NR
Acrylonitrile	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acetone	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	NR	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	NR	NR	NR
Chloroform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	ND	1.2 J	1.2	1.1	0.69 J	0.64 J	0.76 J	0.40 J	0.33 J	ND	ND	ND	ND	ND	ND	ND
1,2-dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-dichloroethene	ND	0.57 J	0.69 J	0.74 J	0.43 J	0.42 J	0.41 J	0.29 J	0.21 J	ND	ND	ND	ND	ND	ND	ND
cis-1,2-dichloroethene	ND	0.43 J	0.41 J	0.38 J	0.30 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND
2-hexanone	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
styrene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	1.7 J	1.2	1.6	1.5	1.6	2.2	1.6	2.5	2.3	1.9	1.6	1.7	1.71	ND	1.69 J	1.73 J
Toluene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	ND	0.61 J	0.66 J	0.66 J	0.39 J	0.35 J	0.36 J	0.30 J	0.21 J	ND	ND	ND	ND	ND	ND	ND
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	48	62.7	60.5	60.0	43.4	41.8	45.4	37.6	40	27	22	19	19.2	19.3	21.1	18.4
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	0.04 J	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	9.5 J	ND	15	14	8	12	ND	ND	ND	3.3	2.9	1.3	3.3	16.4	16	15.3

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW3-MW1				RW3-MW2														
	10/6/2020	3/11/2021	9/29/2021	3/9/2022	1/19/2010	1/19/2010	4/22/2010	7/29/2010	11/9/2010	11/9/2010	3/25/2011	6/14/2011	9/27/2011	11/30/2011	3/8/2012	6/7/2012	8/22/2012	8/22/2012	
Comments						Duplicate				Duplicate									Duplicate
Well Depth (Ft)	350				495														
Screened Interval (Ft)	330-350				475-495														
VOCS (EPA 624) ug/L ⁽⁴⁾																			
Acrolein	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	30 R	30 R
Acrylonitrile	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND
Acetone	NR	NR	NR	ND	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	ND	NR	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	NR	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
Chloroethane	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND
Chloroform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	0.23 J	ND	ND	ND
Chloromethane	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	ND	ND	ND	0.107 J	ND	ND	0.54J	ND	ND	ND	ND	0.52 J	0.37 J	ND	0.41 J	0.66 J	0.74 J	0.73 J	
1,2-dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-dichloroethene	ND	ND	ND	ND	ND	ND	1.2	ND	ND	ND	ND	0.57 J	0.45 J	0.27 J	0.27 J	0.36 J	0.49 J	0.49 J	
cis-1,2-dichloroethene	ND	ND	ND	ND	1.5J	1.6J	2.4	1.1	0.92J	0.92J	1.6	1.7	1.1	1.4	1.3	1.5	1.6	1.5	
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	0.43 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	NR	NR	ND	NR	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
isopropylbenzene	NR	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	NR	ND	NR	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
styrene	NR	NR	NR	ND	NR	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	NR	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	2.50 J	1.38 J	1.91 J	1.44 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.28 J	ND
Toluene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	ND	ND	ND	ND	ND	ND	0.58J	ND	ND	ND	ND	0.39 J	0.43 J	ND	ND	0.54 J	0.52 J	0.49 J	
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	0.25 J	0.27J	ND	NR	0.32 J	0.32 J	0.32 J	ND	ND	ND	ND
Trichloroethene	23.1	18.7	21.6	16.9	160	170	211	73	58.2	60.9	110	135	151	71.9	96.5	209	198	192	
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	NR	NR	<0.20	<0.20	<0.20	<0.20	<0.20	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	1.1	1.3	ND	ND	NR	NR	5.0	6.0	ND	10.0	10.0	7	6	ND	8	ND	ND	ND	ND

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW3-MW2															
Sample Date	12/4/2012	12/4/2012	3/14/2013	6/20/2013 ⁽²⁾	9/17/2013	12/17/2013	3/25/2014	9/23/2014	9/23/2014	3/25/2015	9/14/2015	3/22/2016	9/14/2016	9/14/2016	3/2/2017	3/2/2017
Comments		Duplicate							Duplicate					Duplicate		Duplicate
Well Depth (Ft)	495															
Screened Interval (Ft)	475-495															
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acrylonitrile	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acetone	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR
Chloroform	0.62 J	0.64 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.27 J	0.24 J	0.23 J	0.26 J	0.24 J
Chloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	0.69 J	0.71 J	0.68 J	ND	0.65 J	0.59 J	0.62 J	0.51 J	0.51 J	0.56 J	0.47 J	0.52 J	0.39 J	0.34 J	0.39 J	0.47 J
1,2-dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-dichloroethene	0.40 J	0.43 J	0.53 J	ND	0.29 J	0.45 J	0.44 J	0.38 J	0.33 J	0.33 J	0.30 J	0.46 J	0.31 J	0.37 J	0.25 J	ND
cis-1,2-dichloroethene	1.6	1.6	1.6	ND	1.3 J	1.9	1.7	1.4	1.3	1.5	1.4	1.7	1.5	1.5	1.5	1.3
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	ND	0.69 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR
2-hexanone	NR	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
styrene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	ND	ND	ND	ND	ND	ND	0.29 J	ND	ND	ND	0.52 J	0.66 J	0.48 J	0.54 J	0.44 J	0.38 J
Toluene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	0.42 J	0.43 J	0.41 J	ND	0.47 J	0.50 J	0.43 J	0.36 J	0.39 J	0.38 J	0.41 J	0.47 J	0.44 J	0.47 J	0.41 J	0.34 J
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.32 J	0.31 J	0.21 J	0.32 J	0.24 J
Trichloroethene	173 J	171	155	140	174	176	164	148	151	159	169	204	190	190	160	150
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW3-MW2									
Sample Date	9/12/2017	3/6/2018	9/11/2018	3/5/2019	9/25/2019	3/11/2020	10/6/2020	3/11/2021	9/29/2021	3/10/2022
Comments										
Well Depth (Ft)	495									
Screened Interval (Ft)	475-495									
VOCS (EPA 624) ug/L ⁽⁴⁾										
Acrolein	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR
Acrylonitrile	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR
Acetone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR
Chloroform	0.24 J	0.23 J	ND	ND	ND	ND	ND	ND	ND	ND
Chloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,1-dichloroethane	0.36 J	0.29 J	0.290 J	0.364 J	ND	0.203 J	0.287 J	0.279 J	0.350 J	0.371 J
1,2-dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-dichloroethene	0.26 J	ND	ND	0.256 J	ND	ND	ND	ND	ND	ND
cis-1,2-dichloroethene	1.3	1.2	0.990 J	1.10 J	0.994 J	1.00 J	0.809 J	1.05 J	0.828 J	.0774 J
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Methylene chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
styrene	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	0.43 J	0.38 J	0.430 J	0.328 J	0.477 J	0.367 J	0.317 J	0.274 J	0.485 J	ND
Toluene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	0.26 J	0.33 J	ND	ND	ND	ND	ND	ND	ND	ND
1,1,2-trichloroethane	0.26 J	ND	ND	0.240 J	0.204 J	ND	ND	ND	ND	ND
Trichloroethene	140	130	131	118	131	128	119	90.0	89.8	69.2
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW3-MW3															
Sample Date	1/20/2010	4/22/2010	4/22/2010	7/28/2010	11/3/2010 ⁽¹⁾	3/25/2011	6/15/2011	9/28/2011	11/29/2011	3/7/2012	3/7/2012	6/7/2012	8/22/2012	12/4/2012	3/14/2013	6/21/2013 ⁽²⁾
Comments			Duplicate								Duplicate					
Well Depth (Ft)	340															
Screened Interval (Ft)	320-340															
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	150 R	ND	ND	ND
Acrylonitrile	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acetone	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Benzene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
carbon disulfide	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroethane	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroform	ND	ND	0.40J	0.46J	ND	0.33J	NR	0.48 J	ND	0.42 J	0.42 J	2.3 J	ND	0.88 J	ND	ND
Chloromethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	ND	1.6	1.6	2.3	1.0	1.5	7.1	3.2 J	1.5	3.3	3.3	2.6 J	ND	4.2	4.5 J	ND
1,2-dichloroethane	ND	0.52J	0.54J	ND	ND	ND	0.37 J	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1-dichloroethene	ND	1.1	1.3	1.2	ND	0.96J	2.6	1.8 J	0.96 J	1.9	1.9	1.7 J	1.4 J	1.9	2.1 J	ND
cis-1,2-dichloroethene	ND	2.1	2.1	1.7	ND	2.3	1.2	1.9	2.1	2.1	2.1	1.4 J	1.8 J	1.2	ND	ND
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	3.2 J	ND
4-methyl-2-pentanone	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
styrene	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	ND	0.45J	0.49J	ND	ND	ND	0.40 J	0.50 J	ND	0.72 J	0.69 J	ND	ND	0.43 J	ND	ND
Toluene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	ND	0.95J	1.0J	0.72J	ND	0.62J	1.3	1.0 J	0.49 J	0.84 J	0.87 J	ND	ND	0.85 J	ND	ND
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	350	397	382	297	8.5	288	331	215 J	250	312	325	285	248	291	347	410
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	NR	<0.20	<0.20	<0.20	<0.20	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	NR	4.0	5.0	<4.0	<4.0	<4.0	ND	ND	ND	ND	ND	13	10	5	ND	ND

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW3-MW3															
Sample Date	9/18/2013	12/17/2013	3/26/2014	9/23/2014	3/25/2015	3/25/2015	9/15/2015	3/21/2016	9/15/2016	3/2/2017	9/12/2017	9/12/2017	3/6/2018	3/6/2018	9/12/2018	9/12/2018
Comments						Duplicate						Duplicate		Duplicate		Duplicate
Well Depth (Ft)	340															
Screened Interval (Ft)	320-340															
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acrylonitrile	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acetone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	ND	ND	2.0 R	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND
Chloroform	ND	3.4 J	ND	0.27 J	0.40 J	0.33 J	ND	ND	0.48 J	0.45 J	0.35 J	0.27 J	0.33 J	0.37 J	0.400 J	0.400 J
Chloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	ND	3.7 J	4.9 J	1.3 J	1.8	1.8	1.2	4.0	3.5	2.9	2.5	2.2	2.0	2.3	2.08	2.24
1,2-dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	0.30 J	ND	ND	ND	ND	ND	ND	ND
1,1-dichloroethene	ND	ND	2.4 J	0.94 J	1.5 J	1.4 J	1.1	2.4	2.0	1.3	ND	0.78 J	1.1	1.2	1.00	1.14
cis-1,2-dichloroethene	ND	ND	ND	1.2	1.3	1.3	1.3	1.1	1.1	0.83 J	0.8 J	0.76 J	0.63 J	0.59 J	0.590 J	0.640 J
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND
2-hexanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	6.2 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
styrene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	ND	ND	ND	ND	0.36 J	0.37 J	0.77 J	0.71 J	0.58 J	0.43 J	0.31 J	0.44 J	0.36 J	0.32 J	0.390 J	0.390 J
Toluene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	ND	ND	ND	0.40 J	0.48 J	0.45 J	0.36 J	1.1	0.75 J	0.69 J	0.46 J	0.38 J	0.61 J	0.57 J	0.550 J	0.530 J
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	322	322	350	147	182	184	138	284	260	200	100	95	150	160	124	155
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	ND	ND	ND	ND	ND	ND	ND	ND	1.1	2.4	3	1.9	4.7 J	2.8 J	5.7	6.0

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW3-MW3													
Sample Date	3/5/2019	3/5/2019	9/25/2019	9/25/2019	3/11/2020	3/11/2020	10/6/2020	10/6/2020	3/11/2021	3/11/2021	9/29/2021	9/29/2021	3/9/2022	3/9/2022
Comments		Duplicate		Duplicate		Duplicate		Duplicate		Duplicate		Duplicate		Duplicate
Well Depth (Ft)	340													
Screened Interval (Ft)	320-340													
VOCS (EPA 624) ug/L ⁽⁴⁾														
Acrolein	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Acrylonitrile	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR
Acetone	NR	NR	NR	NR	NR	ND	NR	NR	NR	NR	NR	NR	NR	ND
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Chloroform	0.420 J	0.370 J	ND	ND	0.269 J	0.324 J	0.328 J	0.342 J	0.364 J	0.334 J	ND	ND	ND	ND
Chloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,1-dichloroethane	2.21 J	1.97 J	1.85 J	1.80 J	2.01 J	2.06 J	1.78 J	1.90 J	1.59 J	1.50 J	1.73 J	1.66 J	1.56	1.61
1,2-dichloroethane	ND	ND	0.255 J	ND	ND	0.223 J	ND	ND	ND	ND	ND	ND	0.159 J	0.150 J
1,1-dichloroethene	1.17 J	1.14 J	1.52 J	1.36 J	1.13 J	1.26 J	1.38 J	1.39 J	0.880 J	0.970 J	1.01 J	1.13 J	0.925 J	1.01
cis-1,2-dichloroethene	0.840 J	0.805 J	1.07 J	1.05 J	0.91 J	0.983 J	0.803 J	0.840 J	0.655 J	0.686 J	0.578 J	0.777 J	0.595 J	0.581 J
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Methylene chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
styrene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	ND	ND	0.672 J	0.727 J	0.446 J	0.471 J	0.533 J	0.545 J	0.429 J	0.517 J	0.411 J	0.493 J	0.336 J	0.302 J
Toluene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	0.594 J	0.599 J	0.518 J	0.467 J	0.472 J	0.388 J	0.402 J	0.384 J	ND	0.273 J	0.438 J	0.286 J	0.32 J	0.302 J
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	151	147	176	172	178 J	183	180	180	159	159	176	179	146 J	149 J
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Mercury (EPA 245.1) ug/L	0.88 J	0.122 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	5.1	1.6	2.6 J	1.7	2.3	2.3	6.5	5.9	1.2	1.6	3.2	2.7	ND	ND

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	RW3-MW4															
Sample Date	1/20/2010	4/22/2010	7/28/2010	7/28/2010	11/3/2010 ⁽¹⁾	3/24/2011	6/15/2011	9/28/2011	11/29/2011	3/7/2012	6/7/2012	8/22/2012	12/4/2012	3/14/2013	6/21/2013 ⁽²⁾	9/17/2013
Comments				Duplicate												
Well Depth (Ft)	495															
Screened Interval (Ft)	475-495															
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	30 R	ND	ND	NR	ND
Acrylonitrile	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	NR	ND
Acetone	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	NR
Benzene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroethane	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	NR	ND
Chloroform	ND	ND	ND	ND	0.32J	ND	NR	0.87 J	ND	0.38 J	ND	ND	0.71 J	ND	1.2	ND
Chloromethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	NR	ND
1,3-dichlorobenzene	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	NR	ND
1,4-dichlorobenzene	NR	NR	NR	NR	NR	NR	NR	ND	ND	ND	ND	ND	ND	ND	NR	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	2.5	0.6	0.54J	0.50J	1.8	0.81	0.78 J	5.4 J	0.84 J	1.8	0.50 J	ND	1.2	3.8	4.6	2.9
1,2-dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.23 J	ND
1,1-dichloroethene	1.0	ND	ND	ND	0.86J	ND	0.20 J	0.53 J	ND	0.21 J	ND	ND	0.19 J	0.38 J	0.42 J	ND
cis-1,2-dichloroethene	0.46J	ND	ND	ND	1.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
styrene	NR	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	NR	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Toluene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	ND	ND	ND	ND	0.67J	ND	ND	0.66 J	ND	ND	ND	ND	ND	ND	0.29 J	ND
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	21	11	7.5	8.0	308	7.7	6.7	3.4 J	5.6	4.6	5.4	5.5	4.5	2.3	1.8	5.0
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	NR	<0.20	<0.20	<0.20	<0.20	<0.20	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	NR	16.0	<4.0	<4.0	<4.0	<4.0	ND	11	6	5	ND	ND	ND	22	ND	ND

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	12/17/2013	3/26/2014	9/23/2014	3/25/2015	9/15/2015	3/21/2016	9/15/2016	3/2/2017	9/12/2017	3/6/2018	9/12/2018	3/5/2019	9/25/2019	3/11/2020	10/5/2020	3/11/2021	9/29/2021	3/9/2022
Comments																		
Well Depth (Ft)	495																	
Screened Interval (Ft)	475-495																	
VOCS (EPA 624) ug/L ⁽⁴⁾																		
Acrolein	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR
Acrylonitrile	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acetone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR
Chloroform	ND	1.2 J	0.38 J	1.2	ND	0.64 J	ND	ND	0.21 J	0.47 J	ND	0.996 J	ND	0.954 J	ND	0.367 J	ND	ND
Chloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,1-dichloroethane	4.9	5.5	2.7 J	6.9	0.88 J	4.9	2.0	1.5	2.6	3.9	1.47	6.22	5.72	6.99	1.50 J	3.03 J	4.60 J	3.81
1,2-dichloroethane	ND	0.37 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.235 J	0.253 J	ND	ND	ND	ND	0.109 J
1,1-dichloroethene	0.39 J	0.95 J	0.37 J	1.3 J	0.21 J	0.85 J	0.40 J	0.27 J	0.41 J	0.70 J	0.340 J	0.981 J	1.37 J	1.70 J	0.409 J	0.842 J	1.22 J	1.00 J
cis-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	0.21 J	ND	ND	0.351 J	0.475 J	0.465 J	ND	ND	0.304 J	0.243 J
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Methylene chloride	ND	ND	ND	ND	ND	0.43 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
styrene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	ND	ND	ND	ND	0.31 J	0.46 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Toluene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	0.39 J	0.48 J	ND	0.60 J	ND	0.48 J	0.24 J	ND	0.26 J	0.40 J	ND	0.481 J	0.668 J	0.727 J	ND	0.422 J	0.624 J	0.686 J
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	4.4	3.3	2.5	2.7	4.1	2.9	4.3	4.1	5.4	1.5	2.66	2.12 J	1.30 J	2.15 J	3.02 J	3.30 J	ND	5.24
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	ND	9	5	5	ND	ND	1.4	ND	1.3	ND	ND	1.3	2.7	2.6	2.2	2.2	ND	ND

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	TP-01															
Sample Date	1/21/2010	6/15/2011	9/27/2011	9/27/2011	11/30/2011	3/8/2012	6/6/2012	8/22/2012	12/4/2012	3/13/2013	3/13/2013	6/17/2013 ⁽²⁾	9/17/2013	9/17/2013	12/16/2013	3/25/2014
Comments				Duplicate							Duplicate			Duplicate		
Well Depth (Ft)	470															
Screened Interval (Ft)	450-470															
VOCS (EPA 624) ug/L ⁽⁴⁾																
Acrolein	NR	NR	ND	ND	ND	ND	ND	30 R	ND	ND	ND	NR	ND	ND	ND	ND
Acrylonitrile	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND
Acetone	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Benzene	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.34 J	ND	ND	ND	ND
Bromoform	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chloroethane	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	NR	NR	ND	ND	ND	ND	ND	ND	ND	2.0 R	2.0 R	NR	ND	ND	ND	ND
Chloroform	ND	NR	0.68 J	0.74 J	ND	0.74 J	0.82 J	ND	2.5 J	1.2	1.1	11	5.2 J	ND	7.4	6.8 J
Chloromethane	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND
1,3-dichlorobenzene	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND
1,4-dichlorobenzene	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1-dichloroethane	3.6J	5.0	3.7	3.7	2.9	3.7	3.7	3.4	1.1	1.5	1.4	3.2	2.1 J	2.8	1.5	ND
1,2-dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	0.35 J	0.36 J	0.37 J	0.30 J	ND	ND	ND	ND
1,1-dichloroethene	ND	1.7	1.1	1.0	1.0	1.2	1.4	1.1	0.23 J	0.44 J	0.42 J	0.77	0.66 J	0.74 J	0.33 J	0.22 J
cis-1,2-dichloroethene	190	43.4	40.4	40.2	74.9	53.3	29.9	16.1	4.2	5.8	5.8	8.7	14.1 J	14.7	8.0	5.3
trans-1,2-dichloroethene	3.0J	1.1	1.0 J	0.92 J	1.1	0.87 J	0.79 J	0.35 J	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Methylene chloride	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
styrene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	NR	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	3.4J	3.3	4.4	4.4	3.6	4.7	6.0	4.0	0.42 J	0.34 J	0.32 J	1.6	0.77 J	1.5 J	0.57 J	ND
Toluene	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	ND	0.63 J	0.73 J	0.76 J	0.29 J	0.57 J	1.1 J	0.86 J	ND	0.35 J	0.35 J	0.62	0.66 J	0.66 J	0.50 J	ND
1,1,2-trichloroethane	ND	NR	0.31 J	0.31 J	0.32 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	65	35.3	41.0	39.6	38.0	38.1	40.4	27.9	22.0	25.9	25.4	25	27.0	26.7	29.8	21.7
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	NR	63	18	NR	ND	7	6	ND	ND	ND	ND	ND	ND	ND	ND	ND

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	TP-01																
Sample Date	9/22/2014	3/25/2015	9/14/2015	9/14/2015	3/21/2016	9/14/2016	3/1/2017	9/13/2017	3/5/2018	9/11/2018	3/6/2019	9/25/2019	3/12/2020	10/6/2020	3/11/2021	9/29/2021	3/10/2022
Comments				Duplicate													
Well Depth (Ft)	470																
Screened Interval (Ft)	450-470																
VOCS (EPA 624) ug/L ⁽⁴⁾																	
Acrolein	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR
Acrylonitrile	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Acetone	ND	ND	ND	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Benzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	0.53 J	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
carbon disulfide	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	NR
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	ND	ND	2.0 R	ND	ND	ND	NR	ND	ND	ND	NR	NR	NR	NR	NR	NR	NR
Chloroform	1.9	2.6	1.3	1.3	1.7	1.6	1.2	6.3	2.0	1.08	0.684 J	ND	ND	0.292 J	1.17 J	0.478 J	ND
Chloromethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cyclohexane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,2-dibromo-3-chloro-propane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dibromomethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
1,2-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,1-dichloroethane	1.3 J	2.5	2.1	2.0	1.8	2.1	0.78 J	1.3	1.2	1.24	0.717 J	0.381 J	0.335 J	0.363 J	0.629 J	0.533 J	0.895 J
1,2-dichloroethane	0.67 J	0.88 J	0.82 J	0.82 J	0.86 J	0.70 J	0.45 J	0.79	0.79 J	0.650 J	ND	ND	ND	ND	ND	ND	ND
1,1-dichloroethene	0.47 J	1.2 J	0.77 J	0.83 J	0.75 J	0.68 J	0.23 J	0.36 J	0.46 J	0.420 J	ND	ND	ND	ND	0.301 J	0.221 J	0.339 J
cis-1,2-dichloroethene	7.6	13.4	11.3	11.6	10.8	12	5	11	12	12.1	6.01	3.75 J	3.01 J	3.14 J	4.73 J	2.51 J	1.99
trans-1,2-dichloroethene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Ethylbenzene	ND	ND	ND	ND	ND	ND	NR	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
2-hexanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
isopropylbenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
methyl acetate	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Methylene chloride	ND	ND	ND	ND	0.37 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
4-methyl-2-pentanone	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
styrene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR
Tetrachloroethene	ND	0.48 J	0.82 J	0.88 J	0.72 J	0.37 J	0.22 J	ND	ND	ND	ND	ND	ND	ND	0.680 J	1.21 J	1.84 J
Toluene	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
1,1,1-trichloroethane	ND	ND	ND	ND	ND	0.49 J	0.25 J	0.29 J	0.27 J	ND	ND	ND	ND	ND	ND	ND	ND
1,1,2-trichloroethane	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
Trichloroethene	31.9	52.3	53.0	53.9	61.7	47	21	54	55	38.2	28.3	14.4	12.7	11.1	15.6	13	12.4
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	ND
Mercury (EPA 245.1) ug/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.1	ND	ND	1.0	ND	1.7	ND

Table 7
GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Summary of Historical Groundwater Analytical Results
Through First Quarter 2022

Sample ID	IW-1 MW-1		IW-1	RW-3 ⁽³⁾				
	5/3/2005	6/18/2013 ⁽²⁾	5/27/2009	9/15/2015	3/22/2016	9/15/2016	3/2/2017	9/13/2017
Comments								
Well Depth (Ft)	150		230	530				
Screened Interval (Ft)	20-150		200-230	392-412				
VOCS (EPA 624) ug/L⁽⁴⁾								
Acrolein	NR	NR	NR	ND	ND	ND	ND	ND
Acrylonitrile	NR	NR	NR	ND	ND	ND	ND	ND
Acetone	ND	ND	ND	ND	ND	ND	NR	NR
Benzene	ND	ND	ND	ND	ND	ND	ND	ND
Bromodichloromethane	ND	ND	ND	ND	ND	ND	ND	ND
Bromoform	ND	ND	ND	ND	ND	ND	ND	ND
Bromomethane	ND	ND	ND	ND	ND	ND	ND	ND
2-butanone	R	ND	ND	NR	NR	NR	NR	NR
carbon disulfide	ND	NR	ND	NR	NR	NR	NR	NR
Carbon tetrachloride	ND	ND	ND	ND	ND	ND	ND	ND
Chlorobenzene	ND	ND	ND	ND	ND	ND	ND	ND
Dibromochloromethane	NR	ND	ND	ND	ND	ND	ND	ND
Chloroethane	ND	ND	ND	ND	ND	ND	ND	ND
2-chloroethylvinyl ether	NR	NR	NR	ND	ND	ND	NR	ND
Chloroform	0.94J	ND	0.98J	ND	0.46 J	0.26 J	ND	0.28 J
Chloromethane	ND	ND	ND	ND	ND	ND	NR	ND
cyclohexane	NR	NR	ND	NR	NR	NR	NR	NR
1,2-dibromo-3-chloro-propane	ND	NR	ND	NR	NR	NR	NR	NR
1,2-dibromomethane	ND	NR	ND	NR	NR	NR	NR	NR
1,2-dichlorobenzene	NR	NR	ND	ND	ND	ND	ND	ND
1,3-dichlorobenzene	NR	NR	ND	ND	ND	ND	ND	ND
1,4-dichlorobenzene	NR	NR	ND	ND	ND	ND	ND	ND
dichlorodifluoromethane	NR	NR	ND	NR	NR	NR	NR	NR
1,1-dichloroethane	0.39J	0.51	0.22J	1.9	2.1	1.8	1.4 J	1.5
1,2-dichloroethane	ND	ND	ND	ND	ND	ND	ND	ND
1,1-dichloroethene	ND	ND	ND	1.9	2.5	1.5	1.3 J	1.4
cis-1,2-dichloroethene	ND	ND	ND	1.6	2.4	1.4	1.6 J	1.9
trans-1,2-dichloroethene	ND	ND	ND	ND	0.23 J	ND	ND	ND
1,2-dichloropropane	ND	ND	ND	ND	ND	ND	ND	ND
cis-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND
trans-1,3-dichloropropene	ND	ND	ND	ND	ND	ND	ND	ND
1,4-dioxane	NR	NR	NR	NR	NR	NR	NR	ND
Ethylbenzene	ND	ND	ND	ND	ND	ND	NR	ND
2-hexanone	ND	ND	ND	NR	NR	NR	NR	NR
isopropylbenzene	NR	NR	ND	NR	NR	NR	NR	NR
methyl acetate	NR	NR	ND	NR	NR	NR	NR	NR
Methylene chloride	ND	ND	ND	ND	0.64 J	ND	ND	ND
4-methyl-2-pentanone	ND	ND	ND	NR	NR	NR	NR	NR
styrene	ND	NR	ND	NR	NR	NR	NR	NR
1,1,2,2-tetrachloroethane	ND	ND	ND	ND	ND	ND	ND	ND
1,2,4-trichlorobenzene	NR	NR	ND	NR	NR	NR	NR	NR
Tetrachloroethene	ND	0.55	ND	0.68 J	0.79 J	0.64 J	0.60 J	0.65 J
Toluene	ND	ND	0.19J	ND	ND	ND	ND	ND
1,1,1-trichloroethane	0.47	0.92	0.49J	0.96 J	1.3	0.95 J	ND	0.83 J
1,1,2-trichloroethane	ND	ND	ND	0.30 J	0.49 J	0.29 J	ND	0.45 J
Trichloroethene	ND	ND	0.17J	237	371	230	230	220
Vinyl chloride	ND	ND	ND	ND	ND	ND	ND	ND
xylenes (total)	ND	NR	ND	NR	NR	NR	NR	NR
Mercury (EPA 245.1) ug/L	NR	NR	0.20	ND	ND	ND	ND	ND
TSS (SM20 2540D) mg/L	NR	NR	2.4	ND	ND	ND	2.4	8.1

Note:

VOC analysis changed from SW846 8260B to EPA Method 624 in January 2010.

D = Dilution

J = estimated value

J- =biased low estimated value

ND = not detected

NR = not reported / required

R = rejected

mg/L - milligrams per liter

µg/L - micrograms per liter

(1) Analytical results presented above for samples collected from RW3-MW3 and RW3-MW4 in November 2010 are not consistent with historical trends, indicating samples may have been switched. For trend analysis, concentrations for RW3-MW3 were used for RW3-MW4 for November 2010 and vice versa.

(2) VOCs were analyzed by USEPA Method 524.2 (as opposed to Method 624) in June 2013 to correlate with samples collected under the Bethpage Regional Plume Comprehensive Groundwater Sampling Plan conducted in June 2013.

(3) RW-3, previously an active extraction well sampled on a monthly basis, was taken off-line on 7/1/15. While off-line, RW-3 was sampled semi-annually in conjunction with the semi-annual LTM events.

(4) Samples were analyzed for TCL VOCs, including tentatively identified compounds (TICs), beginning in March 2016. No TICs were detected, unless otherwise indicated.

Data prior to June 2011 were collected by others.

APPENDIX A

**NYSDEC EFFLUENT LIMITATIONS AND MONITORING
REQUIREMENTS AND
JANUARY - MARCH 2022 DMRS**

JANUARY 2022



7 February 2022

Mr. Jason Pelton
New York State Department of Environmental Conservation
Division of Solid & Hazardous Materials
625 Broadway
Albany, NY 12233-7252

**Subject: GROUNDWATER DISCHARGE MONITORING/AIR EMISSION REPORT
GM-38 AREA, NWIRP BETHPAGE, NY; DER SITE # 1-30-003B-OU 2
JANUARY 2022 REPORTING PERIOD**

Dear Mr. Pelton:

KOMAN Government Solutions, LLC (KGS) is submitting this monthly monitoring report of the groundwater discharge and air emission results for the Groundwater Treatment Plant (GWTP) located at the Former Naval Weapons Industrial Reserve Plant (NWIRP), Bethpage, NY, GM-38 Area. This report was prepared in accordance with GWTP operational requirements for DER Site # 1-30-003B-OU 2, and the SPDES Permit Equivalent # 13003B.

GWTP operational data from 1 January to 31 January 2022 are presented in Attachment A. The plant was down for approximately 77 hours during the reporting period as the result of heavy sediment loads from RW-4 causing high differential pressures at the bag filter system and storm related intermittent power outages the weekend of 29-31 January 2022.

As indicated in Attachment A, all SPDES permitted constituents are in compliance with regulatory guidelines during this reporting period.

Please contact me at 610-400-0636 with any questions or concerns you may have regarding this report.

Sincerely,

KOMAN Government Solutions, LLC

A handwritten signature in black ink that reads 'Robert G. Gregory'.

Robert G. Gregory
Project Manager

Attachment A: Groundwater and Air Sampling Results for January 2022

cc: C. Haas, NYSDEC Region 1
C. Engelhardt, NYSDEC Region 1
J. Pilewski, NYSDEC – Region 1 Water Engineer
J. Sullivan, NYSDOH
G. Ennis, Nassau County Department of Public Works
T. Licata, Town of Oyster Bay
M. Russo, Town of Oyster Bay
S. Sokolowski, NAVFAC Mid-Atlantic
V. Varricchio, NWIRP Bethpage Facilities Management
P. Schauble, KGS
GM-38 Copy

ATTACHMENT A
GROUNDWATER AND AIR SAMPLING RESULTS
JANUARY 2022

**GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Discharge Monitoring Report
January 2022**

SPDES Parameters			January 2022 ⁽¹⁾				
Process Stream	Daily Treated Effluent Maximum ⁽¹⁾	Units	RW-1	RW-3	RW-4	Combined Influent (RW-1 + RW-3 + RW-4)	Treated Effluent
Well Depth	N/A	ft	445	530	655*	N/A	N/A
Screened Interval	N/A	ft bgs	335-395 410-430	392-412 442-504	550-650*	N/A	N/A
Sampling Date	N/A		1/6/22				
Effective Flowrate	1100	GPM	660	0	266	925	986
Total Flow	N/A	gallons	26,405,666	0	10,626,279	37,031,944	39,461,845
pH	5.5 - 8.5	SU	5.55	NS	6.23	5.75	7.13
Chloroform	5	µg/L	ND (0.90)	NS	ND (2.3)	--	ND (0.90)
1,1-Dichloroethane	5	µg/L	0.97 J	NS	ND (2.3)	0.69	ND (0.90)
1,2-Dichloroethane	0.6	µg/L	ND (0.75)	NS	ND (1.9)	--	ND (0.75)
1,1-Dichloroethene	5	µg/L	0.60 J	NS	1.9 J	0.97 J	ND (0.75)
cis 1,2-Dichloroethene	5	µg/L	3.1	NS	1.4 J	2.61	ND (0.75)
trans 1,2-Dichloroethene	5	µg/L	ND (0.90)	NS	ND (2.3)	--	ND (0.90)
Tetrachloroethene	5	µg/L	14.9	NS	5.2	12.12	ND (0.90)
1,1,1-Trichloroethane	5	µg/L	ND (0.90)	NS	ND (2.3)	--	ND (0.90)
Trichloroethene	5	µg/L	54.2	NS	752 D	254.4	ND (0.90)
1,1,2-Trichlorotrifluoroethane	5	µg/L	ND (0.90)	NS	3.1 J	0.89	ND (1.5)
Vinyl Chloride	2	µg/L	ND (0.90)	NS	ND (2.3)	--	ND (0.90)
1,4-Dioxane	1	µg/L	0.747	NS	4.49	1.82	ND (0.20)
Mercury	0.00025	mg/L	ND (0.00015)	NS	ND (0.00015)	ND (0.00015)	ND (0.00015)
Total Suspended Solids (TSS)	N/A	mg/L	ND (2.0)	NS	13.5	ND (2.0)	ND (2.0)

Notes:

J - Estimated result between laboratory method detection limit and reporting limit

ND - Not detected above laboratory method detection limit. Limit of Detection (LOD) given in parentheses.

NR - Not Recorded

N/A - Not Applicable

NS - Not Sampled

-- LOD for non-detect combined well influent not applicable; RW-4 sample required dilution.

(1) Wastewater discharge equivalence permit renewed on 18 August 2017. Discharge limits established for 10 years. Chloroform, 1,4-dioxane and 1,1,2-trichlorotrifluoroethane are now monitored under the new permit.

* Design depths

**GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Air Sampling Results
January 2022**

DAR Parameters			January 2022	
Process Stream	Units	Discharge Goal ⁽¹⁾	Influent	Effluent
Sampling Date			1/6/22	
Average Flowrate	CFM	N/A	NR	9,228
Total Flow	ft ³	N/A	NR	369,271,758
Total Flow	m ³	N/A	NR	10,456,612
1,2-Dichloroethane	µg/m ³	N/A	ND	ND
cis 1,2-Dichloroethene	µg/m ³	≤ 100,000 ⁽²⁾	14	40
trans 1,2-Dichloroethene	µg/m ³		ND	ND
1,2-Dichloroethene (total)	µg/m ³	≤ 100,000	14	40
Toluene	µg/m ³	N/A	2.5 J	ND
Total Xylene	µg/m ³	N/A	ND	ND
1,1,2-Trichloroethane	µg/m ³	N/A	ND	ND
Trichloroethene	µg/m ³	≤ 2600	1500	ND
Vinyl Chloride	µg/m ³	≤ 560	ND	ND
Tetrachloroethene	µg/m ³	≤ 5100	64	ND

Notes:

CFM - cubic feet per minute

DAR - Division of Air Resources

J - Estimated result between laboratory method detection limit and reporting limit

N/A - Not Applicable

NR - Not recorded

(1) Discharge goal as approved by NYSDEC's letter dated 31 October 2013.

(2) Discharge goal is for total 1,2-Dichloroethene.

**GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Controlled Stack Emissions
January 2022**

DAR Parameters	Units	Discharge Goal ⁽¹⁾	January 2022
Sampling Date			1/6/22
Average Flowrate	CFM	N/A	9,228
Total Flow	ft ³	N/A	369,271,758
Total Flow	m ³	N/A	10,456,612
Trichloroethene	lb/hr	≤ 0.09	0.00000
Vinyl Chloride	lb/hr	≤ 0.02	0.00000
1,2 Dichloroethene	lb/hr	≤ 11	0.00124
1,2-Dichloroethane	lb/hr	N/A	0.00000
Toluene	lb/hr	N/A	0.00000
Total Xylene	lb/hr	N/A	0.00000
1,1,2-Trichloroethane	lb/hr	N/A	0.00000
Tetrachloroethene	lb/hr	≤ 0.18	0.00000

Notes:

CFM - cubic feet per minute

DAR - Division of Air Resources

N/A - Not Applicable

(1) Discharge goal as approved by NYSDEC's letter dated 31 October 2013.

FEBRUARY 2022



3 March 2022

Mr. Jason Pelton
New York State Department of Environmental Conservation
Division of Solid & Hazardous Materials
625 Broadway
Albany, NY 12233-7252

**Subject: GROUNDWATER DISCHARGE MONITORING/AIR EMISSION REPORT
GM-38 AREA, NWIRP BETHPAGE, NY; DER SITE # 1-30-003B-OU 2
FEBRUARY 2022 REPORTING PERIOD**

Dear Mr. Pelton:

KOMAN Government Solutions, LLC (KGS) is submitting this monthly monitoring report of the groundwater discharge and air emission results for the Groundwater Treatment Plant (GWTP) located at the Former Naval Weapons Industrial Reserve Plant (NWIRP), Bethpage, NY, GM-38 Area. This report was prepared in accordance with GWTP operational requirements for DER Site # 1-30-003B-OU 2, and the SPDES Permit Equivalent # 13003B.

GWTP operational data from 1 February to 28 February 2022 are presented in Attachment A. The plant was down for approximately 15 hours during the reporting period as the result of service on the AOP PLC system, evaluation of the hydrogen peroxide feed system, and the vapor carbon changeout for the lead unit.

As indicated in Attachment A, all SPDES permitted constituents are in compliance with regulatory guidelines during this reporting period.

Please contact me at 610-400-0636 with any questions or concerns you may have regarding this report.

Sincerely,

KOMAN Government Solutions, LLC

A handwritten signature in black ink that reads 'Robert G. Gregory'.

Robert G. Gregory
Project Manager

Attachment A: Groundwater and Air Sampling Results for February 2022

cc: C. Haas, NYSDEC Region 1
C. Engelhardt, NYSDEC Region 1
J. Pilewski, NYSDEC – Region 1 Water Engineer
K. Granzen, NYSDEC
J. Sullivan, NYSDOH
G. Ennis, Nassau County Department of Public Works
T. Licata, Town of Oyster Bay
M. Russo, Town of Oyster Bay
S. Sokolowski, NAVFAC Mid-Atlantic
V. Varricchio, NWIRP Bethpage Facilities Management
P. Schauble, KGS
GM-38 Copy

ATTACHMENT A
GROUNDWATER AND AIR SAMPLING RESULTS
FEBRUARY 2022

**GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Discharge Monitoring Report
February 2022**

SPDES Parameters			February 2022 ⁽¹⁾				
Process Stream	Daily Treated Effluent Maximum ⁽¹⁾	Units	RW-1	RW-3	RW-4	Combined Influent (RW-1 + RW-3 + RW-4)	Treated Effluent
Well Depth	N/A	ft	445	530	655*	N/A	N/A
Screened Interval	N/A	ft bgs	335-395 410-430	392-412 442-504	550-650*	N/A	N/A
Sampling Date	N/A		2/11/22				
Effective Flowrate	1100	GPM	506	0	368	874	923
Total Flow	N/A	gallons	19,932,300	0	14,512,800	34,445,100	36,375,000
pH	5.5 - 8.5	SU	5.42	NS	6.37	5.82	7.16
Chloroform	5	µg/L	ND (0.90)	NS	8.3	3.50	ND (0.90)
1,1-Dichloroethane	5	µg/L	1.0	NS	ND (4.5)	0.58	ND (0.90)
1,2-Dichloroethane	0.6	µg/L	ND (0.75)	NS	ND (3.8)	--	ND (0.75)
1,1-Dichloroethene	5	µg/L	0.75 J	NS	ND (3.8)	0.43 J	ND (0.75)
cis 1,2-Dichloroethene	5	µg/L	3.1	NS	ND (3.8)	1.79	ND (0.75)
trans 1,2-Dichloroethene	5	µg/L	ND (0.90)	NS	ND (4.5)	--	ND (0.90)
Tetrachloroethene	5	µg/L	15.4	NS	6.3	11.57	ND (0.90)
1,1,1-Trichloroethane	5	µg/L	ND (0.90)	NS	ND (4.5)	--	ND (0.90)
Trichloroethene	5	µg/L	54.0	NS	784	361.6	ND (0.90)
1,1,2-Trichlorotrifluoroethane	5	µg/L	ND (1.5)	NS	ND (7.5)	--	ND (1.5)
Vinyl Chloride	2	µg/L	ND (0.90)	NS	ND (4.5)	--	ND (0.90)
1,4-Dioxane	1	µg/L	0.28 J	NS	3.3	1.55	ND (0.20)
Mercury	0.00025	mg/L	ND (0.00015)	NS	ND (0.00015)	ND (0.00015)	ND (0.00015)
Total Suspended Solids (TSS)	N/A	mg/L	ND (2.5)	NS	ND (2.5)	ND (2.0)	ND (2.5)

Notes:

J - Estimated result between laboratory method detection limit and reporting limit

ND - Not detected above laboratory method detection limit. Limit of Detection (LOD) given in parentheses.

NR - Not Recorded

N/A - Not Applicable

NS - Not Sampled

(1) Wastewater discharge equivalence permit renewed on 18 August 2017. Discharge limits established for 10 years. Chloroform, 1,4-dioxane and 1,1,2-trichlorotrifluoroethane are now monitored under the new permit.

* Design depths

**GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Air Sampling Results
February 2022**

DAR Parameters			February 2022	
Process Stream	Units	Discharge Goal ⁽¹⁾	Influent	Effluent
Sampling Date			2/11/22	
Average Flowrate	CFM	N/A	NR	9,397
Total Flow	ft ³	N/A	NR	370,348,287
Total Flow	m ³	N/A	NR	10,487,096
1,2-Dichloroethane	µg/m ³	N/A	ND	ND
cis 1,2-Dichloroethene	µg/m ³	≤ 100,000 ⁽²⁾	36	55
trans 1,2-Dichloroethene	µg/m ³		ND	ND
1,2-Dichloroethene (total)	µg/m ³	≤ 100,000	36	56
Toluene	µg/m ³	N/A	2.0 J	ND
Total Xylene	µg/m ³	N/A	ND	ND
1,1,2-Trichloroethane	µg/m ³	N/A	ND	ND
Trichloroethene	µg/m ³	≤ 2600	5500	ND
Vinyl Chloride	µg/m ³	≤ 560	ND	ND
Tetrachloroethene	µg/m ³	≤ 5100	150	ND

Notes:

CFM - cubic feet per minute

DAR - Division of Air Resources

J - Estimated result between laboratory method detection limit and reporting limit

N/A - Not Applicable

NR - Not recorded

(1) Discharge goal as approved by NYSDEC's letter dated 31 October 2013.

(2) Discharge goal is for total 1,2-Dichloroethene.

**GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Controlled Stack Emissions
February 2022**

DAR Parameters	Units	Discharge Goal ⁽¹⁾	February 2022
Sampling Date			2/11/22
Average Flowrate	CFM	N/A	9,397
Total Flow	ft ³	N/A	370,348,287
Total Flow	m ³	N/A	10,487,096
Trichloroethene	lb/hr	≤ 0.09	0.00000
Vinyl Chloride	lb/hr	≤ 0.02	0.00000
1,2 Dichloroethene	lb/hr	≤ 11	0.00193
1,2-Dichloroethane	lb/hr	N/A	0.00000
Toluene	lb/hr	N/A	0.00000
Total Xylene	lb/hr	N/A	0.00000
1,1,2-Trichloroethane	lb/hr	N/A	0.00000
Tetrachloroethene	lb/hr	≤ 0.18	0.00000

Notes:

CFM - cubic feet per minute

DAR - Division of Air Resources

N/A - Not Applicable

(1) Discharge goal as approved by NYSDEC's letter dated 31 October 2013.

MARCH 2022



11 April 2022

Mr. Jason Pelton
New York State Department of Environmental Conservation
Division of Solid & Hazardous Materials
625 Broadway
Albany, NY 12233-7252

**Subject: GROUNDWATER DISCHARGE MONITORING/AIR EMISSION REPORT
GM-38 AREA, NWIRP BETHPAGE, NY; DER SITE # 1-30-003B-OU 2
MARCH 2022 REPORTING PERIOD**

Dear Mr. Pelton:

KOMAN Government Solutions, LLC (KGS) is submitting this monthly monitoring report of the groundwater discharge and air emission results for the Groundwater Treatment Plant (GWTP) located at the Former Naval Weapons Industrial Reserve Plant (NWIRP), Bethpage, NY, GM-38 Area. This report was prepared in accordance with GWTP operational requirements for DER Site # 1-30-003B-OU 2, and the SPDES Permit Equivalent # 13003B.

GWTP operational data from 1 March to 31 March 2022 are presented in Attachment A. The plant was down for approximately 54 hours during the reporting period as the result of upgrades and recalibration of the plant PLC system alarm call out equipment and communication losses between the AOP unit and the hydrogen peroxide feed system.

As indicated in Attachment A, all SPDES permitted constituents are in compliance with regulatory guidelines during this reporting period.

Please contact me at 610-400-0636 with any questions or concerns you may have regarding this report.

Sincerely,

KOMAN Government Solutions, LLC

A handwritten signature in black ink that reads 'Robert G. Gregory'.

Robert G. Gregory
Project Manager

Attachment A: Groundwater and Air Sampling Results for March 2022

cc: C. Haas, NYSDEC Region 1
C. Engelhardt, NYSDEC Region 1
J. Pilewski, NYSDEC – Region 1 Water Engineer
K. Granzen, NYSDEC
M. Travis, NYSDEC
J. Sullivan, NYSDOH
G. Ennis, Nassau County Department of Public Works
T. Licata, Town of Oyster Bay
M. Russo, Town of Oyster Bay
S. Sokolowski, NAVFAC Mid-Atlantic
V. Varricchio, NWIRP Bethpage Facilities Management
P. Schauble, KGS
GM-38 Copy

ATTACHMENT A
GROUNDWATER AND AIR SAMPLING RESULTS
MARCH 2022

**GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Discharge Monitoring Report
March 2022**

SPDES Parameters			March 2022 ⁽¹⁾				
Process Stream	Daily Treated Effluent Maximum ⁽¹⁾	Units	RW-1	RW-3	RW-4	Combined Influent (RW-1 + RW-3 + RW-4)	Treated Effluent
Well Depth	N/A	ft	445	530	655*	N/A	N/A
Screened Interval	N/A	ft bgs	335-395 410-430	392-412 442-504	550-650*	N/A	N/A
Sampling Date	N/A		3/18/22				
Effective Flowrate	1100	GPM	498	0	395	894	942
Total Flow	N/A	gallons	20,634,100	0	16,374,600	37,008,700	39,014,300
pH	5.5 - 8.5	SU	NS	NS	6.28	6.28	6.77
Chloroform	5	µg/L	0.248 J	NS	ND (5.0)	0.14	ND (1.0)
1,1-Dichloroethane	5	µg/L	0.958 J	NS	ND (5.0)	0.53	ND (1.0)
1,2-Dichloroethane	0.6	µg/L	ND (1.0)	NS	ND (5.0)	--	ND (1.0)
1,1-Dichloroethene	5	µg/L	0.523 J	NS	1.84 J	1.11 J	ND (1.0)
cis 1,2-Dichloroethene	5	µg/L	3.16 J	NS	1.38 J	2.37	ND (1.0)
trans 1,2-Dichloroethene	5	µg/L	ND (1.0)	NS	ND (5.0)	--	ND (1.0)
Tetrachloroethene	5	µg/L	15.5	NS	6.20 J	11.39	ND (1.0)
1,1,1-Trichloroethane	5	µg/L	0.371 J	NS	ND (5.0)	0.21 J	ND (1.0)
Trichloroethene	5	µg/L	54.4	NS	781	375.9	ND (1.0)
1,1,2-Trichlorotrifluoroethane	5	µg/L	ND (1.0)	NS	4.92 J	2.2 J	ND (1.0)
Vinyl Chloride	2	µg/L	ND (1.0)	NS	ND (5.0)	--	ND (1.0)
1,4-Dioxane	1	µg/L	2.2 J	NS	16	8.31	0.17
Mercury	0.00025	mg/L	ND (0.00010)	NS	ND (0.00010)	ND (0.00010)	ND (0.00010)
Total Suspended Solids (TSS)	N/A	mg/L	ND (1.0)	NS	ND (1.0)	ND (1.0)	ND (1.0)

Notes:

J - Estimated result between laboratory method detection limit and reporting limit

ND - Not detected above laboratory method detection limit. Limit of Detection (LOD) given in parentheses.

NR - Not Recorded

N/A - Not Applicable

NS - Not Sampled

-- LOD for non-detect combined well influent not applicable; RW-4 sample required dilution.

(1) Wastewater discharge equivalence permit renewed on 18 August 2017. Discharge limits established for 10 years. Chloroform, 1,4-dioxane and 1,1,2-trichlorotrifluoroethane are now monitored under the new permit.

* Design depths

**GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Air Sampling Results
March 2022**

DAR Parameters			March 2022	
Process Stream	Units	Discharge Goal ⁽¹⁾	Influent	Effluent
Sampling Date			3/18/22	
Average Flowrate	CFM	N/A	NR	9,211
Total Flow	ft ³	N/A	NR	381,473,565
Total Flow	m ³	N/A	NR	10,802,128
1,2-Dichloroethane	µg/m ³	N/A	ND	ND
cis 1,2-Dichloroethene	µg/m ³	≤ 100,000 ⁽²⁾	27	40
trans 1,2-Dichloroethene	µg/m ³		ND	ND
1,2-Dichloroethene (total)	µg/m ³	≤ 100,000	27	40
Toluene	µg/m ³	N/A	ND	ND
Total Xylene	µg/m ³	N/A	ND	ND
1,1,2-Trichloroethane	µg/m ³	N/A	ND	ND
Trichloroethene	µg/m ³	≤ 2600	4900	ND
Vinyl Chloride	µg/m ³	≤ 560	ND	ND
Tetrachloroethene	µg/m ³	≤ 5100	140	ND

Notes:

CFM - cubic feet per minute

DAR - Division of Air Resources

J - Estimated result between laboratory method detection limit and reporting limit

N/A - Not Applicable

NR - Not recorded

(1) Discharge goal as approved by NYSDEC's letter dated 31 October 2013.

(2) Discharge goal is for total 1,2-Dichloroethene.

**GM-38 Area Groundwater Remediation
Groundwater Treatment Plant
Naval Weapons Industrial Reserve Plant - Bethpage, NY
Controlled Stack Emissions
March 2022**

DAR Parameters	Units	Discharge Goal ⁽¹⁾	March 2022
Sampling Date			3/18/22
Average Flowrate	CFM	N/A	9,211
Total Flow	ft ³	N/A	381,473,565
Total Flow	m ³	N/A	10,802,128
Trichloroethene	lb/hr	≤ 0.09	0.00000
Vinyl Chloride	lb/hr	≤ 0.02	0.00000
1,2 Dichloroethene	lb/hr	≤ 11	0.00128
1,2-Dichloroethane	lb/hr	N/A	0.00000
Toluene	lb/hr	N/A	0.00000
Total Xylene	lb/hr	N/A	0.00000
1,1,2-Trichloroethane	lb/hr	N/A	0.00000
Tetrachloroethene	lb/hr	≤ 0.18	0.00000

Notes:

CFM - cubic feet per minute

DAR - Division of Air Resources

N/A - Not Applicable

(1) Discharge goal as approved by NYSDEC's letter dated 31 October 2013.

APPENDIX B

**NYSDEC AIR DISCHARGE LIMIT
DOCUMENTATION**

New York State Department of Environmental Conservation
Division of Environmental Remediation
Remedial Action Bureau A, 12th Floor
625 Broadway, Albany, New York 12233-7015
Phone: (518) 402-9620 FAX: (518) 402-9022



Joseph Martens
Commissioner

October 31, 2013

Lora Fly
Remedial Program Manager
NAVFAC Mid-Atlantic
Northeast IPT
9742 Maryland Avenue
Norfolk, VA, 23511-3095

RE: Northrop Grumman, Naval Weapons Industrial Reserve Plant (NWIRP) and Grumman Steel Los Sites, NYSDEC Site No.'s I-30-003 A & B.

Dear Ms. Fly:

Tetra Tech NUS Inc., on behalf of the Department of the Navy NAVFAC Midlantic, has submitted an application to remove the GM 38 Area Groundwater Extraction and Treatment system impregnated Xeolite™ resin from the air discharge treatment system. Currently, the air treatment system uses a combined activated carbon with permanganate impregnated resin treatment train. The New York State Department of Environmental Conservation (NYSDEC) has reviewed the Department of the Navy application and concurs with the findings presented.

The routine monitoring, as detailed in Table 1, clearly indicates that vinyl chloride, one of the main contaminants of concern, has diminished to almost non-detect, and discharge concentrations have dropped to below the limit to require air treatment for the other contaminants as well. However, NAVFAC Midlantic is still proposing activated carbon to reduce the other discharge contaminant levels. Therefore, the NYSDEC hereby approves the proposed changes to the GM 38 Area air treatment. The Xeolite™ resin beds will remain in place should reactivation, based on routine monitoring, be required.

If you have any questions in the interim, please contact me at (518)402-9620.

Sincerely,

Steven M. Scharf, P.E.
Project Engineer
Remedial Action Bureau A
Division of Environmental Remediation

EC: J. Swartwout
S. Scharf
W. Parish, Region 1
S. Karpinski, NYSDOH
E. Hannon, NGC
D. Stern, Arcadis
D. Brayack, TTNUS



NOR-01264

November 21, 2011

Mr. Stephen Scharf
New York Department of Environmental Conservation
Division of Environmental Remediation
Bureau of Remedial Action A
625 Broadway, 11th Floor
Albany, New York 12233-7015

Reference: CLEAN Contract No. N62470-08-D-1001
Contract Task Order WE06

Subject: Proposed Modification to Discharge Limits for Off Gas Volatile Organic Compounds (VOCs)
for Air Stripping Tower
GM-38 Offsite Groundwater Treatment Plant,
NWIRP Bethpage, New York

Dear Mr. Scharf:


On behalf of the Navy, please find enclosed a copy of the subject document. This document presents an evaluation of current concentrations of off gas VOCs from the GM-38 groundwater treatment plant air-stripping tower (prior to treatment with granular activated carbon). Maximum emission rates were re-evaluated due to decreasing maximum concentrations of target VOCs in un-treated air stripper AS-1 off gas. In addition, breakthrough of target contaminants (e.g., cis-1,2-dichloroethene) is beginning to occur in the granular activated carbon bed. Maximum emission rates were re-evaluated to provide a determination if breakthrough of contaminants would trigger the need for a replacement of the granular activated carbon bed.

Existing Discharge Goals were established in the "Final Operation, Maintenance and Monitoring Plan for Groundwater Treatment Plant GM-38 Area Groundwater Remediation" prepared by Tetra Tech EC (April 2010). Existing goals were based on emission estimates for a 95% reduction (see Attachment A), instead of being based on the original DAR-1 analysis of air stripper off gas. Emission estimates were calculated using the air stripper design flow rate of 8,000 cubic feet per minute (cfm), and previous contaminant discharge rates in pounds per hour (lb/hr). Original emission estimates are provided in Attachment B.

Proposed Revised Discharge Goals were calculated using an average flow rate of 9,200 cfm, January to March 2011 VOC loading rates (taken from the Quarterly Operations Report First Quarter 2011 from ECOR Federal Services), and the Actual Annual % of Annual Guideline Concentrations (AGCs), taken from the revised DAR-1 Model Output. The revised DAR-1 Model Output is provided in Attachment C. Existing Discharge Goals and Proposed Revised Discharge Goals are compared in tabular format in the first page of the attachment. Proposed Revised Discharge Goals for trichloroethene (TCE) are the same as previous. The proposed limit for tetrachloroethene (PCE) is approximately 10 times the previous limit, and vinyl chloride is approximately 2 times the previous limit. Revised Discharge Goals for 1,2-dichloroethene (goals are the same for cis-1,2-dichloroethene) are 100 times greater than previously established limits. It is recommended that these revised limits replace previous discharge goals, and treatment of air stripper off gas by granular activated carbon is recommended to continue for TCE and PCE, with no treatment required for vinyl chloride and 1,2-dichloroethene.

If you have any questions please contact Ms. Lora Fly, NAVFAC Mid-LANT, at (757) 341-2012.

Sincerely,



David D. Brayack, P.E.
Project Manager

Enclosure: (1) Proposed Modification to Discharge Limits for Off Gas Volatile Organic Compounds
(VOCs) for Air Stripping Tower
GM-38 Offsite Groundwater Treatment Plant

Distribution:

Mid-Lant, Lora Fly
NYSDEC (Albany), Henry Wilkie
NYSDOH (Troy), Steve Karpinski
NAVAIR, Richard Smith
USEPA, Carol Stein
NGC, Kent Smith
Tetra Tech NUS, Dave Brayack
ECOR Solutions, Al Taormina
Administrative Record
Public Repository
Project File

Tetra Tech NUS, Inc.

5700 Lake Wright Drive, Suite 309, Norfolk, VA 23502
Tel 757.461.3768 Fax 757.461.4148 www.ttnus.com

TABLE 1
COMPARISON OF EXISTING DISCHARGE GOALS WITH ACTUAL EMISSIONS AND PROPOSED DISCHARGE GOALS
AIR STRIPPING TOWER GM-38 OFFSITE GROUNDWATER TREATMENT PLANT
NWIRP BETHPAGE, NEW YORK

Chemical	Existing Discharge Goal		Actual January to March 2011 Values (Pre-Off Gas Treatment)		Proposed Revised Discharge Goals based on DAR-1 Analysis	
	Existing Discharge Loading Rate (pounds (lbs)/hour) ⁽¹⁾	Equivalent Existing Discharge Goals (µg/m ³) ⁽²⁾	Actual Jan-Mar 2011 Concentration (µg/m ³) ⁽³⁾	Actual VOC Loading Pre-Off Gas Treatment (lbs/hour) ⁽⁴⁾	Proposed Discharge Loading Rate (lbs/hour) ⁽⁵⁾	Equivalent Proposed Discharge Goal (µg/m ³) ⁽⁵⁾
TCE	0.09	2,600	10,000	0.345	0.09	2,600
PCE	0.02	580	6,800	0.234	0.18	5,100
Vinyl Chloride	0.01	290	76	0.003	0.02	560
1,2-Dichloroethene (total)	0.03	870	750	0.026	11	greater than 100,000

Notes:

⁽¹⁾Existing Discharge Goals are based on the design flow rate of 8,000 cfm. Existing Discharge Goals were taken from the Final Operations and Maintenance Plan for GM-38 Area Groundwater Remediation from Tetra Tech EC. Existing goals were based on emission estimates for a 95% reduction, and not the previous DAR-1 Analysis. Attachment B (provided at the end of this package) provides the original emission estimates.

⁽²⁾Existing Discharge Goals were calculated using the actual flow rate of 9,200 cfm and the existing discharge loading rate in pounds per hour (lb/hr).

⁽³⁾Values were taken from the Quarterly Operations Report First Quarter 2011 from ECOR Federal Services. Values were the maximum effluent concentration in off gas from air stripper stack AS-1 prior to treatment with vapor phase granular activated carbon (GAC), for the months of January, February and March 2011.

⁽⁴⁾Actual VOC Loading was calculated using an average flow rate of 9,200 cfm and the January-March 2011 concentrations. Existing off gas treatment consists of two stage vapor phase GAC followed by potassium permanganate zeolite media to provide additional treatment for vinyl chloride.

⁽⁵⁾Values were calculated using an average flow rate of 9,200 cfm, and the Actual Annual % of the AGCs from the 2011 DAR-1 Model Output to achieve air quality requirements.

ATTACHMENT A
2008 AIR PERMIT SUBMITTAL

New York State Department of Environmental Conservation Air Permit Application



DEC ID									
-									

APPLICATION ID									
-							/		

OFFICE USE ONLY									

Section I - Certification

Title V Certification	
I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gather and evaluate the information submitted. Based on my inquiry of the person or persons directly responsible for gathering the information [required pursuant to 6 NYCRR 201-6.3(d)] I believe the information is, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fines and imprisonment for knowing violations.	
Responsible Official	Title
Signature	Date ____ / ____ / ____

State Facility Certification	
I certify that this facility will be operated in conformance with all provisions of existing regulations.	
Responsible Official	Title
Signature	Date ____ / ____ / ____

Section II - Identification Information

Title V Facility Permit <u>N/A</u>	<input type="checkbox"/> New	<input type="checkbox"/> Significant Modification	<input type="checkbox"/> Administrative Amendment	State Facility Permit <u>N/A</u>	<input type="checkbox"/> New	<input type="checkbox"/> Modification
<input type="checkbox"/> Renewal	<input type="checkbox"/> Minor Modification	General Permit Title: _____		General Permit Title: _____		
<input checked="" type="checkbox"/> Application involves construction of new facility			<input type="checkbox"/> Application involves construction of new emission unit(s)			

Owner/Firm			
Name <u>US Navy/NAVFAC Midlant</u>			
Street Address <u>9742 Maryland Ave, Bldg Z-144</u>			
City <u>Norfolk</u>	State <u>VA</u>	Country <u>US</u>	Zip <u>23511-3095</u>
Owner Classification <input checked="" type="checkbox"/> Federal		<input type="checkbox"/> State <input type="checkbox"/> Municipal	
<input type="checkbox"/> Corporation/Partnership		<input type="checkbox"/> Individual	
Taxpayer ID [] [] [] [] [] [] [] [] [] []			
Facility			<input type="checkbox"/> Confidential
Name <u>Naval Weapons Industrial Reserve Plant (NWIRP) GM-38 Area</u>			
Location Address <u>Bethpage</u>			
<input type="checkbox"/> City / <input checked="" type="checkbox"/> Town / <input type="checkbox"/> Village <u>Oyster Bay, New York</u>			Zip <u>11714</u>
Project Description			<input type="checkbox"/> Continuation Sheet(s)
<u>Air stripping of groundwater to remove VOCs</u>			

Owner/Firm Contact Mailing Address			
Name (Last, First, Middle Initial) <u>Fly, Lora</u>		Phone No. (757)444-0781	
Affiliation <u>Department of the Navy</u>		Title <u>Remedial PM</u>	
Street Address <u>9742 Maryland Ave. Bldg Z-144</u>		Fax No. ()	
City <u>Norfolk</u>	State <u>VA</u>	Country <u>US</u>	Zip <u>23511-3095</u>
Facility Contact Mailing Address			
Name (Last, First, Middle Initial) <u>Same</u>		Phone No. ()	
Affiliation		Title	
Street Address		Fax No. ()	
City	State	Country	Zip

New York State Department of Environmental Conservation
Air Permit Application



DEC ID									
-									

Section III - Facility Information

Classification					
<input type="checkbox"/> Hospital	<input type="checkbox"/> Residential	<input type="checkbox"/> Educational/Institutional	<input type="checkbox"/> Commercial	<input checked="" type="checkbox"/> Industrial	<input type="checkbox"/> Utility

Affected States (Title V Only) N/A					
<input type="checkbox"/> Vermont	<input type="checkbox"/> Massachusetts	<input type="checkbox"/> Rhode Island	<input type="checkbox"/> Pennsylvania	Tribal Land: _____	
<input type="checkbox"/> New Hampshire	<input type="checkbox"/> Connecticut	<input type="checkbox"/> New Jersey	<input type="checkbox"/> Ohio	Tribal Land: _____	

SIC Codes									
9999									

Facility Description		<input type="checkbox"/> Continuation Sheet(s)
Groundwater Remediation by Air Stripping followed by Vapor-Phase GAC for emission control		

Compliance Statements (Title V Only) N/A	
<p>I certify that as of the date of this application the facility is in compliance with all applicable requirements: <input type="checkbox"/> YES <input type="checkbox"/> NO</p> <p>If one or more emission units at the facility are not in compliance with all applicable requirements at the time of signing this application (the 'NO' box must be checked), the noncomplying units must be identified in the "Compliance Plan" block on page 8 of this form along with the compliance plan information required. For all emission units at this facility that are operating <u>in compliance</u> with all applicable requirements complete the following:</p> <ul style="list-style-type: none"> <input type="checkbox"/> This facility will continue to be operated and maintained in such a manner as to assure compliance for the duration of the permit, except those units referenced in the compliance plan portion of Section IV of this application. <input type="checkbox"/> For all emission units, subject to any applicable requirements that will become effective during the term of the permit, this facility will meet all such requirements on a timely basis. <input type="checkbox"/> Compliance certification reports will be submitted at least once a year. Each report will certify compliance status with respect to each requirement, and the method used to determine the status. 	

Facility Applicable Federal Requirements N/A										<input type="checkbox"/> Continuation Sheet(s)
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause	
	CERCLA	all substantive requirements								

Facility State Only Requirements										<input type="checkbox"/> Continuation Sheet(s)
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause	



DEC ID									
-					-				

Section III - Facility Information (continued)

Facility Compliance Certification N/A										<input type="checkbox"/> Continuation Sheet(s)		
Rule Citation												
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause			
<input type="checkbox"/> Applicable Federal Requirement		<input type="checkbox"/> Capping		CAS No.	Contaminant Name							
<input type="checkbox"/> State Only Requirement				-	-							
Monitoring Information												
<input type="checkbox"/> Ambient Air Monitoring			<input type="checkbox"/> Work Practice Involving Specific Operations				<input type="checkbox"/> Record Keeping/Maintenance Procedures					
Description												
Work Practice		Process Material					Reference Test Method					
Type	Code	Description										
				Parameter				Manufacturer Name/Model No.				
Code		Description										
Limit				Limit Units								
Upper		Lower		Code		Description						
Averaging Method			Monitoring Frequency				Reporting Requirements					
Code	Description		Code	Description			Code	Description				

Facility Emissions Summary										<input type="checkbox"/> Continuation Sheet(s)	
CAS No.	Contaminant Name				PTE		Actual (lbs/yr)				
					(lbs/yr)	Range Code					
NY075 - 00 - 5	PM-10										
NY075 - 00 - 0	PARTICULATES										
7446 - 09 - 5	SULFUR DIOXIDE										
NY210 - 00 - 0	OXIDES OF NITROGEN										
630 - 08 - 0	CARBON MONOXIDE										
7439 - 92 - 1	LEAD										
NY998 - 00 - 0	VOC				117						
NY100 - 00 - 0	HAP				110						
0079 - 01 - 6	Trichloroethylene				99						
00075 - 01 - 4	Vinyl Chloride				3.7						
00540 - 59 - 0	1,2-Dichloroethylene				7.3						
-											
-											

New York State Department of Environmental Conservation
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information

Emission Unit Description										<input type="checkbox"/> Continuation Sheet(s)
EMISSION UNIT	0	-	0	0	E	U	1			
Air Stripper AS-1 for groundwater remediation, provided with activated carbon for emission control.										
The emission point is stack 00ST-1. The 2-stage VGAC is followed by a 3rd vessel containing a potassium permanganate zeolite media for increased VC capacity.										

Building					<input type="checkbox"/> Continuation Sheet(s)	
Building	Building Name			Length (ft)	Width (ft)	Orientation
BLDG-1	Treatment Plant			75	75	0

Emission Point							<input type="checkbox"/> Continuation Sheet(s)
EMISSION PT.	00ST1						
Ground Elev. (ft)	Height (ft)	Height Above Structure (ft)	Inside Diameter (in)	Exit Temp. (°F)	Cross Section		
90	40	15	36	80	Length (in)	Width (in)	
Exit Velocity (FPS)	Exit Flow (ACFM)	NYTM (E) (KM)	NYTM (N) (KM)	Building	Distance to Property Line (ft)	Date of Removal	
19	8020			BLDG-1	50		
EMISSION PT.							
Ground Elev. (ft)	Height (ft)	Height Above Structure (ft)	Inside Diameter (in)	Exit Temp. (°F)	Cross Section		
					Length (in)	Width (in)	
Exit Velocity (FPS)	Exit Flow (ACFM)	NYTM (E) (KM)	NYTM (N) (KM)	Building	Distance to Property Line (ft)	Date of Removal	

Emission Source/Control								<input type="checkbox"/> Continuation Sheet(s)
Emission Source		Date of Construction	Date of Operation	Date of Removal	Control Type		Manufacturer's Name/Model No.	
ID	Type				Code	Description		
AS-1	I				048	Granular Act. Carbon	Air Stripping Column	
Design Capacity	Design Capacity Units			Waste Feed		Waste Type		
	Code	Description		Code	Description	Code	Description	
Emission Source		Date of Construction	Date of Operation	Date of Removal	Control Type		Manufacturer's Name/Model No.	
ID	Type				Code	Description		
Design Capacity	Design Capacity Units			Waste Feed		Waste Type		
	Code	Description		Code	Description	Code	Description	

New York State Department of Environmental Conservation
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information (continued)

Process Information										<input type="checkbox"/> Continuation Sheet(s)	
EMISSION UNIT 0 - 00 E U 1								PROCESS		P R 1	
Description											
The remedial system is air stripping, using a packed column at a groundwater flow rate of 1,100 gpm (plus 100 gpm recycle, for a total of 1,200 gpm). Vapor phase treatment includes the use of 3 vessels, a 2-stage GAC unit, followed by a 3rd vessel containing a potassium permanganate impregnated zeolite for increased VC capacity. Prior to entering the vapor-phase GAC adsorption system, the humidity of the air stripper exhaust is reduced to approximately 50 percent or less to optimize the efficiency of the vapor-phase GAC.											
Air Stripper AS-1: Existing. Type: Vertical, Cylindrical Construction: Aluminum											
Packing: 25-foot Jaeger Tripack. Dimensions: 10.0 ft. Dia x 47 ft. H											
Source Classification Code (SCC)		Total Thruput		Thruput Quantity Units							
		Quantity/Hr	Quantity/Yr	Code	Description						
<input type="checkbox"/> Confidential <input checked="" type="checkbox"/> Operating at Maximum Capacity <input type="checkbox"/> Activity with Insignificant Emissions		Operating Schedule		Building		Floor/Location					
		Hrs/Day	Days/Yr								
		24	365	BLDG-1		Main					
Emission Source/Control Identifier(s)											
AS-1											
EMISSION UNIT -								PROCESS			
Description											
Source Classification Code (SCC)		Total Thruput		Thruput Quantity Units							
		Quantity/Hr	Quantity/Yr	Code	Description						
<input type="checkbox"/> Confidential <input type="checkbox"/> Operating at Maximum Capacity <input type="checkbox"/> Activity with Insignificant Emissions		Operating Schedule		Building		Floor/Location					
		Hrs/Day	Days/Yr								
Emission Source/Control Identifier(s)											

New York State Department of Environmental Conservation
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information (continued)

Emission Unit	Emission Point	Process	Emission Source	Emission Unit Applicable Federal Requirements										<input type="checkbox"/> Continuation Sheet(s)	
				Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause		
-															
-															
-															
-															

Emission Unit	Emission Point	Process	Emission Source	Emission Unit State Only Requirements										<input type="checkbox"/> Continuation Sheet(s)	
				Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause		
-															
-															
-															
-															

Emission Unit Compliance Certification											<input type="checkbox"/> Continuation Sheet(s)
Rule Citation											
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause		
6	NYCRR	212									
<input checked="" type="checkbox"/> Applicable Federal Requirement				<input type="checkbox"/> State Only Requirement				<input type="checkbox"/> Capping			
Emission Unit	Emission Point	Process	Emission Source	CAS No.			Contaminant Name				
0-00EU1	00ST1	PR1	AS-1	00079 - 01 - 6			Trichloroethylene				
Monitoring Information											
<input type="checkbox"/> Continuous Emission Monitoring				<input type="checkbox"/> Monitoring of Process or Control Device Parameters as Surrogate							
<input checked="" type="checkbox"/> Intermittent Emission Testing				<input type="checkbox"/> Work Practice Involving Specific Operations							
<input type="checkbox"/> Ambient Air Monitoring				<input type="checkbox"/> Record Keeping/Maintenance Procedures							
Description											
Monthly grab samples analyzed for VOCs from the vapor phase treatment system influent, effluent and two intermediate locations.											
Work Practice		Process Material					Reference Test Method				
Type	Code	Description									
Parameter		Manufacturer Name/Model No.									
Code	Description										
23	Concentration										
Limit			Limit Units								
Upper	Lower	Code	Description								
3,125		255	micrograms per cubic meter								
Averaging Method			Monitoring Frequency			Reporting Requirements					
Code	Description	Code	Description	Code	Description						
01	Instantaneous	05	Monthly	10	Upon Request						

New York State Department of Environmental Conservation
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information (continued)

Determination of Non-Applicability (Title V Only) N/A <input type="checkbox"/> Continuation Sheet(s)										
Rule Citation										
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause	
Emission Unit		Emission Point		Process		Emission Source		<input type="checkbox"/> Applicable Federal Requirement <input type="checkbox"/> State Only Requirement		
Description										
Rule Citation										
Title	Type	Part	Sub Part	Section	Sub Division	Paragraph	Sub Paragraph	Clause	Sub Clause	
Emission Unit		Emission Point		Process		Emission Source		<input type="checkbox"/> Applicable Federal Requirement <input type="checkbox"/> State Only Requirement		
Description										
Process Emissions Summary <input type="checkbox"/> Continuation Sheet(s)										
EMISSION UNIT	0 - 0 0 E U 1						PROCESS	P	R	1
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined		
0079 - 01 - 6	Trichloroethylene					95	1.87	02		
PTE			Standard Units	PTE How Determined		Actual				
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)			
0.09	99			02						
EMISSION UNIT	0 - 0 0 E U 1						PROCESS	P	R	1
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined		
00075 - 01 - 4	Vinyl Chloride					95	0.17	03		
PTE			Standard Units	PTE How Determined		Actual				
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)			
0.01	3.7			02						
EMISSION UNIT	0 - 0 0 E U 1						PROCESS	P	R	1
CAS No.	Contaminant Name			% Thruput	% Capture	% Control	ERP (lbs/hr)	ERP How Determined		
000540 - 59 - 0	1,2-Dichloroethylene					95	0.6	02		
PTE			Standard Units	PTE How Determined		Actual				
(lbs/hr)	(lbs/yr)	(standard units)				(lbs/hr)	(lbs/yr)			
0.03	7.3			02						

New York State Department of Environmental Conservation
Air Permit Application



DEC ID									
-									

Section IV - Emission Unit Information (continued)

EMISSION UNIT		Emission Unit Emissions Summary				<input type="checkbox"/> Continuation Sheet(s)
0	-	0	0	E	U	1
CAS No.		Contaminant Name				
00107- 06 - 2		1,2-Dichloroethane				
ERP (lbs/yr)	PTE Emissions		Actual			
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
13.4	Below Reporting Threshold BRT					
CAS No.		Contaminant Name				
00108 - 88 - 3		Toluene				
ERP (lbs/yr)	PTE Emissions		Actual			
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
72.7	BRT		BRT			
CAS No.		Contaminant Name				
01330- 20 - 7		Xylene				
ERP (lbs/yr)	PTE Emissions		Actual			
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
77.1	BRT		BRT			
CAS No.		Contaminant Name				
-		1,1,2-Trichloroethane				
ERP (lbs/yr)	PTE Emissions		Actual			
	(lbs/hr)	(lbs/yr)	(lbs/hr)	(lbs/yr)		
	BRT		BRT			

Compliance Plan													<input type="checkbox"/> Continuation Sheet(s)
For any emission units which are <u>not in compliance</u> at the time of permit application, the applicant shall complete the following													
Consent Order			Certified progress reports are to be submitted every 6 months beginning ___ / ___ / ___										
Emission Unit	Process	Emission Source	Applicable Federal Requirement										
			Title	Type	Part	Sub Part	Section	Sub Division	Parag.	Sub Parag.	Clause	Sub Clause	
Remedial Measure / Intermediate Milestones											R/I	Date Scheduled	

New York State Department of Environmental Conservation
Air Permit Application



DEC ID											
-											

Section IV - Emission Unit Information (continued)

Request for Emission Reduction Credits										<input type="checkbox"/> Continuation Sheet(s)	
EMISSION UNIT -											
Emission Reduction Description											
Contaminant Emission Reduction Data											
Baseline Period ____ / ____ / ____ to ____ / ____ / ____						Reduction					
						Date		Method			
CAS No.		Contaminant Name				ERC (lbs/yr)					
-		-				Netting		Offset			
-		-									
-		-									
Facility to Use Future Reduction											
Name						APPLICATION ID					
						-					
Location Address											
<input type="checkbox"/> City / <input type="checkbox"/> Town / <input type="checkbox"/> Village						State		Zip			

Use of Emission Reduction Credits										<input type="checkbox"/> Continuation Sheet(s)	
EMISSION UNIT -											
Proposed Project Description											
Contaminant Emissions Increase Data											
CAS No.		Contaminant Name				PEP (lbs/yr)					
-		-									
Statement of Compliance											
<input type="checkbox"/> All facilities under the ownership of this "ownership/firm" are operating in compliance with all applicable requirements and state regulations including any compliance certification requirements under Section 114(a)(3) of the Clean Air Act Amendments of 1990, or are meeting the schedule of a consent order.											
Source of Emission Reduction Credit - Facility											
Name						PERMIT ID					
						-					
Location Address											
<input type="checkbox"/> City / <input type="checkbox"/> Town / <input type="checkbox"/> Village						State		Zip			
Emission Unit		CAS No.		Contaminant Name		ERC (lbs/yr)					
-		-		-		Netting		Offset			
-		-		-							
-		-		-							



DEC ID									
-									

Supporting Documentation

- P.E. Certification (form attached)
- List of Exempt Activities (form attached)
- Plot Plan
- Methods Used to Determine Compliance (form attached)
- Calculations
- Air Quality Model (____ / ____ / ____)
- Confidentiality Justification
- Ambient Air Monitoring Plan (____ / ____ / ____)
- Stack Test Protocols/Reports (____ / ____ / ____)
- Continuous Emissions Monitoring Plans/QA/QC (____ / ____ / ____)
- MACT Demonstration (____ / ____ / ____)
- Operational Flexibility: Description of Alternative Operating Scenarios and Protocols
- Title IV: Application/Registration
- ERC Quantification (form attached)
- Use of ERC(s) (form attached)
- Baseline Period Demonstration
- Analysis of Contemporaneous Emission Increase/Decrease
- LAER Demonstration (____ / ____ / ____)
- BACT Demonstration (____ / ____ / ____)
- Other Document(s): _____ (____ / ____ / ____)
 _____ (____ / ____ / ____)
 _____ (____ / ____ / ____)
 _____ (____ / ____ / ____)
 _____ (____ / ____ / ____)
 _____ (____ / ____ / ____)
 _____ (____ / ____ / ____)
 _____ (____ / ____ / ____)
 _____ (____ / ____ / ____)
 _____ (____ / ____ / ____)
 _____ (____ / ____ / ____)
 _____ (____ / ____ / ____)

ATTACHMENT B

2008 EMISSION ESTIMATES BASED ON 95% REMOVAL

**ATTACHMENT 1
Emission Estimate**

POTENTIAL EMISSION ESTIMATES,
USED TO DEVELOP 95% REDUCTION
OF EMISSION VALUES AS BASED ON
INFLUENT GROUNDWATER CONCENTRATIONS
(95% REDUCTION OF EMISSION
VALUES ARE PROVIDED
ON PAGE 7 OF THE 2008 AIR
PERMIT APPLICATION PROCESS
EMISSIONS SUMMARY)

Feed Water Flow 1,100 gpm: max or normal
250 m³/hr
Water Flow Including Recycle 1,200 gpm: max or normal
273 m³/hr
Air Flow 8,000 cfm
13,592 m³/hr
A/W vol ratio 50

EXAMPLE EMISSION CALC: Vinyl Chloride
4.8 ug/L x 1000 L/m³ x 250 m³ water/13,623 m³ air = 88 ug/m³

16

Name	CAS Number	Toxicity: H/M/L ²	VOC ³	HAP ⁴	GW Conc. ¹		Effluent Conc. ¹		Uncontrolled Stripper Exhaust							
					Max ug/L	Avg ug/L	Max ug/L	Avg ug/L	Max lb/day	Avg lb/day	Max lb/hr	Avg lb/hr	Max gm/sec	Avg gm/sec	Max ug/m ³	Avg ug/m ³
1,1,1-Trichloroethane (Methyl Chloroform)	00071-55-6	L	No	Yes	3	3.0			0.04	0.04	0.00	0.00	2.08E-04	2.08E-04	55	55
1,1,2-Trichloroethane	00079-00-5	M	Yes	Yes	3.5	0.3			0.05	0.00	0.00	0.00	2.43E-04	2.08E-05	64	6
1,1-Dichloroethane	00075-34-3	L	Yes	Yes	4	0.7			0.05	0.01	0.00	0.00	2.77E-04	4.85E-05	74	13
1,2-Dichloroethane	00107-06-2	M	Yes	Yes	3	1.0	0.3	0.1	0.04	0.01	0.00	0.00	1.87E-04	6.24E-05	55	18
1,1-Dichloroethylene (Vinylidene Chloride)	00075-35-4	M	Yes	Yes	9	1.6			0.12	0.02	0.00	0.00	6.24E-04	1.11E-04	165	29
1,2-Dichloroethylene	00540-59-0	M	Yes	No	1,100	31.5	1.3	0.0	14.51	0.42	0.60	0.02	7.62E-02	2.18E-03	20,219	579
Benzene	00071-43-2	H	Yes	Yes	4	0.1			0.05	0.00	0.00	0.00	2.77E-04	6.94E-06	74	2
Carbon Tetrachloride	00056-23-5	H	Yes	Yes	4	0.1			0.05	0.00	0.00	0.00	2.77E-04	6.94E-06	74	2
Chlorobenzene (Monochlorobenzene)	00108-90-7	M	Yes	Yes	1	0.1			0.01	0.00	0.00	0.00	6.94E-05	6.94E-06	18	2
Chloroform	00067-66-3	M	Yes	Yes	2	0.8			0.03	0.01	0.00	0.00	1.39E-04	5.55E-05	37	15
Methyl Tert Butyl Ether	01634-04-4	M	Yes	Yes	2	0.1			0.03	0.00	0.00	0.00	1.39E-04	6.94E-06	37	2
Tetrachloroethylene	00127-18-4	M	Yes	Yes	900	33.8	0.9	0.0	11.88	0.45	0.49	0.02	6.24E-02	2.34E-03	16,543	621
Toluene	00108-88-3	L	Yes	Yes	15	0.7			0.20	0.01	0.01	0.00	1.04E-03	4.85E-05	276	13
Trichloroethylene	00079-01-6	M	Yes	Yes	3,400	411.5	4.5	0.5	44.86	5.43	1.87	0.23	2.35E-01	2.85E-02	62,494	7,564
Vinyl chloride	00075-01-4	H	Yes	Yes	300	4.8	0.0	0.0	3.96	0.06	0.17	0.00	2.08E-02	3.33E-04	5,514	88
Xylenes	01330-20-7	M	Yes	Yes	16	0.2			0.21	0.00	0.01	0.00	1.11E-03	1.39E-05	294	4
Total VOCs					5,764	487.3	7.0	0.6	76.05	6.43	3.17	0.27				
Total HAPs					4,667	458.8	5.7	0.6	61.57	6.05	2.57	0.25				

Total Uncontrolled VOC 2,347 lb/yr
Total Uncontrolled HAP 2,209 lb/yr

1. Source: "GM-38 Groundwater Remedy Analysis Report", February 2003
2. Source: DAR-1 AGC/SGC Tables, NYSDEC Division of Air Resources, Air Toxics Section, September 10, 2007.
3. Source: 6 NYCRR Part 200.1(cg)
4. Source: 6 NYCRR Part 200.1(ag)

**ATTACHMENT 1
Emission Estimate**

Feed Water Flow 1,100 gpm: max or normal
250 m³/hr
Water Flow Including Recycle 1,200 gpm: max or normal
273 m³/hr
Air Flow 8,000 cfm
13,592 m³/hr
A/W vol ratio 50

Controlled Stripper Exhat

Name	CAS Number	Toxicity: H/M/L ²	VOC ³	HAP ⁴	Control by	Max	Avg	Max	Avg
					GAC	lb/day	lb/day	gm/sec	gm/sec
1,1,1-Trichloroethane (Methyl Chloroform)	00071-55-6	L	No	Yes	95%	0.00	0.00	1.04E-05	1.04E-05
1,1,2-Trichloroethane	00079-00-5	M	Yes	Yes	95%	0.00	0.00	1.21E-05	1.04E-06
1,1-Dichloroethane	00075-34-3	L	Yes	Yes	95%	0.00	0.00	1.39E-05	2.43E-06
1,2-Dichloroethane	00107-06-2	M	Yes	Yes	95%	0.00	0.00	9.36E-06	3.12E-06
1,1-Dichloroethylene (Vinylidene Chloride)	00075-35-4	M	Yes	Yes	95%	0.01	0.00	3.12E-05	5.55E-06
1,2-Dichloroethylene	00540-59-0	M	Yes	No	95%	0.73	0.02	3.81E-03	1.09E-04
Benzene	00071-43-2	H	Yes	Yes	95%	0.00	0.00	1.39E-05	3.47E-07
Carbon Tetrachloride	00056-23-5	H	Yes	Yes	95%	0.00	0.00	1.39E-05	3.47E-07
Chlorobenzene (Monochlorobenzene)	00108-90-7	M	Yes	Yes	95%	0.00	0.00	3.47E-06	3.47E-07
Chloroform	00067-66-3	M	Yes	Yes	95%	0.00	0.00	6.94E-06	2.77E-06
Methyl Tert Butyl Ether	01634-04-4	M	Yes	Yes	95%	0.00	0.00	6.94E-06	3.47E-07
Tetrachloroethylene	00127-18-4	M	Yes	Yes	95%	0.59	0.02	3.12E-03	1.17E-04
Toluene	00108-88-3	L	Yes	Yes	95%	0.01	0.00	5.20E-05	2.43E-06
Trichloroethylene	00079-01-6	M	Yes	Yes	95%	2.24	0.27	1.18E-02	1.43E-03
Vinyl chloride	00075-01-4	H	Yes	Yes	95%	0.20	0.00	1.04E-03	1.66E-05
Xylenes	01330-20-7	M	Yes	Yes	95%	0.01	0.00	5.55E-05	6.94E-07
Total VOCs						3.80	0.32		
Total HAPs						3.08	0.30		

Total Controlled VOC 117 lb/yr
Total Controlled HAP 110 lb/yr

1. Source: "GM-38 Groundwater Remedy Analysis Report", February 2003
2. Source: DAR-1 AGC/SGC Tables, NYSDEC Division of Air Resources, Air Tox
3. Source: 6 NYCRR Part 200.1(cg)
4. Source: 6 NYCRR Part 200.1(ag)

ATTACHMENT C
2011 DISCHARGE GOALS AND 2011 DAR-1 ANALYSIS

Tetra Tech NUS		STANDARD CALCULATION SHEET	
CLIENT: US CLEAN	FILE No:	BY: SK	PAGE: 1 of 1
SUBJECT: Calculation of Current Discharge Goals GM-38 Area NWIRP Bethpage, New York		CHECKED BY:	DATE: 9/7/2011

1. Purpose:

To calculate current discharge goals for Trichloroethene (TCE), Tetrachloroethene (PCE), Vinyl Chloride, cis 1,2-Dichloroethene, and 1,2-Dichloroethene (total), for treatment of off-gas from the air stripper stack AS-1.

2. Approach:

From the Contaminant Assessment Summary of the DAR-1 Model output for TCE, PCE, Vinyl Chloride, cis 1,2-Dichloroethene, and 1,2-Dichloroethene (total) (see DAR-1 output for analysis inputs), use the Actual Annual % of the Annual Guideline Concentration (AGC), a current average flow rate of 9,200 cubic feet per minute (cfm), and influent chemical emission rates in pounds per hour (lb/hour) and pounds per year (lb/year) to back calculate current discharge goals.

3. Calculation of Current Discharge Goals:

Chemical	Current Actual Annual % of AGC ⁽¹⁾	Current Maximum Concentration (µg/m ³) ⁽²⁾	Current Chemical Emission Rate Prior to Treatment (lb/hour) ⁽³⁾	Current Chemical Emission Rate Prior to Treatment (lb/year) ⁽³⁾	Calculated Discharge Goal (lb/hr) ⁽⁴⁾	Calculated Discharge Goal (lb/year) ⁽⁴⁾	Maximum Allowable Concentration (µg/m ³) ⁽⁴⁾
TCE	390.6	10,000	0.3446	3,019	0.0882	770	2,600
PCE	132.8	6,800	0.2344	2,053	0.1764	1,500	5,100
Vinyl Chloride	13.49	76	0.0026	22.94	0.0194	170	560
cis 1,2-Dichloroethene	0.2322	750	0.0258	226.4	11.13	98,000	320,000
1,2-Dichloroethene (total)	0.2322	750	0.0258	226.4	11.13	98,000	320,000

Notes:

⁽¹⁾Actual Annual % of the AGCs is from the attached DAR-1 Model Output.

⁽²⁾Values were taken from the Quarterly Operations Report First Quarter 2011 (June 2011) from ECOR Federal Services. Values were the maximum effluent concentration in off gas from air stripper stack AS-1 for the months of January, February, and March 2011.

⁽³⁾Chemical Emission Rates were calculated from maximum concentrations and an average flow rate of 9,200 cfm.

⁽⁴⁾Discharge Goals are based on a flow of 9,200 cfm, and calculated from the Actual Annual % of the AGCs from the DAR-1 Model Output to achieve air quality requirements. The summary of additional inputs for this model run is provided in the DAR-1 Model Output. Stack height is 40 feet, and the property line was evaluated at a distance of 50 feet.

BETHPAGE SITE GM-38 OFF-SITE GROUNDWATER AIR STRIPPER STACK EMISSIONS
 DAR-1 MODEL OUTPUT, POINT SOURCE (STACK EMISSIONS) TYPE
 INCLUDES ISCLT MODELING SUMMARY

- I. Summary of Inputs for Model Run to Nearest Property Line (50 feet), worst case scenario (highest contaminant concentrations seen in first quarter 2011 in untreated effluent from Air Stripper AS-1 prior to treatment with granular activated carbon (GAC))

Chemical	CAS No. 00079-01- 6 (TCE)	CAS No. 00127-18- 4 (PCE)	CAS No. 00075-01-4 (Vinyl Chloride)	CAS No. 00156-59-2 (cis 1,2- Dichloroethene)	CAS No. 00540-59-0 (1,2- Dichloroethene, total)
Emission Rate Prior to Treatment ⁽¹⁾ (lb/hour)	0.3444	0.2342	0.0026	0.0258	0.0258
Emission Rate Prior to Treatment ⁽¹⁾ (lb/year)	3,017	2,052	22.93	226.0	226.0
Maximum Concentration of Untreated Off Gas ($\mu\text{g}/\text{m}^3$) ⁽¹⁾	10,000	6,800	76	750	750
Annual Guideline Concentration (AGC) ($\mu\text{g}/\text{m}^3$)	0.5	1.0	0.11	63	63
Short-term Guideline Concentration (SGC) ($\mu\text{g}/\text{m}^3$)	14,000	1,000	180,000	--	--

HA	Height Above stack/ maximum height of plume (HA, feet)	15
SH	Stack Height/Treatment Building Air Stack (SH, feet)	40
D	Stack Diameter (D, inches)	36
T	Stack Exit Temperature (T, degrees Fahrenheit)	80
V	Stack Exit Velocity (V, ft/sec)	21.69
Q ⁽²⁾	Stack Exit Flow Rate [Q, Actual Cubic Feet per Minute (ACFM)]	9,200
Dpl	Shortest Distance from Source Building (Treatment Building) to Property Line (Dpl, feet) for point sources	50
BW	Building Width (BW, feet) of Source Building (Treatment Building) for point sources	75
BL	Building Length (BL, feet) of Source Building (Treatment Building)	75
Q	Actual Hourly Emission Rate (lbs/hour) for source contaminant	Chemical specific, see above
Qa	Actual Annual Emission Rate (lbs/year) for source contaminant	Chemical specific, see above

⁽¹⁾ Emission rates and maximum concentration values were taken from the Quarterly Operations Report First Quarter (June 2011) as provided by ECOR Services, using January, February, and March 2011 maximum rates of untreated off gas from Air Stripper AS-1 in the

GM-38 Treatment Building. Emission rates are based on continuous operation 24 hours per day, 7 days a week, 52 weeks a year, or approximately 8,760 hours of operation.

⁽²⁾ "Q" is an average value of January and February 2011 monthly flow rates. Effective water and vapor flow rates were reduced during the reporting period of March due to a shutdown of the Treatment Plant on March 23, 2011.

II. Contaminant Assessment Summary of TCE, PCE, Vinyl Chloride, cis 1,2-Dichloroethene, and 1,2-Dichloroethene (total):

CONTAMINANT ASSESSMENT SUMMARY OF DAR-1 ANALYSIS						9/ 8/11
						Page 1
CAS NUMBER	AGC ug/m3	SHORT-TERM	CAVITY	POINT or AREA SOURCE		
		MAXIMUM (Cav. Pt. Area) % OF SGC	ACTUAL ANNUAL % OF AGC	POTENTIAL ANNUAL % OF AGC	ACTUAL ANNUAL % OF AGC	
00075-01-4	0.11000000	0.0005	0.0000	13.3889	13.4948	
00079-01-6	0.50000000	0.7757	0.0000	390.1734	390.6266	
00127-18-4	1.00000000	7.3852	0.0000	132.6635	132.8415	
00156-59-2	63.00000000	0.0000	0.0000	0.2320	0.2322	
00540-59-0	63.00000000	0.0000	0.0000	0.2320	0.2322	
SUMMARY TOTALS		8.1614	0.0000	536.6897	537.4274	

III. Contaminant Impact Summary of TCE, PCE, Vinyl Chloride, cis 1,2-Dichloroethene, and 1,2-Dichloroethene (total):

CONTAMINANT IMPACT SUMMARY OF DAR-1 ANALYSIS						9/ 8/11
						Page 1
CAS NUMBER	AGC ug/m3	SHORT-TERM	CAVITY	POINT or AREA SOURCE		
		MAXIMUM (Cav. Pt. Area) ug/m3	ACTUAL ANNUAL ug/m3	POTENTIAL ANNUAL ug/m3	ACTUAL ANNUAL ug/m3	
00075-01-4	0.11000000	0.81988204	0.00000000	0.01472780	0.01484433	
00079-01-6	0.50000000	108.60282900	0.00000000	1.95086694	1.95113296	
00127-18-4	1.00000000	73.85244750	0.00000000	1.32663476	1.32841504	
00156-59-2	63.00000000	8.13575172	0.00000000	0.14614509	0.14630693	
00540-59-0	63.00000000	8.13575172	0.00000000	0.14614509	0.14630693	

IV. Contaminant Impact Summary Step by Step Menu for TCE:

```

*****
NWIRP BETHPAGE GM-38 AREA      BETHPAGE      OYSTER BAY, NEW
EMISSION POINT =          TOTAL      CAS NUMBER = 00079-01-6      SIC = 0
  AGC =          0.500000000 ug/m3      SGC =          14000.000000 ug/m3
  STACK: HA=    15., SH=   40., D=   36., T=   80., U=   21.69, q=  9200.00
BUILDING: Dpl=   50., BW=   75., BL=   75., %CONTROL=  0.0000
** Reported Hourly Emission Rate <Q> is equal to          0.344400000 lbs/hour.
** Reported Annual Emission Rate <Qa> is equal to          3017.000000 lbs/year.
II.B.  REFINED CAVITY IMPACT METHOD <DAR-1, APPENDIX B>.
II.B.1.  Shortest Distance from building to Property Line <  50. feet >
         is less than or equal to the cavity length, or 3 building
         heights <  75. feet >. Therefore, this building will have
         cavity impacts <if they occur> at receptors off plant property.
II.B.2.  The largest building dimension <  75. feet > is greater than or
         equal to the building height <  25. feet >. Therefore, the
         computer will NOT redefine the cavity length.
II.B.3.  Stack height <  40. feet > is greater than cavity height
         <  38. feet >. Therefore, this source does not contribute to
         the buildings cavity impact. The Computer will assume the
         CAVITY Annual Impact equals 0.00 ug/m3.
II.C.  CAVITY Annual Impact <  0.000 ug/m3 > is less than AGC
         <  0.500 ug/m3 >.
III.A.  STANDARD POINT SOURCE METHOD <DAR-1, APPENDIX B>.
III.A.1.b.  Momentum flux, Fm, is equal to  1000.331 ft<4>/sec<2>.
III.A.1.b.  Effective stack height, he, is equal to  51.001 feet.
III.A.2.  STANDARD POINT SOURCE Actual Annual Impact is equal
         to  2.604 ug/m3 for  8760. hours/year of operation.
III.A.3.  STANDARD POINT SOURCE Potential Annual Impact is equal
         to  2.601 ug/m3 assuming 8,760 hours/year of operation.
III.A.4.a.  Stack height to building height ratio is greater than
         1.5, but less than 2.5. Computer will multiply actual
         annual & potential annual impacts by 0.75 factor.

```

III.A.5. STANDARD POINT SOURCE Short-Term Impact is calculated below using the DAR-1 SOFTWARE PROGRAM SHORT-TERM METHOD.

III.D. STANDARD POINT SOURCE Actual Annual Impact < 1.953 ug/m3 > is greater than AGC < 0.500 ug/m3 >.

**** Refer to DAR-1 Section III.D.1. A refined site ****
 **** specific modeling analysis may be required. ****

III.D. STANDARD POINT SOURCE Potential Annual Impact < 1.951 ug/m3 > is greater than AGC < 0.500 ug/m3 >.

**** Potential Annual Impact is based upon 8760 hours/year ****
 **** operation instead of reported 8760. hours/year. ****

2.0 DAR-1 SOFTWARE PROGRAM SHORT-TERM METHOD.
 See "Technical Reference for the Screening Procedures of the DAR-1 Software Program, Wade/Sedefian," 1/11/94.

2.2 CAVITY Short-Term Impact is equal to 0.00 ug/m3 as the plume escaped the cavity region: $h_s < 40. \text{ feet} > > h_c < 26. \text{ feet} >$.

II.C. CAVITY Short-Term Impact < 0.000 ug/m3 > is less than SGC < 14000.000 ug/m3 >.

2.3 Momentum flux, F_m , is equal to 1000.331 ft(4)/sec(2).

2.3 Effective stack height, h_e , is equal to 51.001 feet.

2.4 Maximum non-downwash GEP stack Short-Term Impact (CSTP) is equal to 38.826 ug/m3, for $h_s/h_b = 1.60$

2.5 Maximum downwash Short-Term Impact (CSTD) is equal to 129.908 ug/m3, for: $h_s/h_b = 1.60$ and ESH = 51. feet.

2.6 Adjusted maximum downwash Short-Term (CSTD) is equal to 108.603 ug/m3, for: RF = 0.84

III.D. Maximum non-cavity Short-Term Impact (CST: 108.603 ug/m3 > is less than the SGC < 14000.000 ug/m3 > for the point source.

2.7 Maximum Short-Term cavity, point, or area source impact (SHORT-TERM MAXIMUM, (Cav,Pt,Area)) equals 108.603 ug/m3 and is reported in the ANALYSIS MENU. This value is less than the SGC < 14000.000 ug/m3 >.

V. Contaminant Impact Summary Step by Step Menu for PCE:

```

*****
NWIRP BETHPAGE GM-38 AREA          BETHPAGE          OYSTER BAY, MEV
EMISSION POINT =          TOTAL          CAS NUMBER = 00127-18-4          SIC = 0
AGC =          1.000000000 ug/m3          SGC =          1000.000000 ug/m3
STACK: HA=          15., SH=          40., D=          36., T=          80., U=          21.69, q=          9200.00
BUILDING: Dpl=          50., BW=          75., BL=          75., %CONTROL=          0.0000
** Reported Hourly Emission Rate (Q) is equal to          0.234200000 lbs/hour.
** Reported Annual Emission Rate (Qa) is equal to          2052.000000 lbs/year.
II.B. REFINED CAVITY IMPACT METHOD (DAR-1, APPENDIX B).
II.B.1. Shortest Distance from building to Property Line ( 50. feet )
is less than or equal to the cavity length, or 3 building
heights ( 75. feet ). Therefore, this building will have
cavity impacts (if they occur) at receptors off plant property.
II.B.2. The largest building dimension ( 75. feet ) is greater than or
equal to the building height ( 25. feet ). Therefore, the
computer will NOT redefine the cavity length.
II.B.3. Stack height ( 40. feet ) is greater than cavity height
( 38. feet ). Therefore, this source does not contribute to
the buildings cavity impact. The Computer will assume the
CAVITY Annual Impact equals 0.00 ug/m3.
II.C. CAVITY Annual Impact ( 0.000 ug/m3 ) is less than AGC
( 1.000 ug/m3 ).
III.A. STANDARD POINT SOURCE METHOD (DAR-1, APPENDIX B).
III.A.1.b. Momentum flux, Fm, is equal to 1000.331 ft<4>/sec<2>.
III.A.1.b. Effective stack height, he, is equal to 51.001 feet.
III.A.2. STANDARD POINT SOURCE Actual Annual Impact is equal
to 1.771 ug/m3 for 8762. hours/year of operation.
III.A.3. STANDARD POINT SOURCE Potential Annual Impact is equal
to 1.769 ug/m3 assuming 8,760 hours/year of operation.
III.A.4.a. Stack height to building height ratio is greater than
1.5, but less than 2.5. Computer will multiply actual
annual & potential annual impacts by 0.75 factor.

```

III.A.5. STANDARD POINT SOURCE Short-Term Impact is calculated below using the DAR-1 SOFTWARE PROGRAM SHORT-TERM METHOD.

III.D. STANDARD POINT SOURCE Actual Annual Impact (1.328 ug/m3) is greater than AGC (1.000 ug/m3).

**** Refer to DAR-1 Section III.D.1. A refined site specific modeling analysis may be required. ****

III.D. STANDARD POINT SOURCE Potential Annual Impact (1.327 ug/m3) is greater than AGC (1.000 ug/m3).

**** Potential Annual Impact is based upon 8760 hours/year operation instead of reported 8762. hours/year. ****

2.0 DAR-1 SOFTWARE PROGRAM SHORT-TERM METHOD. See "Technical Reference for the Screening Procedures of the DAR-1 Software Program, Wade/Sedefian," 1/11/94.

2.2 CAVITY Short-Term Impact is equal to 0.00 ug/m3 as the plume escaped the cavity region: hc(40. feet) > hc(26. feet).

II.C. CAVITY Short-Term Impact (0.000 ug/m3) is less than SGC (1000.000 ug/m3).

2.3 Momentum Flux, F_m , is equal to 1000.331 ft⁴/sec².

2.3 Effective stack height, h_e , is equal to 51.001 feet.

2.4 Maximum non-downwash GEP stack Short-Term Impact (CSTP) is equal to 26.403 ug/m3, for $h_c/h_b = 1.60$

2.5 Maximum downwash Short-Term Impact (CSTD) is equal to 88.340 ug/m3, for: $h_c/h_b = 1.60$ and ESH = 51. feet.

2.6 Adjusted maximum downwash Short-Term (CSTD) is equal to 73.852 ug/m3, for: RF = 0.84

III.D. Maximum non-cavity Short-Term Impact (CST: 73.852 ug/m3) is less than the SGC (1000.000 ug/m3) for the point source.

2.7 Maximum Short-Term cavity, point, or area source impact (SHORT-TERM MAXIMUM, (Cav,Pt,Area)) equals 73.852 ug/m3 and is reported in the ANALYSIS MENU. This value is less than the SGC (1000.000 ug/m3).

VI. Contaminant Impact Summary Step by Step Menu for Vinyl Chloride:

```

*****
NWIRP BETHPAGE GM-38 AREA          BETHPAGE          OYSTER BAY, NEW
EMISSION POINT =          TOTAL          CAS NUMBER = 00075-01-4          SIC = 0
AGC =          0.110000000 ug/m3          SGC =          180000.000000 ug/m3
STACK: HA=          15., SH=          40., D=          36., I=          80., U=          21.69, q=          9200.00
BUILDING: Dpl=          50., BW=          75., BL=          75., %CONTROL=          0.0000
** Reported Hourly Emission Rate <Q> is equal to          0.002600000 lbs/hour.
** Reported Annual Emission Rate <Qa> is equal to          22.930000 lbs/year.
II.B. REFINED CAVITY IMPACT METHOD <DAR-1, APPENDIX B>.
II.B.1. Shortest Distance from building to Property Line < 50. feet >
is less than or equal to the cavity length, or 3 building
heights < 75. feet >. Therefore, this building will have
cavity impacts <if they occur> at receptors off plant property.
II.B.2. The largest building dimension < 75. feet > is greater than or
equal to the building height < 25. feet >. Therefore, the
computer will NOT redefine the cavity length.
II.B.3. Stack height < 40. feet > is greater than cavity height
< 38. feet >. Therefore, this source does not contribute to
the buildings cavity impact. The Computer will assume the
CAVITY Annual Impact equals 0.00 ug/m3.
II.C. CAVITY Annual Impact < 0.000 ug/m3 > is less than AGC
< 0.110 ug/m3 >.
III.A. STANDARD POINT SOURCE METHOD <DAR-1, APPENDIX B>.
III.A.1.b. Momentum flux, Fm, is equal to 1000.331 ft<4>/sec<2>.
III.A.1.b. Effective stack height, he, is equal to 51.001 feet.
III.A.2. STANDARD POINT SOURCE Actual Annual Impact is equal
to 0.020 ug/m3 for 8819. hours/year of operation.
III.A.3. STANDARD POINT SOURCE Potential Annual Impact is equal
to 0.020 ug/m3 assuming 8,760 hours/year of operation.
III.A.4.a. Stack height to building height ratio is greater than
1.5, but less than 2.5. Computer will multiply actual
annual & potential annual impacts by 0.75 factor.

```

III.A.5. STANDARD POINT SOURCE Short-Term Impact is calculated below using the DAR-1 SOFTWARE PROGRAM SHORT-TERM METHOD.

III.D. STANDARD POINT SOURCE Actual Annual Impact < 0.015 ug/m3 > is less than AGC < 0.110 ug/m3 >.

III.D. STANDARD POINT SOURCE Potential Annual Impact < 0.015 ug/m3 > is less than AGC < 0.110 ug/m3 >.

**** Potential Annual Impact is based upon 8760 hours/year ****
 **** operation instead of reported 8819. hours/year. ****

2.0 DAR-1 SOFTWARE PROGRAM SHORT-TERM METHOD.
 See "Technical Reference for the Screening Procedures of the DAR-1 Software Program, Wade/Sedefian," 1/11/94.

2.2 CAVITY Short-Term Impact is equal to 0.00 ug/m3 as the plume escaped the cavity region: hs< 40. feet > hc< 26. feet >.

II.C. CAVITY Short-Term Impact < 0.000 ug/m3 > is less than SGC < 180000.000 ug/m3 >.

2.3 Momentum flux, F_m , is equal to 1000.331 ft<4>/sec<2>.

2.3 Effective stack height, h_e , is equal to 51.001 feet.

2.4 Maximum non-downwash GEP stack Short-Term Impact (CSTP) is equal to 0.293 ug/m3, for $h_s/h_b = 1.60$

2.5 Maximum downwash Short-Term Impact (CSTD) is equal to 0.981 ug/m3, for: $h_s/h_b = 1.60$ and $ESH = 51. feet.$

2.6 Adjusted maximum downwash Short-Term (CSTD) is equal to 0.820 ug/m3, for: $RF = 0.84$

III.D. Maximum non-cavity Short-Term Impact (CST: 0.820 ug/m3 > is less than the SGC < 180000.000 ug/m3 > for the point source.

2.7 Maximum Short-Term cavity, point, or area source impact (SHORT-TERM MAXIMUM, (Cav,Pt,Area)) equals 0.820 ug/m3 and is reported in the ANALYSIS MENU. This value is less than the SGC < 180000.000 ug/m3 >.

VII. Contaminant Impact Summary Step by Step Menu for cis 1,2-Dichloroethene:

```

*****
NWIRP BETHPAGE GM-38 AREA          BETHPAGE          OYSTER BAY, NEW
EMISSION POINT =          TOTAL          CAS NUMBER = 00156-59-2          SIC = 0
AGC =          63.000000000 ug/m3          SGC =          0.000000 ug/m3
STACK: HA=          15., SH=          40., D=          36., I=          80., U=          21.69, q=          9200.00
BUILDING: Dpl=          50., BW=          75., BL=          75., %CONTROL=          0.0000
** Reported Hourly Emission Rate <Q> is equal to          0.025800000 lbs/hour.
** Reported Annual Emission Rate <Qa> is equal to          226.000000 lbs/year.
II.B. REFINED CAVITY IMPACT METHOD <DAR-1, APPENDIX B>.
II.B.1. Shortest Distance from building to Property Line < 50. feet >
is less than or equal to the cavity length, or 3 building
heights < 75. feet >. Therefore, this building will have
cavity impacts <if they occur> at receptors off plant property.
II.B.2. The largest building dimension < 75. feet > is greater than or
equal to the building height < 25. feet >. Therefore, the
computer will NOT redefine the cavity length.
II.B.3. Stack height < 40. feet > is greater than cavity height
< 38. feet >. Therefore, this source does not contribute to
the buildings cavity impact. The Computer will assume the
CAVITY Annual Impact equals 0.00 ug/m3.
II.C. CAVITY Annual Impact < 0.000 ug/m3 > is less than AGC
< 63.000 ug/m3 >.
III.A. STANDARD POINT SOURCE METHOD <DAR-1, APPENDIX B>.
III.A.1.b. Momentum flux, Fm, is equal to 1000.331 ft<4>/sec<2>.
III.A.1.b. Effective stack height, he, is equal to 51.001 feet.
III.A.2. STANDARD POINT SOURCE Actual Annual Impact is equal
to 0.195 ug/m3 for 8760. hours/year of operation.
III.A.3. STANDARD POINT SOURCE Potential Annual Impact is equal
to 0.195 ug/m3 assuming 8,760 hours/year of operation.
III.A.4.a. Stack height to building height ratio is greater than
1.5, but less than 2.5. Computer will multiply actual
annual & potential annual impacts by 0.75 factor.

```

III.A.5. STANDARD POINT SOURCE Short-Term Impact is calculated below using the DAR-1 SOFTWARE PROGRAM SHORT-TERM METHOD.

III.D. STANDARD POINT SOURCE Actual Annual Impact < 0.146 ug/m3 > is less than AGC < 63.000 ug/m3 >.

III.D. STANDARD POINT SOURCE Potential Annual Impact < 0.146 ug/m3 > is less than AGC < 63.000 ug/m3 >.

**** Potential Annual Impact is based upon 8760 hours/year ****
 **** operation instead of reported 8760. hours/year. ****

2.0 DAR-1 SOFTWARE PROGRAM SHORT-TERM METHOD.
 See 'Technical Reference for the Screening Procedures of the DAR-1 Software Program, Wade/Sedefian,' 1/11/94.

2.2 CAVITY Short-Term Impact is equal to 0.00 ug/m3 as the plume escaped the cavity region: hs(40. feet) > hc(26. feet).

II.C. CAVITY Short-Term Impact is equal to 0.000 ug/m3.
 There is no SGC for this contaminant.

2.3 Momentum flux, Fm, is equal to 1000.331 ft(4)/sec(2).

2.3 Effective stack height, he, is equal to 51.001 feet.

2.4 Maximum non-downwash GEP stack Short-Term Impact (CSTP) is equal to 2.909 ug/m3, for hs/hb = 1.60

2.5 Maximum downwash Short-Term Impact (CSTD) is equal to 9.732 ug/m3, for: hs/hb = 1.60 and ESH = 51. feet.

2.6 Adjusted maximum downwash Short-Term (CSTD) is equal to 8.136 ug/m3, for: RF = 0.84

III.D. Maximum non-cavity Short-Term Impact (CST) equals 8.136 ug/m3 for the point source. There is no SGC for this contaminant.

2.7 Maximum Short-Term cavity, point, or area source impact (SHORT-TERM MAXIMUM, (Cav,Pt,Area)) equals 8.136 ug/m3 and is reported in the ANALYSIS MENU.

VIII. Contaminant Impact Summary Step by Step Menu for 1,2-Dichloroethene (total):

```

*****
NWIRP BETHPAGE GM-38 AREA          BETHPAGE          OYSTER BAY, NEW
EMISSION POINT =          TOTAL          CAS NUMBER = 00540-59-0          SIC = 0
AGC =          63.000000000 ug/m3          SGC =          0.000000 ug/m3
STACK: HA=          15., SH=          40., D=          36., T=          80., U=          21.69, q=          9200.00
BUILDING: Dpl=          50., BW=          75., BL=          75., %CONTROL=          0.0000
** Reported Hourly Emission Rate <Q> is equal to          0.025800000 lbs/hour.
** Reported Annual Emission Rate <Qa> is equal to          226.000000 lbs/year.
II.B. REFINED CAVITY IMPACT METHOD <DAR-1, APPENDIX B>.
II.B.1. Shortest Distance from building to Property Line < 50. feet >
is less than or equal to the cavity length, or 3 building
heights < 75. feet >. Therefore, this building will have
cavity impacts <if they occur> at receptors off plant property.
II.B.2. The largest building dimension < 75. feet > is greater than or
equal to the building height < 25. feet >. Therefore, the
computer will NOT redefine the cavity length.
II.B.3. Stack height < 40. feet > is greater than cavity height
< 38. feet >. Therefore, this source does not contribute to
the buildings cavity impact. The Computer will assume the
CAVITY Annual Impact equals 0.00 ug/m3.
II.C. CAVITY Annual Impact < 0.000 ug/m3 > is less than AGC
< 63.000 ug/m3 >.
III.A. STANDARD POINT SOURCE METHOD <DAR-1, APPENDIX B>.
III.A.1.b. Momentum flux, Pm, is equal to 1000.331 ft<4>/sec<2>.
III.A.1.b. Effective stack height, he, is equal to 51.001 feet.
III.A.2. STANDARD POINT SOURCE Actual Annual Impact is equal
to 0.195 ug/m3 for 8760. hours/year of operation.
III.A.3. STANDARD POINT SOURCE Potential Annual Impact is equal
to 0.195 ug/m3 assuming 8,760 hours/year of operation.
III.A.4.a. Stack height to building height ratio is greater than
1.5, but less than 2.5. Computer will multiply actual
annual & potential annual impacts by 0.75 factor.

```



```

III.A.5. STANDARD POINT SOURCE Short-Term Impact is calculated below
         using the DAR-1 SOFTWARE PROGRAM SHORT-TERM METHOD.

III.D. STANDARD POINT SOURCE Actual Annual Impact < 0.146 ug/m3 > is
         less than AGC < 63.000 ug/m3 >.

III.D. STANDARD POINT SOURCE Potential Annual Impact < 0.146 ug/m3 >
         is less than AGC < 63.000 ug/m3 >.

**** Potential Annual Impact is based upon 8760 hours/year ****
**** operation instead of reported 8760. hours/year. ****

2.0 DAR-1 SOFTWARE PROGRAM SHORT-TERM METHOD.
    See "Technical Reference for the Screening Procedures of the
    DAR-1 Software Program, Wade/Sedefian," 1/11/94.

2.2 CAVITY Short-Term Impact is equal to 0.00 ug/m3 as the plume
     escaped the cavity region: hs< 40. feet > hc< 26. feet >.

II.C. CAVITY Short-Term Impact is equal to 0.000 ug/m3.
       There is no SGC for this contaminant.

2.3 Momentum flux, Fm, is equal to 1000.331 ft<4>/sec<2>.

2.3 Effective stack height, he, is equal to 51.001 feet.

2.4 Maximum non-downwash GEP stack Short-Term Impact <CSTP> is equal
     to 2.909 ug/m3, for hs/hb = 1.60

2.5 Maximum downwash Short-Term Impact <CSTD> is equal
     to 9.732 ug/m3, for: hs/hb = 1.60 and ESH = 51. feet.

2.6 Adjusted maximum downwash Short-Term <CSTD> is equal
     to 8.136 ug/m3, for: RF = 0.84

III.D. Maximum non-cavity Short-Term Impact <CST> equals 8.136 ug/m3
       for the point source. There is no SGC for this contaminant.

2.7 Maximum Short-Term cavity, point, or area source impact
     <SHORT-TERM MAXIMUM, <Cav.Pt.Area>> equals 8.136 ug/m3
     and is reported in the ANALYSIS MENU.

```

IX. AGCs and SGCs for TCE, PCE, Vinyl Chloride, cis 1,2-Dichloroethene, and 1,2-Dichloroethene (total):

AGCs & SGCs				9/ 8/11	
				Page 1	
CAS NUMBER	CONTAMINANT NAME	SGC ug/m3	II O V	AGC ug/m3	II I O O V X CODES
00075-01-4	VINYL CHLORIDE	18000.00000	D	0.110000000	E H U HA
00079-01-6	TRICHLOROETHYLENE	14000.00000	Z	0.500000000	D M O HO
00127-10-4	TETRACHLOROETHYLENE	1000.00000	H	1.000000000	H M O HI
00156-59-2	DICHLOROETHYLENE, cis	0.00000		63.000000000	D M
00540-59-0	DICHLOROETHYLENE, 12	0.00000		63.000000000	D M

X. Contaminant Emissions Summary for TCE, PCE, Vinyl Chloride, cis 1,2-Dichloroethene, and 1,2-Dichloroethene (total):

CONTAMINANT EMISSIONS SUMMARY				9/ 8/11
				Page 1
CAS NUMBER	CONTAMINANT NAME	NUM. OF EPs PER CONTAM.	EMISSIONS <lbs/hour>	EMISSIONS <lbs/year>
00075-01-4	VINYL CHLORIDE	1	0.0026000	22.93000
00079-01-6	TRICHLOROETHYLENE	1	0.3444000	3017.00000
00127-10-4	TETRACHLOROETHYLENE	1	0.2342000	2052.00000
00156-59-2	DICHLOROETHYLENE, cis	1	0.0258000	226.00000
00540-59-0	DICHLOROETHYLENE, 1,2	1	0.0258000	226.00000
SUMMARY TOTALS		5	0.6328000	5543.93000

XI. Meter Grid Modeling Results for Maximum Annual Concentrations of TCE, within 25 meters:

CONCENTRATIONS x 10 ⁻² <ug/m3> for 00079-01-6														09/08/11
AGC = 0.500000000 ug/m3														13:17:58
TIME	367000.	368000.	369000.	370000.	371000.	372000.	373000.	374000.	375000.	376000.	377000.	378000.	379000.	
4511000.	0.04	0.06	0.08	0.14	0.23	0.32	0.41	0.30	0.14	0.10	0.08	0.06	0.05	
4510000.	0.03	0.05	0.08	0.13	0.25	0.43	0.60	0.40	0.17	0.12	0.09	0.07	0.06	
4509000.	0.02	0.03	0.06	0.11	0.24	0.58	1.01	0.52	0.22	0.14	0.11	0.08	0.06	
4508000.	0.02	0.03	0.04	0.06	0.18	0.62	2.16	0.64	0.31	0.19	0.13	0.11	0.09	
4507000.	0.02	0.03	0.04	0.06	0.11	0.26	7.27	1.43	0.60	0.34	0.22	0.15	0.12	
4506000.	0.03	0.03	0.05	0.07	0.13	0.33	2.58	2.99	1.12	0.51	0.30	0.20	0.14	
4505000.	0.03	0.04	0.05	0.08	0.20	0.45	0.94	0.81	0.60	0.45	0.33	0.23	0.16	
4504000.	0.03	0.04	0.07	0.12	0.20	0.22	0.47	0.43	0.33	0.27	0.24	0.20	0.16	

TOP 100 CONTRIBUTORS TO MAXIMUM CONCENTRATION FOR 00079-01-6							09/08/11
@ UTMN: 373000. UTMN: 4507000.							13:17:58
Emission Point	Facility Name (shortened)	EP DIR	Distance to Max.(m)	CONC. ug/m3	Percent of Max.		
TOTAL	NWIRP BETHPAGE GM-38 AREA	SSE	539.	0.727E-01	100.000		
TOTAL OF ALL	1 CONTRIBUTORS			0.727E-01	100.000		

XII. ISCLT Model Run Information, within 25 meters:

```

                                MODEL RUN INFORMATION
                                09/08/11
                                13:17:58

1. Current GRID SPACING equals      1000. meters.
2. Maximum Concentration (flashing) equals      0.0727115273 ug/m3
   @ UTME:      373000.      UTMN:      4507000.

3. RUN FILE: TEMP?.RUN
4. METEOROLOGICAL FILE: ALB.MET
5. RUN MODE: URBAN
6. HALF-LIVES: not used to account for pollutant removal from air.
7. BLD. WAKE EFFECTS: AG-1 METHOD, All data KNOWN (hb, hv, hl, orientation)
8. EMISSIONS: ACTUAL ANNUAL EMISSIONS
9. SOURCES: All sources within      25. meters of
   UTME:      373275.      UTMN:      4506537.
10. CONTAMINANT CAS NUMBER(s): 00079-01-6
11. EMISSION POINT - CONTAMINANT(s) found by computer:      1
12. No data is being copied to DUMP file.
```

APPENDIX C

**FIELD LOGS AND CHAIN OF CUSTODY DOCUMENTATION
FIRST QUARTER 2022**

Date: _____



Groundwater Level Measurement Sheet

Project Site: NWIPR Bethpage – GM-38
 Location: Bethpage, NY
 Field Crew: Seiler + Goernemann

Water Level Meter: Solinst
 Weather: _____
 Time of Low Tide: N/A
 Time of High Tide: N/A

Well ID	Time	Depth to Water (Ft.)	Total Depth of Well/ Screened Interval (Ft.)	Comments
RW1-MW1	3/10 1013	32.71	435 / 395 – 435	
RW1-MW2	3/11 1200	38.72	435 / 395 – 435	
RW1-MW3	3/10 1414	26.55	435 / 395 – 435	
RW2-MW1	3/9 1613	36.44	510 / 470 – 510	
RW2-MW2	3/10 1336	36.11	510 / 470 – 510	
RW2-MW3	3/10 1312	35.75	510 / 470 – 510	
RW3-MW1	3/9 1356	35.94	350 / 330 – 350	
RW3-MW2	3/10 1151	36.68	495 / 475 – 495	
RW3-MW3	3/9 1050	36.45	340 / 320 – 340	
RW3-MW4	3/9 0920	36.90	495 / 475 – 495	
TP1	3/10 0834	31.47	470 / 450 – 470	
IW1-MW1	3/11 1200	49.81	470 / 450 – 470	
RW-1	—	—		Open vault and check integrity of piping, etc.
RW-3	—	—		Open vault and check integrity of piping, etc.

Signature: _____

Date: _____



Instrument Calibration Log

Project/Site Name: Bethpage GM38 Date: 3-9-2022

Weather: 34° v snowing

Calibrated By: E. Seiler + E. Goetzmann Instrument: XSI

Serial Number: 20B006238

Parameters	Morning Calibration Time: <u>6740</u>	Cal. Temperature °C	Afternoon Cal. Check Time: _____	Comments
Conductivity ($\mu\text{S}/\text{cm}$)	<u>1.41 (ms/cm) \rightarrow 1.4</u>	<u>6.4</u>		
pH (7)	<u>7.20 - 7.00</u>	<u>6.4</u>		
pH (4)	<u>3.67 - 4.00</u>	<u>5.9</u>		
pH (10)	<u>10.76 - 10.00</u>	<u>6.6</u>		
ORP (mV)	<u>258 - 240</u>	<u>6.5</u>		
Dissolved Oxygen (%)	<u>102.9%</u>	<u>7.6</u>		
Zero Dissolved Oxygen (mg/L)				
Barometric Pressure (mm Hg)				
Turbidity (21030D000582)	<u>10.0 - 10.0</u>	<u>20.5 - 20</u>	<u>102 - 100</u>	<u>820 - 800</u>
	<u>10 - 10.1 (cal check)</u>			

Signature: *Elinor Seiler*

Date: 3-9-2022



Instrument Calibration Log

Project/Site Name: Bethpage GM38

Date: 3-10-2022

Weather: foggy mid 30's

Calibrated By: E. Goernemann

Instrument: XSI

Serial Number: 203000238

Parameters	Morning Calibration Time: <u>0728</u>	Cal. Temperature °C	Afternoon Cal. Check Time: _____	Comments
^{eg} pH (4) Conductivity (µS/cm)	3.98 - 4.00	17.3		
pH (7)	6.86 - 7.00	16.9		
^{eg} Conductivity (µS/cm) pH (4)	1397 - 1413	16.96 14.9		
pH (10)	9.98 - 10.00	16.6		
ORP (mV)	243.6 - 240	16.1		
Dissolved Oxygen (%)	99.7	11.3		
Zero Dissolved Oxygen (mg/L)				
Barometric Pressure (mm Hg)				
Turbidity	CALIBRATION CHECK (10 int.) 9.60	^{21.6} 24.7 - 20.0	107 - 100	800 - 800
(21630D000582) HACH 2100Q	Passed			

Signature: Elizabeth Goernemann

Date: 3-10-2022

Koman Government Solutions, LLC

Low Flow/ Low Stress Groundwater Sampling Log

Project: NWIRP Bethpage - GM38
 Location: Bethpage, NY
 Well ID: RW3-MW3

Date: 03/9/2022
 Sampler: Seiler + Goernemann
 PID: -----



Start Time: 1050 End Time: 1200
 Well Construction: 4" PVC
 Depth to Water: 36.45
 Well Depth: 340
 Water Column: 303.55
 Total Volume Removed (L): 9.00
 Dedicated Pump In Well?: No

Field Testing Equipment

Make	Model	Serial #
YSI	Pro Series	2013000288
Hach	2100Q	21030000582
QED MP15 Portable Backpack		
GeoTech Bladder Pump		47427

Time (hh:mm)	Volume Removed (L)	Flow Rate (ml/min)	Depth to Water (ft)	Temp (°C)	pH (STD)	SPC (µS/cm)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Salinity (ppm)	Color
1105	3.00	200	36.51	11.8	5.01	128	1.55	341.2	11.6		none
1110	4.00		36.53	11.8	4.95	128	1.63	341.6	9.63		none
1115	5.00		36.53	11.9	4.93	128	1.61	340.2	10.3		none
1120	6.00		36.55	11.8	4.92	128	1.61	342.6	8.06		none
1125	7.00		36.58	12.0	4.89	128	1.59	343.5	6.81		none
1130	8.00		36.60	11.8	4.90	128	1.54	342.0	6.98		none
1135	9.00		36.60	12.5	4.88	128	1.54	343.0	6.70		none

Acceptance Criteria: <0.3ft 3% ±0.1 3% 10% ± 10mv 10%

2" Screen Volume = 0.163 gal/ft or 616 ml per foot

Sample Collection

Time	Sample ID	Container	# Bottles	Preservative	Analysis
1140	GM-38-GW-RW3-MW3-0322	40 mL CG	3	---	TCL VOCs (624)
		500 mL PL	1	HNO ₃	Hg (245.1)
		1000 mL PL	2	---	TSS (SM2540D)
1145	GM-38-GW-RW3-MW3-DUP-0322				

Comments

Duplicate

[Signature]

Signature

3/11/2022

Date

Koman Government Solutions, LLC

Low Flow/ Low Stress Groundwater Sampling Log

Project: NWIRP Bethpage - GM38
 Location: Bethpage, NY
 Well ID: RW3-MW4

Date: 03/ 9 /2022
 Sampler: Seiler + Goernemann
 PID: -----



Start Time: 0920 End Time: ~ 1040
 Well Construction: 4" PVC
 Depth to Water: 36.90
 Well Depth: 495
 Water Column: 485.10
 Total Volume Removed (L): 1000
 Dedicated Pump in Well?: No

Field Testing Equipment

Make	Model	Serial #
YSI	Pro Series	2013000238
Hach	2100Q	21030D000582
QED MP15 Portable Backpack		
GeoTech Bladder Pump		33708

Time (hh:mm)	Volume Removed (gallons)	Flow Rate (ml/min)	Depth to Water (ft)	Temp (°C)	pH (STD)	SPC (µS/cm)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Salinity (ppm)	Color
0925	2.50	250	36.92	12.5	4.68	0.139	0.53	263.6	1.76		None
0930	2.50		36.93	12.8	4.65	0.139	0.46	280.9	1.58		none
0936	3.75		36.95	12.9	4.59	0.138	0.42	293.1	1.07		none
0940	5.00		36.99	13.0	4.60	0.138	0.41	296.5	0.81		none
0945	6.25		37.28	13.0	4.58	138	0.37	301.5	1.18		none
0950	7.50		37.40	13.1	4.56	138	0.36	305.4	1.24		none
0955	8.75		37.60	13.0	4.53	138	0.35	312.5	0.95		
1000	10.00		37.07	13.0	4.50	137	0.32	315.2	1.25		

Acceptance Criteria: <0.3ft 3% ±0.1 3% 10% ± 10mv 10%

2" Screen Volume = 0.163 gal/ft or 616 ml per foot

Sample Collection

Time	Sample ID	Container	# Bottles	Preservative	Analysis
1005	GM-38-GW-RW 3-MW4-0322	40 mL CG	19	---	TCL VOCs (624)
		500 mL PL	13	HNO ₃	Hg (245.1)
		1000 mL PL	76	---	TSS (SM2540D)

Comments

MS/MSD

[Signature]
 Signature

3/11/2022
 Date

Koman Government Solutions, LLC

Low Flow/ Low Stress Groundwater Sampling Log

Project: NWIRP Bethpage - GM38
 Location: Bethpage, NY
 Well ID: RW 3-MWI

Date: 03/ 9 /2022
 Sampler: Seiler + Goernemann
 PID: -----



Start Time: 1356 End Time: 1450
 Well Construction: 4" PVC
 Depth to Water: 35.94
 Well Depth: 350
 Water Column: 314.00
 Total Volume Removed (L): 8.50
 Dedicated Pump in Well?: No

Field Testing Equipment

Make	Model	Serial #
YSI	Pro Series	<u>203000238</u>
Hach	2100Q	<u>21030D600582</u>
QED MP15 Portable Backpack		
GeoTech Bladder Pump		<u>47427</u>

Time (hh:mm)	Volume Removed (L)	Flow Rate (ml/min)	Depth to Water (ft)	Temp (°C)	pH (STD)	SPC (μS/cm)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Salinity (ppm)	Color
14:10	3.50	250	35.97	10.2	4.51	170	3.12	383.7	2.70		none
14:15	4.75	250	36.01	10.1	4.48	169	3.17	387.7	0.89		none
14:20	6.00	250	36.02	10.1	4.51	169	3.19	388.3	0.66		none
14:25	7.25	250	36.02	10.2	4.51	169	3.21	389.3	0.70		none
14:30	8.50	250	36.03	10.0	4.51	170	3.20	390.5	0.72		none

Acceptance Criteria: <0.3ft 3% ±0.1 3% 10% ± 10mv 10%

2" Screen Volume = 0.163 gal/ft or 616 ml per foot

Sample Collection

Time	Sample ID	Container	# Bottles	Preservative	Analysis
14:35	GM-38-GW-RW 3-MWI-0322				
		40 mL CG	3	---	TCL VOCs (624)
		500 mL PL	1	HNO ₃	Hg (245.1)
		1000 mL PL	2	---	TSS (SM2540D)

Comments

[Signature]
 Signature

3/11/2022
 Date

Koman Government Solutions, LLC

Low Flow/ Low Stress Groundwater Sampling Log

Project: NWIRP Bethpage - GM38
 Location: Bethpage, NY
 Well ID: 28W RW2-MW1

Date: 03/ 9 /2022
 Sampler: Seiler + Goernemann
 PID: -----



Start Time: ~~1530~~ ¹⁶¹³ End Time: ~ 1725
 Well Construction: 4" PVC
 Depth to Water: 36.44
 Well Depth: 510
 Water Column: 473.56
 Total Volume Removed (L): 31.50
 Dedicated Pump in Well?: No

Field Testing Equipment

Make	Model	Serial #
YSI	Pro Series	203000238
Hach	2100Q	21030P00582
QED MP15 Portable Backpack		
GeoTech Bladder Pump		33708

Time (hh:mm)	Volume Removed (L)	Flow Rate (ml/min)	Depth to Water (ft)	Temp (°C)	pH (STD)	SPC (µS/cm)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Salinity (ppm)	Color
1620	3.50	500	36.36	11.9	9.01	154	0.16	243.8	-	X	clear
1625	6.00		36.36	11.9	8.96	154	0.12	278.6	6.72		clear
1630	8.50		36.36	12.1	8.95	154	0.11	253.2	5.25		clear
1635	11.00		36.36	12.1	8.93	155	0.11	237.7	4.87		clear
1640	13.50		36.36	12.2	8.89	155	0.09	221.6	4.43		clear
1645	16.00		36.34	11.9	8.86	155	0.09	208.1	4.26		clear
1650	18.50		36.34	12.1	8.93	155	0.08	195.2	4.06		clear
1655	21.00		36.34	12.3	8.93	155	0.08	179.2	4.19		clear
1700	23.50		36.35	12.3	8.86	155	0.07	165.3	63.88		clear
1705	26.00		36.35	12.2	8.90	158	0.08	159.2	3.61		clear
1710	28.50		36.35	12.2	8.87	155	0.06	156.9	3.21		clear
1715	31.50	↓	36.35	12.3	8.86	155	0.06	149.7	3.24		clear

Acceptance Criteria: <0.3ft 3% ±0.1 3% 10% ± 10mv 10%

2" Screen Volume = 0.163 gal/ft or 616 ml per foot

Sample Collection

Time	Sample ID	Container	# Bottles	Preservative	Analysis
1715	GM-38-GW-RW2-MW1-0322	40 mL CG	3	---	TCL VOCs (624)
		500 mL PL	1	HNO ₃	Hg (245.1)
		1000 mL PL	2	---	TSS (SM2540D)

Comments


 Signature

3/11/2022
 Date

Koman Government Solutions, LLC

Low Flow/ Low Stress Groundwater Sampling Log

Project: NWIRP Bethpage - GM38
 Location: Bethpage, NY
 Well ID: TP01

Date: 03/10/2022
 Sampler: Seiler + Goernemann
 PID: -----



Start Time: 0834 End Time: 0924
 Well Construction: 4" PVC
 Depth to Water: 31.47
 Well Depth: 470
 Water Column: 438.53
 Total Volume Removed (L): 9.00
 Dedicated Pump in Well?: No

Field Testing Equipment

Make	Model	Serial #
YSI	Pro Series	20B000238
Hach	2100Q	21036D000582
QED MP15 Portable Backpack		
GeoTech Bladder Pump		33708

Time (hh:mm)	Volume Removed (L)	Flow Rate (ml/min)	Depth to Water (ft)	Temp (°C)	pH (STD)	SPC (µS/cm)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Salinity (ppm)	Color
0845	2.75	250	31.50	12.5	6.26	257	3.85	267.0	1.59		none
0850	4.00	250	31.51	12.6	6.16	256	3.82	274.7	1.46		none
0855	5.25	250	31.50	12.6	6.08	256	3.72	283.2	0.895		none
0900	6.50	250	31.50	12.6	6.02	255	3.58	290.3	0.96		none
0905	7.75	250	31.49	12.9	5.98	254	3.57	295.5	0.81		none
0910	9.00	250	31.49	12.7	5.99	253	3.56	296.1	0.85		none

Acceptance Criteria: <0.3ft 3% ±0.1 3% 10% ± 10mv 10%

2" Screen Volume = 0.163 gal/ft or 616 ml per foot

Sample Collection

Time	Sample ID	TP	Container	# Bottles	Preservative	Analysis
0915	GM-38-GW-NW01-MW		-0322			
			40 mL CG	3	---	TCL VOCs (624)
			500 mL PL	1	HNO ₃	Hg (245.1)
			1000 mL PL	2	---	TSS (SM2540D)

Comments

Elizaveta Goernemann
 Signature

3-10-2022
 Date

Koman Government Solutions, LLC

Low Flow/ Low Stress Groundwater Sampling Log

Project: NWIRP Bethpage - GM38
 Location: Bethpage, NY
 Well ID: RWL-MW1

Date: 03/10/2022
 Sampler: Seiler + Goernemann
 PID: -----



Start Time: 1013 End Time: 1052
 Well Construction: 4" pvc
 Depth to Water: 32.71
 Well Depth: 435
 Water Column: 402.29
 Total Volume Removed (L): 8.10
 Dedicated Pump In Well?: No

Field Testing Equipment

Make	Model	Serial #
YSI	Pro Series	<u>203000238</u>
Hach	2100Q	<u>216301200582</u>
QED MP15 Portable Backpack		
GeoTech Bladder Pump		<u>33708</u>

Time (hh:mm)	Volume Removed (L)	Flow Rate (ml/min)	Depth to Water (ft)	Temp (°C)	pH (STD)	SPC (µS/cm)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Salinity (ppm)	Color
1020	2.10	300	33.79	14.3	5.38	152	0.77	326.0	0.76	X	Clear
1025	3.60		33.75	14.2	5.27	154	0.77	320.6	4.04		Clear
1030	5.10		33.76	14.3	5.16	154	0.78	323.5	3.71		Clear
1035	6.60		33.80	14.3	5.10	153	0.83	327.4	2.57		Clear
1040	8.10	↓	33.81	14.3	5.06	153	0.81	329.5	2.75		Clear

Acceptance Criteria: <0.3ft 3% ±0.1 3% 10% ± 10mv 10%

2" Screen Volume = 0.163 gal/ft or 616 ml per foot

Sample Collection

Time	Sample ID	Container	# Bottles	Preservative	Analysis
1045	GM-38-GW-RW 1-MW 1-0322				
		40 mL CG	3	---	TCL VOCs (624)
		500 mL PL	1	HNO ₃	Hg (245.1)
		1000 mL PL	2	---	TSS (SM2540D)

Comments

Signature

3/10/2022
 Date

Koman Government Solutions, LLC

Low Flow/ Low Stress Groundwater Sampling Log

Project: NWIRP Bethpage - GM38
 Location: Bethpage, NY
 Well ID: RW3 - MW2

Date: 03/10/2022
 Sampler: Seiler + Goernemann
 PID: -----



Start Time: 11:51 End Time: 12:52
 Well Construction: 4" PVC
 Depth to Water: 36.68
 Well Depth: 495
 Water Column: 458.32
 Total Volume Removed (L): 4.2
 Dedicated Pump in Well?: No

Field Testing Equipment

Make	Model	Serial #
YSI	Pro Series	20B000238
Hach	2100Q	21030N000582
QED MP15 Portable Backpack		
GeoTech Bladder Pump		47427

Time (hh:mm)	Volume Removed (L)	Flow Rate (ml/min)	Depth to Water (ft)	Temp (°C)	pH (STD)	SPC (µS/cm)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Salinity (ppm)	Color
12:08	1.7	100	36.70	10.4	5.19	88	2.63	312.5	1.69		None
12:13	2.2	100	36.98	10.5	5.05	88	1.40	307.9	1.62		None
12:18	2.7	100	37.00	10.6	5.09	88	0.94	302.6	2.02		None
12:23	3.2	100	37.01	10.7	5.08	87	0.79	303.4	1.78		None
12:28	3.7	100	37.03	10.8	5.10	87	0.72	304.3	1.15		None
12:33	4.2	100	37.03	10.8	5.08	87	0.71	302.9	1.31		

Acceptance Criteria: <0.3ft 3% ±0.1 3% 10% ± 10mv 10%

2" Screen Volume = 0.163 gal/ft or 616 ml per foot

Sample Collection

Time	Sample ID	Container	# Bottles	Preservative	Analysis
12:38	GM-38-GW-RW 3-MW2 -0322	40 mL CG	3	---	TCL VOCs (624)
		500 mL PL	1	HNO ₃	Hg (245.1)
		1000 mL PL	2	---	TSS (SM2540D)

Comments

Elizabeth Goernemann
 Signature

3-10-2022
 Date

Koman Government Solutions, LLC

Low Flow/ Low Stress Groundwater Sampling Log

Project: NWIRP Bethpage - GM38
 Location: Bethpage, NY
 Well ID: RW1-MW3

Date: 03/10/2022
 Sampler: Seiler + Goernemann
 PID: -----



Start Time: 1414 End Time: 1514
 Well Construction: 4" pvc
 Depth to Water: 26.55
 Well Depth: 435
 Water Column: 408.45
 Total Volume Removed (L): 11.50
 Dedicated Pump in Well?: No

Field Testing Equipment

Make	Model	Serial #
YSI	Pro Series	20B00238
Hach	2100Q	21030D000582
QED MP15 Portable Backpack		
GeoTech Bladder Pump		33708

Time (hh:mm)	Volume Removed (L)	Flow Rate (ml/min)	Depth to Water (ft)	Temp (°C)	pH (STD)	SPC (µS/cm)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Salinity (ppm)	Color
1420	1.5	250	26.58	13.3	5.27	185	0.73	247.2	7.23		clear
1425	2.75		26.56	13.4	5.17	185	0.30	274.3	5.13		clear
1430	4.00		26.55	13.4	5.28	185	0.25	257.5	5.76		clear
1435	5.25		26.55	13.4	5.32	185	0.25	257.8	3.68		clear
* 1440	6.50		26.54	13.3	5.60	185	0.25	234.3	3.71		clear
1445	7.75		26.51	13.3	5.12	185	0.24	261.7	3.14		clear
1450	9.00		26.51	13.3	5.24	185	0.24	250.8	4.10		clear
1455	10.25		26.51	13.3	5.31	185	0.23	247.8	3.50		clear
1500	11.50	✓	26.51	13.3	5.31	185	0.22	245.8	3.95		clear

Acceptance Criteria: <0.3ft 3% ±0.1 3% 10% ±10mv 10%

2" Screen Volume = 0.183 gal/ft or 616 ml per foot

Sample Collection

Time	Sample ID	Container	# Bottles	Preservative	Analysis
1505	GM-38-GW-RW1-MW3-0322				
		40 mL CG	3	---	TCL VOCs (624)
		500 mL PL	1	HNO ₃	Hg (245.1)
		1000 mL PL	2	---	TSS (SM2540D)

Comments

* YSI flow through cell became ~~discon~~ disconnected

 R. Seiler
 Signature

 3/10/2022
 Date



CHAIN OF CUSTODY

SGS North America Inc. - Dayton

2235 Route 130, Dayton, NJ 08810

TEL: 732-329-0200 FAX: 732-329-3499/3481

www.sgs.com/ehsusa

L1471543 Page 1 of 1

F122

EHSQA-QAC-0023-04-FORM-Standard COC

FED-EX Tracking #	Bottle Order Control #
#	SGS Job #

Client / Reporting Information		Project Information		Requested Analysis						Matrix Codes
Company Name: Komen Government Solutions		Project Name: Bethpage Gm38 Annual LTM		VOCs #g						DW - Drinking Water GW - Ground Water WW - Water SW - Surface Water SO - Soil SL - Sludge SED - Sediment OI - Oil LIQ - Other Liquid AIR - Air SOL - Other Solid WP - Wipe FB - Field Blank EB - Equipment Blank RB - Rinse Blank TB - Trip Blank
Street Address: 180 Gordon Drive Ste 110		Street: 100 Broadway								
City State Zip: Exton PA 19341		City State Zip: Bethpage NY								
Project Contact E-mail: Bob Gregory RGregory@komegs.com		Project #: 2605.002								
Phone #: 610-363-3000		Client Purchase Order #:								
Sampler(s) Name(s): Ericka Seiler		Project Manager: Bob Gregory		Attention:						

SGS Sample #	Field ID / Point of Collection	MEOH/DI Vial #	Collection		Sampled by	Grab (G) Comp (C)	Source Chlorinated (Y/N)	Matrix	# of bottles	Number of preserved Bottles							pH Check (Lab Use Only)		LAB USE ONLY		
			Date	Time						HCl	NaOH	HNO ₃	H ₂ SO ₄	NONE	DI Water	MEOH	ENCORE				
	Gm-38-GW-RW3-MW4-0322		3/4/22	1005	ES	G	N	GW	12	9	3								9	3	-01
	Gm-38-GW-RW3-MW3-0322			1140	ES	G	N	GW	4	3	4								3	1	-02
	Gm-38-GW-RW3-MW3-DUP-0322			1145	ES	G	N	GW	4	3	4								3	1	-03
	Gm-38-EB-0322			1250	ES	G	N	EB	4	3	4								3	1	-04
	Gm-38-GW-RW3-MW1-0322			1435	ES	G	N	GW	4	3	4								3	1	-05
	Gm-38-GW-RW2-MW1-0322		↓	1715	ES	G	N	GW	5	4	1								4	1	-06
	Gm-38-GW-TP01-0322		3/10/22	0915	ES	G	N	GW	4	3	1								3	1	-07
	Gm-38-GW-RW1-MW1-0322			1045	ES	G	N	GW	4	3	1								3	1	-08
	Gm-38-GW-RW3-MW2-0322			1238	ES	G	N	GW	4	3	1								3	1	-09
	Gm-38-GW-RW1-MW3-0322		↓	1505	ES	G	N	GW	4	3	1								3	1	-10
	Trip Blank		3/4/22	-	-	-	-	TB	2	2									2		-11

Turn Around Time (Business Days)	Deliverable	Comments / Special Instructions
----------------------------------	-------------	---------------------------------

<input checked="" type="checkbox"/> 10 Business Days <input type="checkbox"/> 5 Business Days <input type="checkbox"/> 3 Business Days* <input type="checkbox"/> 2 Business Days* <input type="checkbox"/> 1 Business Day* <input type="checkbox"/> Other _____ <small>All data available via Lablink</small>	Approved By (SGS PM): / Date: _____ _____ _____ _____ _____	<input type="checkbox"/> Commercial "A" (Level 1) <input type="checkbox"/> Commercial "B" (Level 2) <input type="checkbox"/> NJ Reduced (Level 3) <input type="checkbox"/> Full Tier 1 (Level 4) <input type="checkbox"/> Commercial "C" <input type="checkbox"/> NJ DKQP	<input type="checkbox"/> NYASP Category A <input type="checkbox"/> NYASP Category B <input type="checkbox"/> MA MCP Criteria <input type="checkbox"/> CT RCP Criteria <input type="checkbox"/> State Forms <input type="checkbox"/> EDD Format	<input type="checkbox"/> DOD-QSM5 *ms/msd on RW3-MW4
---	---	--	---	---

Sample Receipt Checklist

COC Seal Present/Intact: Y N IF Applicable

COC Signed/Accurate: Y N VOA Zero Headspace: Y N

Bottles arrive intact: Y N Pres. Correct/Check: Y N

Correct bottles used: Y N

Sufficient volume sent: Y N

RAP Screen ≤ 0.5 mR/hr: Y N

Sample Custody must be documented below each time samples change possession, including courier delivery.					
Relinquished by: <i>[Signature]</i>	Date / Time: 3-11-	Received By: <i>[Signature]</i>	1	Relinquished By: <i>[Signature]</i>	2
Relinquished by: <i>[Signature]</i>	Date / Time:	Received By: <i>[Signature]</i>	3	Relinquished By: <i>[Signature]</i>	4
Relinquished by:	Date / Time:	Received By:	5	Custody Seal #	<input type="checkbox"/> Intact <input type="checkbox"/> Not Intact Absent

#527206398056 BAA6-1.940=1.9 3.1 3.2 C-1P 3.2



CHAIN OF CUSTODY

SGS North America Inc. - Dayton
 2235 Route 130, Dayton, NJ 08810
 TEL. 732-329-0200 FAX: 732-329-3493/3480
 www.sgs.com/ehsusa

FA93984
 Page 1 of 1

EHSA-QAC-0023-04-FORM-Standard COC

FED-EX Tracking #	Bottle Order Control #
SGS Quote #	SGS Job #

Client / Reporting Information		Project Information		Requested Analysis						Matrix Codes	
Company Name: <i>Koman Government Solutions</i>		Project Name: <i>Bethpage GM38 Annual LTM</i>		TSS VOC						DW - Drinking Water GW - Ground Water WW - Water SW - Surface Water SO - Soil SL - Sludge SED - Sediment OI - Oil LIQ - Other Liquid AIR - Air SOL - Other Solid WP - Wipe FB - Field Blank EB - Equipment Blank RB - Rinse Blank TB - Trip Blank	
Street Address: <i>180 Gordon Dr Ste 110</i>		Street: <i>100 Broadway</i>									
City State Zip: <i>Exton PA 19341</i>		City State Zip: <i>Bethpage NY</i>									
Project Contact E-mail: <i>Bob Gregory RBGregory@koman.com</i>		Project #: <i>2605.002</i>									
Phone #: <i>610-363-3000</i>		Client Purchase Order #:									
Sampler(s) Name(s) Phone #: <i>Ericka Seiler 610-357-1946</i>		Project Manager: <i>Bob Gregory</i>		Attention:							

SGS Sample #	Field ID / Point of Collection	MEOH/DI Vial #	Collection		Sampled by	Grab (G) Comp (C)	Source Chlorinated (Y/N)	Matrix	# of bottles	Number of preserved Bottles										pH Check (Lab Use Only)		LAB USE ONLY							
			Date	Time						HCl	NaOH	HNO ₃	H ₂ SO ₄	NONE	DI Water	MEOH	ENCORE												
1	GM-38-GW-RW3-MW4-0322		3/4/22	1005	ES	G	N	GW	12	6																			
2	GM-38-GW-RW3-MW3-0322		↓	1140	ES	G	N	GW	2																				
3	GM-38-GW-RW3-MW3-DUP-0322			1145	ES	G	N	GW	2																				
4	GM-38-EB-0322			1250	ES	G	N	EB	2																				
5	GM-38-GW-RW3-MW1-0322			1435	ES	G	N	GW	2																				
6	GM-38-GW-RW2-MW1-0322		1715	ES	G	N	GW	2																					
7	GM-38-GW-TP01-0322		3/10/22	0915	ES	G	N	GW	2																				
8	GM-38-GW-RW1-MW1-0322			1045	ES	G	N	GW	2																				
9	GM-38-GW-RW3-MW2-0322			1238	ES	G	N	GW	2																				
10	GM-38-GW-RW1-MW3-0322			1505	ES	G	N	GW	2																				

Turn Around Time (Business Days)		Deliverable		Comments / Special Instructions	
<input checked="" type="checkbox"/> 10 Business Days <input type="checkbox"/> 5 Business Days <input type="checkbox"/> 3 Business Days* <input type="checkbox"/> 2 Business Days* <input type="checkbox"/> 1 Business Day* <input type="checkbox"/> Other _____ <small>All data available via Lablink</small>	Approved By (SGS PM) / Date: _____ _____ _____ _____ _____ _____ _____ _____ _____ _____ <small>Approval needed for 1-3 Business Day TAT</small>	<input type="checkbox"/> Commercial "A" (Level 1) <input type="checkbox"/> Commercial "B" (Level 2) <input type="checkbox"/> NJ Reduced (Level 3) <input type="checkbox"/> Full Tier I (Level 4) <input type="checkbox"/> Commercial "C" <input type="checkbox"/> NJ DKQP	<input type="checkbox"/> NYASP Category A <input type="checkbox"/> NYASP Category B <input type="checkbox"/> MA MCP Criteria <input type="checkbox"/> CT RCP Criteria <input type="checkbox"/> State Forms <input type="checkbox"/> EDD Format	<input type="checkbox"/> DOD-QSM5	*MS/MSD on RW3-MW4 INITIAL ASSESSMENT _____ LABEL VERIFICATION _____ 170C + 3.20C 18#

Sample Custody must be documented below each time samples change possession, including courier delivery.

Relinquished by: <i>[Signature]</i>	Date / Time: 3/11	Received By: <i>[Signature]</i>	Relinquished By: <i>[Signature]</i>	Date / Time: 3/11/22 1927	Received By: <i>[Signature]</i>		
Relinquished by: 3	Date / Time:	Received By: 3	Relinquished By: 4	Date / Time:	Received By: 4		
Relinquished by: 5	Date / Time:	Received By: 5	Custody Seal #	<input type="checkbox"/> Intact <input type="checkbox"/> Not intact Absent	Therm ID: See Sample Receipt Summary	On Ice <input checked="" type="checkbox"/>	Cooler Temp. °C 3.1

3.2
3.2 C-1P

SGS Sample Receipt Summary

Job Number: FA93984

Client: KOMAN GOVERNMENT SOLUTIONS

Project: BETHPAGE GM38 ANNUAL LTM

Date / Time Received: 3/17/2022 9:30:00 AM

Delivery Method: FEDEX

Airbill #'s: 5272 0639 7612

Therm ID: IR 1;

Therm CF: 0.4;

of Coolers: 2

Cooler Temps (Raw Measured) °C: Cooler 1: (0.8); Cooler 2: (3.2);

Cooler Temps (Corrected) °C: Cooler 1: (1.2); Cooler 2: (3.6);

Cooler Information

Y or N

- 1. Custody Seals Present
- 2. Custody Seals Intact
- 3. Temp criteria achieved
- 4. Cooler temp verification IR Gun
- 5. Cooler media Ice (Bag)

Sample Information

Y or N N/A

- 1. Sample labels present on bottles
- 2. Samples preserved properly
- 3. Sufficient volume/containers recvd for analysis:
- 4. Condition of sample Intact
- 5. Sample recvd within HT
- 6. Dates/Times/IDs on COC match Sample Label
- 7. VOCs have headspace
- 8. Bottles received for unspecified tests
- 9. Compositing instructions clear
- 10. Voa Soil Kits/Jars received past 48hrs?
- 11. % Solids Jar received?
- 12. Residual Chlorine Present?

Trip Blank Information

Y or N N/A

- 1. Trip Blank present / cooler
- 2. Trip Blank listed on COC

W or S N/A

- 3. Type Of TB Received

Misc. Information

Number of Encores: 25-Gram _____ 5-Gram _____ Number of 5035 Field Kits: _____ Number of Lab Filtered Metals: _____
 Test Strip Lot #s: pH 0-3 _____ 230315 _____ pH 10-12 _____ 219813A _____ Other: (Specify) _____
 Residual Chlorine Test Strip Lot #: _____

Comments SAMPLES #1, ID: "GM-38-GW-RW3-MW4-0322", THROUGH SAMPLE #7, ID: "GM-38-GW-TP01-0322", WERE RECEIVED OUT OF HOLD.

Technician: SAMUELM

Date: 3/17/2022 9:30:00 AM

Reviewer: _____

Date: _____

APPENDIX D
DATA VALIDATION REPORTS

VOLATILE ORGANIC COMPOUNDS
USEPA Region II –Data Validation

Project Name: Naval Weapons Industrial Reserve Plant, GM-38 Area-LTM
Location: 100 Broadway, Bethpage, NY
SDG #: L1471543
Client: KOMAN Government Solutions, LLC
Date: 4/28/2022
Laboratory: SGS, Orlando, FL subcontracted to Pace Analytical National, TN
Reviewer: Sherri Pullar

Summary:

1. Data validation was performed on the data for nine (9) water samples, one (1) trip blank and one (1) equipment blank analyzed for Volatiles by EPA Method 624.1.
2. The samples were collected on 3/9-10/2022. The samples were submitted to SGS North America, Inc. – Dayton, NJ on 3/15/2022 for analysis; analysis of VOC fractions was subcontracted to Pace Analytical, Mount Juliet, TN. The laboratory report was amended to include results for cis-1,2-dichloroethene, 26 May 2022.
3. The USEPA Region II SOP HW-34, Revision No.: 3, Trace Volatile Data Validation; USEPA National Functional Guidelines for Organic Data Review, EPA 540/R-2017-002, January 2017; EPA Method 624 and Quality Assurance Project Plan for GM-38 Area, Naval Weapons Industrial Reserve Plant, Bethpage, NY; September 3, 2009 were used in evaluating the Volatiles data in this summary report.
4. In general, the data are valid as reported and may be used for decision making purposes. Selected data points were qualified due to nonconformance of certain Quality Control criteria (See discussion below).

Samples:

The samples included in this review are listed below:

Client Sample ID	Laboratory Sample ID	Collection Date	Matrix	Sample Status
GM-38-GW-RW3-MW4-0322	L1471543-01	3/9/2022	Water	
GM-38-GW-RW3-MW3-0322	L1471543-02	3/9/2022	Water	
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	3/9/2022	Water	Field Duplicate of sample GM-38-GW-RW3-MW3-0322
GM-38-EB-0322	L1471543-04	3/9/2022	Water	Equipment Blank
GM-38-GW-RW3-MW1-0322	L1471543-05	3/9/2022	Water	
GM-38-GW-RW2-MW1-0322	L1471543-06	3/9/2022	Water	
GM-38-GW-TP01-0322	L1471543-07	3/10/2022	Water	
GM-38-GW-RW1-MW1-0322	L1471543-08	3/10/2022	Water	
GM-38-GW-RW3-MW2-0322	L1471543-09	3/10/2022	Water	
GM-38-GW-RW1-MW3-0322	L1471543-10	3/10/2022	Water	
Trip Blank	L1471543-11	3/9/2022	Water	Trip Blank

Sample Conditions/Problems:

1. The Traffic Reports/Chain-of-Custody Records, Sampling Report and/or Laboratory Case Narrative did not indicate any problems with sample receipt, condition of samples, analytical problems or special circumstances affecting the quality of the data. No qualifications were required.

Holding Times:

1. All water samples were analyzed within 14 days from sample collection. Results for trichloroethene were re-extracted outside of holding time in samples GM-38-GW-RW3-MW3-0322, GM-38-GW-RW3-MW3-0322-DUP-0322, and GM-38-EB-0322.

Results for trichloroethene were qualified as estimated (J) in samples GM-38-GW-RW3-MW3-0322, GM-38-GW-RW3-MW3-0322-DUP-0322, and GM-38-EB-0322.

2. All water samples were properly preserved (pH<2.0). No qualifications were required.

Surrogates:

1. All surrogates %REC values for all water samples and associated QC were within the laboratory control limits. No qualifications were required.

Method Blank (MB), Storage Blank (SB), Trip Blank (TB), Field Blank (FB), Rinsate Blank (RB) and Equipment Blank (EB):

1. Method Blank (R3772550-2) analyzed on 3/21/2022 was free of contamination. No qualifications were required.
2. Method Blank (R3772878-3) analyzed on 3/22/2022 was free of contamination. No qualifications were required.
3. Method Blank (R3773318-3) analyzed on 3/23/2022 was free of contamination. No qualifications were required.
4. Method Blank (R3773515-3) analyzed on 3/24/2022 was free of contamination. No qualifications were required.
5. Method Blank (R3773595-3) analyzed on 3/24/2022 was free of contamination. No qualifications were required.
6. Equipment Blank (GM-38-EB-0322) (L1471543-04) analyzed on 3/23/2023 contained chloroform (0.278 ug/L). Result for chloroform was qualified as non-detect in the equipment blank due to trip blank contamination. No qualifications were required.
7. Trip Blank (L1471543-11) analyzed on 3/23/2022 contained bromodichloromethane (1.19 ug/L), chloroform (5.06 ug/L), and methylene chloride (0.903 ug/L). Results for bromodichloromethane and methylene chloride were non-detect in the field samples. No qualifications were required.

Results for chloroform were qualified as non-detect (U and reported to the LOD) in samples GM-38-GW-RW3-MW4-0322, GM-38-GW-RW3-MW3-0322, GM-38-GW-RW3-MW3-DUP-0322, GM-38-EB-0322, GM-38-GW-TP01-0322, GM-38-GW-RW1-MW1-0322, and GM-38-GW-RW1-MW3-0322.

Laboratory Control Sample (LCS)/ Laboratory Control Sample Duplicate (LCSD):

1. Laboratory Control Sample (R3772550-1) was analyzed on 03/21/2022. All %RECs were within the laboratory control limits except for naphthalene (144%). Associated field

samples were non-detect for naphthalene; no qualifications were required.

2. Laboratory Control Sample/Laboratory Control Sample Duplicate (R3772878-1/-2) was analyzed on 3/22/2022. All %RECs were within the laboratory control limits. No qualifications were required.
3. Laboratory Control Sample/Laboratory Control Sample Duplicate (R3773318-1/-2) was analyzed on 3/23/2022. All %RECs were within the laboratory control limits. No qualifications were required.
4. Laboratory Control Sample/Laboratory Control Sample Duplicate (R3773515-1/-2) was analyzed on 3/24/2022. All %RECs were within the laboratory control limits. No qualifications were required.
5. Laboratory Control Sample/Laboratory Control Sample Duplicate (R3773595-1) was analyzed on 3/24/2022. All %RECs were within the laboratory control limits. No qualifications were required.

Field Duplicate:

1. Sample GM-38-GW-RW3-MW3-DUP-0322 (L1471543-03) was collected as field duplicate for sample GM-38-GW-RW3-MW3-0322 (L1471543-02). All RPDs were ≤50.0%.

Field Sample	Compound	Analytical Method	Result	Units	Field Duplicate	Result	Units	RPD	Qualifier
GM-38-GW-RW3-MW3-0322	1,1,1-Trichloroethane	EPA 624	0.32 J	µg/l	GM-38-GW-RW3-MW3-DUP-0322	0.302 J	µg/l	5.8	NONE
GM-38-GW-RW3-MW3-0322	1,1-Dichloroethane	EPA 624	1.56	µg/l	GM-38-GW-RW3-MW3-DUP-0322	1.61	µg/l	3.2	NONE
GM-38-GW-RW3-MW3-0322	1,1-Dichloroethene	EPA 624	0.925 J	µg/l	GM-38-GW-RW3-MW3-DUP-0322	1.01	µg/l	8.8	NONE
GM-38-GW-RW3-MW3-0322	1,2-Dichloroethane	EPA 624	0.159 J	µg/l	GM-38-GW-RW3-MW3-DUP-0322	0.15 J	µg/l	5.8	NONE
GM-38-GW-RW3-MW3-0322	Cis-1,2-dichloroethene	EPA 624	0.595 J	µg/l	GM-38-GW-RW3-MW3-DUP-0322	0.581 J	µg/l	2.4	NONE
GM-38-GW-RW3-MW3-0322	Methyl tert-butyl ether	EPA 624	0.135 J	µg/l	GM-38-GW-RW3-MW3-DUP-0322	0.149 J	µg/l	9.9	NONE
GM-38-GW-RW3-MW3-0322	Tetrachloroethene	EPA 624	0.336 J	µg/l	GM-38-GW-RW3-MW3-DUP-0322	0.302 J	µg/l	10.7	NONE
GM-38-GW-RW3-MW3-0322	Trichloroethene	EPA 624	146 J	µg/l	GM-38-GW-RW3-MW3-DUP-0322	149 J	µg/l	2.0	NONE

No qualifications were required.



Matrix Spike (MS)/ Matrix Spike Duplicate (MSD):

1. Matrix Spike (MS) and Matrix Spike Duplicate (MSD) were performed on sample GM-38-GW-RW3-MW4-0322 (L1471543-01). All RPDs were within the laboratory control limits. %RECs were within the laboratory control limits except for carbon disulfide (135% and 138% %R), 2-chloroethyl vinyl ether (0% and 0% %R), cyclohexane (131% %R), 1,1-dichloroethene (132% and 134% %R), 1,2-Dichloropropane (123% %R), methyl cyclohexane (27.3% and 28.9% %R), naphthalene (131% and 148% %R), toluene (128% and 127% %R), vinyl chloride (140% and 148% %R), total xylenes (125% and 125% %R), and m&p-xylene (126% and 126% %R). Results for carbon disulfide, cyclohexane, 1,2-dichloropropane, naphthalene, toluene, vinyl chloride, total xylenes, and m&p-xylene were non-detect in the parent sample; no qualifications were required.

Result for 1,1-dichloroethene was qualified as estimated (J), non-detect result for methyl cyclohexane was qualified as estimated (UJ), and the non-detect result for 2-chloroethyl vinyl ether was qualified as exclusion of data recommended (X) in sample GM-38-GW-RW3-MW4-0322.

Compound Quantitation and Reported Contract Required Quantitation Limits (CRQLs):

1. All results were within the linear calibration range. No qualifications were required.

Target Compound Identification:

1. All Relative Retention Times (RRTs) of the reported compounds were within ± 0.06 RRT units of the standard (opening CCV).
2. Sample compound spectra were compared against the laboratory standard spectra.
3. No QC deviations were observed.

Comments:

1. Validation qualifiers (if required) were entered into the EDD for SDG: L1471543.
2. Summary of the qualified data is listed in the Qualification Summary Table for SDG: L1471543 at the end of the data validation report.

MERCURY
USEPA Region II – Data Validation

Project Name: Naval Weapons Industrial Reserve Plant, GM-38 Area-LTM
Location: 100 Broadway, Bethpage, NY
SDG #: L1471543
Client: KOMAN Government Solutions, LLC
Date: 04/29/2022
Laboratory: SGS, Orlando, FL subcontracted to Pace Analytical National, TN
Reviewer: Sherri Pullar

Summary:

1. Data validation was performed on the data for nine (9) water samples and one (1) field blank analyzed for Mercury (Hg) by EPA Method 7470A.
2. The samples were collected on 03/9-10/2022. The samples were submitted to SGS North America, Inc. – Dayton, NJ on 3/15/2022 for analysis; analysis of Hg fractions was subcontracted to Pace Analytical, Mount Juliet, TN.
3. The USEPA Region II SOP No. HW-2C, Revision 15, December 2012, Mercury and Cyanide Data Validation; USEPA National Functional Guidelines for Inorganic Data Review, EPA 540-R-2017-001, January 2017 and Quality Assurance Project Plan for GM-38 Area, Naval Weapons Industrial Reserve Plant, Bethpage, NY; September 3, 2009 were used in evaluating the Mercury data in this summary report.
4. In general, the data are valid as reported and may be used for decision making purposes. Selected data points were qualified due to nonconformance of certain Quality Control criteria (See discussion below).

Samples:

The samples included in this review are listed below:

Client Sample ID	Laboratory Sample ID	Collection Date	Matrix	Sample Status
GM-38-GW-RW3-MW4-0322	L1471543-01	3/9/2022	Water	
GM-38-GW-RW3-MW3-0322	L1471543-02	3/9/2022	Water	
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	3/9/2022	Water	Field Duplicate of sample GM-38-GW-RW3-MW3-0322
GM-38-EB-0322	L1471543-04	3/9/2022	Water	Equipment Blank
GM-38-GW-RW3-MW1-0322	L1471543-05	3/9/2022	Water	
GM-38-GW-RW2-MW1-0322	L1471543-06	3/9/2022	Water	
GM-38-GW-TP01-0322	L1471543-07	3/10/2022	Water	
GM-38-GW-RW1-MW1-0322	L1471543-08	3/10/2022	Water	
GM-38-GW-RW3-MW2-0322	L1471543-09	3/10/2022	Water	
GM-38-GW-RW1-MW3-0322	L1471543-10	3/10/2022	Water	

Sample Conditions/Problems:

1. The Traffic Reports/Chain-of-Custody Records, Sampling Report and/or Laboratory Case Narrative did not indicate any problems with sample receipt, condition of samples, analytical problems or special circumstances affecting the quality of the data. No qualifications were required.

Holding Times:

1. All water samples were digested and analyzed within the 28 days holding times for Mercury. No qualifications were required.

Blanks (Method Blank, ICB and CCB):

1. All ICBs and CCBs were free of contamination. No qualifications were required.
2. Method Blank digested on 3/21/2022 was free of contamination. No qualifications were required.



3. Method Blank digested on 3/22/2022 was free of contamination. No qualifications were required.

Field Blank (FB) and Equipment Blank (EB):

1. Field Blank (GM-38-EB-0322) (L1471543-04) analyzed on 03/9/2022 was free of contamination. No qualifications were required.

Laboratory Control Sample (LCS)/ Laboratory Control Sample Duplicate (LCSD):

1. Mercury %REC in Laboratory Control Sample analyzed on 3/21-22/2022 was within the laboratory control limits. No qualifications were required.

Field Duplicate:

1. Sample GM-38-GW-RW3-MW3-DUP-0322 (L1471543-03) was collected as field duplicate for sample GM-38-GW-RW3-MW3-0322 (L1471543-02). Results for mercury were non-detect in the field duplicate pair. No qualifications were required.

Matrix Spike (MS)/ Matrix Spike Duplicate (MSD) and Duplicate/Laboratory Duplicate:

1. Matrix Spike (MS) and Matrix Spike Duplicate (MSD) were performed on sample GM-38-GW-RW3-MW4-0322 (L1471543-01). All %RECs and RPD were within the laboratory control limits. No qualifications were required.
2. Matrix Spike (MS) and Matrix Spike Duplicate (MSD) were performed on sample GM-38-GW-RW3-MW3-0322 (L1471543-02). All %RECs and RPD were within the laboratory control limits. No qualifications were required.

Compound Quantitation and Reported Detection Limits:

1. All sample results were reported within the linear calibration range.

Comments:

1. Validation qualifiers (if required) were entered into the EDD for SDG: L1471543.
2. Summary of the qualified data is listed in the Qualification Summary Table for SDG: L1471543 at the end of the data validation report.

GENERAL CHEMISTRY
USEPA Region II – Data Validation

Project Name: Naval Weapons Industrial Reserve Plant, GM-38 Area-LTM
Location: 100 Broadway, Bethpage, NY
SDG #: FA93984
Client: KOMAN Government Solutions, LLC
Date: 04/29/2021
Laboratory: SGS, Orlando, FL
Reviewer: Sherri Pullar

Summary:

1. Data validation was performed on the data for nine (9) water samples and one (1) equipment blank (EB) sample analyzed for Solids, Total Suspended (TSS) by SM2540D.
2. The samples were collected on 03/09-10/2022. The samples were submitted to SGS North America, Inc. – Dayton, NJ on 3/15/2022 for analysis; analysis of TSS fractions was performed by SGS North America, Inc. – Orlando, FL.
3. Quality Assurance Project Plan for GM-38 Area, Naval Weapons Industrial Reserve Plant, Bethpage, NY; September 3, 2009 was used in evaluating the Solids, Total Suspended data in this summary report.
4. In general, the data are valid as reported and may be used for decision making purposes. No data points were qualified due to nonconformance of Quality Control criteria (See discussion below).

Samples:

The samples included in this review are listed below:

Client Sample ID	Laboratory Sample ID	Collection Date	Matrix	Sample Status
GM-38-GW-RW3-MW4-0322	FA93984-1	3/9/2022	Water	
GM-38-GW-RW3-MW3-0322	FA93984-2	3/9/2022	Water	
GM-38-GW-RW3-MW3-DUP-0322	FA93984-3	3/9/2022	Water	Field Duplicate of sample GM-38-GW-RW3-MW3-0322
GM-38-EB-0322	FA93984-4	3/9/2022	Water	Equipment Blank
GM-38-GW-RW3-MW1-0322	FA93984-5	3/9/2022	Water	
GM-38-GW-RW2-MW1-0322	FA93984-6	3/9/2022	Water	
GM-38-GW-TP01-0322	FA93984-7	3/10/2022	Water	
GM-38-GW-RW1-MW1-0322	FA93984-8	3/10/2022	Water	
GM-38-GW-RW3-MW2-0322	FA93984-9	3/10/2022	Water	
GM-38-GW-RW1-MW3-0322	FA93984-10	3/10/2022	Water	

Sample Conditions/Problems:

1. The Traffic Reports/Chain-of-Custody Records, Sampling Report and/or Laboratory Case Narrative did not indicate any problems with sample receipt, condition of samples, analytical problems or special circumstances affecting the quality of the data. No qualifications were required.

Holding Times:

1. All water samples were analyzed within the 7 days holding times for Solids, Total Suspended. No qualifications were required.

Method Blank (MB), Storage Blank (SB), Field Blank (FB), Rinsate Blank (RB) and Equipment Blank (EB):

1. Method Blank (GN90844) analyzed on 03/17/2022 was free of contamination. No qualifications were required.
2. Equipment Blank (GM-38-EB-0322) (FA93984-4) analyzed on 03/17/2022 was free of contamination. No qualifications were required.

Field Duplicate:

1. Sample GM-38-GW-RW3-MW3-DUP-0322 (FA93984-3) was collected as field duplicate for sample GM-38-GW-RW3-MW3-0322 (FA93984-2). Results for TSS were non-detect in the field duplicate pair. No qualifications were required.



Laboratory Duplicate:

1. Sample Duplicate was performed on sample GM-38-GW-RW3-MW4-0322 (FA93984-1). TSS RPD was outside the laboratory control limits due to low duplicate and sample concentrations. TSS was non-detect in the parent sample; no qualifications were required.

Compound Quantitation and Reported Detection Limits:

1. All sample results were reported within the linear calibration range.

Comments:

1. Validation qualifiers (if required) were entered into the EDD for SDG: FA93984.
2. Summary of the qualified data is listed in the Qualification Summary Table for SDG: FA93984 at the end of the data validation report.

**NWIRP, GM-38 AREA LTM
MARCH 2022
QUALIFICATION SUMMARY TABLE
GROUNDWATER
SDG: L1471543/FA93984
VOCs, MERCURY, and TSS**

Sample Name	Lab ID	Analytical Method	Analyte	Unit	Reported Result	Lab Qualifier	Validated Value	DV Qualifier	Reason Code
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	1,1-Dichloroethene	ug/l	1	J J5	1	J	MS/MSD
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	2-Chloroethyl vinyl ether	ug/l	25	J6 U	25	X	MS/MSD
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	Chloroform	ug/l	0.454	J	2	U	FB
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	Methyl Cyclohexane	ug/l	0.65	J6 U	0.65	UJ	MS/MSD
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	Chloroform	ug/l	0.319	J	2	U	FB
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	Trichloroethene	ug/l	146	Q	146	J	H
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	Chloroform	ug/l	0.299	J	2	U	FB
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	Trichloroethene	ug/l	149	Q	149	J	H
GM-38-EB-0322	L1471543-04	E624	Chloroform	ug/l	0.278	J	2	U	FB
GM-38-EB-0322	L1471543-04	E624	Trichloroethene	ug/l	0.211	J Q	0.211	J	H
GM-38-GW-TP01-0322	L1471543-07	E624	Chloroform	ug/l	0.622	J	2	U	FB
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	Chloroform	ug/l	0.422	J	2	U	FB
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	Chloroform	ug/l	0.632	J	2	U	FB

NOTE: Only results that had qualifications added after validation are listed in this table.

Reason Codes

- | | |
|--------|---|
| FB | Qualification due to field blank contamination. |
| MS/MSD | Qualification due to MS/MSD recovery outside QC criteria. |
| H | Qualification due to exceedance to holding time criteria. |



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW3-MW4-0322	FA93984-1	2540D	3/9/2022	1	Solids, Total Suspended (TSS)	2.5	MG_L	U	2.5	2.5
GM-38-GW-RW3-MW3-0322	FA93984-2	2540D	3/9/2022	1	Solids, Total Suspended (TSS)	2.5	MG_L	U	2.5	2.5
GM-38-GW-RW3-MW3-DUP-0322	FA93984-3	2540D	3/9/2022	1	Solids, Total Suspended (TSS)	2.5	MG_L	U	2.5	2.5
GM-38-EB-0322	FA93984-4	2540D	3/9/2022	1	Solids, Total Suspended (TSS)	2.5	MG_L	U	2.5	2.5
GM-38-GW-RW3-MW1-0322	FA93984-5	2540D	3/9/2022	1	Solids, Total Suspended (TSS)	2.5	MG_L	U	2.5	2.5
GM-38-GW-RW2-MW1-0322	FA93984-6	2540D	3/9/2022	1	Solids, Total Suspended (TSS)	2.5	MG_L	U	2.5	2.5
GM-38-GW-TP01-0322	FA93984-7	2540D	3/10/2022	1	Solids, Total Suspended (TSS)	2.5	MG_L	U	2.5	2.5
GM-38-GW-RW1-MW1-0322	FA93984-8	2540D	3/10/2022	1	Solids, Total Suspended (TSS)	1.4	MG_L		1.3	1.3
GM-38-GW-RW3-MW2-0322	FA93984-9	2540D	3/10/2022	1	Solids, Total Suspended (TSS)	2.5	MG_L	U	2.5	2.5
GM-38-GW-RW1-MW3-0322	FA93984-10	2540D	3/10/2022	1	Solids, Total Suspended (TSS)	2.5	MG_L	U	2.5	2.5
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,1,1-Trichloroethane	0.686	ug/l	J	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,1,2,2-Tetrachloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,1,2-Trichloro-1,2,2-trifluoroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,1,2-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,1-Dichloroethane	3.81	ug/l		0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,1-Dichloroethene	1	ug/l	J	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,2-Dibromo-3-Chloropropane		ug/l	U	2.5	5
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,2-Dibromoethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,2-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,2-Dichloroethane	0.109	ug/l	J	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,2-Dichloropropane		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,3-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	1,4-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	2-Chloroethyl vinyl ether		ug/l	X	25	50
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	2-Hexanone		ug/l	U	5	10
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	4-Methyl-2-pentanone (MIBK)		ug/l	U	5	10
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Acetone		ug/l	U	25	50
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Benzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Bromochloromethane		ug/l	U	0.55	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Bromodichloromethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Bromoform		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Bromomethane		ug/l	U	2	5
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Carbon disulfide		ug/l	U	0.5	1



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Carbon tetrachloride		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Chlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Chlorodibromomethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Chloroethane		ug/l	U	2	5
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Chloroform	2	ug/l	U	2	5
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Chloromethane		ug/l	U	2	4
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	cis-1,2-Dichloroethene	0.243	ug/l	J	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	cis-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Cyclohexane		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Dichlorodifluoromethane		ug/l	U	2	5
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Ethylbenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Isopropylbenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	m&p-Xylenes		ug/l	U	1	2
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Methyl Acetate		ug/l	U	5	20
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Methyl Cyclohexane		ug/l	UJ	0.65	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Methyl Ethyl Ketone		ug/l	U	5	10
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Methyl tert-butyl ether		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Methylene Chloride		ug/l	U	2	5
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Naphthalene		ug/l	U	2	5
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	o-Xylene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Styrene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Tetrachloroethene		ug/l	U	6	12
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Toluene		ug/l	U	0.6	1.2
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	trans-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	trans-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Trichloroethene	5.24	ug/l		0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Trichlorofluoromethane		ug/l	U	2	5
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Vinyl chloride		ug/l	U	0.5	1
GM-38-GW-RW3-MW4-0322	L1471543-01	E624	3/9/2022	1	Xylenes, Total		ug/l	U	1.5	3
GM-38-GW-RW3-MW4-0322	L1471543-01	SW7470A	3/9/2022	1	Mercury		ug/l	U	0.2	0.4
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,1,1-Trichloroethane	0.32	ug/l	J	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,1,2,2-Tetrachloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,1,2-Trichloro-1,2,2-trifluoroethane		ug/l	U	0.5	1



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,1,2-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,1-Dichloroethane	1.56	ug/l		0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,1-Dichloroethene	0.925	ug/l	J	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,2-Dibromo-3-Chloropropane		ug/l	U	2.5	5
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,2-Dibromoethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,2-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,2-Dichloroethane	0.159	ug/l	J	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,2-Dichloropropane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,3-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	1,4-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	2-Chloroethyl vinyl ether		ug/l	U	25	50
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	2-Hexanone		ug/l	U	5	10
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	4-Methyl-2-pentanone (MIBK)		ug/l	U	5	10
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Acetone		ug/l	U	25	50
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Benzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Bromochloromethane		ug/l	U	0.55	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Bromodichloromethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Bromoform		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Bromomethane		ug/l	U	2	5
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Carbon disulfide		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Carbon tetrachloride		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Chlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Chlorodibromomethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Chloroethane		ug/l	U	2	5
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Chloroform	2	ug/l	U	2	5
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Chloromethane		ug/l	U	2	4
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	cis-1,2-Dichloroethene	0.595	ug/l	J	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	cis-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Cyclohexane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Dichlorodifluoromethane		ug/l	U	2	5
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Ethylbenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Isopropylbenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	m&p-Xylenes		ug/l	U	1	2



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Methyl Acetate		ug/l	U	5	20
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Methyl Cyclohexane		ug/l	U	0.65	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Methyl Ethyl Ketone		ug/l	U	5	10
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Methyl tert-butyl ether	0.135	ug/l	J	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Methylene Chloride		ug/l	U	2	5
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Naphthalene		ug/l	U	2	5
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	o-Xylene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Styrene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Tetrachloroethene	0.336	ug/l	J	6	12
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Toluene		ug/l	U	0.6	1.2
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	trans-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	trans-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	10	Trichloroethene	146	ug/l	J	5	10
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Trichlorofluoromethane		ug/l	U	2	5
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Vinyl chloride		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-0322	L1471543-02	E624	3/9/2022	1	Xylenes, Total		ug/l	U	1.5	3
GM-38-GW-RW3-MW3-0322	L1471543-02	SW7470A	3/9/2022	1	Mercury		ug/l	U	0.2	0.4
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,1,1-Trichloroethane	0.302	ug/l	J	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,1,2,2-Tetrachloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,1,2-Trichloro-1,2,2-trifluoroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,1,2-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,1-Dichloroethane	1.61	ug/l		0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,1-Dichloroethene	1.01	ug/l		0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,2-Dibromo-3-Chloropropane		ug/l	U	2.5	5
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,2-Dibromoethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,2-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,2-Dichloroethane	0.15	ug/l	J	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,2-Dichloropropane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,3-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	1,4-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	2-Chloroethyl vinyl ether		ug/l	U	25	50
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	2-Hexanone		ug/l	U	5	10
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	4-Methyl-2-pentanone (MIBK)		ug/l	U	5	10



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Acetone		ug/l	U	25	50
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Benzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Bromochloromethane		ug/l	U	0.55	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Bromodichloromethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Bromoform		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Bromomethane		ug/l	U	2	5
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Carbon disulfide		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Carbon tetrachloride		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Chlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Chlorodibromomethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Chloroethane		ug/l	U	2	5
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Chloroform	2	ug/l	U	2	5
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Chloromethane		ug/l	U	2	4
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	cis-1,2-Dichloroethene	0.581	ug/l	J	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	cis-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Cyclohexane		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Dichlorodifluoromethane		ug/l	U	2	5
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Ethylbenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Isopropylbenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	m&p-Xylenes		ug/l	U	1	2
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Methyl Acetate		ug/l	U	5	20
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Methyl Cyclohexane		ug/l	U	0.65	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Methyl Ethyl Ketone		ug/l	U	5	10
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Methyl tert-butyl ether	0.149	ug/l	J	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Methylene Chloride		ug/l	U	2	5
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Naphthalene		ug/l	U	2	5
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	o-Xylene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Styrene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Tetrachloroethene	0.302	ug/l	J	6	12
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Toluene		ug/l	U	0.6	1.2
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	trans-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	trans-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	10	Trichloroethene	149	ug/l	J	5	10



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Trichlorofluoromethane		ug/l	U	2	5
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Vinyl chloride		ug/l	U	0.5	1
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	E624	3/9/2022	1	Xylenes, Total		ug/l	U	1.5	3
GM-38-GW-RW3-MW3-DUP-0322	L1471543-03	SW7470A	3/9/2022	1	Mercury		ug/l	U	0.2	0.4
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,1,1-Trichloroethane		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,1,2,2-Tetrachloroethane		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,1,2-Trichloro-1,2,2-trifluoroethane		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,1,2-Trichloroethane		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,1-Dichloroethane		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,1-Dichloroethene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,2-Dibromo-3-Chloropropane		ug/l	U	2.5	5
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,2-Dibromoethane		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,2-Dichlorobenzene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,2-Dichloroethane		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,2-Dichloropropane		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,3-Dichlorobenzene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	1,4-Dichlorobenzene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	2-Chloroethyl vinyl ether		ug/l	U	25	50
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	2-Hexanone		ug/l	U	5	10
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	4-Methyl-2-pentanone (MIBK)		ug/l	U	5	10
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Acetone		ug/l	U	25	50
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Benzene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Bromochloromethane		ug/l	U	0.55	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Bromodichloromethane		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Bromoform		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Bromomethane		ug/l	U	2	5
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Carbon disulfide		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Carbon tetrachloride		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Chlorobenzene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Chlorodibromomethane		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Chloroethane		ug/l	U	2	5
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Chloroform	2	ug/l	U	2	5
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Chloromethane		ug/l	U	2	4



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	cis-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	cis-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Cyclohexane		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Dichlorodifluoromethane		ug/l	U	2	5
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Ethylbenzene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Isopropylbenzene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	m&p-Xylenes		ug/l	U	1	2
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Methyl Acetate		ug/l	U	5	20
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Methyl Cyclohexane		ug/l	U	0.65	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Methyl Ethyl Ketone		ug/l	U	5	10
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Methyl tert-butyl ether		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Methylene Chloride		ug/l	U	2	5
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Naphthalene		ug/l	U	2	5
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	o-Xylene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Styrene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Tetrachloroethene		ug/l	U	6	12
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Toluene		ug/l	U	0.6	1.2
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	trans-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	trans-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Trichloroethene	0.211	ug/l	J	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Trichlorofluoromethane		ug/l	U	2	5
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Vinyl chloride		ug/l	U	0.5	1
GM-38-EB-0322	L1471543-04	E624	3/9/2022	1	Xylenes, Total		ug/l	U	1.5	3
GM-38-EB-0322	L1471543-04	SW7470A	3/9/2022	1	Mercury		ug/l	U	0.2	0.4
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,1,1-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,1,2,2-Tetrachloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,1,2-Trichloro-1,2,2-trifluoroethane	0.219	ug/l	J	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,1,2-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,1-Dichloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,1-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,2-Dibromo-3-Chloropropane		ug/l	U	2.5	5
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,2-Dibromoethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,2-Dichlorobenzene		ug/l	U	0.5	1



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,2-Dichloroethane	0.107	ug/l	J	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,2-Dichloropropane		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,3-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	1,4-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	2-Chloroethyl vinyl ether		ug/l	U	25	50
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	2-Hexanone		ug/l	U	5	10
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	4-Methyl-2-pentanone (MIBK)		ug/l	U	5	10
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Acetone		ug/l	U	25	50
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Benzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Bromochloromethane		ug/l	U	0.55	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Bromodichloromethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Bromoform		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Bromomethane		ug/l	U	2	5
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Carbon disulfide		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Carbon tetrachloride		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Chlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Chlorodibromomethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Chloroethane		ug/l	U	2	5
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Chloroform		ug/l	U	2	5
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Chloromethane		ug/l	U	2	4
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	cis-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	cis-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Cyclohexane		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Dichlorodifluoromethane		ug/l	U	2	5
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Ethylbenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Isopropylbenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	m&p-Xylenes		ug/l	U	1	2
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Methyl Acetate		ug/l	U	5	20
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Methyl Cyclohexane		ug/l	U	0.65	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Methyl Ethyl Ketone		ug/l	U	5	10
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Methyl tert-butyl ether		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Methylene Chloride		ug/l	U	2	5
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Naphthalene		ug/l	U	2	5



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	o-Xylene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Styrene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Tetrachloroethene	1.44	ug/l	J	6	12
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Toluene		ug/l	U	0.6	1.2
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	trans-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	trans-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Trichloroethene	16.9	ug/l		0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Trichlorofluoromethane		ug/l	U	2	5
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Vinyl chloride		ug/l	U	0.5	1
GM-38-GW-RW3-MW1-0322	L1471543-05	E624	3/9/2022	1	Xylenes, Total		ug/l	U	1.5	3
GM-38-GW-RW3-MW1-0322	L1471543-05	SW7470A	3/9/2022	1	Mercury		ug/l	U	0.2	0.4
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,1,1-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,1,2,2-Tetrachloroethane		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,1,2-Trichloro-1,2,2-trifluoroethane		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,1,2-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,1-Dichloroethane	2.26	ug/l		0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,1-Dichloroethene	0.413	ug/l	J	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,2-Dibromo-3-Chloropropane		ug/l	U	2.5	5
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,2-Dibromoethane		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,2-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,2-Dichloroethane	0.356	ug/l	J	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,2-Dichloropropane		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,3-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	1,4-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	2-Chloroethyl vinyl ether		ug/l	U	25	50
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	2-Hexanone		ug/l	U	5	10
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	4-Methyl-2-pentanone (MIBK)		ug/l	U	5	10
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Acetone		ug/l	U	25	50
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Benzene	0.113	ug/l	J	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Bromochloromethane		ug/l	U	0.55	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Bromodichloromethane		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Bromoform		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Bromomethane		ug/l	U	2	5



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Carbon disulfide		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Carbon tetrachloride		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Chlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Chlorodibromomethane		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Chloroethane		ug/l	U	2	5
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Chloroform		ug/l	U	2	5
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Chloromethane		ug/l	U	2	4
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	cis-1,2-Dichloroethene	3.9	ug/l		0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	cis-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Cyclohexane		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Dichlorodifluoromethane		ug/l	U	2	5
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Ethylbenzene		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Isopropylbenzene		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	m&p-Xylenes		ug/l	U	1	2
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Methyl Acetate		ug/l	U	5	20
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Methyl Cyclohexane		ug/l	U	0.65	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Methyl Ethyl Ketone		ug/l	U	5	10
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Methyl tert-butyl ether	0.265	ug/l	J	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Methylene Chloride		ug/l	U	2	5
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Naphthalene		ug/l	U	2	5
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	o-Xylene		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Styrene		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Tetrachloroethene		ug/l	U	6	12
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Toluene		ug/l	U	0.6	1.2
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	trans-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	trans-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Trichloroethene	2.45	ug/l		0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Trichlorofluoromethane		ug/l	U	2	5
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Vinyl chloride		ug/l	U	0.5	1
GM-38-GW-RW2-MW1-0322	L1471543-06	E624	3/9/2022	1	Xylenes, Total		ug/l	U	1.5	3
GM-38-GW-RW2-MW1-0322	L1471543-06	SW7470A	3/9/2022	1	Mercury		ug/l	U	0.2	0.4
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,1,1-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,1,2,2-Tetrachloroethane		ug/l	U	0.5	1



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,1,2-Trichloro-1,2,2-trifluoroethane		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,1,2-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,1-Dichloroethane	0.895	ug/l	J	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,1-Dichloroethene	0.339	ug/l	J	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,2-Dibromo-3-Chloropropane		ug/l	U	2.5	5
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,2-Dibromoethane		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,2-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,2-Dichloroethane		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,2-Dichloropropane		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,3-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	1,4-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	2-Chloroethyl vinyl ether		ug/l	U	25	50
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	2-Hexanone		ug/l	U	5	10
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	4-Methyl-2-pentanone (MIBK)		ug/l	U	5	10
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Acetone		ug/l	U	25	50
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Benzene		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Bromochloromethane		ug/l	U	0.55	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Bromodichloromethane		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Bromoform		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Bromomethane		ug/l	U	2	5
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Carbon disulfide		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Carbon tetrachloride		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Chlorobenzene		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Chlorodibromomethane		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Chloroethane		ug/l	U	2	5
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Chloroform	2	ug/l	U	2	5
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Chloromethane		ug/l	U	2	4
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	cis-1,2-Dichloroethene	1.99	ug/l		0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	cis-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Cyclohexane		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Dichlorodifluoromethane		ug/l	U	2	5
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Ethylbenzene		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Isopropylbenzene		ug/l	U	0.5	1



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	m&p-Xylenes		ug/l	U	1	2
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Methyl Acetate		ug/l	U	5	20
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Methyl Cyclohexane		ug/l	U	0.65	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Methyl Ethyl Ketone		ug/l	U	5	10
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Methyl tert-butyl ether	0.44	ug/l	J	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Methylene Chloride		ug/l	U	2	5
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Naphthalene		ug/l	U	2	5
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	o-Xylene		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Styrene		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Tetrachloroethene	1.84	ug/l	J	6	12
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Toluene		ug/l	U	0.6	1.2
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	trans-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	trans-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Trichloroethene	12.4	ug/l		0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Trichlorofluoromethane		ug/l	U	2	5
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Vinyl chloride		ug/l	U	0.5	1
GM-38-GW-TP01-0322	L1471543-07	E624	3/10/2022	1	Xylenes, Total		ug/l	U	1.5	3
GM-38-GW-TP01-0322	L1471543-07	SW7470A	3/10/2022	1	Mercury		ug/l	U	0.2	0.4
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,1,1-Trichloroethane	0.673	ug/l	J	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,1,2,2-Tetrachloroethane		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,1,2-Trichloro-1,2,2-trifluoroethane		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,1,2-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,1-Dichloroethane	4.18	ug/l		0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,1-Dichloroethene	1.39	ug/l		0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,2-Dibromo-3-Chloropropane		ug/l	U	2.5	5
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,2-Dibromoethane		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,2-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,2-Dichloroethane	0.119	ug/l	J	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,2-Dichloropropane		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,3-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	1,4-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	2-Chloroethyl vinyl ether		ug/l	U	25	50
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	2-Hexanone		ug/l	U	5	10



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	4-Methyl-2-pentanone (MIBK)		ug/l	U	5	10
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Acetone		ug/l	U	25	50
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Benzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Bromochloromethane		ug/l	U	0.55	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Bromodichloromethane		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Bromoform		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Bromomethane		ug/l	U	2	5
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Carbon disulfide		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Carbon tetrachloride		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Chlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Chlorodibromomethane		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Chloroethane		ug/l	U	2	5
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Chloroform	2	ug/l	U	2	5
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Chloromethane		ug/l	U	2	4
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	cis-1,2-Dichloroethene	4.33	ug/l		0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	cis-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Cyclohexane		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Dichlorodifluoromethane		ug/l	U	2	5
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Ethylbenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Isopropylbenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	m&p-Xylenes		ug/l	U	1	2
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Methyl Acetate		ug/l	U	5	20
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Methyl Cyclohexane		ug/l	U	0.65	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Methyl Ethyl Ketone		ug/l	U	5	10
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Methyl tert-butyl ether	0.175	ug/l	J	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Methylene Chloride		ug/l	U	2	5
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Naphthalene		ug/l	U	2	5
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	o-Xylene		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Styrene		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Tetrachloroethene		ug/l	U	6	12
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Toluene		ug/l	U	0.6	1.2
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	trans-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	trans-1,3-Dichloropropene		ug/l	U	0.5	1



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Trichloroethene	73.2	ug/l		0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Trichlorofluoromethane		ug/l	U	2	5
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Vinyl chloride		ug/l	U	0.5	1
GM-38-GW-RW1-MW1-0322	L1471543-08	E624	3/10/2022	1	Xylenes, Total		ug/l	U	1.5	3
GM-38-GW-RW1-MW1-0322	L1471543-08	SW7470A	3/10/2022	1	Mercury		ug/l	U	0.2	0.4
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,1,1-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,1,2,2-Tetrachloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,1,2-Trichloro-1,2,2-trifluoroethane	0.637	ug/l	J	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,1,2-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,1-Dichloroethane	0.371	ug/l	J	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,1-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,2-Dibromo-3-Chloropropane		ug/l	U	2.5	5
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,2-Dibromoethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,2-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	0.5	1,2-Dichloroethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,2-Dichloropropane		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,3-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	1,4-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	2-Chloroethyl vinyl ether		ug/l	U	25	50
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	2-Hexanone		ug/l	U	5	10
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	4-Methyl-2-pentanone (MIBK)		ug/l	U	5	10
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Acetone		ug/l	U	25	50
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Benzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Bromochloromethane		ug/l	U	0.55	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Bromodichloromethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Bromoform		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Bromomethane		ug/l	U	2	5
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Carbon disulfide		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Carbon tetrachloride		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Chlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Chlorodibromomethane		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Chloroethane		ug/l	U	2	5
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Chloroform		ug/l	U	2	5



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Chloromethane		ug/l	U	2	4
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	cis-1,2-Dichloroethene	0.774	ug/l	J	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	cis-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Cyclohexane		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Dichlorodifluoromethane		ug/l	U	2	5
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Ethylbenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Isopropylbenzene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	m&p-Xylenes		ug/l	U	1	2
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Methyl Acetate		ug/l	U	5	20
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Methyl Cyclohexane		ug/l	U	0.65	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Methyl Ethyl Ketone		ug/l	U	5	10
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Methyl tert-butyl ether		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Methylene Chloride		ug/l	U	2	5
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Naphthalene		ug/l	U	2	5
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	o-Xylene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Styrene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Tetrachloroethene		ug/l	U	6	12
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Toluene		ug/l	U	0.6	1.2
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	trans-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	trans-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Trichloroethene	69.2	ug/l		0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Trichlorofluoromethane		ug/l	U	2	5
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Vinyl chloride		ug/l	U	0.5	1
GM-38-GW-RW3-MW2-0322	L1471543-09	E624	3/10/2022	1	Xylenes, Total		ug/l	U	1.5	3
GM-38-GW-RW3-MW2-0322	L1471543-09	SW7470A	3/10/2022	1	Mercury		ug/l	U	0.2	0.4
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,1,1-Trichloroethane	0.767	ug/l	J	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,1,2,2-Tetrachloroethane		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,1,2-Trichloro-1,2,2-trifluoroethane		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,1,2-Trichloroethane		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,1-Dichloroethane	3.83	ug/l		0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,1-Dichloroethene	1.06	ug/l		0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,2-Dibromo-3-Chloropropane		ug/l	U	2.5	5
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,2-Dibromoethane		ug/l	U	0.5	1



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,2-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,2-Dichloroethane	0.17	ug/l	J	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,2-Dichloropropane		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,3-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	1,4-Dichlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	2-Chloroethyl vinyl ether		ug/l	U	25	50
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	2-Hexanone		ug/l	U	5	10
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	4-Methyl-2-pentanone (MIBK)		ug/l	U	5	10
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Acetone		ug/l	U	25	50
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Benzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Bromochloromethane		ug/l	U	0.55	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Bromodichloromethane		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Bromoform		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Bromomethane		ug/l	U	2	5
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Carbon disulfide		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Carbon tetrachloride		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Chlorobenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Chlorodibromomethane		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Chloroethane		ug/l	U	2	5
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Chloroform	2	ug/l	U	2	5
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Chloromethane		ug/l	U	2	4
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	cis-1,2-Dichloroethene	0.273	ug/l	J	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	cis-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Cyclohexane		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Dichlorodifluoromethane		ug/l	U	2	5
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Ethylbenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Isopropylbenzene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	m&p-Xylenes		ug/l	U	1	2
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Methyl Acetate		ug/l	U	5	20
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Methyl Cyclohexane		ug/l	U	0.65	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Methyl Ethyl Ketone		ug/l	U	5	10
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Methyl tert-butyl ether	0.235	ug/l	J	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Methylene Chloride		ug/l	U	2	5



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Naphthalene		ug/l	U	2	5
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	o-Xylene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Styrene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Tetrachloroethene	0.343	ug/l	J	6	12
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Toluene		ug/l	U	0.6	1.2
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	trans-1,2-Dichloroethene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	trans-1,3-Dichloropropene		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Trichloroethene	3.42	ug/l		0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Trichlorofluoromethane		ug/l	U	2	5
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Vinyl chloride		ug/l	U	0.5	1
GM-38-GW-RW1-MW3-0322	L1471543-10	E624	3/10/2022	1	Xylenes, Total		ug/l	U	1.5	3
GM-38-GW-RW1-MW3-0322	L1471543-10	SW7470A	3/10/2022	1	Mercury		ug/l	U	0.2	0.4
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,1,1-Trichloroethane		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,1,2,2-Tetrachloroethane		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,1,2-Trichloro-1,2,2-trifluoroethane		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,1,2-Trichloroethane		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,1-Dichloroethane		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,1-Dichloroethane		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,2-Dibromo-3-Chloropropane		ug/l	U	2.5	5
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,2-Dibromoethane		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,2-Dichlorobenzene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,2-Dichloroethane		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,2-Dichloropropane		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,3-Dichlorobenzene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	1,4-Dichlorobenzene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	2-Chloroethyl vinyl ether		ug/l	U	25	50
TRIP BLANK	L1471543-11	E624	3/9/2022	1	2-Hexanone		ug/l	U	5	10
TRIP BLANK	L1471543-11	E624	3/9/2022	1	4-Methyl-2-pentanone (MIBK)		ug/l	U	5	10
TRIP BLANK	L1471543-11	E624	3/9/2022	25	Acetone		ug/l	U	25	50
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Benzene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Bromochloromethane		ug/l	U	0.55	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Bromodichloromethane	1.19	ug/l		0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Bromoform		ug/l	U	0.5	1



NWIRP BETHPAGE GM-38
MARCH 2022 EVENT
DATA SUMMARY TABLE
AQUEOUS
SDG: L1471543/FA93984

Sample Name	Lab ID	Analytical Method	Collection Date	Dilution Factor	Analyte	Result	Unit	Qualifier	LOD	LOQ
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Bromomethane		ug/l	U	2	5
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Carbon disulfide		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Carbon tetrachloride		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Chlorobenzene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Chlorodibromomethane		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Chloroethane		ug/l	U	2	5
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Chloroform	5.06	ug/l		2	5
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Chloromethane		ug/l	U	2	4
TRIP BLANK	L1471543-11	E624	3/9/2022	1	cis-1,2-Dichloroethene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	cis-1,3-Dichloropropene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Cyclohexane		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Dichlorodifluoromethane		ug/l	U	2	5
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Ethylbenzene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Isopropylbenzene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	m&p-Xylenes		ug/l	U	1	2
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Methyl Acetate		ug/l	U	5	20
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Methyl Cyclohexane		ug/l	U	0.65	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Methyl Ethyl Ketone		ug/l	U	5	10
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Methyl tert-butyl ether		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Methylene Chloride	0.903	ug/l	J	2	5
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Naphthalene		ug/l	U	2	5
TRIP BLANK	L1471543-11	E624	3/9/2022	1	o-Xylene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Styrene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Tetrachloroethene		ug/l	U	6	12
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Toluene		ug/l	U	0.6	1.2
TRIP BLANK	L1471543-11	E624	3/9/2022	1	trans-1,2-Dichloroethene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	trans-1,3-Dichloropropene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Trichloroethene		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Trichlorofluoromethane		ug/l	U	2	5
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Vinyl chloride		ug/l	U	0.5	1
TRIP BLANK	L1471543-11	E624	3/9/2022	1	Xylenes, Total		ug/l	U	1.5	3