



DAY ENVIRONMENTAL, INC.

ENVIRONMENTAL CONSULTANTS
AN AFFILIATE OF DAY ENGINEERING, P.C.

July 29, 2022

Silence Dogood, LLC
c/o Jeffrey Belt
211 Franklin Street
Olean, New York 14760

RE: Annual Groundwater Monitoring and Cover Inspection
NYSDEC BCP Site No. C905043
202 Franklin Street
Olean, New York

Dear Mr. Belt:

As required in the Site Management Plan (SMP) dated December 2019, Day Environmental, Inc. (DAY) completed an annual groundwater monitoring event and cover inspection at the above-referenced property (Site) on June 14, 2022. The following sections describe the work completed and present data generated. A project locus map, depicting the location of the Site, is provided as Figure 1.

Background

The Site was remediated under the New York State Department of Environmental Conservation (NYSDEC) Brownfield Cleanup Program (BCP), and the NYSDEC issued a certificate of completion for the Site on December 11, 2019.

Following the completion of the remedial work, some contamination was left beneath a cover system at the Site. This cover system consists of asphalt pavement (i.e., over the 1.83-acre portion is developed as a paved parking lot); one-foot-thick mulch cover under the driplines of the remaining mature trees (i.e., located along the eastern edge of the Site); one-foot-thick stone cover within a surface drainage channel (i.e., located north of the paved parking lot); and/or one-foot-thick soil cover over the remaining portions of the Site. The December 2019 SMP was prepared to manage the remaining contamination at the Site until the Environmental Easement is extinguished in accordance with New York State Environmental Law (ECL) Article 71, Title 36. As outlined in Section 4.0 *Monitoring and Sampling*, of the December 2019 SMP, the following actions are required to address the residual contamination: 1) the completion of annual groundwater sampling and analysis in the locations, and utilizing the methods, specified in the SMP and 2) completion of the annual cover inspection.

Field Activities

On June 14, 2022, DAY representatives were at the Site to conduct a site inspection and monitoring event in accordance with the December 2019 SMP. The following scope of work was completed:

- Measurement of static water level in groundwater monitoring wells MW-A through MW-G using a static water level meter;

1563 LYELL AVENUE
ROCHESTER, NEW YORK 14606
(585) 454-0210
FAX (585) 454-0825

www.dayenvironmental.com

- Collection of groundwater samples from monitoring wells MW-A through MW-G using low flow purge and sample techniques;
- A cover inspection that included photographing representative portions of the site cover and summarizing conditions on the Site-Wide Cover Inspection Form, to document current conditions; and
- Submittal of groundwater samples to Alpha Analytical Laboratory (Alpha) in Westborough, MA for testing of parameters identified in the SMP. [Note: Alpha is a New York State Department of Health (NYSDOH) Environmental Laboratory Approval Program (ELAP)-certified analytical laboratory.]
- Validation of the groundwater test results reported by Alpha, and preparation of Data Usability Summary Report (DUSR), by Vali-Data of WNY, LLC.

The approximate locations of the groundwater monitoring wells that were assessed and sampled on June 14, 2022 are depicted on Figure 2. A summary of the groundwater elevations for June 14, 2022, calculated from the static groundwater levels measured on that date, are presented on Table 1. [Note: Table 1 also summarizes the construction details and the sampling program for the groundwater monitoring wells that comprise the long-term monitoring network required by the SMP.] The groundwater elevations calculated for June 14, 2022 were used to prepare the potentiometric groundwater contours that are depicted on Figure 2. The groundwater sampling activities are documented on the groundwater sampling logs included in Attachment A.

A copy of the June 14, 2022 Site-Wide Cover Inspection Form and copies of select photographs are included in Attachment B.

Analytical Laboratory Test Results

The groundwater samples collected on June 14, 2022 were tested by Alpha for target analyte list (TAL) metals using USEPA Methods 6020B and 7040A.

A copy of the analytical laboratory report prepared by Alpha and executed chain-of-custody documentation are included in Attachment C. A copy of the DUSR prepared by Vali-Data of WNY, LLC is also included in Attachment C. The constituents detected in the samples submitted for analytical laboratory testing as part of this groundwater monitoring event are summarized on Table 2 *Summary of TAL Metals: Groundwater Samples*. The TAL metals detected in the groundwater samples collected from the Site during the previous groundwater monitoring events are also summarized on Table 2. The results of the data validation have been incorporated into Table 2.

Table 2 includes applicable Class GA (i.e., potable drinking water from a groundwater source) standards or guidance values for the detected parameters as presented in NYSDEC Division of Water Technical and Operational Guidance Series 1.1.1 document titled, Ambient Water Quality Standards and Guidance Effluent Limitations dated June 1998 as amended April 2000 (TOGS 1.1.1).

Jeffrey Belt
July 29, 2022
Page 3

Conclusions and Recommendations

The annual inspection of the cover system revealed that repairs to cracking/separation of the asphalt in the Employee Parking Lot had been completed (i.e., as recommended following the previous annual inspection, conducted on June 29, 2021), and that the cover system on the Site was in-place and in overall good condition with no repairs needed at this time.

With the exception of total arsenic detected in the sample from monitoring well MW-D, the concentrations of metals detected in the groundwater samples collected on June 14, 2022, were comparable to the concentrations from the samples collected on June 29, 2021 and during previous sampling events. The concentration of total arsenic (i.e., 124.8 µg/l) measured in the groundwater sample collected on June 14, 2022 from monitoring well MW-D is approximately 2.5 times greater than the concentration of total arsenic measured in the groundwater sample collected from this location during the previous annual sampling event (i.e., 49.4 µg/l, collected on June 29, 2021); and is approximately 2 times greater than the average concentration of total arsenic (i.e., 62.4 µg/l) measured in groundwater samples collected from this location since the monitoring well was installed in 2014.

It is recommended that monitoring well MW-D be re-sampled in September 2022, and potentially December 2022 and March 2023 depending on test results (i.e., during the current reporting period, which ends on April 11, 2023), using low-flow sampling procedures; and that the sample be tested for total arsenic in order to assess whether the concentration of total arsenic measured in the groundwater sample collected on June 14, 2022 was anomalous, or represents a change in the water quality trend for this location.

If there are questions regarding this submittal, please contact this office.

Very truly,
Day Environmental, Inc.



Charles Hampton
Project Geologist



Raymond L. Kampff
Principal

Enclosure

Figures:

Figure 1 – Project Locus Map

Figure 2 – Site Plan and Potentiometric Groundwater Contour Map measured on June 14, 2022

Jeffrey Belt
July 29, 2022
Page 4

Tables:

Table 1 – Summary of Monitoring Well Location Details, Construction, Groundwater Elevations and Analytical Parameters for Long Term Monitoring

Table 2 – Summary of TAL Metals: Groundwater Samples


Attachments:

Attachment A – Groundwater Sampling Logs for June 14, 2022

Attachment B – Site-Wide Cover Inspection Form and Photographs

Attachment C – Analytical Laboratory Report, Chain-of Custody Documentation and DUSR

FIGURES



NOTE:

Topo imagery provided by ESRI Online Services and USGS 7.5 Minute Quad of Olean, NY, dated 1968.

Site Coordinates are in Decimal Degrees:

77° 26' 23.58" W 43° 5' 42.67" N

0 1,000 2,000 4,000
Feet

Copyright:© 2013 National Geographic Society, i-cubed


Date	07/15/2019
Drawn By	CAH
Scale	AS NOTED

day
DAY ENVIRONMENTAL, INC.
 Environmental Consultants
 Rochester, New York 14606
 New York, New York 10170

Project Title	202 FRANKLIN STREET OLEAN, NEW YORK
	BCP SITE NO. C905043
Drawing Title	Site Location Map

Project No.	4884S-13
	FIGURE 1

Last Date Saved: 26 Jul 2022 Document Path: E:\GIS Mapping\SoE\proj\4884S-13\SoE\p1202Franklin\Long_Term_Monitoring\4884S-04-06-14-2022_GW_Contour.mxd




Legend

- Groundwater monitoring well with groundwater elevation calculated based on static water level measured June 14, 2022
- Potentiometric Groundwater Contour
- BCP Site 202 Franklin Street Property Boundary
- Apparent direction of groundwater flow

NOTE:

Property boundary based on a Survey entitled, "Goodban Belt LLC of lands at 202 Franklin Street", dated November 25, 2013, prepared by D. Michael Canada, New York State Licensed Land Surveyor, 483 Union Street, Olean, NY 14760.

Aerial imagery provided by the New York State GIS Clearinghouse, date 2021.



DESIGNED BY	DATE
CAH	07-2022
DRAWN BY	DATE DRAWN
CAH/CPS	07-2022
SCALE	DATE ISSUED
AS NOTED	07-26-2022

day ENVIRONMENTAL, INC.
 Environmental Consultants
 Rochester, New York 14606
 New York, New York 10170

Project Title	202 FRANKLIN STREET OLEAN, NEW YORK
Project No.	4884S-13
Drawing Title	Groundwater Contour Map: June 14, 2022
BCP SITE NO.	C905043

FIGURE 2

TABLES

TABLE 1
202 FRANKLIN STREET
OLEAN, NEW YORK
BCP SITE NO. C905043

SUMMARY OF MONITORING WELL LOCATION DETAILS, CONSTRUCTION, GROUNDWATER ELEVATIONS
AND ANALYTICAL PARAMETERS FOR LONGTERM MONITORING

Monitoring Well ID Sample Locations	Well Location	UTM NAD83 Coordinates (feet) (northing/easting)	Well Diameter (inches)	Elevation (feet above mean sea level)									Analytical Parameters to be Analyzed Year 3
				Casing	Surface	Screen Top	Screen Bottom	Groundwater					
								7/10/2014	11/5/2014	6/25/2020	6/29/2021	6/14/2022	
MW-A	On-site perimeter (up-gradient)	763496.8 1186801.0	1	1427.70	1428.04	1411.80	1401.80	1412.66	1410.17	1411.95	1411.39	1412.56	TAL Metals
MW-B	On-site	763736.2 1186986.0	2	1429.95	1427.72*	1412.45	1402.45	1412.44	1410.02	1411.72	1411.19	1412.31	TAL Metals
MW-C	On-site perimeter (up-gradient)	763995.0 1186888.3	2	1429.34	1426.69*	1417.34	1407.34	1412.71	1410.27	1411.93	1411.45	1412.63	TAL Metals
MW-D	On-site	763978.7 1187071.6	2	1428.08	1426.12*	1412.08	1402.08	1412.52	1410.09	1411.76	1411.25	1412.41	TAL Metals
MW-E	On-site perimeter (down-gradient)	763824.9 1187192.4	2	1427.40	1427.81*	1409.40	1399.40	1412.59	1409.90	1411.47	1411.01	1412.12	TAL Metals
MW-F	On-site perimeter (down-gradient)	763624.6 1187259.2	2	1428.53	1428.92	1411.03	1401.03	1411.78	1409.31	1410.85	1410.37	1411.47	TAL Metals
MW-G	On-site perimeter (down-gradient)	763493.8 1187059.7	2	1429.26	1429.66	1411.76	1401.76	1412.39	1410.05	1411.65	1411.14	1412.21	TAL Metals

Notes:

* - Surface elevation prior to the placement of the minimum 1 foot tick soil cover over the portion of the Site on which this monitoring well is located.

ATTACHMENT A

GROUNDWATER SAMPLING LOGS

DAY ENVIRONMENTAL, INC.
LOW-FLOW GROUNDWATER PURGING AND SAMPLING LOG
WELL MW-A

SECTION 1 - SITE AND WELL INFORMATION			
SITE LOCATION	202 Franklin Street, Olean, New York	JOB #	4884S-13
PROJECT NAME:	NYSDEC BCP Site C905043	DATE:	June 14, 2022
SAMPLE COLLECTOR(S):	CCD/CMC	WEATHER:	Sunny, ~71° F
PID READING IN WELL HEADSPACE (PPM):	NM	MEASURING POINT (for water levels):	Top of Casing
CASING TYPE:	PVC	WELL DIAMETER (INCHES):	1
SCREENED INTERVAL [FT BTOC]:	15.56 - 25.56	INITIAL WATER LEVEL (SWL) [FT]:	SWL / Date Measured 15.14 / 6-14-22
WELL DEPTH [FT BTOC]:	25.56	DEPTH OF PUMP INTAKE [FT BTOC]:	20.9
<small>(Do NOT Measure Well depth Prior To Purging And Sampling)</small>			
LNAPL:	ND	DNAPL:	NM
OTHER OBSERVATIONS: None			

SECTION 2 – SAMPLING EQUIPMENT	
PUMP TYPE:	Geotech Geopump™ - Peristaltic pump
WATER LEVEL METER:	Solonist OWI Meter
WATER QUALITY METER(S):	YSI Pro DDS
STABILIZED PUMP RATE (ml/min):	160
STABILIZED DRAWDOWN WATER LEVEL [FT]:	15.20

SECTION 3 – WATER QUALITY DATA MONITORING									
Time	Pumping Rate (ml/min)	Water Level (ft)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Conductivity (mS/cm)	pH	Temp. (C°)	Total Vol. Pumped (ml)
15:10	NM								0
15:13	160	15.20	1.51	-181.6	24.96	0.741	6.83	13.3	360
15:15	160	15.20	1.45	-179.4	18.32	0.738	6.83	13.1	680
15:17	160	15.20	1.42	-176.8	14.09	0.736	6.84	13.2	1,000
15:19	160	15.20	1.40	-176.2	11.90	0.736	6.84	13.2	1,320
15:21	160	15.20	1.37	-176.9	8.08	0.735	6.84	13.0	1,640
15:23	160	15.20	1.36	-177.4	6.56	0.732	6.84	13.2	1,960
15:25	160	15.20	1.35	-178.7	5.62	0.733	6.84	12.8	2,280
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
SAMPLE OBSERVATIONS: Clear									

SECTION 4 - SAMPLE IDENTIFICATION AND ANALYTICAL LABORATORY PARAMETERS			
SAMPLE ID #	DATE / TIME	SAMPLING METHOD	ANALYTICAL SCAN(S)
MW-A/20220614	6-14-22 / 15:26	Peristaltic Pump	TAL Metals

NM = Not Measured
 ND = Not Detected

DAY ENVIRONMENTAL, INC.
LOW-FLOW GROUNDWATER PURGING AND SAMPLING LOG
WELL MW-B

SECTION 1 - SITE AND WELL INFORMATION	
SITE LOCATION <u>202 Franklin Street, Olean, New York</u>	JOB # <u>4884S-13</u>
PROJECT NAME: <u>NYSDEC BCP Site C905043</u>	DATE: <u>June 14, 2022</u>
SAMPLE COLLECTOR(S): <u>CCD/CMC</u>	WEATHER: <u>Sunny, ~71° F</u>
PID READING IN WELL HEADSPACE (PPM): <u>NM</u>	MEASURING POINT (for water levels): <u>Top of Casing</u>
CASING TYPE: <u>PVC</u>	WELL DIAMETER (INCHES): <u>2</u>
SCREENED INTERVAL [FT BTOC]: <u>19.73 - 29.73</u>	INITIAL WATER LEVEL (SWL) [FT]: <u>SWL / Date Measured</u> <u>17.64 / 6-14-22</u>
WELL DEPTH [FT BTOC]: <u>29.73</u> (Do NOT Measure Well depth Prior To Purging And Sampling)	DEPTH OF PUMP INTAKE [FT BTOC]: <u>24.2</u>
LNAPL: <u>ND</u>	DNAPL: <u>NM</u>
OTHER OBSERVATIONS: <u>Iron bacteria on OWI probe</u>	

SECTION 2 – SAMPLING EQUIPMENT	
PUMP TYPE: <u>Geotech Geopump™ - Peristaltic pump</u>	WATER LEVEL METER: <u>Solonist OWI Meter</u>
WATER QUALITY METER(S): <u>YSI Pro DDS</u>	
STABILIZED PUMP RATE (ml/min): <u>180</u>	STABILIZED DRAWDOWN WATER LEVEL [FT]: <u>17.67</u>

SECTION 3 – WATER QUALITY DATA MONITORING									
Time	Pumping Rate (ml/min)	Water Level (ft)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Conductivity (mS/cm)	pH	Temp. (C°)	Total Vol. Pumped (ml)
10:30					NM				0
10:38	180	17.67	1.32	-126.7	14.48	1.505	6.94	12.9	600
10:41	180	17.67	1.26	-136.8	14.37	1.512	6.94	12.9	1,140
10:44	180	17.67	1.23	-139.5	5.17	1.519	6.94	13.0	1,680
10:47	180	17.67	1.21	-146.0	8.63	1.525	6.94	12.8	2,220
10:50	180	17.67	1.20	-152.1	3.41	1.528	6.94	12.9	2,760
10:53	180	17.67	1.18	-156.7	3.08	1.524	6.94	13.2	3,300
10:56	180	17.67	1.17	-163.1	3.85	1.528	6.94	13.2	3,840
10:59	180	17.67	1.16	-167.6	4.88	1.526	6.94	13.1	4,380
11:02	180	17.67	1.15	-171.3	5.74	1.525	6.95	13.0	4,920
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
SAMPLE OBSERVATIONS: Petroleum-type odor noted on sample									

SECTION 4 - SAMPLE IDENTIFICATION AND ANALYTICAL LABORATORY PARAMETERS			
SAMPLE ID #	DATE / TIME	SAMPLING METHOD	ANALYTICAL SCAN(S)
MW-B/20220614	6-14-22 / 11:04	Peristaltic Pump	TAL Metals

NM = Not Measured
 ND = Not Detected

DAY ENVIRONMENTAL, INC.
LOW-FLOW GROUNDWATER PURGING AND SAMPLING LOG
WELL MW-C

SECTION 1 - SITE AND WELL INFORMATION			
SITE LOCATION	202 Franklin Street, Olean, New York	JOB #	4884S-13
PROJECT NAME:	NYSDEC BCP Site C905043	DATE:	June 14, 2022
SAMPLE COLLECTOR(S):	CCD/CMC	WEATHER:	Cloudy, 71° F
PID READING IN WELL HEADSPACE (PPM):	NM	MEASURING POINT (for water levels):	Top of Casing
CASING TYPE:	PVC	WELL DIAMETER (INCHES):	2
SCREENED INTERVAL [FT BTOC]:	14.65 - 24.65	INITIAL WATER LEVEL (SWL) [FT]:	SWL / Date Measured 16.71 / 6-14-22
WELL DEPTH [FT BTOC]:	24.65	DEPTH OF PUMP INTAKE [FT BTOC]:	21.2
(Do NOT Measure Well depth Prior To Purging And Sampling)			
LNAPL:	ND	DNAPL:	NM
OTHER OBSERVATIONS: None			

SECTION 2 – SAMPLING EQUIPMENT	
PUMP TYPE:	Geotech Geopump™ - Peristaltic pump
WATER LEVEL METER:	Solonist OWI Meter
WATER QUALITY METER(S):	YSI Pro DDS
STABILIZED PUMP RATE (ml/min):	100
STABILIZED DRAWDOWN WATER LEVEL [FT]:	16.74

SECTION 3 – WATER QUALITY DATA MONITORING									
Time	Pumping Rate (ml/min)	Water Level (ft)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Conductivity (mS/cm)	pH	Temp. (C°)	Total Vol. Pumped (ml)
08:46					NM				0
08:53	100	16.74	1.48	-81.8	10.02	0.654	6.16	12.7	200
08:56	100	16.74	1.42	-82.4	8.62	0.644	6.16	12.5	500
08:59	100	16.74	1.38	-82.5	5.84	0.629	6.16	12.4	800
09:02	100	16.74	1.33	-83.6	6.74	0.614	6.16	12.7	1,100
09:05	100	16.74	1.32	-84.6	5.18	0.606	6.15	12.8	1,400
09:08	100	16.74	1.30	-85.1	4.83	0.600	6.14	12.6	1,700
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
SAMPLE OBSERVATIONS: Clear									

SECTION 4 - SAMPLE IDENTIFICATION AND ANALYTICAL LABORATORY PARAMETERS			
SAMPLE ID #	DATE / TIME	SAMPLING METHOD	ANALYTICAL SCAN(S)
MW-C/20220617	6-14-22 / 09:10	Peristaltic Pump	TAL Metals (MS + MSD)

NM = Not Measured
 ND = Not Detected

DAY ENVIRONMENTAL, INC.
LOW-FLOW GROUNDWATER PURGING AND SAMPLING LOG
WELL MW-D

SECTION 1 - SITE AND WELL INFORMATION			
SITE LOCATION	202 Franklin Street, Olean, New York	JOB #	4884S-13
PROJECT NAME:	NYSDEC BCP Site C905043	DATE:	June 14, 2022
SAMPLE COLLECTOR(S):	CCD/CMC	WEATHER:	Sunny, ~71° F
PID READING IN WELL HEADSPACE (PPM):	NM	MEASURING POINT (for water levels):	Top of Casing
CASING TYPE:	PVC	WELL DIAMETER (INCHES):	2
SCREENED INTERVAL [FT BTOC]:	17.96 - 27.96	INITIAL WATER LEVEL (SWL) [FT BTOC]:	SWL / Date Measured 15.67 / 6-14-22
WELL DEPTH [FT BTOC]:	27.96	DEPTH OF PUMP INTAKE [FT BTOC]:	22.4
<small>(Do NOT Measure Well depth Prior To Purging And Sampling)</small>			
LNAPL:	ND	DNAPL:	NM
			OTHER OBSERVATIONS: Iron bacteria observed

SECTION 2 – SAMPLING EQUIPMENT	
PUMP TYPE: Geotech Geopump™ - Peristaltic pump	WATER LEVEL METER: Solonist OWI Meter
WATER QUALITY METER(S): YSI Pro DDS	
STABILIZED PUMP RATE (ml/min): 120	STABILIZED DRAWDOWN WATER LEVEL [FT]: 15.68

SECTION 3 – WATER QUALITY DATA MONITORING									
Time	Pumping Rate (ml/min)	Water Level (ft)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Conductivity (mS/cm)	pH	Temp. (C°)	Total Vol. Pumped (ml)
09:40					NM				0
09:45	120	15.68	1.48	-171.8	16.23	1.764	6.84	11.9	320
09:48	120	15.68	1.39	-176.9	20.43	1.764	6.87	11.8	680
09:51	120	15.68	1.34	-180.3	25.92	1.762	6.89	11.9	1,040
09:54	120	15.68	1.31	-182.3	22.77	1.762	6.91	11.8	1,400
09:57	120	15.68	1.28	-185.5	16.98	1.761	6.92	11.7	1,760
10:00	120	15.68	1.27	-186.9	17.42	1.762	6.92	11.6	2,120
10:03	120	15.68	1.26	-189.1	24.07	1.758	6.93	11.6	2,480
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
SAMPLE OBSERVATIONS: Clear									

SECTION 4 - SAMPLE IDENTIFICATION AND ANALYTICAL LABORATORY PARAMETERS			
SAMPLE ID #	DATE / TIME	SAMPLING METHOD	ANALYTICAL SCAN(S)
MW-D/20220614	6-14-22 / 10:05	Peristaltic Pump	TAL Metals

NM = Not Measured
 ND = Not Detected

DAY ENVIRONMENTAL, INC.
LOW-FLOW GROUNDWATER PURGING AND SAMPLING LOG
WELL MW-E

SECTION 1 - SITE AND WELL INFORMATION	
SITE LOCATION	<u>202 Franklin Street, Olean, New York</u> JOB # <u>4884S-13</u>
PROJECT NAME:	<u>NYSDEC BCP Site C905043</u> DATE: <u>June 14, 2022</u>
SAMPLE COLLECTOR(S):	<u>CCD/CMC</u> WEATHER: <u>Sunny, ~73° F</u>
PID READING IN WELL HEADSPACE (PPM):	<u>NM</u> MEASURING POINT (for water levels): <u>Top of Casing</u>
CASING TYPE:	<u>PVC</u> WELL DIAMETER (INCHES): <u>2</u>
SCREENED INTERVAL [FT BTOC]:	<u>17.59 - 27.59</u> INITIAL WATER LEVEL (SWL) [FT BTOC]: <u>SWL / Date Measured</u> <u>15.28 / 6-14-22</u>
WELL DEPTH [FT BTOC]:	<u>27.59</u> DEPTH OF PUMP INTAKE [FT BTOC]: <u>21.9</u> (Do NOT Measure Well depth Prior To Purging And Sampling)
LNAPL:	<u>ND</u> DNAPL: <u>NM</u> OTHER OBSERVATIONS: <u>None</u>

SECTION 2 – SAMPLING EQUIPMENT	
PUMP TYPE:	<u>Geotech Geopump™ - Peristaltic pump</u> WATER LEVEL METER: <u>Solonist OWI Meter</u>
WATER QUALITY METER(S):	<u>YSI Pro DDS</u>
STABILIZED PUMP RATE (ml/min):	<u>220</u> STABILIZED DRAWDOWN WATER LEVEL [FT]: <u>15.28</u>

SECTION 3 – WATER QUALITY DATA MONITORING									
Time	Pumping Rate (ml/min)	Water Level (ft)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Conductivity (mS/cm)	pH	Temp. (C°)	Total Vol. Pumped (ml)
11:35					NM				0
11:40	220	15.28	1.39	-99.2	67.23	1.706	6.94	11.1	920
11:42	220	15.28	1.35	-96.5	73.81	1.693	6.91	11.1	1,360
11:44	220	15.28	1.33	-95.7	60.73	1.686	6.90	11.0	1,800
11:46	220	15.28	1.30	-96.2	47.28	1.680	6.89	11.0	2,240
11:48	220	15.28	1.29	-97.3	40.95	1.675	6.88	10.9	2,680
11:50	220	15.28	1.27	-98.7	31.86	1.675	6.88	11.0	3,120
11:52	220	15.28	1.26	-100.6	22.76	1.675	6.88	11.0	3,560
11:54	220	15.28	1.24	-102.9	16.07	1.679	6.89	11.1	4,000
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
--	--	--	--	--	--	--	--	--	--
SAMPLE OBSERVATIONS: Clear									

SECTION 4 - SAMPLE IDENTIFICATION AND ANALYTICAL LABORATORY PARAMETERS			
SAMPLE ID #	DATE / TIME	SAMPLING METHOD	ANALYTICAL SCAN(S)
MW-E/20220614	6-14-22 / 11:56	Peristaltic Pump	TAL Metals

NM = Not Measured
ND = Not Detected

DAY ENVIRONMENTAL, INC.
LOW-FLOW GROUNDWATER PURGING AND SAMPLING LOG
WELL MW-F

SECTION 1 - SITE AND WELL INFORMATION			
SITE LOCATION	202 Franklin Street, Olean, New York	JOB #	4884S-13
PROJECT NAME:	NYSDEC BCP Site C905043	DATE:	June 14, 2022
SAMPLE COLLECTOR(S):	CCD/CMC	WEATHER:	Sunny, ~73° F
PID READING IN WELL HEADSPACE (PPM):	NM	MEASURING POINT (for water levels):	Top of Casing
CASING TYPE:	PVC	WELL DIAMETER (INCHES):	2
SCREENED INTERVAL [FT BTOC]:	17.11 - 27.11	INITIAL WATER LEVEL (SWL) [FT BTOC]:	SWL / Date Measured 17.06 / 6-14-22
WELL DEPTH [FT BTOC]:	27.11 (Do NOT Measure Well depth Prior To Purging And Sampling)	DEPTH OF PUMP INTAKE [FT BTOC]:	22.5
LNAPL:	ND	DNAPL:	NM
OTHER OBSERVATIONS: None			

SECTION 2 – SAMPLING EQUIPMENT	
PUMP TYPE: Geotech Geopump™ - Peristaltic pump	WATER LEVEL METER: Solonist OWI Meter
WATER QUALITY METER(S): YSI Pro DDS	
STABILIZED PUMP RATE (ml/min): 200	STABILIZED DRAWDOWN WATER LEVEL [FT]: 17.09

SECTION 3 – WATER QUALITY DATA MONITORING									
Time	Pumping Rate (ml/min)	Water Level (ft)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Conductivity (mS/cm)	pH	Temp. (C°)	Total Vol. Pumped (ml)
12:40					NM				0
12:44	200	17.09	1.40	-125.6	23.14	1.193	7.06	13.7	300
12:46	200	17.09	1.26	-124.2	110.88	1.190	7.05	14.6	700
12:48	200	17.09	1.22	-125.0	37.33	1.199	7.04	15.0	1,100
12:50	200	17.09	1.21	-129.1	12.35	1.199	7.06	15.5	1,500
12:52	200	17.09	1.19	-133.1	4.91	1.203	7.03	15.9	1,900
12:55	200	17.09	1.17	-137.0	4.40	1.204	7.06	16.0	2,500
12:58	200	17.09	1.13	-144.1	3.23	1.210	7.04	17.2	3,100
13:00	200	17.09	1.12	-147.8	2.70	1.210	7.04	17.5	3,500
13:02	200	17.09	1.15	-153.4	17.50	1.218	7.05	15.0	3,900
13:05	200	17.09	1.15	-152.3	22.41	1.214	7.04	14.3	4,500
13:07	200	17.09	1.14	-151.2	9.61	1.210	7.04	14.4	4,900
13:09	200	17.07	1.14	-149.7	6.33	1.209	7.04	14.3	5,300
SAMPLE OBSERVATIONS: Black particulates noted on sample									

SECTION 4 - SAMPLE IDENTIFICATION AND ANALYTICAL LABORATORY PARAMETERS			
SAMPLE ID #	DATE / TIME	SAMPLING METHOD	ANALYTICAL SCAN(S)
MW-F/20220614	6-14-22 / 13:10	Peristaltic Pump	TAL Metals

NM = Not Measured
 ND = Not Detected

DAY ENVIRONMENTAL, INC.
LOW-FLOW GROUNDWATER PURGING AND SAMPLING LOG
WELL MW-G

SECTION 1 - SITE AND WELL INFORMATION			
SITE LOCATION	202 Franklin Street, Olean, New York	JOB #	4884S-13
PROJECT NAME:	NYSDEC BCP Site C905043	DATE:	June 14, 2022
SAMPLE COLLECTOR(S):	CCD/CMC	WEATHER:	Sunny, ~77° F
PID READING IN WELL HEADSPACE (PPM):	NM	MEASURING POINT (for water levels):	Top of Casing
CASING TYPE:	PVC	WELL DIAMETER (INCHES):	2
SCREENED INTERVAL [FT BTOC]:	17.10 - 27.10	INITIAL WATER LEVEL (SWL) [FT BTOC]:	SWL / Date Measured 17.05 / 6-14-22
WELL DEPTH [FT BTOC]:	27.10 (Do NOT Measure Well depth Prior To Purging And Sampling)	DEPTH OF PUMP INTAKE [FT BTOC]:	22.6
LNAPL:	ND	DNAPL:	NM
		OTHER OBSERVATIONS:	Iron bacteria observed

SECTION 2 – SAMPLING EQUIPMENT	
PUMP TYPE:	Geotech Geopump™ - Peristaltic pump
WATER LEVEL METER:	Solonist OWI Meter
WATER QUALITY METER(S):	YSI Pro DDS
STABILIZED PUMP RATE (ml/min):	170
STABILIZED DRAWDOWN WATER LEVEL [FT]:	17.05

SECTION 3 – WATER QUALITY DATA MONITORING									
Time	Pumping Rate (ml/min)	Water Level (ft)	DO (mg/L)	ORP (mv)	Turbidity (NTU)	Conductivity (mS/cm)	pH	Temp. (C°)	Total Vol. Pumped (ml)
13:45					NM				0
13:52	170	17.05	1.22	-186.8	20.81	1.286	6.86	13.4	200
13:55	170	17.05	1.19	-190.1	30.23	1.283	6.88	13.3	710
13:58	170	17.05	1.17	-192.3	42.31	1.277	6.89	13.2	1,220
14:01	170	17.05	1.15	-195.4	58.10	1.274	6.90	13.2	1,730
14:04	170	17.05	1.14	-197.1	67.34	1.273	6.90	13.3	2,240
14:07	170	17.05	1.14	-198.8	73.27	1.274	6.90	13.3	2,750
14:10	170	17.05	1.13	-200.0	108.38	1.273	6.90	13.3	3,260
14:12	170	17.05	1.13	-200.7	112.36	1.270	6.90	13.3	3,600
14:14	170	17.05	1.12	-201.6	130.13	1.275	6.90	13.5	3,940
14:16	170	17.05	1.12	-202.6	139.71	1.280	6.91	13.4	4,280
--	--	--	--	--	--	--	--	--	--
SAMPLE OBSERVATIONS: Strong petroleum-type odor noted on sample									

SECTION 4 - SAMPLE IDENTIFICATION AND ANALYTICAL LABORATORY PARAMETERS			
SAMPLE ID #	DATE / TIME	SAMPLING METHOD	ANALYTICAL SCAN(S)
MW-G/20220614	6-14-22 / 14:18	Peristaltic Pump	TAL Metals

NM = Not Measured
 ND = Not Detected

ATTACHMENT B

**SITE-WIDE COVER INSPECITON FORM
AND
PHOTOGRAPHS**

Site-Wide Inspection Form

202 Franklin Street

City of Olean, New York

NYSDEC Site Number: C905043

Date of Inspection Site Visit: *June 14, 2022*

Personnel Performing Inspection Site Visit: *R. Kampff*

Affiliation of Personnel: *Day Environmental, Inc.*

1. Check integrity of impermeable portions (e.g., concrete and asphalt) of cover system, include whether any sloughing, cracks, settlement, damage, etc.

Discuss observations and any corrective actions:

Asphalt pavement was patched recently and cracks were filled w/ sealer. Current condition of pavement is generally good

2. Check integrity of permeable portions (e.g., soil) of cover system, include whether any sloughing, cracks, settlement, damage, etc.

Discuss observations and any corrective actions:

Cover and mulch cover throughout the north/west portion of site except in drainage swale area, which is covered w/ stone above filter fabric - overall cover system is intact

3. Check integrity of vegetative cover (e.g., grass), include whether any dead areas, erosion, etc.

Discuss observations and any corrective actions:

Vegetative cover up to 1-2 ft high throughout site w/ trees in south/west area - lawn area covered w/ vegetation. Although thin in areas - cover vegetation is present throughout site (except paved areas, areas of mulch and drainage swale)

4. Groundwater Monitoring Well Assessment

Discuss observations and any corrective actions:

Monitoring wells are functional and protective
Casings are intact

Wells MWA → MWH sampled 6/14/2022



View of the soil/vegetative cover and drainage swale located on the central portion of the Site, facing southeast.



View of soil/vegetative cover along the the southern property boundary and partial view of the asphalt cover on the central portion of the Employee Parking Lot, facing west.



View of the soil and vegetative cover on the northwest portion of the Site, facing south.



Typical view of a monitoring well protective casing, located on the northern portion of the Site, facing south.



View of repaired asphalt cover located on the eastern portion of the Employee Parking Lot, facing northwest. View of groundwater monitoring event at monitoring well MW-E, amid the soil/vegetative cover and mulch cover (below visible tree) at top of photo.



Typical view of the asphalt repairs completed on the western portion of the Employee Parking Lot, facing west.

ATTACHMENT C

ANALYTICAL LABORATORY REPORTS

CHAIN-OF-CUSTODY DOCUMENTATION

AND

DATA USABILITY SUMMARY REPORT (DUSR)



ANALYTICAL REPORT

Lab Number:	L2231820
Client:	Day Environmental, Inc. 1563 Lyell Avenue Rochester, NY 14606
ATTN:	Ray Kampff
Phone:	(585) 454-0210
Project Name:	SOLEPOXY
Project Number:	SOLEPO.4884S-13
Report Date:	07/08/22

The original project report/data package is held by Alpha Analytical. This report/data package is paginated and should be reproduced only in its entirety. Alpha Analytical holds no responsibility for results and/or data that are not consistent with the original.

Certifications & Approvals: MA (M-MA086), NH NELAP (2064), CT (PH-0574), IL (200077), ME (MA00086), MD (348), NJ (MA935), NY (11148), NC (25700/666), PA (68-03671), RI (LAO00065), TX (T104704476), VT (VT-0935), VA (460195), USDA (Permit #P330-17-00196).

Eight Walkup Drive, Westborough, MA 01581-1019
508-898-9220 (Fax) 508-898-9193 800-624-9220 - www.alphalab.com



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Alpha Sample ID	Client ID	Matrix	Sample Location	Collection Date/Time	Receive Date
L2231820-01	MW-C/20220614	WATER	202 FRANKLIN ST. OLEAN NY	06/14/22 09:10	06/15/22
L2231820-02	MW-D/20220614	WATER	202 FRANKLIN ST. OLEAN NY	06/14/22 10:05	06/15/22
L2231820-03	MW-B/20220614	WATER	202 FRANKLIN ST. OLEAN NY	06/14/22 11:04	06/15/22
L2231820-04	MW-E/20220614	WATER	202 FRANKLIN ST. OLEAN NY	06/14/22 11:56	06/15/22
L2231820-05	MW-F/20220614	WATER	202 FRANKLIN ST. OLEAN NY	06/14/22 13:10	06/15/22
L2231820-06	MW-G/20220614	WATER	202 FRANKLIN ST. OLEAN NY	06/14/22 14:18	06/15/22
L2231820-07	MW-A/20220614	WATER	202 FRANKLIN ST. OLEAN NY	06/14/22 15:26	06/15/22
L2231820-08	EB-1/20220614	WATER	202 FRANKLIN ST. OLEAN NY	06/14/22 15:30	06/15/22

Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Case Narrative

The samples were received in accordance with the Chain of Custody and no significant deviations were encountered during the preparation or analysis unless otherwise noted. Sample Receipt, Container Information, and the Chain of Custody are located at the back of the report.

Results contained within this report relate only to the samples submitted under this Alpha Lab Number and meet NELAP requirements for all NELAP accredited parameters unless otherwise noted in the following narrative. The data presented in this report is organized by parameter (i.e. VOC, SVOC, etc.). Sample specific Quality Control data (i.e. Surrogate Spike Recovery) is reported at the end of the target analyte list for each individual sample, followed by the Laboratory Batch Quality Control at the end of each parameter. Tentatively Identified Compounds (TICs), if requested, are reported for compounds identified to be present and are not part of the method/program Target Compound List, even if only a subset of the TCL are being reported. If a sample was re-analyzed or re-extracted due to a required quality control corrective action and if both sets of data are reported, the Laboratory ID of the re-analysis or re-extraction is designated with an "R" or "RE", respectively.

When multiple Batch Quality Control elements are reported (e.g. more than one LCS), the associated samples for each element are noted in the grey shaded header line of each data table. Any Laboratory Batch, Sample Specific % recovery or RPD value that is outside the listed Acceptance Criteria is bolded in the report. In reference to questions H (CAM) or 4 (RCP) when "NO" is checked, the performance criteria for CAM and RCP methods allow for some quality control failures to occur and still be within method compliance. In these instances, the specific failure is not narrated but noted in the associated QC Outlier Summary Report, located directly after the Case Narrative. QC information is also incorporated in the Data Usability Assessment table (Format 11) of our Data Merger tool, where it can be reviewed in conjunction with the sample result, associated regulatory criteria and any associated data usability implications.

Soil/sediments, solids and tissues are reported on a dry weight basis unless otherwise noted. Definitions of all data qualifiers and acronyms used in this report are provided in the Glossary located at the back of the report.

HOLD POLICY - For samples submitted on hold, Alpha's policy is to hold samples (with the exception of Air canisters) free of charge for 21 calendar days from the date the project is completed. After 21 calendar days, we will dispose of all samples submitted including those put on hold unless you have contacted your Alpha Project Manager and made arrangements for Alpha to continue to hold the samples. Air canisters will be disposed after 3 business days from the date the project is completed.

Please contact Project Management at 800-624-9220 with any questions.

Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Case Narrative (continued)

Report Submission

All non-detect (ND) or estimated concentrations (J-qualified) have been quantitated to the limit noted in the MDL column.

I, the undersigned, attest under the pains and penalties of perjury that, to the best of my knowledge and belief and based upon my personal inquiry of those responsible for providing the information contained in this analytical report, such information is accurate and complete. This certificate of analysis is not complete unless this page accompanies any and all pages of this report.

Authorized Signature:



Steven Gniadek

Title: Technical Director/Representative

Date: 07/08/22

METALS

Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

SAMPLE RESULTS

Lab ID: L2231820-01
 Client ID: MW-C/20220614
 Sample Location: 202 FRANKLIN ST. OLEAN NY

Date Collected: 06/14/22 09:10
 Date Received: 06/15/22
 Field Prep: Not Specified

Sample Depth:
 Matrix: Water

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Aluminum, Total	0.0209		mg/l	0.0100	0.00327	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Antimony, Total	ND		mg/l	0.00400	0.00042	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Arsenic, Total	0.00996		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Barium, Total	0.01510		mg/l	0.00050	0.00017	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Beryllium, Total	ND		mg/l	0.00050	0.00010	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Cadmium, Total	0.00007	J	mg/l	0.00020	0.00005	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Calcium, Total	101.		mg/l	0.100	0.0394	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Chromium, Total	0.00037	J	mg/l	0.00100	0.00017	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Cobalt, Total	0.00042	J	mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Copper, Total	0.00174		mg/l	0.00100	0.00038	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Iron, Total	0.870		mg/l	0.0500	0.0191	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Lead, Total	0.00099	J	mg/l	0.00100	0.00034	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Magnesium, Total	10.1		mg/l	0.0700	0.0242	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Manganese, Total	0.4414		mg/l	0.00100	0.00044	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Mercury, Total	ND		mg/l	0.00020	0.00009	1	06/28/22 22:55	07/05/22 23:25	EPA 7470A	1,7470A	AW
Nickel, Total	0.00621		mg/l	0.00200	0.00055	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Potassium, Total	5.46		mg/l	0.100	0.0309	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Selenium, Total	0.00408	J	mg/l	0.00500	0.00173	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Silver, Total	ND		mg/l	0.00040	0.00016	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Sodium, Total	16.0		mg/l	0.100	0.0293	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Thallium, Total	0.00059	J	mg/l	0.00100	0.00014	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Vanadium, Total	ND		mg/l	0.00500	0.00157	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD
Zinc, Total	0.01104		mg/l	0.01000	0.00341	1	06/28/22 19:32	07/07/22 22:07	EPA 3005A	1,6020B	CD



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

SAMPLE RESULTS

Lab ID: L2231820-02
 Client ID: MW-D/20220614
 Sample Location: 202 FRANKLIN ST. OLEAN NY

Date Collected: 06/14/22 10:05
 Date Received: 06/15/22
 Field Prep: Not Specified

Sample Depth:
 Matrix: Water

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Aluminum, Total	0.0466		mg/l	0.0100	0.00327	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Antimony, Total	ND		mg/l	0.00400	0.00042	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Arsenic, Total	0.1248		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Barium, Total	2.525		mg/l	0.00050	0.00017	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Beryllium, Total	ND		mg/l	0.00050	0.00010	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Cadmium, Total	ND		mg/l	0.00020	0.00005	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Calcium, Total	136.		mg/l	0.100	0.0394	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Chromium, Total	0.00050	J	mg/l	0.00100	0.00017	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Cobalt, Total	0.00030	J	mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Copper, Total	0.00119		mg/l	0.00100	0.00038	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Iron, Total	19.8		mg/l	0.0500	0.0191	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Lead, Total	ND		mg/l	0.00100	0.00034	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Magnesium, Total	25.6		mg/l	0.0700	0.0242	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Manganese, Total	1.843		mg/l	0.00100	0.00044	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Mercury, Total	ND		mg/l	0.00020	0.00009	1	06/28/22 22:55	07/05/22 23:35	EPA 7470A	1,7470A	AW
Nickel, Total	0.00066	J	mg/l	0.00200	0.00055	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Potassium, Total	5.01		mg/l	0.100	0.0309	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Selenium, Total	ND		mg/l	0.00500	0.00173	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Silver, Total	ND		mg/l	0.00040	0.00016	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Sodium, Total	183.		mg/l	0.100	0.0293	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Thallium, Total	0.00024	J	mg/l	0.00100	0.00014	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Vanadium, Total	ND		mg/l	0.00500	0.00157	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD
Zinc, Total	ND		mg/l	0.01000	0.00341	1	06/28/22 19:32	07/07/22 22:12	EPA 3005A	1,6020B	CD



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

SAMPLE RESULTS

Lab ID: L2231820-03
 Client ID: MW-B/20220614
 Sample Location: 202 FRANKLIN ST. OLEAN NY

Date Collected: 06/14/22 11:04
 Date Received: 06/15/22
 Field Prep: Not Specified

Sample Depth:
 Matrix: Water

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Aluminum, Total	0.00586	J	mg/l	0.0100	0.00327	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Antimony, Total	ND		mg/l	0.00400	0.00042	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Arsenic, Total	0.00101		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Barium, Total	1.616		mg/l	0.00050	0.00017	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Beryllium, Total	ND		mg/l	0.00050	0.00010	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Cadmium, Total	ND		mg/l	0.00020	0.00005	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Calcium, Total	158.		mg/l	0.100	0.0394	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Chromium, Total	ND		mg/l	0.00100	0.00017	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Cobalt, Total	ND		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Copper, Total	0.00051	J	mg/l	0.00100	0.00038	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Iron, Total	3.57		mg/l	0.0500	0.0191	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Lead, Total	ND		mg/l	0.00100	0.00034	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Magnesium, Total	24.6		mg/l	0.0700	0.0242	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Manganese, Total	1.731		mg/l	0.00100	0.00044	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Mercury, Total	ND		mg/l	0.00020	0.00009	1	06/28/22 22:55	07/05/22 23:38	EPA 7470A	1,7470A	AW
Nickel, Total	ND		mg/l	0.00200	0.00055	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Potassium, Total	4.55		mg/l	0.100	0.0309	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Selenium, Total	ND		mg/l	0.00500	0.00173	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Silver, Total	ND		mg/l	0.00040	0.00016	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Sodium, Total	133.		mg/l	0.100	0.0293	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Thallium, Total	0.00015	J	mg/l	0.00100	0.00014	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Vanadium, Total	ND		mg/l	0.00500	0.00157	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD
Zinc, Total	ND		mg/l	0.01000	0.00341	1	06/28/22 19:32	07/07/22 22:17	EPA 3005A	1,6020B	CD



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

SAMPLE RESULTS

Lab ID: L2231820-04
 Client ID: MW-E/20220614
 Sample Location: 202 FRANKLIN ST. OLEAN NY

Date Collected: 06/14/22 11:56
 Date Received: 06/15/22
 Field Prep: Not Specified

Sample Depth:
 Matrix: Water

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Aluminum, Total	0.0776		mg/l	0.0100	0.00327	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Antimony, Total	ND		mg/l	0.00400	0.00042	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Arsenic, Total	0.00521		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Barium, Total	1.519		mg/l	0.00050	0.00017	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Beryllium, Total	ND		mg/l	0.00050	0.00010	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Cadmium, Total	ND		mg/l	0.00020	0.00005	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Calcium, Total	150.		mg/l	0.100	0.0394	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Chromium, Total	0.00029	J	mg/l	0.00100	0.00017	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Cobalt, Total	0.00047	J	mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Copper, Total	0.00232		mg/l	0.00100	0.00038	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Iron, Total	2.00		mg/l	0.0500	0.0191	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Lead, Total	0.00276		mg/l	0.00100	0.00034	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Magnesium, Total	26.4		mg/l	0.0700	0.0242	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Manganese, Total	2.576		mg/l	0.00100	0.00044	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Mercury, Total	ND		mg/l	0.00020	0.00009	1	06/28/22 22:55	07/05/22 23:48	EPA 7470A	1,7470A	AW
Nickel, Total	0.00261		mg/l	0.00200	0.00055	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Potassium, Total	3.83		mg/l	0.100	0.0309	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Selenium, Total	ND		mg/l	0.00500	0.00173	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Silver, Total	ND		mg/l	0.00040	0.00016	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Sodium, Total	168.		mg/l	0.100	0.0293	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Thallium, Total	0.00014	J	mg/l	0.00100	0.00014	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Vanadium, Total	ND		mg/l	0.00500	0.00157	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD
Zinc, Total	0.00353	J	mg/l	0.01000	0.00341	1	06/28/22 19:32	07/07/22 22:22	EPA 3005A	1,6020B	CD



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

SAMPLE RESULTS

Lab ID: L2231820-05
 Client ID: MW-F/20220614
 Sample Location: 202 FRANKLIN ST. OLEAN NY

Date Collected: 06/14/22 13:10
 Date Received: 06/15/22
 Field Prep: Not Specified

Sample Depth:
 Matrix: Water

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Aluminum, Total	0.0148		mg/l	0.0100	0.00327	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Antimony, Total	ND		mg/l	0.00400	0.00042	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Arsenic, Total	0.00073		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Barium, Total	0.4057		mg/l	0.00050	0.00017	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Beryllium, Total	ND		mg/l	0.00050	0.00010	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Cadmium, Total	ND		mg/l	0.00020	0.00005	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Calcium, Total	127.		mg/l	0.100	0.0394	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Chromium, Total	0.00021	J	mg/l	0.00100	0.00017	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Cobalt, Total	0.00088		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Copper, Total	0.00098	J	mg/l	0.00100	0.00038	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Iron, Total	0.134		mg/l	0.0500	0.0191	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Lead, Total	ND		mg/l	0.00100	0.00034	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Magnesium, Total	17.0		mg/l	0.0700	0.0242	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Manganese, Total	1.460		mg/l	0.00100	0.00044	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Mercury, Total	ND		mg/l	0.00020	0.00009	1	06/28/22 22:55	07/05/22 23:52	EPA 7470A	1,7470A	AW
Nickel, Total	0.00127	J	mg/l	0.00200	0.00055	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Potassium, Total	4.31		mg/l	0.100	0.0309	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Selenium, Total	ND		mg/l	0.00500	0.00173	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Silver, Total	ND		mg/l	0.00040	0.00016	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Sodium, Total	106.		mg/l	0.100	0.0293	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Thallium, Total	ND		mg/l	0.00100	0.00014	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Vanadium, Total	ND		mg/l	0.00500	0.00157	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD
Zinc, Total	ND		mg/l	0.01000	0.00341	1	06/28/22 19:32	07/07/22 22:28	EPA 3005A	1,6020B	CD



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

SAMPLE RESULTS

Lab ID: L2231820-06
 Client ID: MW-G/20220614
 Sample Location: 202 FRANKLIN ST. OLEAN NY

Date Collected: 06/14/22 14:18
 Date Received: 06/15/22
 Field Prep: Not Specified

Sample Depth:
 Matrix: Water

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Aluminum, Total	0.00350	J	mg/l	0.0100	0.00327	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Antimony, Total	ND		mg/l	0.00400	0.00042	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Arsenic, Total	0.00372		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Barium, Total	1.227		mg/l	0.00050	0.00017	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Beryllium, Total	ND		mg/l	0.00050	0.00010	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Cadmium, Total	ND		mg/l	0.00020	0.00005	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Calcium, Total	189.		mg/l	0.100	0.0394	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Chromium, Total	0.00020	J	mg/l	0.00100	0.00017	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Cobalt, Total	ND		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Copper, Total	ND		mg/l	0.00100	0.00038	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Iron, Total	5.81		mg/l	0.0500	0.0191	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Lead, Total	ND		mg/l	0.00100	0.00034	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Magnesium, Total	18.0		mg/l	0.0700	0.0242	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Manganese, Total	1.675		mg/l	0.00100	0.00044	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Mercury, Total	ND		mg/l	0.00020	0.00009	1	06/28/22 22:55	07/05/22 23:55	EPA 7470A	1,7470A	AW
Nickel, Total	ND		mg/l	0.00200	0.00055	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Potassium, Total	5.52		mg/l	0.100	0.0309	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Selenium, Total	ND		mg/l	0.00500	0.00173	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Silver, Total	ND		mg/l	0.00040	0.00016	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Sodium, Total	75.8		mg/l	0.100	0.0293	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Thallium, Total	ND		mg/l	0.00100	0.00014	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Vanadium, Total	ND		mg/l	0.00500	0.00157	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD
Zinc, Total	ND		mg/l	0.01000	0.00341	1	06/28/22 19:32	07/07/22 22:33	EPA 3005A	1,6020B	CD



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

SAMPLE RESULTS

Lab ID: L2231820-07
 Client ID: MW-A/20220614
 Sample Location: 202 FRANKLIN ST. OLEAN NY

Date Collected: 06/14/22 15:26
 Date Received: 06/15/22
 Field Prep: Not Specified

Sample Depth:
 Matrix: Water

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Aluminum, Total	0.0109		mg/l	0.0100	0.00327	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Antimony, Total	ND		mg/l	0.00400	0.00042	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Arsenic, Total	0.00149		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Barium, Total	0.1894		mg/l	0.00050	0.00017	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Beryllium, Total	ND		mg/l	0.00050	0.00010	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Cadmium, Total	ND		mg/l	0.00020	0.00005	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Calcium, Total	92.9		mg/l	0.100	0.0394	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Chromium, Total	0.00022	J	mg/l	0.00100	0.00017	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Cobalt, Total	0.00064		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Copper, Total	0.00074	J	mg/l	0.00100	0.00038	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Iron, Total	19.6		mg/l	0.0500	0.0191	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Lead, Total	ND		mg/l	0.00100	0.00034	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Magnesium, Total	4.79		mg/l	0.0700	0.0242	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Manganese, Total	1.328		mg/l	0.00100	0.00044	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Mercury, Total	ND		mg/l	0.00020	0.00009	1	06/28/22 22:55	07/05/22 23:58	EPA 7470A	1,7470A	AW
Nickel, Total	0.00056	J	mg/l	0.00200	0.00055	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Potassium, Total	5.22		mg/l	0.100	0.0309	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Selenium, Total	ND		mg/l	0.00500	0.00173	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Silver, Total	ND		mg/l	0.00040	0.00016	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Sodium, Total	38.3		mg/l	0.100	0.0293	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Thallium, Total	ND		mg/l	0.00100	0.00014	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Vanadium, Total	ND		mg/l	0.00500	0.00157	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD
Zinc, Total	0.00688	J	mg/l	0.01000	0.00341	1	06/28/22 19:32	07/07/22 22:38	EPA 3005A	1,6020B	CD



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

SAMPLE RESULTS

Lab ID: L2231820-08
 Client ID: EB-1/20220614
 Sample Location: 202 FRANKLIN ST. OLEAN NY

Date Collected: 06/14/22 15:30
 Date Received: 06/15/22
 Field Prep: Not Specified

Sample Depth:
 Matrix: Water

Parameter	Result	Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Prep Method	Analytical Method	Analyst
Total Metals - Mansfield Lab											
Aluminum, Total	0.00334	J	mg/l	0.0100	0.00327	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Antimony, Total	ND		mg/l	0.00400	0.00042	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Arsenic, Total	ND		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Barium, Total	0.00218		mg/l	0.00050	0.00017	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Beryllium, Total	ND		mg/l	0.00050	0.00010	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Cadmium, Total	ND		mg/l	0.00020	0.00005	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Calcium, Total	0.347		mg/l	0.100	0.0394	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Chromium, Total	0.00022	J	mg/l	0.00100	0.00017	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Cobalt, Total	ND		mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Copper, Total	ND		mg/l	0.00100	0.00038	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Iron, Total	0.0459	J	mg/l	0.0500	0.0191	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Lead, Total	ND		mg/l	0.00100	0.00034	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Magnesium, Total	0.0246	J	mg/l	0.0700	0.0242	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Manganese, Total	0.00170		mg/l	0.00100	0.00044	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Mercury, Total	ND		mg/l	0.00020	0.00009	1	06/28/22 22:55	07/06/22 00:02	EPA 7470A	1,7470A	AW
Nickel, Total	ND		mg/l	0.00200	0.00055	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Potassium, Total	ND		mg/l	0.100	0.0309	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Selenium, Total	ND		mg/l	0.00500	0.00173	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Silver, Total	ND		mg/l	0.00040	0.00016	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Sodium, Total	0.0805	J	mg/l	0.100	0.0293	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Thallium, Total	ND		mg/l	0.00100	0.00014	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Vanadium, Total	ND		mg/l	0.00500	0.00157	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD
Zinc, Total	ND		mg/l	0.01000	0.00341	1	06/28/22 19:32	07/07/22 22:44	EPA 3005A	1,6020B	CD



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Method Blank Analysis Batch Quality Control

Parameter	Result Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst	
Total Metals - Mansfield Lab for sample(s): 01-08 Batch: WG1656424-1										
Aluminum, Total	ND	mg/l	0.0100	0.00327	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Antimony, Total	ND	mg/l	0.00400	0.00042	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Arsenic, Total	ND	mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Barium, Total	ND	mg/l	0.00050	0.00017	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Beryllium, Total	ND	mg/l	0.00050	0.00010	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Cadmium, Total	ND	mg/l	0.00020	0.00005	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Calcium, Total	ND	mg/l	0.100	0.0394	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Chromium, Total	ND	mg/l	0.00100	0.00017	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Cobalt, Total	ND	mg/l	0.00050	0.00016	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Copper, Total	ND	mg/l	0.00100	0.00038	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Iron, Total	ND	mg/l	0.0500	0.0191	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Lead, Total	ND	mg/l	0.00100	0.00034	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Magnesium, Total	ND	mg/l	0.0700	0.0242	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Manganese, Total	ND	mg/l	0.00100	0.00044	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Nickel, Total	ND	mg/l	0.00200	0.00055	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Potassium, Total	ND	mg/l	0.100	0.0309	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Selenium, Total	ND	mg/l	0.00500	0.00173	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Silver, Total	ND	mg/l	0.00040	0.00016	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Sodium, Total	ND	mg/l	0.100	0.0293	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Thallium, Total	0.00032	J	mg/l	0.00100	0.00014	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD
Vanadium, Total	ND	mg/l	0.00500	0.00157	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	
Zinc, Total	ND	mg/l	0.01000	0.00341	1	06/28/22 19:32	07/07/22 20:57	1,6020B	CD	

Prep Information

Digestion Method: EPA 3005A

Parameter	Result Qualifier	Units	RL	MDL	Dilution Factor	Date Prepared	Date Analyzed	Analytical Method	Analyst
Total Metals - Mansfield Lab for sample(s): 01-08 Batch: WG1656426-1									
Mercury, Total	ND	mg/l	0.00020	0.00009	1	06/28/22 22:55	07/05/22 23:19	1,7470A	AW



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Method Blank Analysis Batch Quality Control

Prep Information

Digestion Method: EPA 7470A

Lab Control Sample Analysis

Batch Quality Control

Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Parameter	LCS		LCSD		%Recovery Limits	RPD	Qual	RPD Limits
	%Recovery	Qual	%Recovery	Qual				
Total Metals - Mansfield Lab Associated sample(s): 01-08 Batch: WG1656424-2								
Aluminum, Total	105		-		80-120	-		
Antimony, Total	100		-		80-120	-		
Arsenic, Total	104		-		80-120	-		
Barium, Total	105		-		80-120	-		
Beryllium, Total	104		-		80-120	-		
Cadmium, Total	105		-		80-120	-		
Calcium, Total	87		-		80-120	-		
Chromium, Total	98		-		80-120	-		
Cobalt, Total	95		-		80-120	-		
Copper, Total	95		-		80-120	-		
Iron, Total	99		-		80-120	-		
Lead, Total	101		-		80-120	-		
Magnesium, Total	107		-		80-120	-		
Manganese, Total	103		-		80-120	-		
Nickel, Total	94		-		80-120	-		
Potassium, Total	105		-		80-120	-		
Selenium, Total	102		-		80-120	-		
Silver, Total	107		-		80-120	-		
Sodium, Total	104		-		80-120	-		
Thallium, Total	110		-		80-120	-		
Vanadium, Total	100		-		80-120	-		

Lab Control Sample Analysis

Batch Quality Control

Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Parameter	LCS %Recovery	LCSD %Recovery	%Recovery Limits	RPD	RPD Limits
Total Metals - Mansfield Lab Associated sample(s): 01-08 Batch: WG1656424-2					
Zinc, Total	97	-	80-120	-	
Total Metals - Mansfield Lab Associated sample(s): 01-08 Batch: WG1656426-2					
Mercury, Total	100	-	80-120	-	

Matrix Spike Analysis Batch Quality Control

Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Parameter	Native Sample	MS Added	MS Found	MS %Recovery	MSD Qual	MSD Found	MSD %Recovery	MSD Qual	Recovery Limits	RPD	RPD Qual	RPD Limits
Total Metals - Mansfield Lab Associated sample(s): 01-08 QC Batch ID: WG1656424-3 WG1656424-4 QC Sample: L2231820-01 Client ID: MW-C/20220614												
Aluminum, Total	0.0209	2	2.03	100		2.02	100		75-125	0		20
Antimony, Total	ND	0.5	0.5069	101		0.4871	97		75-125	4		20
Arsenic, Total	0.00996	0.12	0.1310	101		0.1328	102		75-125	1		20
Barium, Total	0.01510	2	2.046	102		2.018	100		75-125	1		20
Beryllium, Total	ND	0.05	0.05021	100		0.04902	98		75-125	2		20
Cadmium, Total	0.00007J	0.053	0.05681	107		0.05430	102		75-125	5		20
Calcium, Total	101.	10	99.4	0	Q	100	0	Q	75-125	1		20
Chromium, Total	0.00037J	0.2	0.1917	96		0.1903	95		75-125	1		20
Cobalt, Total	0.00042J	0.5	0.4608	92		0.4566	91		75-125	1		20
Copper, Total	0.00174	0.25	0.2336	93		0.2342	93		75-125	0		20
Iron, Total	0.870	1	1.79	92		1.79	92		75-125	0		20
Lead, Total	0.00099J	0.53	0.5267	99		0.5257	99		75-125	0		20
Magnesium, Total	10.1	10	19.9	98		19.7	96		75-125	1		20
Manganese, Total	0.4414	0.5	0.8984	91		0.9107	94		75-125	1		20
Nickel, Total	0.00621	0.5	0.4780	94		0.4646	92		75-125	3		20
Potassium, Total	5.46	10	14.9	94		15.1	96		75-125	1		20
Selenium, Total	0.00408J	0.12	0.127	106		0.125	104		75-125	2		20
Silver, Total	ND	0.05	0.05159	103		0.05188	104		75-125	1		20
Sodium, Total	16.0	10	25.2	92		25.0	90		75-125	1		20
Thallium, Total	0.00059J	0.12	0.1286	107		0.1266	106		75-125	2		20
Vanadium, Total	ND	0.5	0.4907	98		0.4940	99		75-125	1		20

Matrix Spike Analysis Batch Quality Control

Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Parameter	Native Sample	MS Added	MS Found	MS %Recovery	MSD Found	MSD %Recovery	Recovery Limits	RPD	RPD Limits
Total Metals - Mansfield Lab Associated sample(s): 01-08 QC Batch ID: WG1656424-3 WG1656424-4 QC Sample: L2231820-01 Client ID: MW-C/20220614									
Zinc, Total	0.01104	0.5	0.4897	96	0.4780	93	75-125	2	20
Total Metals - Mansfield Lab Associated sample(s): 01-08 QC Batch ID: WG1656426-3 WG1656426-4 QC Sample: L2231820-01 Client ID: MW-C/20220614									
Mercury, Total	ND	0.005	0.00488	98	0.00490	98	75-125	0	20

Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

**Lab Serial Dilution
Analysis
Batch Quality Control**

Lab Number: L2231820
Report Date: 07/08/22

Parameter	Native Sample	Serial Dilution	Units	% D	Qual	RPD Limits
Total Metals - Mansfield Lab Associated sample(s): 01-08 QC Batch ID: WG1656424-6 QC Sample: L2231820-01 Client ID: MW-C/20220614						
Barium, Total	0.01510	0.01495	mg/l	1		20
Calcium, Total	101.	96.8	mg/l	4		20
Magnesium, Total	10.1	9.77	mg/l	3		20
Manganese, Total	0.4414	0.4384	mg/l	1		20
Potassium, Total	5.46	5.19	mg/l	5		20
Sodium, Total	16.0	15.6	mg/l	3		20

Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Serial_No:07082215:43
Lab Number: L2231820
Report Date: 07/08/22

Sample Receipt and Container Information

Were project specific reporting limits specified? YES

Cooler Information

Cooler **Custody Seal**
A Absent

Container Information

Container ID	Container Type	Cooler	Initial pH	Final pH	Temp deg C	Pres	Seal	Frozen Date/Time	Analysis(*)
L2231820-01A	Plastic 250ml HNO3 preserved	A	<2	<2	3.7	Y	Absent		FE-6020T(180),BA-6020T(180),SE-6020T(180),TL-6020T(180),CA-6020T(180),CR-6020T(180),K-6020T(180),NI-6020T(180),CU-6020T(180),NA-6020T(180),ZN-6020T(180),PB-6020T(180),MN-6020T(180),BE-6020T(180),SB-6020T(180),AS-6020T(180),V-6020T(180),AL-6020T(180),HG-T(28),MG-6020T(180),AG-6020T(180),CD-6020T(180),CO-6020T(180)
L2231820-01A1	Plastic 250ml HNO3 preserved	A	<2	<2	3.7	Y	Absent		FE-6020T(180),BA-6020T(180),SE-6020T(180),TL-6020T(180),CA-6020T(180),CR-6020T(180),K-6020T(180),NI-6020T(180),CU-6020T(180),NA-6020T(180),ZN-6020T(180),PB-6020T(180),MN-6020T(180),BE-6020T(180),SB-6020T(180),AS-6020T(180),V-6020T(180),AL-6020T(180),HG-T(28),MG-6020T(180),AG-6020T(180),CD-6020T(180),CO-6020T(180)
L2231820-01A2	Plastic 250ml HNO3 preserved	A	<2	<2	3.7	Y	Absent		FE-6020T(180),BA-6020T(180),SE-6020T(180),TL-6020T(180),CA-6020T(180),CR-6020T(180),K-6020T(180),NI-6020T(180),CU-6020T(180),NA-6020T(180),ZN-6020T(180),PB-6020T(180),MN-6020T(180),BE-6020T(180),SB-6020T(180),AS-6020T(180),V-6020T(180),AL-6020T(180),HG-T(28),MG-6020T(180),AG-6020T(180),CD-6020T(180),CO-6020T(180)
L2231820-02A	Plastic 250ml HNO3 preserved	A	<2	<2	3.7	Y	Absent		FE-6020T(180),TL-6020T(180),BA-6020T(180),SE-6020T(180),CA-6020T(180),CR-6020T(180),NI-6020T(180),K-6020T(180),ZN-6020T(180),CU-6020T(180),NA-6020T(180),PB-6020T(180),MN-6020T(180),BE-6020T(180),AS-6020T(180),SB-6020T(180),V-6020T(180),CD-6020T(180),AG-6020T(180),MG-6020T(180),AL-6020T(180),HG-T(28),CO-6020T(180)

*Values in parentheses indicate holding time in days



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Serial_No:07082215:43
Lab Number: L2231820
Report Date: 07/08/22

Container Information

Container ID	Container Type	Cooler	Initial pH	Final pH	Temp deg C	Pres	Seal	Frozen Date/Time	Analysis(*)
L2231820-03A	Plastic 250ml HNO3 preserved	A	<2	<2	3.7	Y	Absent		TL-6020T(180),SE-6020T(180),BA-6020T(180),FE-6020T(180),CR-6020T(180),K-6020T(180),NI-6020T(180),CA-6020T(180),ZN-6020T(180),CU-6020T(180),NA-6020T(180),PB-6020T(180),BE-6020T(180),MN-6020T(180),V-6020T(180),AS-6020T(180),SB-6020T(180),CD-6020T(180),AL-6020T(180),HG-T(28),MG-6020T(180),AG-6020T(180),CO-6020T(180)
L2231820-04A	Plastic 250ml HNO3 preserved	A	<2	<2	3.7	Y	Absent		FE-6020T(180),BA-6020T(180),SE-6020T(180),TL-6020T(180),CR-6020T(180),NI-6020T(180),CA-6020T(180),K-6020T(180),NA-6020T(180),CU-6020T(180),ZN-6020T(180),PB-6020T(180),MN-6020T(180),BE-6020T(180),SB-6020T(180),V-6020T(180),AS-6020T(180),AL-6020T(180),MG-6020T(180),AG-6020T(180),CD-6020T(180),HG-T(28),CO-6020T(180)
L2231820-05A	Plastic 250ml HNO3 preserved	A	<2	<2	3.7	Y	Absent		FE-6020T(180),BA-6020T(180),SE-6020T(180),TL-6020T(180),NI-6020T(180),K-6020T(180),CA-6020T(180),CR-6020T(180),NA-6020T(180),ZN-6020T(180),CU-6020T(180),PB-6020T(180),BE-6020T(180),MN-6020T(180),AS-6020T(180),SB-6020T(180),V-6020T(180),AL-6020T(180),CD-6020T(180),MG-6020T(180),HG-T(28),AG-6020T(180),CO-6020T(180)
L2231820-06A	Plastic 250ml HNO3 preserved	A	<2	<2	3.7	Y	Absent		FE-6020T(180),TL-6020T(180),SE-6020T(180),BA-6020T(180),CR-6020T(180),CA-6020T(180),K-6020T(180),NI-6020T(180),NA-6020T(180),ZN-6020T(180),CU-6020T(180),PB-6020T(180),BE-6020T(180),MN-6020T(180),SB-6020T(180),V-6020T(180),AS-6020T(180),HG-T(28),AL-6020T(180),CD-6020T(180),AG-6020T(180),MG-6020T(180),CO-6020T(180)
L2231820-07A	Plastic 250ml HNO3 preserved	A	<2	<2	3.7	Y	Absent		BA-6020T(180),FE-6020T(180),TL-6020T(180),SE-6020T(180),K-6020T(180),CR-6020T(180),NI-6020T(180),CA-6020T(180),CU-6020T(180),NA-6020T(180),ZN-6020T(180),PB-6020T(180),BE-6020T(180),MN-6020T(180),V-6020T(180),AS-6020T(180),SB-6020T(180),AG-6020T(180),HG-T(28),MG-6020T(180),AL-6020T(180),CD-6020T(180),CO-6020T(180)

*Values in parentheses indicate holding time in days



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Serial_No:07082215:43
Lab Number: L2231820
Report Date: 07/08/22

Container Information

Container ID	Container Type	Cooler	Initial pH	Final pH	Temp deg C	Pres	Seal	Frozen Date/Time	Analysis(*)
L2231820-08A	Plastic 250ml HNO3 preserved	A	<2	<2	3.7	Y	Absent		SE-6020T(180),BA-6020T(180),TL-6020T(180),FE-6020T(180),CR-6020T(180),NI-6020T(180),CA-6020T(180),K-6020T(180),CU-6020T(180),ZN-6020T(180),NA-6020T(180),PB-6020T(180),MN-6020T(180),BE-6020T(180),V-6020T(180),AS-6020T(180),SB-6020T(180),MG-6020T(180),AL-6020T(180),AG-6020T(180),CD-6020T(180),HG-T(28),CO-6020T(180)

*Values in parentheses indicate holding time in days



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

GLOSSARY

Acronyms

DL	- Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the limit of quantitation (LOQ). The DL includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
EDL	- Estimated Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The EDL includes any adjustments from dilutions, concentrations or moisture content, where applicable. The use of EDLs is specific to the analysis of PAHs using Solid-Phase Microextraction (SPME).
EMPC	- Estimated Maximum Possible Concentration: The concentration that results from the signal present at the retention time of an analyte when the ions meet all of the identification criteria except the ion abundance ratio criteria. An EMPC is a worst-case estimate of the concentration.
EPA	- Environmental Protection Agency.
LCS	- Laboratory Control Sample: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LCSD	- Laboratory Control Sample Duplicate: Refer to LCS.
LFB	- Laboratory Fortified Blank: A sample matrix, free from the analytes of interest, spiked with verified known amounts of analytes or a material containing known and verified amounts of analytes.
LOD	- Limit of Detection: This value represents the level to which a target analyte can reliably be detected for a specific analyte in a specific matrix by a specific method. The LOD includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
LOQ	- Limit of Quantitation: The value at which an instrument can accurately measure an analyte at a specific concentration. The LOQ includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.) Limit of Quantitation: The value at which an instrument can accurately measure an analyte at a specific concentration. The LOQ includes any adjustments from dilutions, concentrations or moisture content, where applicable. (DoD report formats only.)
MDL	- Method Detection Limit: This value represents the level to which target analyte concentrations are reported as estimated values, when those target analyte concentrations are quantified below the reporting limit (RL). The MDL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
MS	- Matrix Spike Sample: A sample prepared by adding a known mass of target analyte to a specified amount of matrix sample for which an independent estimate of target analyte concentration is available. For Method 332.0, the spike recovery is calculated using the native concentration, including estimated values.
MSD	- Matrix Spike Sample Duplicate: Refer to MS.
NA	- Not Applicable.
NC	- Not Calculated: Term is utilized when one or more of the results utilized in the calculation are non-detect at the parameter's reporting unit.
NDPA/DPA	- N-Nitrosodiphenylamine/Diphenylamine.
NI	- Not Ignitable.
NP	- Non-Plastic: Term is utilized for the analysis of Atterberg Limits in soil.
NR	- No Results: Term is utilized when 'No Target Compounds Requested' is reported for the analysis of Volatile or Semivolatile Organic TIC only requests.
RL	- Reporting Limit: The value at which an instrument can accurately measure an analyte at a specific concentration. The RL includes any adjustments from dilutions, concentrations or moisture content, where applicable.
RPD	- Relative Percent Difference: The results from matrix and/or matrix spike duplicates are primarily designed to assess the precision of analytical results in a given matrix and are expressed as relative percent difference (RPD). Values which are less than five times the reporting limit for any individual parameter are evaluated by utilizing the absolute difference between the values; although the RPD value will be provided in the report.
SRM	- Standard Reference Material: A reference sample of a known or certified value that is of the same or similar matrix as the associated field samples.
STLP	- Semi-dynamic Tank Leaching Procedure per EPA Method 1315.
TEF	- Toxic Equivalency Factors: The values assigned to each dioxin and furan to evaluate their toxicity relative to 2,3,7,8-TCDD.
TEQ	- Toxic Equivalent: The measure of a sample's toxicity derived by multiplying each dioxin and furan by its corresponding TEF and then summing the resulting values.
TIC	- Tentatively Identified Compound: A compound that has been identified to be present and is not part of the target compound list (TCL) for the method and/or program. All TICs are qualitatively identified and reported as estimated concentrations.

Report Format: DU Report with 'J' Qualifiers



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Footnotes

- 1 - The reference for this analyte should be considered modified since this analyte is absent from the target analyte list of the original method.

Terms

Analytical Method: Both the document from which the method originates and the analytical reference method. (Example: EPA 8260B is shown as 1,8260B.) The codes for the reference method documents are provided in the References section of the Addendum.

Chlordane: The target compound Chlordane (CAS No. 57-74-9) is reported for GC ECD analyses. Per EPA, this compound "refers to a mixture of chlordane isomers, other chlorinated hydrocarbons and numerous other components." (Reference: USEPA Toxicological Review of Chlordane, In Support of Summary Information on the Integrated Risk Information System (IRIS), December 1997.)

Difference: With respect to Total Oxidizable Precursor (TOP) Assay analysis, the difference is defined as the Post-Treatment value minus the Pre-Treatment value.

Final pH: As it pertains to Sample Receipt & Container Information section of the report, Final pH reflects pH of container determined after adjustment at the laboratory, if applicable. If no adjustment required, value reflects Initial pH.

Frozen Date/Time: With respect to Volatile Organics in soil, Frozen Date/Time reflects the date/time at which associated Reagent Water-preserved vials were initially frozen. Note: If frozen date/time is beyond 48 hours from sample collection, value will be reflected in 'bold'.

Gasoline Range Organics (GRO): Gasoline Range Organics (GRO) results include all chromatographic peaks eluting from Methyl tert butyl ether through Naphthalene, with the exception of GRO analysis in support of State of Ohio programs, which includes all chromatographic peaks eluting from Hexane through Dodecane.

Initial pH: As it pertains to Sample Receipt & Container Information section of the report, Initial pH reflects pH of container determined upon receipt, if applicable.

PAH Total: With respect to Alkylated PAH analyses, the 'PAHs, Total' result is defined as the summation of results for all or a subset of the following compounds: Naphthalene, C1-C4 Naphthalenes, 2-Methylnaphthalene, 1-Methylnaphthalene, Biphenyl, Acenaphthylene, Acenaphthene, Fluorene, C1-C3 Fluorenes, Phenanthrene, C1-C4 Phenanthrenes/Anthracenes, Anthracene, Fluoranthene, Pyrene, C1-C4 Fluoranthenes/Pyrenes, Benz(a)anthracene, Chrysene, C1-C4 Chrysenes, Benzo(b)fluoranthene, Benzo(j)+(k)fluoranthene, Benzo(e)pyrene, Benzo(a)pyrene, Perylene, Indeno(1,2,3-cd)pyrene, Dibenz(ah)+(ac)anthracene, Benzo(g,h,i)perylene. If a 'Total' result is requested, the results of its individual components will also be reported.

PFAS Total: With respect to PFAS analyses, the 'PFAS, Total (5)' result is defined as the summation of results for: PFHpA, PFHxS, PFOA, PFNA and PFOS. In addition, the 'PFAS, Total (6)' result is defined as the summation of results for: PFHpA, PFHxS, PFOA, PFNA, PFDA and PFOS. For MassDEP DW compliance analysis only, the 'PFAS, Total (6)' result is defined as the summation of results at or above the RL. Note: If a 'Total' result is requested, the results of its individual components will also be reported.

Total: With respect to Organic analyses, a 'Total' result is defined as the summation of results for individual isomers or Aroclors. If a 'Total' result is requested, the results of its individual components will also be reported. This is applicable to 'Total' results for methods 8260, 8081 and 8082.

Data Qualifiers

- A** - Spectra identified as "Aldol Condensates" are byproducts of the extraction/concentration procedures when acetone is introduced in the process.
- B** - The analyte was detected above the reporting limit in the associated method blank. Flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For MCP-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank. For DOD-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte at less than ten times (10x) the concentration found in the blank AND the analyte was detected above one-half the reporting limit (or above the reporting limit for common lab contaminants) in the associated method blank. For NJ-Air-related projects, flag only applies to associated field samples that have detectable concentrations of the analyte above the reporting limit. For NJ-related projects (excluding Air), flag only applies to associated field samples that have detectable concentrations of the analyte, which was detected above the reporting limit in the associated method blank or above five times the reporting limit for common lab contaminants (Phthalates, Acetone, Methylene Chloride, 2-Butanone).
- C** - Co-elution: The target analyte co-elutes with a known lab standard (i.e. surrogate, internal standards, etc.) for co-extracted analyses.
- D** - Concentration of analyte was quantified from diluted analysis. Flag only applies to field samples that have detectable concentrations of the analyte.
- E** - Concentration of analyte exceeds the range of the calibration curve and/or linear range of the instrument.
- F** - The ratio of quantifier ion response to qualifier ion response falls outside of the laboratory criteria. Results are considered to be an estimated maximum concentration.
- G** - The concentration may be biased high due to matrix interferences (i.e. co-elution) with non-target compound(s). The result should be considered estimated.
- H** - The analysis of pH was performed beyond the regulatory-required holding time of 15 minutes from the time of sample collection.
- I** - The lower value for the two columns has been reported due to obvious interference.
- J** - Estimated value. The Target analyte concentration is below the quantitation limit (RL), but above the Method Detection Limit (MDL) or Estimated Detection Limit (EDL) for SPME-related analyses. This represents an estimated concentration for Tentatively

Report Format: DU Report with 'J' Qualifiers



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Data Qualifiers

Identified Compounds (TICs).

- M** - Reporting Limit (RL) exceeds the MCP CAM Reporting Limit for this analyte.
- ND** - Not detected at the method detection limit (MDL) for the sample, or estimated detection limit (EDL) for SPME-related analyses.
- NJ** - Presumptive evidence of compound. This represents an estimated concentration for Tentatively Identified Compounds (TICs), where the identification is based on a mass spectral library search.
- P** - The RPD between the results for the two columns exceeds the method-specified criteria.
- Q** - The quality control sample exceeds the associated acceptance criteria. For DOD-related projects, LCS and/or Continuing Calibration Standard exceedences are also qualified on all associated sample results. Note: This flag is not applicable for matrix spike recoveries when the sample concentration is greater than 4x the spike added or for batch duplicate RPD when the sample concentrations are less than 5x the RL. (Metals only.)
- R** - Analytical results are from sample re-analysis.
- RE** - Analytical results are from sample re-extraction.
- S** - Analytical results are from modified screening analysis.
- V** - The surrogate associated with this target analyte has a recovery outside the QC acceptance limits. (Applicable to MassDEP DW Compliance samples only.)
- Z** - The batch matrix spike and/or duplicate associated with this target analyte has a recovery/RPD outside the QC acceptance limits. (Applicable to MassDEP DW Compliance samples only.)

Report Format: DU Report with 'J' Qualifiers



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

REFERENCES

- 1 Test Methods for Evaluating Solid Waste: Physical/Chemical Methods. EPA SW-846. Third Edition. Updates I - VI, 2018.

LIMITATION OF LIABILITIES

Alpha Analytical performs services with reasonable care and diligence normal to the analytical testing laboratory industry. In the event of an error, the sole and exclusive responsibility of Alpha Analytical shall be to re-perform the work at it's own expense. In no event shall Alpha Analytical be held liable for any incidental, consequential or special damages, including but not limited to, damages in any way connected with the use of, interpretation of, information or analysis provided by Alpha Analytical.

We strongly urge our clients to comply with EPA protocol regarding sample volume, preservation, cooling, containers, sampling procedures, holding time and splitting of samples in the field.



Certification Information

The following analytes are not included in our Primary NELAP Scope of Accreditation:

Westborough Facility

EPA 624/624.1: m/p-xylene, o-xylene, Naphthalene

EPA 625/625.1: alpha-Terpineol

EPA 8260C/8260D: NPW: 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene, Azobenzene; SCM: Iodomethane (methyl iodide), 1,2,4,5-Tetramethylbenzene; 4-Ethyltoluene.

EPA 8270D/8270E: NPW: Dimethylnaphthalene, 1,4-Diphenylhydrazine, alpha-Terpineol; SCM: Dimethylnaphthalene, 1,4-Diphenylhydrazine.

SM4500: NPW: Amenable Cyanide; SCM: Total Phosphorus, TKN, NO₂, NO₃.

Mansfield Facility

SM 2540D: TSS

EPA 8082A: NPW: PCB: 1, 5, 31, 87,101, 110, 141, 151, 153, 180, 183, 187.

EPA TO-15: Halothane, 2,4,4-Trimethyl-2-pentene, 2,4,4-Trimethyl-1-pentene, Thiophene, 2-Methylthiophene,

3-Methylthiophene, 2-Ethylthiophene, 1,2,3-Trimethylbenzene, Indan, Indene, 1,2,4,5-Tetramethylbenzene, Benzothiophene, 1-Methylnaphthalene.

Biological Tissue Matrix: EPA 3050B

The following analytes are included in our Massachusetts DEP Scope of Accreditation

Westborough Facility:

Drinking Water

EPA 300.0: Chloride, Nitrate-N, Fluoride, Sulfate; **EPA 353.2:** Nitrate-N, Nitrite-N; **SM4500NO3-F:** Nitrate-N, Nitrite-N; **SM4500F-C, SM4500CN-CE,**

EPA 180.1, SM2130B, SM4500CI-D, SM2320B, SM2540C, SM4500H-B, SM4500NO2-B

EPA 332: Perchlorate; **EPA 524.2:** THMs and VOCs; **EPA 504.1:** EDB, DBCP.

Microbiology: **SM9215B; SM9223-P/A, SM9223B-Colilert-QT, SM9222D.**

Non-Potable Water

SM4500H,B, EPA 120.1, SM2510B, SM2540C, SM2320B, SM4500CL-E, SM4500F-BC, SM4500NH3-BH: Ammonia-N and Kjeldahl-N, **EPA 350.1:**

Ammonia-N, **LCHAT 10-107-06-1-B:** Ammonia-N, **EPA 351.1, SM4500NO3-F, EPA 353.2:** Nitrate-N, **SM4500P-E, SM4500P-B, E, SM4500SO4-E,**

SM5220D, EPA 410.4, SM5210B, SM5310C, SM4500CL-D, EPA 1664, EPA 420.1, SM4500-CN-CE, SM2540D, EPA 300: Chloride, Sulfate, Nitrate.

EPA 624.1: Volatile Halocarbons & Aromatics,

EPA 608.3: Chlordane, Toxaphene, Aldrin, alpha-BHC, beta-BHC, gamma-BHC, delta-BHC, Dieldrin, DDD, DDE, DDT, Endosulfan I, Endosulfan II,

Endosulfan sulfate, Endrin, Endrin Aldehyde, Heptachlor, Heptachlor Epoxide, PCBs

EPA 625.1: SVOC (Acid/Base/Neutral Extractables), **EPA 600/4-81-045:** PCB-Oil.

Microbiology: **SM9223B-Colilert-QT; Enterolert-QT, SM9221E, EPA 1600, EPA 1603, SM9222D.**

Mansfield Facility:

Drinking Water

EPA 200.7: Al, Ba, Cd, Cr, Cu, Fe, Mn, Ni, Na, Ag, Ca, Zn. **EPA 200.8:** Al, Sb, As, Ba, Be, Cd, Cr, Cu, Pb, Mn, Ni, Se, Ag, TL, Zn. **EPA 245.1 Hg.**

EPA 522, EPA 537.1.

Non-Potable Water


EPA 200.7: Al, Sb, As, Be, Cd, Ca, Cr, Co, Cu, Fe, Pb, Mg, Mn, Mo, Ni, K, Se, Ag, Na, Sr, TL, Ti, V, Zn.

EPA 200.8: Al, Sb, As, Be, Cd, Cr, Cu, Fe, Pb, Mn, Ni, K, Se, Ag, Na, TL, Zn.

EPA 245.1 Hg.

SM2340B

For a complete listing of analytes and methods, please contact your Alpha Project Manager.

 NEW YORK CHAIN OF CUSTODY Westborough, MA 01581 8 Walkup Dr. TEL: 508-898-9220 FAX: 508-898-9193	Mansfield, MA 02048 320 Forbes Blvd TEL: 508-822-9300 FAX: 508-822-3288	Service Centers Mahwah, NJ 07430: 35 Whitney Rd, Suite 5 Albany, NY 12205: 14 Walker Way Tonawanda, NY 14150: 275 Cooper Ave, Suite 105	Page 1 of 1	Date Rec'd in Lab: 6/16/22	ALPHA Job # L2231820															
		Project Information Project Name: SOLEPOXY Project Location: 202 Franklin St. Ocean NY Project # SOLEPO. 48845-13 (Use Project name as Project #) <input checked="" type="checkbox"/>		Deliverables <input type="checkbox"/> ASP-A <input checked="" type="checkbox"/> ASP-B <input type="checkbox"/> EQUIS (1 File) <input checked="" type="checkbox"/> EQUIS (4 File) <input type="checkbox"/> Other		Billing Information <input checked="" type="checkbox"/> Same as Client Info PO #														
Client Information Client: Day Environmental Address: 1503 W 211 Ave Rochester NY 14600 Phone: 585-454-0210 Fax: _____ Email: rkampff@daymail.net		Project Manager: Ray Kampff ALPHAQuote #: _____ Turn-Around Time Standard <input checked="" type="checkbox"/> Due Date: _____ Rush (only if pre approved) <input type="checkbox"/> # of Days: _____		Regulatory Requirement <input checked="" type="checkbox"/> NY TOGS <input type="checkbox"/> NY Part 375 <input type="checkbox"/> AWQ Standards <input type="checkbox"/> NY CP-51 <input type="checkbox"/> NY Restricted Use <input type="checkbox"/> Other <input type="checkbox"/> NY Unrestricted Use <input type="checkbox"/> NYC Sewer Discharge		Disposal Site Information Please identify below location of applicable disposal facilities. Disposal Facility: <input type="checkbox"/> NJ <input type="checkbox"/> NY <input type="checkbox"/> Other:														
These samples have been previously analyzed by Alpha <input type="checkbox"/>				ANALYSIS																
Other project specific requirements/comments: _____ _____				Sample Filtration <input type="checkbox"/> Done <input type="checkbox"/> Lab to do Preservation <input type="checkbox"/> Lab to do (Please Specify below)																
Please specify Metals or TAL. _____ _____																				
ALPHA Lab ID (Lab Use Only)		Sample ID		Collection		Sample Matrix		Sampler's Initials		TAL Metals		Sample Specific Comments		Total Bottles						
				Date		Time														
31820		01		MW-C/20220614		6-14-22		0910		GW		CMC			X		also do MS/MSD		3	
		02		MW-D/20220614				1005		GW					X				1	
		03		MW-B/20220614				1104		GW					X				1	
		04		MW-E/20220614				1156		GW					X				1	
		05		MW-F/20220614				1310		GW					X				1	
		06		MW-G/20220614				1418		GW					X				1	
		07		MW-A/20220614				1526		GW					X				1	
		08		EB-1/20220614				1530		DI					X				1	
Preservative Code: A = None B = HCl C = HNO ₃ D = H ₂ SO ₄ E = NaOH F = MeOH G = NaHSO ₄ H = Na ₂ S ₂ O ₃ K/E = Zn Ac/NaOH O = Other		Container Code P = Plastic A = Amber Glass V = Vial G = Glass B = Bacteria Cup C = Cube O = Other E = Encore D = BOD Bottle		Westboro: Certification No: MA935 Mansfield: Certification No: MA015		Container Type: P		Preservative: C								Please print clearly, legibly and completely. Samples can not be logged in and turnaround time clock will not start until any ambiguities are resolved. BY EXECUTING THIS COC, THE CLIENT HAS READ AND AGREES TO BE BOUND BY ALPHA'S TERMS & CONDITIONS. (See reverse side.)				
				Relinquished By:		Date/Time		Received By:		Date/Time										
				Cat Demion		6/15/22 8:00		SECURE STORAGE AAL		6-15-22 15:45										
				SECURE STORAGE AAL		6-15-22 15:45		R Cunniff HAM AAL		6-15-22 15:45										
				R Cunniff HAM AAL		6-15-22 15:45		_____		6/16/22 0020										

Data Usability Summary Report

Vali-Data of WNY, LLC
20 Hickory Grove Spur
Fulton, NY 13069

202 Franklin St., Olean, NY
Alpha Analytical SDG#L2231820
July 13, 2022
Sampling date: 6/14/2022

Prepared by:
Jodi Zimmerman
Vali-Data of WNY, LLC
20 Hickory Grove Spur
Fulton, NY 13069

202 Franklin St., Olean, NY
SDG# L2231820

DELIVERABLES

This Data Usability Summary Report (DUSR) was prepared by evaluating the analytical data package for Day Environmental, project located at 202 Franklin St., Olean, NY, Alpha Analytical #L2231820 submitted to Vali-Data of WNY, LLC on July 13, 2022. This DUSR has been prepared in general compliance with USEPA National Functional Guidelines(NFG) and NYSDEC Analytical Services Protocols. The laboratory performed the analyses using USEPA method Inorganics (6020B) and Mercury (7470A).

DUSR ID	Sample ID	Laboratory ID
1	MW-C/20220614	L2231820-01
2	MW-D/20220614	L2231820-02
3	MW-B/20220614	L2231820-03
4	MW-E/20220614	L2231820-04
5	MW-F/20220614	L2231820-05
6	MW-G/20220614	L2231820-06
7	MW-A/20220614	L2231820-07
8	EB-1/20220614	L2231820-08

METALS

The following items/criteria were reviewed for this analytical suite:

- Data Completeness
- Narrative and Data Reporting Forms
- Chain of Custody and Traffic Reports
- Holding Times
- Blanks
- Laboratory Control Sample
- MS/MSD/Duplicate
- Field Duplicate
- Serial Dilution
- Compound Quantitation
- Calibration

The items listed above were technically in compliance with the method and SOP criteria with the exceptions discussed in the text below. The data have been reviewed according to the procedures outlined above.

OVERALL EVALUATION OF DATA AND POTENTIAL USABILITY ISSUES

The data are acceptable for use but are qualified below in Blanks and Compound Quantitation.

DATA COMPLETENESS

All criteria were met.

NARRATIVE AND DATA REPORTING FORMS

All criteria were met.

CHAIN OF CUSTODY AND TRAFFIC REPORTS

All criteria were met.

HOLDING TIMES

All holding times were met.

BLANKS

All criteria were met except several target analytes were detected in the blank above the MDL, below the reporting limit and is qualified as estimated. These target analytes should be qualified as undetected at the reporting limit in associated samples in which they were detected below the reporting limit. These target analytes should be qualified as estimated high in associated samples in which they were detected above the reporting limit.

Blank ID	Target Analyte	Concentration(mg/L)	Qualifier	Associated Sample
WG1656424	TI	.00032	U at RL	1-4
R1584211-20	Al	9.28	JH	1, 2, 4, 5, 7
R1584211-20	Al	9.28	U at RL	3, 6, 8
R1584211-20	Fe	26.8	JH	1-7
R1584211-20	Fe	26.8	U at RL	8
R1584211-20	TI	1.41	U at RL	1-4
R1584211-22	Al	8.83	JH	1, 2, 4, 5, 7
R1584211-22	Al	8.83	U at RL	3, 6, 8
R1584211-22	As	.169	JH	1-7
R1584211-22	Fe	28.5	JH	1-7
R1584211-22	Fe	28.5	U at RL	8
R1584211-22	TI	1.45	U at RL	1-4

LABORATORY CONTROL SAMPLE

All criteria were met.

MS/MSD/DUPLICATE

All criteria were met.

FIELD DUPLICATE

No field duplicate was acquired.

SERIAL DILUTION

All criteria were met.

COMPOUND QUANTITATION

All criteria were met except several target analytes were detected in the blank above the MDL, below the reporting limit and is qualified as estimated. These target analytes should be qualified as undetected at the reporting limit in associated samples in which they were detected below the reporting limit. These target analytes should be qualified as estimated high in associated samples in which they were detected above the reporting limit.

Blank ID	Target Analyte	Concentration(mg/L)	Qualifier	Associated Sample
8	Cr	.00022	U at RL	1, 2, 4-7
8	Mg	.0246	JH	1-7
8	Na	.0805	JH	1-7
8	Ba	.00218	JH	1-7
8	Ca	.347	JH	1-7
8	Mn	.0017	JH	1-7

Some target analytes were detected in DUSR ID#8 but due to being detected in the method blank and thus qualified as undetected, no further action is required.

CALIBRATION

All criteria were met.

Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13

Lab Number: L2231820
Report Date: 07/08/22

Case Narrative

The samples were received in accordance with the Chain of Custody and no significant deviations were encountered during the preparation or analysis unless otherwise noted. Sample Receipt, Container Information, and the Chain of Custody are located at the back of the report.

Results contained within this report relate only to the samples submitted under this Alpha Lab Number and meet NELAP requirements for all NELAP accredited parameters unless otherwise noted in the following narrative. The data presented in this report is organized by parameter (i.e. VOC, SVOC, etc.). Sample specific Quality Control data (i.e. Surrogate Spike Recovery) is reported at the end of the target analyte list for each individual sample, followed by the Laboratory Batch Quality Control at the end of each parameter. Tentatively Identified Compounds (TICs), if requested, are reported for compounds identified to be present and are not part of the method/program Target Compound List, even if only a subset of the TCL are being reported. If a sample was re-analyzed or re-extracted due to a required quality control corrective action and if both sets of data are reported, the Laboratory ID of the re-analysis or re-extraction is designated with an "R" or "RE", respectively. When multiple Batch Quality Control elements are reported (e.g. more than one LCS), the associated samples for each element are noted in the grey shaded header line of each data table. Any Laboratory Batch, Sample Specific % recovery or RPD value that is outside the listed Acceptance Criteria is bolded in the report. All specific QC information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications. Soil/sediments, solids and tissues are reported on a dry weight basis unless otherwise noted. Definitions of all data qualifiers and acronyms used in this report are provided in the Glossary located at the back of the report.

In reference to questions H (CAM) or 4 (RCP) when "NO" is checked, the performance criteria for CAM and RCP methods allow for some quality control failures to occur and still be within method compliance. In these instances the specific failure is not narrated but noted in the associated QC table. The information is also incorporated in the Data Usability format of our Data Merger tool where it can be reviewed along with any associated usability implications.

Please see the associated ADEx data file for a comparison of laboratory reporting limits that were achieved with the regulatory Numerical Standards requested on the Chain of Custody.

HOLD POLICY

For samples submitted on hold, Alpha's policy is to hold samples (with the exception of Air canisters) free of charge for 21 calendar days from the date the project is completed. After 21 calendar days, we will dispose of all samples submitted including those put on hold unless you have contacted your Client Service Representative and made arrangements for Alpha to continue to hold the samples. Air canisters will be disposed after 3 business days from the date the project is completed.

Please contact Client Services at 800-624-9220 with any questions.



Project Name: SOLEPOXY
Project Number: SOLEPO.4884S-13


Lab Number: L2231820
Report Date: 07/08/22

Case Narrative (continued)

Report Submission

All non-detect (ND) or estimated concentrations (J-qualified) have been quantitated to the limit noted in the MDL column.

I, the undersigned, attest under the pains and penalties of perjury that, to the best of my knowledge and belief and based upon my personal inquiry of those responsible for providing the information contained in this analytical report, such information is accurate and complete. This certificate of analysis is not complete unless this page accompanies any and all pages of this report.

Authorized Signature: 

Report Date: 07/08/22

Title: Technical Director/Representative



Form 1 METALS

Client : Day Environmental, Inc.
 Project Name : SOLEPOXY
 Lab ID : L2231820-01
 Client ID : MW-C/20220614
 Sample Location : 202 FRANKLIN ST. OLEAN NY
 Sample Matrix : WATER
 Analytical Method : 1,6020B
 Lab File ID : WG1659999.pdf
 Sample Amount : 50ml
 Digestion Method : EPA 3005A

Lab Number : L2231820
 Project Number : SOLEPO.4884S-13
 Date Collected : 06/14/22 09:10
 Date Received : 06/15/22
 Date Analyzed : 07/07/22 22:07
 Dilution Factor : 1
 Analyst : CD
 Instrument ID : ICPMSQ2
 %Solids : N/A
 Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7429-90-5	Aluminum, Total	0.0209	0.0100	0.00327	
7440-36-0	Antimony, Total	ND	0.00400	0.00042	U
7440-38-2	Arsenic, Total	0.00996	0.00050	0.00016	
7440-39-3	Barium, Total	0.01510	0.00050	0.00017	
7440-41-7	Beryllium, Total	ND	0.00050	0.00010	U
7440-43-9	Cadmium, Total	0.00007	0.00020	0.00005	J
7440-70-2	Calcium, Total	101.	0.100	0.0394	
7440-47-3	Chromium, Total	0.00037	0.00100	0.00017	J
7440-48-4	Cobalt, Total	0.00042	0.00050	0.00016	J
7440-50-8	Copper, Total	0.00174	0.00100	0.00038	
7439-89-6	Iron, Total	0.870	0.0500	0.0191	
7439-92-1	Lead, Total	0.00099	0.00100	0.00034	J
7439-95-4	Magnesium, Total	10.1	0.0700	0.0242	
7439-96-5	Manganese, Total	0.4414	0.00100	0.00044	
7440-02-0	Nickel, Total	0.00621	0.00200	0.00055	
7440-09-7	Potassium, Total	5.46	0.100	0.0309	
7782-49-2	Selenium, Total	0.00408	0.00500	0.00173	J
7440-22-4	Silver, Total	ND	0.00040	0.00016	U
7440-23-5	Sodium, Total	16.0	0.100	0.0293	
7440-28-0	Thallium, Total	0.00059	0.00100	0.00014	J
7440-62-2	Vanadium, Total	ND	0.00500	0.00157	U
7440-66-6	Zinc, Total	0.01104	0.01000	0.00341	



Form 1 METALS

Client : Day Environmental, Inc.
 Project Name : SOLEPOXY
 Lab ID : L2231820-02
 Client ID : MW-D/20220614
 Sample Location : 202 FRANKLIN ST. OLEAN NY
 Sample Matrix : WATER
 Analytical Method : 1,6020B
 Lab File ID : WG1659999.pdf
 Sample Amount : 50ml
 Digestion Method : EPA 3005A

Lab Number : L2231820
 Project Number : SOLEPO.4884S-13
 Date Collected : 06/14/22 10:05
 Date Received : 06/15/22
 Date Analyzed : 07/07/22 22:12
 Dilution Factor : 1
 Analyst : CD
 Instrument ID : ICPMSQ2
 %Solids : N/A
 Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7429-90-5	Aluminum, Total	0.0466	0.0100	0.00327	
7440-36-0	Antimony, Total	ND	0.00400	0.00042	U
7440-38-2	Arsenic, Total	0.1248	0.00050	0.00016	
7440-39-3	Barium, Total	2.525	0.00050	0.00017	
7440-41-7	Beryllium, Total	ND	0.00050	0.00010	U
7440-43-9	Cadmium, Total	ND	0.00020	0.00005	U
7440-70-2	Calcium, Total	136.	0.100	0.0394	
7440-47-3	Chromium, Total	0.00050	0.00100	0.00017	J
7440-48-4	Cobalt, Total	0.00030	0.00050	0.00016	J
7440-50-8	Copper, Total	0.00119	0.00100	0.00038	
7439-89-6	Iron, Total	19.8	0.0500	0.0191	
7439-92-1	Lead, Total	ND	0.00100	0.00034	U
7439-95-4	Magnesium, Total	25.6	0.0700	0.0242	
7439-96-5	Manganese, Total	1.843	0.00100	0.00044	
7440-02-0	Nickel, Total	0.00066	0.00200	0.00055	J
7440-09-7	Potassium, Total	5.01	0.100	0.0309	
7782-49-2	Selenium, Total	ND	0.00500	0.00173	U
7440-22-4	Silver, Total	ND	0.00040	0.00016	U
7440-23-5	Sodium, Total	183.	0.100	0.0293	
7440-28-0	Thallium, Total	0.00024	0.00100	0.00014	J
7440-62-2	Vanadium, Total	ND	0.00500	0.00157	U
7440-66-6	Zinc, Total	ND	0.01000	0.00341	U



Form 1 METALS

Client : Day Environmental, Inc.
 Project Name : SOLEPOXY
 Lab ID : L2231820-03
 Client ID : MW-B/20220614
 Sample Location : 202 FRANKLIN ST. OLEAN NY
 Sample Matrix : WATER
 Analytical Method : 1,6020B
 Lab File ID : WG1659999.pdf
 Sample Amount : 50ml
 Digestion Method : EPA 3005A

Lab Number : L2231820
 Project Number : SOLEPO.4884S-13
 Date Collected : 06/14/22 11:04
 Date Received : 06/15/22
 Date Analyzed : 07/07/22 22:17
 Dilution Factor : 1
 Analyst : CD
 Instrument ID : ICPMSQ2
 %Solids : N/A
 Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7429-90-5	Aluminum, Total	0.00586	0.0100	0.00327	J
7440-36-0	Antimony, Total	ND	0.00400	0.00042	U
7440-38-2	Arsenic, Total	0.00101	0.00050	0.00016	
7440-39-3	Barium, Total	1.616	0.00050	0.00017	
7440-41-7	Beryllium, Total	ND	0.00050	0.00010	U
7440-43-9	Cadmium, Total	ND	0.00020	0.00005	U
7440-70-2	Calcium, Total	158.	0.100	0.0394	
7440-47-3	Chromium, Total	ND	0.00100	0.00017	U
7440-48-4	Cobalt, Total	ND	0.00050	0.00016	U
7440-50-8	Copper, Total	0.00051	0.00100	0.00038	J
7439-89-6	Iron, Total	3.57	0.0500	0.0191	
7439-92-1	Lead, Total	ND	0.00100	0.00034	U
7439-95-4	Magnesium, Total	24.6	0.0700	0.0242	
7439-96-5	Manganese, Total	1.731	0.00100	0.00044	
7440-02-0	Nickel, Total	ND	0.00200	0.00055	U
7440-09-7	Potassium, Total	4.55	0.100	0.0309	
7782-49-2	Selenium, Total	ND	0.00500	0.00173	U
7440-22-4	Silver, Total	ND	0.00040	0.00016	U
7440-23-5	Sodium, Total	133.	0.100	0.0293	
7440-28-0	Thallium, Total	0.00015	0.00100	0.00014	J
7440-62-2	Vanadium, Total	ND	0.00500	0.00157	U
7440-66-6	Zinc, Total	ND	0.01000	0.00341	U



Form 1 METALS

Client : Day Environmental, Inc.
 Project Name : SOLEPOXY
 Lab ID : L2231820-04
 Client ID : MW-E/20220614
 Sample Location : 202 FRANKLIN ST. OLEAN NY
 Sample Matrix : WATER
 Analytical Method : 1,6020B
 Lab File ID : WG1659999.pdf
 Sample Amount : 50ml
 Digestion Method : EPA 3005A

Lab Number : L2231820
 Project Number : SOLEPO.4884S-13
 Date Collected : 06/14/22 11:56
 Date Received : 06/15/22
 Date Analyzed : 07/07/22 22:22
 Dilution Factor : 1
 Analyst : CD
 Instrument ID : ICPMSQ2
 %Solids : N/A
 Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7429-90-5	Aluminum, Total	0.0776	0.0100	0.00327	
7440-36-0	Antimony, Total	ND	0.00400	0.00042	U
7440-38-2	Arsenic, Total	0.00521	0.00050	0.00016	
7440-39-3	Barium, Total	1.519	0.00050	0.00017	
7440-41-7	Beryllium, Total	ND	0.00050	0.00010	U
7440-43-9	Cadmium, Total	ND	0.00020	0.00005	U
7440-70-2	Calcium, Total	150.	0.100	0.0394	
7440-47-3	Chromium, Total	0.00029	0.00100	0.00017	J
7440-48-4	Cobalt, Total	0.00047	0.00050	0.00016	J
7440-50-8	Copper, Total	0.00232	0.00100	0.00038	
7439-89-6	Iron, Total	2.00	0.0500	0.0191	
7439-92-1	Lead, Total	0.00276	0.00100	0.00034	
7439-95-4	Magnesium, Total	26.4	0.0700	0.0242	
7439-96-5	Manganese, Total	2.576	0.00100	0.00044	
7440-02-0	Nickel, Total	0.00261	0.00200	0.00055	
7440-09-7	Potassium, Total	3.83	0.100	0.0309	
7782-49-2	Selenium, Total	ND	0.00500	0.00173	U
7440-22-4	Silver, Total	ND	0.00040	0.00016	U
7440-23-5	Sodium, Total	168.	0.100	0.0293	
7440-28-0	Thallium, Total	0.00014	0.00100	0.00014	J
7440-62-2	Vanadium, Total	ND	0.00500	0.00157	U
7440-66-6	Zinc, Total	0.00353	0.01000	0.00341	J



Form 1 METALS

Client : Day Environmental, Inc.
 Project Name : SOLEPOXY
 Lab ID : L2231820-05
 Client ID : MW-F/20220614
 Sample Location : 202 FRANKLIN ST. OLEAN NY
 Sample Matrix : WATER
 Analytical Method : 1,6020B
 Lab File ID : WG1659999.pdf
 Sample Amount : 50ml
 Digestion Method : EPA 3005A

Lab Number : L2231820
 Project Number : SOLEPO.4884S-13
 Date Collected : 06/14/22 13:10
 Date Received : 06/15/22
 Date Analyzed : 07/07/22 22:28
 Dilution Factor : 1
 Analyst : CD
 Instrument ID : ICPMSQ2
 %Solids : N/A
 Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7429-90-5	Aluminum, Total	0.0148	0.0100	0.00327	
7440-36-0	Antimony, Total	ND	0.00400	0.00042	U
7440-38-2	Arsenic, Total	0.00073	0.00050	0.00016	
7440-39-3	Barium, Total	0.4057	0.00050	0.00017	
7440-41-7	Beryllium, Total	ND	0.00050	0.00010	U
7440-43-9	Cadmium, Total	ND	0.00020	0.00005	U
7440-70-2	Calcium, Total	127.	0.100	0.0394	
7440-47-3	Chromium, Total	0.00021	0.00100	0.00017	J
7440-48-4	Cobalt, Total	0.00088	0.00050	0.00016	
7440-50-8	Copper, Total	0.00098	0.00100	0.00038	J
7439-89-6	Iron, Total	0.134	0.0500	0.0191	
7439-92-1	Lead, Total	ND	0.00100	0.00034	U
7439-95-4	Magnesium, Total	17.0	0.0700	0.0242	
7439-96-5	Manganese, Total	1.460	0.00100	0.00044	
7440-02-0	Nickel, Total	0.00127	0.00200	0.00055	J
7440-09-7	Potassium, Total	4.31	0.100	0.0309	
7782-49-2	Selenium, Total	ND	0.00500	0.00173	U
7440-22-4	Silver, Total	ND	0.00040	0.00016	U
7440-23-5	Sodium, Total	106.	0.100	0.0293	
7440-28-0	Thallium, Total	ND	0.00100	0.00014	U
7440-62-2	Vanadium, Total	ND	0.00500	0.00157	U
7440-66-6	Zinc, Total	ND	0.01000	0.00341	U



Form 1 METALS

Client : Day Environmental, Inc.
 Project Name : SOLEPOXY
 Lab ID : L2231820-06
 Client ID : MW-G/20220614
 Sample Location : 202 FRANKLIN ST. OLEAN NY
 Sample Matrix : WATER
 Analytical Method : 1,6020B
 Lab File ID : WG1659999.pdf
 Sample Amount : 50ml
 Digestion Method : EPA 3005A

Lab Number : L2231820
 Project Number : SOLEPO.4884S-13
 Date Collected : 06/14/22 14:18
 Date Received : 06/15/22
 Date Analyzed : 07/07/22 22:33
 Dilution Factor : 1
 Analyst : CD
 Instrument ID : ICPMSQ2
 %Solids : N/A
 Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7429-90-5	Aluminum, Total	0.00350	0.0100	0.00327	J
7440-36-0	Antimony, Total	ND	0.00400	0.00042	U
7440-38-2	Arsenic, Total	0.00372	0.00050	0.00016	
7440-39-3	Barium, Total	1.227	0.00050	0.00017	
7440-41-7	Beryllium, Total	ND	0.00050	0.00010	U
7440-43-9	Cadmium, Total	ND	0.00020	0.00005	U
7440-70-2	Calcium, Total	189.	0.100	0.0394	
7440-47-3	Chromium, Total	0.00020	0.00100	0.00017	J
7440-48-4	Cobalt, Total	ND	0.00050	0.00016	U
7440-50-8	Copper, Total	ND	0.00100	0.00038	U
7439-89-6	Iron, Total	5.81	0.0500	0.0191	
7439-92-1	Lead, Total	ND	0.00100	0.00034	U
7439-95-4	Magnesium, Total	18.0	0.0700	0.0242	
7439-96-5	Manganese, Total	1.675	0.00100	0.00044	
7440-02-0	Nickel, Total	ND	0.00200	0.00055	U
7440-09-7	Potassium, Total	5.52	0.100	0.0309	
7782-49-2	Selenium, Total	ND	0.00500	0.00173	U
7440-22-4	Silver, Total	ND	0.00040	0.00016	U
7440-23-5	Sodium, Total	75.8	0.100	0.0293	
7440-28-0	Thallium, Total	ND	0.00100	0.00014	U
7440-62-2	Vanadium, Total	ND	0.00500	0.00157	U
7440-66-6	Zinc, Total	ND	0.01000	0.00341	U



Form 1 METALS

Client : Day Environmental, Inc.
 Project Name : SOLEPOXY
 Lab ID : L2231820-07
 Client ID : MW-A/20220614
 Sample Location : 202 FRANKLIN ST. OLEAN NY
 Sample Matrix : WATER
 Analytical Method : 1,6020B
 Lab File ID : WG1659999.pdf
 Sample Amount : 50ml
 Digestion Method : EPA 3005A

Lab Number : L2231820
 Project Number : SOLEPO.4884S-13
 Date Collected : 06/14/22 15:26
 Date Received : 06/15/22
 Date Analyzed : 07/07/22 22:38
 Dilution Factor : 1
 Analyst : CD
 Instrument ID : ICPMSQ2
 %Solids : N/A
 Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7429-90-5	Aluminum, Total	0.0109	0.0100	0.00327	
7440-36-0	Antimony, Total	ND	0.00400	0.00042	U
7440-38-2	Arsenic, Total	0.00149	0.00050	0.00016	
7440-39-3	Barium, Total	0.1894	0.00050	0.00017	
7440-41-7	Beryllium, Total	ND	0.00050	0.00010	U
7440-43-9	Cadmium, Total	ND	0.00020	0.00005	U
7440-70-2	Calcium, Total	92.9	0.100	0.0394	
7440-47-3	Chromium, Total	0.00022	0.00100	0.00017	J
7440-48-4	Cobalt, Total	0.00064	0.00050	0.00016	
7440-50-8	Copper, Total	0.00074	0.00100	0.00038	J
7439-89-6	Iron, Total	19.6	0.0500	0.0191	
7439-92-1	Lead, Total	ND	0.00100	0.00034	U
7439-95-4	Magnesium, Total	4.79	0.0700	0.0242	
7439-96-5	Manganese, Total	1.328	0.00100	0.00044	
7440-02-0	Nickel, Total	0.00056	0.00200	0.00055	J
7440-09-7	Potassium, Total	5.22	0.100	0.0309	
7782-49-2	Selenium, Total	ND	0.00500	0.00173	U
7440-22-4	Silver, Total	ND	0.00040	0.00016	U
7440-23-5	Sodium, Total	38.3	0.100	0.0293	
7440-28-0	Thallium, Total	ND	0.00100	0.00014	U
7440-62-2	Vanadium, Total	ND	0.00500	0.00157	U
7440-66-6	Zinc, Total	0.00688	0.01000	0.00341	J



Form 1 METALS

Client : Day Environmental, Inc.
 Project Name : SOLEPOXY
 Lab ID : L2231820-08
 Client ID : EB-1/20220614
 Sample Location : 202 FRANKLIN ST. OLEAN NY
 Sample Matrix : WATER
 Analytical Method : 1,6020B
 Lab File ID : WG1659999.pdf
 Sample Amount : 50ml
 Digestion Method : EPA 3005A

Lab Number : L2231820
 Project Number : SOLEPO.4884S-13
 Date Collected : 06/14/22 15:30
 Date Received : 06/15/22
 Date Analyzed : 07/07/22 22:44
 Dilution Factor : 1
 Analyst : CD
 Instrument ID : ICPMSQ2
 %Solids : N/A
 Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7429-90-5	Aluminum, Total	0.00334	0.0100	0.00327	J
7440-36-0	Antimony, Total	ND	0.00400	0.00042	U
7440-38-2	Arsenic, Total	ND	0.00050	0.00016	U
7440-39-3	Barium, Total	0.00218	0.00050	0.00017	
7440-41-7	Beryllium, Total	ND	0.00050	0.00010	U
7440-43-9	Cadmium, Total	ND	0.00020	0.00005	U
7440-70-2	Calcium, Total	0.347	0.100	0.0394	
7440-47-3	Chromium, Total	0.00022	0.00100	0.00017	J
7440-48-4	Cobalt, Total	ND	0.00050	0.00016	U
7440-50-8	Copper, Total	ND	0.00100	0.00038	U
7439-89-6	Iron, Total	0.0459	0.0500	0.0191	J
7439-92-1	Lead, Total	ND	0.00100	0.00034	U
7439-95-4	Magnesium, Total	0.0246	0.0700	0.0242	J
7439-96-5	Manganese, Total	0.00170	0.00100	0.00044	
7440-02-0	Nickel, Total	ND	0.00200	0.00055	U
7440-09-7	Potassium, Total	ND	0.100	0.0309	U
7782-49-2	Selenium, Total	ND	0.00500	0.00173	U
7440-22-4	Silver, Total	ND	0.00040	0.00016	U
7440-23-5	Sodium, Total	0.0805	0.100	0.0293	J
7440-28-0	Thallium, Total	ND	0.00100	0.00014	U
7440-62-2	Vanadium, Total	ND	0.00500	0.00157	U
7440-66-6	Zinc, Total	ND	0.01000	0.00341	U



Form 1 METALS

Client : Day Environmental, Inc.
 Project Name : SOLEPOXY
 Lab ID : WG1656424-1
 Client ID : WG1656424-1BLANK
 Sample Location :
 Sample Matrix : WATER
 Analytical Method : 1,6020B
 Lab File ID : WG1659999.pdf
 Sample Amount : 50ml
 Digestion Method : EPA 3005A

Lab Number : L2231820
 Project Number : SOLEPO.4884S-13
 Date Collected : NA
 Date Received : NA
 Date Analyzed : 07/07/22 20:57
 Dilution Factor : 1
 Analyst : CD
 Instrument ID : ICPMSQ2
 %Solids : N/A
 Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7429-90-5	Aluminum, Total	ND	0.0100	0.00327	U
7440-36-0	Antimony, Total	ND	0.00400	0.00042	U
7440-38-2	Arsenic, Total	ND	0.00050	0.00016	U
7440-39-3	Barium, Total	ND	0.00050	0.00017	U
7440-41-7	Beryllium, Total	ND	0.00050	0.00010	U
7440-43-9	Cadmium, Total	ND	0.00020	0.00005	U
7440-70-2	Calcium, Total	ND	0.100	0.0394	U
7440-47-3	Chromium, Total	ND	0.00100	0.00017	U
7440-48-4	Cobalt, Total	ND	0.00050	0.00016	U
7440-50-8	Copper, Total	ND	0.00100	0.00038	U
7439-89-6	Iron, Total	ND	0.0500	0.0191	U
7439-92-1	Lead, Total	ND	0.00100	0.00034	U
7439-95-4	Magnesium, Total	ND	0.0700	0.0242	U
7439-96-5	Manganese, Total	ND	0.00100	0.00044	U
7440-02-0	Nickel, Total	ND	0.00200	0.00055	U
7440-09-7	Potassium, Total	ND	0.100	0.0309	U
7782-49-2	Selenium, Total	ND	0.00500	0.00173	U
7440-22-4	Silver, Total	ND	0.00040	0.00016	U
7440-23-5	Sodium, Total	ND	0.100	0.0293	U
7440-28-0	Thallium, Total	0.00032	0.00100	0.00014	J
7440-62-2	Vanadium, Total	ND	0.00500	0.00157	U
7440-66-6	Zinc, Total	ND	0.01000	0.00341	U



Form 3 Blanks

Client : Day Environmental, Inc.
 Project Name : SOLEPOXY
 Instrument ID : ICPMSQ2

Lab Number : L2231820
 Project Number : SOLEPO.4884S-13

Parameter	Initial Calibration Blank		Continuing Calibration Blank(s)				Preparation Blank	
	ug/l	Q	ug/l	Q	ug/l	Q	Q	
Aluminum			9.35	J	9.28	J	8.83	J
Antimony			0.429	U	0.429	U	0.429	U
Arsenic			0.165	U	0.165	U	0.169	J
Barium			0.173	U	0.173	U	0.173	U
Beryllium			0.107	U	0.107	U	0.107	U
Cadmium			0.0599	U	0.0599	U	0.0599	U
Calcium			40.1	J	39.4	U	39.4	U
Chromium			0.178	U	0.178	U	0.178	U
Cobalt			0.163	U	0.163	U	0.163	U
Copper			0.384	U	0.384	U	0.384	U
Iron			28.2	J	26.8	J	28.5	J
Lead			0.343	U	0.343	U	0.343	U
Magnesium			24.2	U	24.2	U	24.2	U
Manganese			0.440	U	0.440	U	0.440	U
Nickel			0.556	U	0.556	U	0.556	U
Potassium			30.9	U	30.9	U	30.9	U
Selenium			1.73	U	1.73	U	1.73	U
Silver			0.163	U	0.163	U	0.163	U
Sodium			29.3	U	29.3	U	29.3	U
Thallium			1.35		1.41		1.45	
Vanadium			1.57	U	1.57	U	1.57	U
Zinc			3.41	U	3.41	U	3.41	U



Form 1 METALS

Client : Day Environmental, Inc.	Lab Number : L2231820
Project Name : SOLEPOXY	Project Number : SOLEPO.4884S-13
Lab ID : L2231820-01	Date Collected : 06/14/22 09:10
Client ID : MW-C/20220614	Date Received : 06/15/22
Sample Location : 202 FRANKLIN ST. OLEAN NY	Date Analyzed : 07/05/22 23:25
Sample Matrix : WATER	Dilution Factor : 1
Analytical Method : 1,7470A	Analyst : AW
Lab File ID : WG1658723.pdf	Instrument ID : NIC3
Sample Amount : 25ml	%Solids : N/A
Digestion Method : EPA 7470A	Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7439-97-6	Mercury, Total	ND	0.00020	0.00009	U



Form 1 METALS

Client : Day Environmental, Inc.	Lab Number : L2231820
Project Name : SOLEPOXY	Project Number : SOLEPO.4884S-13
Lab ID : L2231820-02	Date Collected : 06/14/22 10:05
Client ID : MW-D/20220614	Date Received : 06/15/22
Sample Location : 202 FRANKLIN ST. OLEAN NY	Date Analyzed : 07/05/22 23:35
Sample Matrix : WATER	Dilution Factor : 1
Analytical Method : 1,7470A	Analyst : AW
Lab File ID : WG1658723.pdf	Instrument ID : NIC3
Sample Amount : 25ml	%Solids : N/A
Digestion Method : EPA 7470A	Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7439-97-6	Mercury, Total	ND	0.00020	0.00009	U



Form 1 METALS

Client : Day Environmental, Inc.	Lab Number : L2231820
Project Name : SOLEPOXY	Project Number : SOLEPO.4884S-13
Lab ID : L2231820-03	Date Collected : 06/14/22 11:04
Client ID : MW-B/20220614	Date Received : 06/15/22
Sample Location : 202 FRANKLIN ST. OLEAN NY	Date Analyzed : 07/05/22 23:38
Sample Matrix : WATER	Dilution Factor : 1
Analytical Method : 1,7470A	Analyst : AW
Lab File ID : WG1658723.pdf	Instrument ID : NIC3
Sample Amount : 25ml	%Solids : N/A
Digestion Method : EPA 7470A	Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7439-97-6	Mercury, Total	ND	0.00020	0.00009	U



Form 1 METALS

Client : Day Environmental, Inc.	Lab Number : L2231820
Project Name : SOLEPOXY	Project Number : SOLEPO.4884S-13
Lab ID : L2231820-04	Date Collected : 06/14/22 11:56
Client ID : MW-E/20220614	Date Received : 06/15/22
Sample Location : 202 FRANKLIN ST. OLEAN NY	Date Analyzed : 07/05/22 23:48
Sample Matrix : WATER	Dilution Factor : 1
Analytical Method : 1,7470A	Analyst : AW
Lab File ID : WG1658723.pdf	Instrument ID : NIC3
Sample Amount : 25ml	%Solids : N/A
Digestion Method : EPA 7470A	Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7439-97-6	Mercury, Total	ND	0.00020	0.00009	U



Form 1 METALS

Client : Day Environmental, Inc.	Lab Number : L2231820
Project Name : SOLEPOXY	Project Number : SOLEPO.4884S-13
Lab ID : L2231820-05	Date Collected : 06/14/22 13:10
Client ID : MW-F/20220614	Date Received : 06/15/22
Sample Location : 202 FRANKLIN ST. OLEAN NY	Date Analyzed : 07/05/22 23:52
Sample Matrix : WATER	Dilution Factor : 1
Analytical Method : 1,7470A	Analyst : AW
Lab File ID : WG1658723.pdf	Instrument ID : NIC3
Sample Amount : 25ml	%Solids : N/A
Digestion Method : EPA 7470A	Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7439-97-6	Mercury, Total	ND	0.00020	0.00009	U



Form 1 METALS

Client : Day Environmental, Inc.	Lab Number : L2231820
Project Name : SOLEPOXY	Project Number : SOLEPO.4884S-13
Lab ID : L2231820-06	Date Collected : 06/14/22 14:18
Client ID : MW-G/20220614	Date Received : 06/15/22
Sample Location : 202 FRANKLIN ST. OLEAN NY	Date Analyzed : 07/05/22 23:55
Sample Matrix : WATER	Dilution Factor : 1
Analytical Method : 1,7470A	Analyst : AW
Lab File ID : WG1658723.pdf	Instrument ID : NIC3
Sample Amount : 25ml	%Solids : N/A
Digestion Method : EPA 7470A	Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7439-97-6	Mercury, Total	ND	0.00020	0.00009	U



Form 1 METALS

Client : Day Environmental, Inc.	Lab Number : L2231820
Project Name : SOLEPOXY	Project Number : SOLEPO.4884S-13
Lab ID : L2231820-07	Date Collected : 06/14/22 15:26
Client ID : MW-A/20220614	Date Received : 06/15/22
Sample Location : 202 FRANKLIN ST. OLEAN NY	Date Analyzed : 07/05/22 23:58
Sample Matrix : WATER	Dilution Factor : 1
Analytical Method : 1,7470A	Analyst : AW
Lab File ID : WG1658723.pdf	Instrument ID : NIC3
Sample Amount : 25ml	%Solids : N/A
Digestion Method : EPA 7470A	Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7439-97-6	Mercury, Total	ND	0.00020	0.00009	U



Form 1 METALS

Client : Day Environmental, Inc.	Lab Number : L2231820
Project Name : SOLEPOXY	Project Number : SOLEPO.4884S-13
Lab ID : L2231820-08	Date Collected : 06/14/22 15:30
Client ID : EB-1/20220614	Date Received : 06/15/22
Sample Location : 202 FRANKLIN ST. OLEAN NY	Date Analyzed : 07/06/22 00:02
Sample Matrix : WATER	Dilution Factor : 1
Analytical Method : 1,7470A	Analyst : AW
Lab File ID : WG1658723.pdf	Instrument ID : NIC3
Sample Amount : 25ml	%Solids : N/A
Digestion Method : EPA 7470A	Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7439-97-6	Mercury, Total	ND	0.00020	0.00009	U



Form 1 METALS

Client : Day Environmental, Inc.
 Project Name : SOLEPOXY
 Lab ID : WG1656426-1
 Client ID : WG1656426-1BLANK
 Sample Location :
 Sample Matrix : WATER
 Analytical Method : 1,7470A
 Lab File ID : WG1658723.pdf
 Sample Amount : 25ml
 Digestion Method : EPA 7470A

Lab Number : L2231820
 Project Number : SOLEPO.4884S-13
 Date Collected : NA
 Date Received : NA
 Date Analyzed : 07/05/22 23:19
 Dilution Factor : 1
 Analyst : AW
 Instrument ID : NIC3
 %Solids : N/A
 Date Digested : 06/28/22

CAS NO.	Parameter	mg/l			Qualifier
		Results	RL	MDL	
7439-97-6	Mercury, Total	ND	0.00020	0.00009	U

