AECOM Environment

Prepared for:
Scott Technologies, Inc.
aka Scott Figgie LLC
Frankford, DE

Prepared by:
AECOM
Buffalo, NY
60536398
June 2018

Periodic Review Report
(April 12, 2017 through April 12, 2018)

Former Scott Aviation Facility (Area 1)
Lancaster, New York
NYSDEC Site Code No. C915233

Periodic Review Report
(April 12, 2017 through April 12, 2018)

Former Scott Aviation Facility (Area 1)
Lancaster, New York
NYSDEC Site Code No. C915233

Dino L. Zack, PG, STS

_____

Prepared By [Name]

James Kaczor, PG

_____

Reviewed By [Name]

Contents

Executive Summary 3

1.0 Introduction 1-1

1.1 Report Organization 1-1

2.0 Site Overview 2-1

2.1 Site Location 2-1

2.2 Physical Setting 2-1

2.2.1 Land Use 2-1

2.2.2 Site Geology/Hydrogeology 2-1

2.2.3 Site Investigation and Remedial History 2-2

2.3 Remedial Action Objectives 2-8

2.3.1 Groundwater 2-8

2.3.2 Soil 2-9

2.3.3 Soil Vapor 2-9

2.4 Contaminants of Concern 2-9

3.0 Groundwater Monitoring Program Summary 3-1

3.1 Groundwater Monitoring Activities 3-1

3.1.1 Quarterly Groundwater Sampling 3-2

3.2 April 2018 Groundwater Elevation and Flow Direction 3-2

3.3 April 2018 Groundwater Analytical Data 3-2

3.4 April 2018 Storm Sewer Catch Basin and Storm Sewer Pipe Bedding Analytical Data 3-3

3.5 Comparison of April 2018 COCs in Groundwater with Pre-IRM Groundwater Analytical Data 3-4

3.6 Groundwater MNA Data Summary 3-4

3.7 Dechlorinating Bacteria Analysis 3-4

3.8 Dechlorinating Chemical Analysis 3-5

3.9 Total Organic Carbon 3-5

4.0 Site Inspection 4-1

4.1 Boiler Room 4-1

4.2 Monitoring Wells 4-1

5.0 Conclusions and Recommendations 5-1

5.1 Conclusions 5-1

5.2 Recommendations 5-1

5.3 Proposed Monitoring and Compliance Sampling Schedule 5-2

6.0 Evaluate Remedy Performance, Effectiveness, and Protectiveness 6-1

6.1 Institutional Controls and Engineering Controls Certification 6-1

7.0 References 7-1

List of Appendices

Appendix A Former Scott Aviation Area 1 Pre-Injection and Post-Injection Groundwater Quality Data

Appendix B Former Scott Aviation Area 1 Summary of VOCs in Groundwater

Appendix C Well Decommissioning Logs

Appendix D Institutional Controls and Engineering Controls Certification Form

List of Tables

Table	Title
1	Summary of Groundwater Monitoring Program
2	Monitoring Well, Piezometer, and Catch Basin Specifications
3	Summary of Groundwater Monitoring Well Water Level Data – April 2018
4	Summary of Groundwater Analytical Data – April 2018

List of Figures

Figure	Title
1	Site Location Map
2	Site Layout Map
3	Monitoring Well, Piezometer and Catch Basin Locations
4	Geologic Cross-Section
5	Pre-Injection Shallow Overburden Groundwater Total VOC Contaminant Plume
6	Pre-Injection Deep Overburden Groundwater Total VOC Contaminant Plume
7	Pre-Injection Shallow Overburden Groundwater TCE Contaminant Plume
8	Pre-Injection Deep Overburden Groundwater TCE Contaminant Plume
9	Injection Zone Details
10	Shallow Overburden Groundwater Surface Contour Elevations – April 2018
11	Deep Overburden Groundwater Surface Contour Elevations – April 2018
12	Post-Injection Shallow Overburden Monitoring 1,1,1-Trichloroethane Plume – April 2018
13	Post-Injection Deep Overburden Monitoring 1,1,1-Trichloroethane Plume – April 2018
14	Post-Injection Shallow Overburden Monitoring 1,1-Dichloroethane Plume – April 2018
15	Post-Injection Deep Overburden Monitoring 1,1-Dichloroethane Plume – April 2018
16	Post-Injection Shallow Overburden Monitoring 1,1-Dichloroethene Plume – April 2018
17	Post-Injection Shallow Overburden Monitoring 1,2-Dichloroethane Plume – April 2018
18	Post-Injection Shallow Overburden Monitoring Vinyl Chloride Plume – April 2018
19	Post-Injection Deep Overburden Monitoring Vinyl Chloride Plume – April 2018
20	Post-Injection Shallow Overburden Monitoring Total VOCs Plume – April 2018
21	Post-Injection Deep Overburden Monitoring Total VOCs Plume – April 2018
22	Post-Injection Shallow Overburden Monitoring Total Organic Carbon – April 2018
23	Post-Injection Deep Overburden Monitoring Total Organic Carbon – April 2018

List of Acronyms

1,1-DCA	1,1-dichloroethane
1,1-DCE	1,1-dichloroethene
1,2-DCA	1,2-dichloroethane
1,1,1-TCA	1,1,1-trichloroethane
1,1,2-TCA	1,1,2-trichloroethane
AAR	Alternatives Analysis Report
ABC®	Anaerobic Biochem
ABC+®	Anaerobic Biochem with Zero Valence Iron
AECOM	AECOM Technical Services, Inc.
AMSL	above mean sea level
AVOX	AVOX Systems Inc
BCP	Brownfield Cleanup Program
bgs	below ground surface
CCR	Construction Completion Report
cis-1,2 DCE	cis-1,2-dichloroethene
cm/sec	centimeters per second
COC	contaminants of concern
COPC	constituents of potential concern
CVOC	chlorinated volatile organic compound
DHC	*Dehalococcoides*
ERD	Enhanced Reductive Dechlorination
ESA	Environmental Site Assessment
ft	feet
HPT	hydraulic profiling tool
IC/EC	Institutional Controls/Engineering Controls
IRM	interim remedial measure
K	hydraulic conductivity
METI	Matrix Environmental Technologies, Inc.
mg/L	milligrams per liter
MIP	membrane interface probe
MNA	monitored natural attenuation
NYCRR	New York Codes, Rules and Regulations

NYSDEC	New York State Department of Environmental Conservation
NYSDOH	New York State Department of Health
O&M	operation and maintenance
PCB	polychlorinated biphenyl
PCE	Tetrachloroethene (Perchloroethene)
PGA	Preliminary Groundwater Assessment
PID	photoionization detector
PRR	Periodic Review Report
QA/QC	quality assurance / quality control
RAO	remedial action objective
RAWP	Remedial Action Work Plan
RI	remedial investigation
SCO	soil cleanup objective
SMP	Site Management Plan
SRI	Supplemental Remedial Investigation
SVI	soil vapor intrusion
SVOC	semi volatile organic compound
TCE	trichloroethene
TOC	total organic carbon
TOGS	Technical and Operational Guidance Series
TVOC	total volatile organic compounds
µg/L	micrograms per liter
USEPA	United States Environmental Protection Agency
UST	underground storage tank
VC	vinyl chloride
VOC	volatile organic compound
XSD	halogen specific detector
ZVI	zero valence iron

Executive Summary

On September 1, 2004, the former Scott Aviation Facility (three plant facility) was sold by Scott Technologies, Inc. to the current facility owner/operator, AVOX Systems Inc. (AVOX). On September 11, 2008, Scott Technologies, Inc. submitted an application for the area located adjacent to the southwest corner of the Plant 1 property (the "Site", also known as Area 1) to enter the New York State Department of Environmental Conservation (NYSDEC) Brownfield Cleanup Program (BCP), per Title 6 New York Codes, Rules, and Regulations Part 375-3.4 (Applications), effective December 14, 2006. Scott Technologies, Inc. applied for entry into NYSDEC BCP as a participant to investigate and remediate, as appropriate, potential areas of environmental concern associated with the Site. On July 8, 2009, NYSDEC approved the application and Scott Technologies was accepted into the BCP program as a participant (NYSDEC Site Code No. C915233). Scott Technologies, a successor to Figgie International, is now known as Scott Figgie LLC. In December 2015, AVOX was added to the BCP as a Volunteer.

Soil, groundwater, surface water, and soil vapor impacts at the Site were outlined in reports submitted to the NYSDEC that describe the results of a series of investigations which took place over several years. Impacts identified during these investigations were addressed via interim remedial measures (IRMs) prior to the issuance in December 2015 of a final Decision Document and Certificate of Completion for the Site.

Based on the implementation of the IRMs, findings of the investigation of the Site indicate that the Site no longer poses a threat to human health or the environment; therefore No Further Action is the selected remedy by NYSDEC. The No Further Action remedy includes quarterly groundwater monitoring and quarterly inspections of the boiler room repairs to the floor cracks and joints, and sealing of the annulus around each floor drain to mitigate the potential for subslab vapors to enter the building.

Quarterly post-IRM groundwater monitoring shows a notable decrease in the concentrations of contaminants of concern (COC), and no off-Site migration of COCs in groundwater. Additionally, microbial analysis of shallow and deep overburden groundwater indicates that the necessary microflora, such as *Dehalococcoides* (DHC) bacterial species, producing the enzymes tceA reductase and vinyl chloride reductase, are present in the subsurface.

A continuation of quarterly groundwater monitoring for volatile organic compounds, quarterly inspections of the boiler room floor, and annual reporting per the NYSDEC-approved Site Management Plan is recommended for the next reporting period.

1.0 Introduction

On behalf of Scott Figgie LLC (successor to Scott Technologies, Inc.), and pursuant to the requirements of New York State Department of Environmental Conservation (NYSDEC), Decision Document (NYSDEC, December 2015) and Site Management Plan (AECOM, December 2015), AECOM Technical Services, Inc. (AECOM) has prepared this Periodic Review Report (PRR) to summarize the groundwater monitoring activities for the former Scott Aviation facility (the "Site", also known as Area 1), NYSDEC Site Code No. C915233, located within two parcels at 215 and 221 Erie Street, Village of Lancaster, County of Erie, State of New York (**Figure 1**). The reporting period discussed herein encompasses the period between April 12, 2017 through April 12, 2018. The Site is currently owned and operated by AVOX Systems, Inc. (AVOX).

1.1 Report Organization

The purposes of this PRR are to provide a summary of the controls implemented for the Site as required by Section 7.2 of the Site Management Plan (SMP) (AECOM, December 2015) and to provide recommendations for future controls at the Site.

This PRR was developed to adhere to NYSDEC site investigation and remediation requirements (NYSDEC DER-10, May 2010). More specifically, this report provides the following information:

- An Executive Summary including a brief summary of the Site, nature and extent of contamination, remedial history, the effectiveness of the remedial program, and recommendations for changes to the SMP;
- Brief summary of the Site and PRR organizational details (Section 1.0);
- A Site overview, describing the Site location, significant features, surrounding areas, and the extent of environmental impacts prior to the Site remediation. A description of the chronology of the main features of the remedial program for the Site, the components of the selected remedy, cleanup goals, site closure criteria, and any significant changes to the selected remedy that have been made since remedy selection (Section 2.0);
- A groundwater monitoring program summary including a description of the requirements of the monitoring, a summary of the groundwater monitoring activities completed during the PRR reporting period, a comparison of the most recent (April 2018) groundwater results to the Remedial Action Objectives (RAOs) of the Site, and conclusions regarding the monitoring completed and the resulting evaluations regarding remedial performance, effectiveness, and protectiveness (Section 3.0);
- A description of the operations and maintenance (O&M) tasks completed and recommendations for improvements (Section 4.0);
- A summary of overall conclusions and recommendations regarding compliance with the SMP, performance and effectiveness of the remedy, a description of upcoming Site-related activities, and a proposed monitoring and compliance sampling and reporting schedule (Section 5.0);
- A review of the Institutional Controls/Engineering Controls (IC/EC) for the Site (Section 6.0); and

- References used in the preparation of this report (Section 7.0).

2.0 Site Overview

The following subsections present a description the Site location, significant features, surrounding areas, and the extent of contamination prior to the Site remediation. A description of the chronology of the main features of the remedial program for the Site, the components of the selected remedy, cleanup goals, site closure criteria, and any significant changes to the selected remedy that have been made since remedy selection is also presented.

2.1 Site Location

The Site is located in Lancaster, Erie County, New York and is identified as Section 104 Block 5 and Lots 8 and 9 on the Erie County Tax Map; refer to **Figure 1** – Site Location Map. The Site is approximately 1.25 acres in area and is bounded by non-impacted AVOX land and then Erie Street to the north, railroad tracks to the south, AVOX Plant 1 (currently vacant) to the east, and residential zoned property (with a house) to the west; refer to **Figure 2** – Site Layout Map).

2.2 Physical Setting

2.2.1 Land Use

The Site consists of the following: outbuildings that support Plant 1 (which is not part of the Site), asphalt driveways and parking areas, and lawn and brush-covered areas. Site occupants include only occasional maintenance and shipping/receiving personal, as manufacturing activities have been moved to the two plants located on the north side of Erie Street.

The properties adjoining the Site and in the neighborhood surrounding the Site include both commercial and residential properties. The properties immediately south of the Site include railroad tracks; the properties immediately north of the Site include commercial properties; the properties immediately east of the Site include AVOX Plant 1 and its parking lot, and then residential properties (including vacant land); and the properties to the west of the Site include residential properties.

2.2.2 Site Geology/Hydrogeology

The native soils underlying the Site generally consist of interbedded silts and clays, with discontinuous sporadic fine sand lenses (shallow overburden). A thin coarse-grained layer of weathered shale is located above the bedrock (deep overburden). Overburden thickness ranges from 20 feet (ft) in the southern portion of the Site to 26 ft in the northern portion of the Site.

The average depth to bedrock is approximately 21 ft. Bedrock was observed to consist of black shale of the Marcellus Formation (Hamilton Group).

A transect for a geologic cross section with monitoring well and piezometer locations is shown on **Figure 3**, and the geologic cross-section is shown on **Figure 4**.

Groundwater monitoring wells are installed at three intervals: shallow overburden, deep overburden, and bedrock. Overburden groundwater is first encountered at the Site in the shallow overburden, and then again just above the bedrock. An observation of the groundwater within the deep overburden, which is present on top of bedrock, indicates a semi-confined state.

Results of the in-situ hydraulic conductivity (K) tests performed in the monitoring wells at the Site showed that K values range from 1.49E-03 centimeters per second (cm/sec) to 3.13E-05 cm/sec in the shallow overburden, and range from 4.72E-03 cm/sec to 8.96E-05 cm/sec in the deep overburden. Hydraulic conductivity testing was not performed in the bedrock monitoring well.

The natural flow of groundwater at the Site in both the shallow and deep overburden is to the northwest. The flow direction is most pronounced in the deep overburden, as the shallow overburden groundwater is influenced by seasonal standing water to the southwest, a storm sewer network cutting through the Site, large asphalt areas to the north and east, and Plant 1 to the east. Depth to groundwater across the Site in both the shallow and deep overburden was measured in April 2018 and is discussed in detail in Section 5.0 of this report.

2.2.3 Site Investigation and Remedial History

The following narrative provides a remedial history timeline and a brief summary of the available project records to document key investigative and remedial milestones for the Site. Full titles for each of the reports referenced below are provided in Section 7.0.

The general historical operations that existed in the Plant 1 building adjacent to the Site were primarily manufacturing, development, testing, and distribution for aircraft and military supplied-air systems. The oldest portion of Plant 1 dates to the early 1950s. That original building was expanded several times, with most of it in place by 1975 except for a small warehouse addition in 1996. Plant 1 historical activities included the chemical cleaning and repainting of oxygen cylinders, the chemical cleaning (with inorganic acid solutions) and chromium coating (in a non-electrolytic “soak bath”) of metallic components of oxygen supply systems, and the fabrication of oxygen-regulating assemblies. Plant 1 also supported a Class 10,000 clean room and a Class 100,000 clean room. The office area contained management, administrative, engineering, training, and other support activities, and a cafeteria.

As of 2010, Plant 1 has no longer been used for production (i.e., painting and plating activities have terminated). The BCP boundary for the Site is located immediately west/southwest of Plant 1. In general, the pre-remediated areas as described below consisted of low-level metals in the top of the shallow overburden soil immediately south of Plant 1, volatile organic chemicals (VOCs) in shallow overburden soil at the fence gate southwest of Plant 2, and VOCs in shallow and deep overburden groundwater west/southwest of Plant 1. Note: the BCP boundary, or VOC-impacted groundwater plume, does not extend off the AVOX property.

2.2.3.1 Phase I

In 2004, a Phase I Environmental Site Assessment (ESA) was performed at the Site by Earth Tech, Inc. (now AECOM) on behalf of the then owner, Scott Technologies, Inc. The entire facility was sold to the current owner, AVOX, in September 2004. Historical aerial photographs included in the Phase I ESA Report indicated an area of potentially disturbed soil on the west side of Plant 1, south of the existing visitor parking area, and just outside the Plant 1 western perimeter fence line on the adjacent vacant parcel (Earth Tech, April 2004). The Phase I ESA also identified two former underground storage tanks (USTs) that had contained gasoline starting in the early 1970s which were removed from the southeastern portion of the Plant 1 Area in November of 1987; however, no records were found to indicate that any post-excavation sampling was done to demonstrate that the soil and groundwater in the vicinity had not been impacted.

Another former UST that had contained gasoline from an unknown date until the early 1970s was reportedly cleaned and closed in place at that time by filling it with sand. It is believed to be located beneath the current hazardous materials storage shed. No records were found to indicate exactly where that tank is located, when closure occurred, or that any post-closure sampling was done to demonstrate that soil and ground water in the vicinity had not been impacted. From the early 1950s to about 1973, used sand from a steel-casting foundry operation, located in the western portion of Plant 1, was disposed behind (south of) Plant 1.

2.2.3.2 Phase II

A Phase II Environmental Site Investigation was completed in 2004 for the entire Scott Aviation facility, to address environmental concerns described in the Phase I ESA Report, including the area of potentially disturbed soil on the west side of Plant I. During the Phase II ESI, seven test pits were excavated. Residual paint sludge of unknown origin was observed in two of the test pits. The paint sludge area was approximately 150 square ft in size, and located just west and south of the vehicle gate located in the western perimeter fence, immediately north of the water tower. Elevated levels of VOCs and semi-volatile organic compounds (SVOCs) present in the soil immediately below the waste indicated that some leaching of the waste had occurred (Earth Tech, June 2004).

2.2.3.3 Interim Remedial Measure - Soil Excavation

On June 28, 2005, Earth Tech, in accordance with a NYSDEC-approved Interim Remedial Measures (IRM) / Supplemental Site Investigation Work Plan, performed an initial excavation of the buried paint sludge material located to the west of Plant 1. A total of 60 cubic yards of soil was excavated to the west of Plant 1, down to the level at which groundwater was encountered - about 6 ft below ground surface (bgs). Further excavation was not completed during the IRM, as the scope of work only addressed vadose zone soil.

2.2.3.4 Preliminary Groundwater Assessment

The above investigations identified the general areas of concern. As a result of the elevated VOC and SVOC soil concentrations detected in the excavation bottom at Area 1 during the 2005 IRM, a Preliminary Groundwater Assessment (PGA) was performed in 2006 and 2007. The purpose of the PGA was to assess the nature and extent of VOCs in groundwater in the vicinity of Area 1. A series of groundwater wells was installed, and samples were collected and analyzed as a part of the PGA (Earth Tech, January 2008). Eighteen temporary piezometers were installed during the PGA to monitor shallow overburden groundwater. Groundwater samples collected from these piezometers contained VOCs, with 18 of these compounds detected at concentrations that exceeded the NYSDEC Technical and Operational Guidance Series (TOGS) 1.1.1 (NYSDEC, June 1998, January 1999 errata sheet, April 2000 addendum, June 2004 addendum) protection for source of drinking water (groundwater) standards (i.e., water class GA). Samples of deep overburden groundwater also contained VOCs, but to a lesser degree than the shallow overburden groundwater.

2.2.3.5 Remedial Investigation

The BCP Remedial Investigation (RI) began in December 2010 with the completion of soil borings, the installation of monitoring wells, and the collection of soil, groundwater and vapor samples for chemical analysis. This initial work was completed during the summer of 2010. A Supplemental RI (SRI), completed in June 2011, included the installation of additional monitoring wells, groundwater sampling, and an evaluation of a storm sewer system that was located throughout the BCP Site. The RI and SRI were performed to gather the data necessary to complete the characterization of chemical presence in on-Site groundwater, soil, and soil vapor, in order to identify and evaluate

necessary and appropriate remedial alternatives. The proposed remedial alternatives were presented in an Alternatives Analysis Report (AAR) (AECOM, September 2015). That AAR was completed in accordance with the NYSDEC DER Draft BCP Guide (NYSDEC, May 2004), 6 New York Codes, Rules and Regulations (NYCRR) Part 375 Environmental Remediation Programs (NYSDEC, December 14, 2006), and NYSDEC DER-10 (NYSDEC, May 3, 2010).

These studies investigated Area 1 for contamination in surface soil, subsurface soil, groundwater, and impacts to on-Site storm sewers. Constituents of potential concern (COPCs) were identified for soil by comparison of maximum detected concentrations for VOCs to 6 NYCRR Part 375 Unrestricted Use soil cleanup objectives (SCOs), and for SVOCs, metals, pesticides, and polychlorinated biphenyls (PCBs) by comparison to 6 NYCRR Part 375 Commercial Use SCOs. COPCs were identified for groundwater by comparison of maximum detected concentrations for VOCs, SVOCs, metals, pesticides, and PCBs to NYSDEC TOGS 1.1.1 protection for source of drinking water (groundwater) standards (i.e., water class GA). The results of this comparison to applicable standards are detailed below.

- Surface Soil - VOC concentrations for surface soil (i.e., 0 to 2 inches bgs) were below the NYSDEC Subpart 375-6 SCOs for Unrestricted Use at the borings sampled. SVOC, metal, PCB, and pesticide concentrations were below the SCOs for Commercial Use, with the exceptions of benzo(a)pyrene (potentially resulting from asphalt paving and/or the adjacent active rail line) and metals cadmium and nickel.

- Subsurface Soil - VOC concentrations from subsurface soil samples collected from borings during the RI and SRI were below the SCO for Unrestricted Use, with the exception of acetone and methylene chloride (common laboratory contaminants) at two borings: DPT8-2A and DPT8-2B, both located south of Plant 1. VOC concentrations from one confirmation sample collected from the bottom of the historic IRM (B-1A) exhibited seven compounds exceeding Unrestricted Use SCOs (all seven compounds were below Commercial Use SCOs). SVOC, pesticide and PCB concentrations from subsurface soil samples were all below Unrestricted Use SCOs. Regarding metals, only mercury, copper, and cadmium exceeded SCOs for Commercial Use. These exceedances occurred at two borings: DPT8-1A and DPT8-2A.

- Groundwater - Analytical data for groundwater samples collected from the shallow and deep overburden wells during the RI and SRI identified the presence of VOCs exceeding NYSDEC TOGS 1.1.1 protection for source of drinking water (groundwater) standards. Refer to **Figure 5** and **Figure 6** for the RI/SRI total VOC (TVOC) contaminant concentration contours for shallow and deep overburden concentration contours, respectively. There were no exceedances of NYSDEC TOGS 1.1.1 protection for source of drinking water (groundwater) standards in the bedrock groundwater. The most frequently detected VOCs were trichloroethene (TCE) and cis-1,2-dichloroethene (cis-1,2-DCE). Refer to **Figure 7** and **Figure 8** for the RI/SRI TCE contaminant concentration contours for shallow and deep overburden concentration contours respectively. The greatest VOC concentrations were detected in the area of the previously-excavated source area during the 2005 IRM. At perimeter wells, VOCs were either not detected or were detected at concentrations below or slightly above NYSDEC TOGS 1.1.1 protection for source of drinking water (groundwater) standards for TCE. See **Appendix A** for a summary of groundwater VOC data collected during the RI, SRI, and quarterly monitoring, and **Appendix B** for trend plots illustrating concentrations of contaminants of concerns (COCs) which include 1,1,1-trichloroethane (1,1,1-TCA), 1,1,2-trichloroethane (1,1,2-TCA), 1,1-dichloroethane (1,1-

DCA), 1,1-dichloroethene (1,1-DCE), 1,2,dichlroethane (1,2-DCA), tetrachloroethene (PCE), TCE, and vinyl chloride (VC) over time. SVOCs in groundwater were below NYSDEC TOGS 1.1.1 protection for source of drinking water (groundwater) standards. Three naturally occurring metals (iron, magnesium, and sodium) were detected in groundwater above NYSDEC TOGS 1.1.1 protection for source of drinking water (groundwater) standards. No PCBs were detected, and only one pesticide was tentatively detected in one groundwater sample at a concentration greater than NYSDEC TOGS 1.1.1 protection for source of drinking water (groundwater) standards. Refer to the Alternatives Analysis Report (AAR) (AECOM, April 2015) for groundwater VOC, SVOC, metal, and PCB/pesticide data.

- Storm Sewer Catch Basins - A storm sewer with several catch basins is present in Area 1; refer to **Figure 3** for the location of the storm sewer system. VOCs were detected within storm sewer catch basins located on the Site and from water within the storm sewer pipe bedding. Groundwater is present above the storm sewer piping; refer to the AAR (AECOM, April 2015) for storm sewer VOC data and for temporary piezometer water sample data that was collected from within the storm sewer pipe bedding gravel.

- Soil Vapor - Based on the evaluation of the data against the decision matrices, a vapor intrusion condition is not present at the Site, and indoor air quality has not been adversely impacted by the presence of the adjacent groundwater plume. However, per a June 1, 2012 letter from the NYSDEC to Scott, the New York State Department of Health (NYSDOH) considered this Site to be a significant threat due to elevated concentrations of VOCs in sub-slab soil vapor, and the potential for this vapor to impact indoor air. Refer to the AAR (AECOM, September 2015) for air sampling data, for vapor data compared to 2006 NYSDOH guidance values, and for the United States Environmental Protection Agency (USEPA) 2001 Building Assessment and Survey Evaluation database indoor air values, respectively.

2.2.3.6 Soil Vapor Intrusion Evaluation

Based on NYSDEC comments on the draft AAR (AECOM, April 2013), AECOM completed a targeted soil vapor intrusion (SVI) investigation for the Site in July 2013. The purpose of that SVI investigation was to assess whether soil vapor on the Site in the vicinity of a nearby residence at 205 Erie Street contained chlorinated VOCs (CVOCs), and if so at concentrations sufficiently elevated to represent a potential indoor air quality issue for the nearby buildings (AECOM, August 2013). A second investigation and report was completed in September 2013 to follow up on one TCE detection in soil vapor above the method detection limit. Both groundwater and soil samples were collected hydraulically downgradient of Area 1, between the facility and the 205 Erie Street residence, and focused on seven CVOCs that, per NYSDOH guidance values, should be considered as part of an SVI analysis for the residence: 1,1,1-TCA; cis-1,2-DCE; VC; 1,1-DCE; carbon tetrachloride, PCE, and TCE.

No CVOC listed above was reported in any of the soil or groundwater samples. Acetone was reported in one soil sample (12 micrograms per kilogram). Acetone was also reported in five of the six groundwater samples and in the trip blank. The only other VOC reported was 2-butanone at 4.1 micrograms per liter (µg/L). AECOM reviewed historical soil, groundwater, soil vapor, and stormwater data from the northern portion of the Area 1 Site to assess the potential relationship between the low level TCE concentration reported in SV-1 in July 2013 and the Area 1 contamination. The collective data does not identify a clear relationship between the two that would

warrant further SVI sampling at the residential property. Multiple media have been evaluated. The property boundary between AVOX (which includes the Site) and 205 Erie Street appears to not be impacted by the BCP Site (AECOM, October 2013).

2.2.3.7 Interim Remedial Measures - 2014

During a conference call between NYSDEC, Scott, AECOM, and AVOX on February 28, 2014, the NYSDEC recommended moving forward with the BCP cleanup in advance of an approved Final AAR by completing four IRMs to address soil and selected groundwater impacts at the Site. They included:

- Excavation and off-Site disposal of shallow soils impacted by metals (cadmium, copper and nickel);
- Excavation and off-Site disposal of subsurface soils impacted by VOCs in some locations;
- Grout sealing on-Site storm sewer joints to prevent groundwater infiltration, and installation of impermeable plugs across the pipe bedding to prevent migration of groundwater; and
- Mitigation of SVI concerns at the AVOX boiler room (the only structure within Area 1 that is occasionally occupied).

Those four IRMs were described in an IRM Remedial Action Work Plan (RAWP) dated June 4, 2014. On August 14, 2014, NYSDEC provided approval to begin the described work per the 2014 IRM RAWP.

Soil Excavation and Storm Sewer Interim Remedial Measures

The 2014 IRM activities were initiated on September 8, 2014. The soil excavation and storm sewer IRMs were completed during October 2014. Metals impacted soil was excavated to 1 ft bgs in the vicinity of MW-41B, with all confirmatory samples passing metal Commercial Use SCOs for the target parameters. Confirmation soil samples were collected from the excavation sidewalls and bottoms. Soil was excavated to 2 ft bgs in the vicinity of DPT8-1 and DPT8-2. Following the initial excavation, an additional 2 ft wide by 2 ft deep excavation occurred on the south side wall of DPT8-1 and on the north side wall of DPT8-2, until sample results were below Commercial Use SCOs. Following receipt of passing sample confirmation data, and with concurrence from the NYSDEC, the excavated areas were backfilled with imported soil that met NYSDEC Unrestricted Use SCOs, and restored to pre-excavation conditions. Each excavation remained open until receipt of soil analytical results determined that confirmation soil samples were below respective SCOs, and the NYSDEC issued approval to discontinue excavation.

VOC concentrations from soil confirmation bottom samples collected in 2005 following an IRM soil excavation were found to be in exceedance of the Unrestricted Use SCO. These samples were collected at or below typical shallow overburden groundwater depths. The concentrations of 1,1-DCE, cis-1,2-DCE, ethylbenzene, toluene, 1,1,1-TCA, TCE, and total xylenes exceeded NYSDEC Subpart 375-6 Unrestricted Use SCOs. An initial horizontal excavation limit was established following the same footprint of the previously excavated area (approximately 14 ft by 18 ft, by 6 ft deep). The 2014 IRM scope was to remove the top 0 to 6 ft of previous clean fill and excavate material from 6 to 8 ft bgs. Elevated Photoionization Detector (PID) headspace readings on side wall and bottom samples were observed following excavation of the 6 to 8 ft bgs interval, and reported to NYSDEC. Due to the depth of observed elevated PID readings and below-average

shallow groundwater elevations, an additional 2 ft of soil was removed from the side walls (where physical constraints allowed) and from the bottom of the excavation. Characterization samples from the side walls and bottom of the excavation were collected and resulted in VOC detections exceeding Unrestricted Use SCOs. Refer to the 2014 IRM Construction Completion Report (CCR) for characterization sample results and for the location of the VOC IRM. With approval from the NYSDEC, no further excavation of soil took place; impacts were left in place to be addressed as part of the groundwater IRM, since all impacted material was below the water table. Prior to backfilling, and with approval from the NYSDEC, 270 pounds of Klozur® CR engineered calcium peroxide was placed on the bottom of the excavation area and mixed with the small amount of groundwater that had accumulated in the excavation. Fill from the 2005 IRM and imported fill in compliance with NYSDEC DER-10 was used to backfill the excavation areas created for this IRM.

Following the completion of the IRMs in November 2014, AECOM submitted a draft IRM CCR on February 15, 2015 describing those 2014 IRMs. The 2014 IRM CCR was written in compliance with DER-10 Section 5.8, Construction Completion Report and Final Engineering Report, and summarizes these IRM activities. The Final 2014 IRM CCR was approved by NYSDEC on March 27, 2015 (AECOM, March 2015).

Sub-slab Soil Vapor Interim Remedial Measure

On November 4, 2014, AECOM and NYSDEC inspected the concrete floor of the boiler room and AECOM sealed visible floor cracks with concrete caulking. In addition, the annulus between a drain line effluent and the associated floor penetration foundation perforations was sealed with expanding foam. Two other foundation perforations (drains) were observed and temporarily plugged with modelling clay just prior to a sampling event. The floor drains appeared to discharge to the bedding gravel beneath the concrete floor slab. On December 24, 2014 one sub-slab vapor sample, one indoor vapor sample, one ambient (outdoor) air sample, and an associated quality assurance / quality control sample were collected from the boiler room building at AVOX Plant 1, to determine if CVOCs were currently at indoor concentrations sufficiently elevated to trigger a need for mitigation activities. The December 2014 indoor air sample did not detect any chlorinated VOCs listed in the NYSDOH Guidance document. The 2014 sub-slab vapor sample detected 1,1,1-TCA, cis-1,2-DCE, 1,1-DCE, PCE, and TCE. According to the NYSDOH decision matrices, PCE and TCE concentrations trigger an action of ‘monitor’ only, while the 1,1,1-TCA, cis-1,2-DCE, and 1,1-DCE concentrations are below an action level. Low concentrations of 1,1,1-TCA, cis-1,2-DCE, and TCE were detected in the ambient (outdoor) air sample. The sealing of floor cracks and foundation perforations have decreased the concentrations in the indoor air samples and lowered the action level from ‘mitigation’ to ‘monitoring’ (AECOM, January 2015).

Groundwater Interim Remedial Measure

In 2014, an IRM pre-design investigation utilizing a combined membrane interface probe (MIP) and hydraulic profiling tool (HPT) was performed in Area 1; refer to **Figure 9** for MIP locations. That pre-design investigation was performed in accordance with the MIP/HPT and Baseline Sampling Work Plan (AECOM, October 2014).

On November 24-25, 2014, 11 borings were completed throughout the groundwater plume in Area 1 to a depth of 20 ft bgs, with the objective of verifying the distribution of VOC COPCs within that area. The MIP/HPT was used to capture data at continuous depths at each boring. The MIP is a percussion tolerant VOC sensor that can continuously log VOCs that diffuse through a semi-permeable membrane. Using a carrier gas, the VOCs are brought to the surface through tubing which is connected to a laboratory grade halogen specific detector (XSD), PID, and flame ionization

detector to provide immediate analysis. Concurrently, the HPT allows the user to create continuous real-time profiles of soil hydraulic properties in both fine-grained and coarse-grained material. The HPT uses a sensitive downhole transducer to measure the pressure response of the soil to injection of water. Injection pressure is a measure of the hydraulic properties of the soil; a relatively high pressure response indicates a higher proportion of clays and fine-grained materials, whereas a relatively low pressure response indicates a larger grain size and a higher K value.

The 3D Imaging Summary, MIP/HPT Boring Summary, and MIP Data Cross Section figures summarize the field activities and results of the MIP/HPT analysis. XSD data were used as the prime indicator of CVOC impacts, as they are highly sensitive to chlorinated VOCs compared to the other data collection methods. Within the investigated zones, target treatment depths were identified using K data provided by the HPT analysis. The MIP/HPT results were generally consistent with groundwater data collected from June 2010 through June 2011. The data indicated that there are lower VOC concentrations present in the northern portion of the Site and that, where present, they are limited to the upper 14 ft of the overburden. In the southern portion of the Site, VOC concentrations were greater and also present in significant concentrations throughout the entire depth of the soil borings, with the 5-15 ft bgs region exhibiting the highest XSD response. In addition to MIP-8 located in the center of the groundwater plume, the easternmost and westernmost boring locations, MIP-1 and MIP-11, showed the highest VOC concentrations.

Remedial activities for the groundwater IRM were described in the Final Remedial Action Work Plan - 2015 Interim Remedial Measures - Groundwater Treatment (2015 IRM RAWP) (AECOM, March 25, 2015). On April 10, 2015 the NYSDEC provided approval to begin the described work per the 2015 IRM RAWP. In accordance with the AAR and the 2015 IRM RAWP, the remedial approach to address VOCs in Site groundwater was in-situ enhanced reductive dechlorination (ERD) via direct-push injections of Anaerobic Biochem (ABC®) with zero valent iron (ZVI), i.e., ABC+®. The final 2015 IRM CCR describes work completed to remediate VOCs in Site groundwater (AECOM, August 12, 2015). Refer to **Figure 9** for the injection zone details.

2.3 Remedial Action Objectives

The objectives for the remedial program have been established though the remedy selection process stated in 6 NYCRR Part 375. The goal for the remedial program is to restore the Site to pre-disposal conditions to the extent feasible. At a minimum, the remedy must eliminate or mitigate all significant threats to the public health and the environment presented by CVOCs identified at the Site through the proper application of scientific and engineering principles.

The RAOs for the Site as listed in the Decision Document (NYSDEC, December 2015) are as follows:

2.3.1 Groundwater

- RAOs for Public Health Protection
    - Prevent ingestion of groundwater with contaminant levels exceeding drinking water standards.
    - Prevent contact with, or inhalation of, volatile organic compounds from impacted groundwater.

- RAOs for Environmental Protection
    - Restore ground water aquifer to pre-disposal/pre-release conditions, to the extent practicable.
    - Prevent the discharge of COCs to surface water.
    - Remove the source of ground or surface water constituents of concern.

2.3.2 Soil

- RAOs for Public Health Protection
    - Prevent ingestion/direct contact with impacted soil.
    - Prevent inhalation of or exposure from contaminants volatilizing from soil.
- RAOs for Environmental Protection
    - Prevent migration of constituents that would result in groundwater or surface water contamination.

2.3.3 Soil Vapor

- RAOs for Public Health Protection
    - Mitigate impacts to public health resulting from existing, or the potential for, SVI into buildings at a site.

2.4 Contaminants of Concern

Eight COCs in groundwater have been determined through sampling associated with the RI and SRI. Per the Decision Document (NYSDEC, December 2015), Section 6.1.2 (NYSDEC, December 2015), a “contaminant of concern” is a contaminant that is sufficiently present in frequency and concentration in the environment to require evaluation for remedial action. Not all constituents identified on the Site are COCs. The groundwater COCs identified at the Site and their associated RAOs (Guidance or Standard Values) from NYSDEC TOGS 1.1.1 protection for source of drinking water (groundwater) standards are listed below:

- 1,1,1-TCA – 5 µg/L
- 1,1,2-TCA – 5 µg/L
- 1,1-DCA – 5 µg/L
- 1,1-DCE – 5 µg/L
- 1,2-DCA – 0.6 µg/L
- PCE – 5 µg/L
- TCE – 5 µg/L
- VC – 2 µg/L

3.0 Groundwater Monitoring Program Summary

The following sections provide a summary of the groundwater monitoring program completed during the reporting period (April 12, 2017 through April 12, 2018); a comparison of the groundwater data collected from the most recent monitoring event (April 2018) to the COCs and historical groundwater analytical data; and conclusions regarding the monitoring completed and the resulting evaluations regarding remedial performance, effectiveness, and protectiveness.

3.1 Groundwater Monitoring Activities

In accordance with the SMP, the groundwater monitoring program during the reporting period consisted of four comprehensive quarterly monitoring events (July 2017, October 2017, January 2018, and April 2018). These sampling events, following the IRMs described in Section 2.2.3.7, were to determine the effectiveness of the groundwater remedy.

Quarterly sampling was performed at 17 wells, two temporary piezometers screened in the storm sewer pipe bedding, and one on-Site storm water catch basin. On August 4, 2017, NYSDEC requested the addition of three wells to the groundwater monitoring program; these wells were added to the program during the October 2017, January 2018, and April 2018 comprehensive quarterly groundwater sampling events. Refer to **Figure 3** for the location of sampling points.

Groundwater samples from the monitoring wells were analyzed for VOCs and total organic carbon (TOC). Six monitoring wells (three shallow overburden and three deep overburden) were also sampled for monitored natural attenuation (MNA) parameters. Two monitoring wells (one shallow overburden and one deep overburden) were sampled annually for concentrations of dechlorinating bacteria (DHC). The two temporary piezometers screened in the storm sewer pipe bedding, and one on-Site storm water catch basin, were analyzed for VOCs only. The groundwater monitoring program is summarized in **Table 1.**

Monitoring of groundwater conditions at this Site includes both groundwater level measurements and groundwater sampling and analysis. All monitoring and laboratory data, including quality assurance / quality control (QA/QC) samples, have been uploaded to the NYSDEC EQuIS database. In addition, groundwater purge data, water levels, VOC, TOC, MNA, and microbial data from these four quarterly events, as well as groundwater data collected prior to the IRMs, are summarized in **Appendix A**.

Groundwater samples were divided into three different groups based on historical analytical concentrations from individual wells: plume wells, downgradient wells, and upgradient wells (refer to **Table 2** for monitoring well, piezometer, and catch basin specifications). To the extent practical, wells were sampled from lowest to highest historical VOC concentrations. QA/QC samples included field duplicates, rinse blanks, and trip blanks, and were collected at the recommended rates stated in the SMP.

In accordance with the SMP, standard low-flow sampling procedures were followed. Each well was purged using a peristaltic pump with dedicated/disposable polyethylene tubing. During purging, field parameters (pH, dissolved oxygen, oxidation reduction potential, specific conductance, turbidity, and temperature) were measured and recorded. Refer to **Appendix A** for final readings prior to sample collection from each well. Purging continued until field parameters had stabilized, and between three

and five well volumes had been purged. After purging was complete, groundwater samples were collected from the wells, with VOC samples being collected first.

Grab samples were collected from the catch basin and temporary piezometers screened in the storm sewer pipe bedding. In some instances, field parameters were collected during sampling of these features; data are included in **Appendix A**.

A discussion of the groundwater analytical results for the four quarterly sampling events as well as a detailed discussion of the most recent quarterly event (April 2018) is presented below.

3.1.1 Quarterly Groundwater Sampling

AECOM collected comprehensive rounds of groundwater samples in July 2017, October 2017, January 2018, and April 2018 in accordance with the procedures outlined in the SMP. Twenty monitoring wells were sampled using low flow methods, including 13 shallow overburden wells, six deep overburden wells, and one well screened through both shallow and deep overburden units. In addition, grab samples were collected from one on-Site stormwater catch basin and two temporary piezometers screened in the storm sewer pipe bedding. VOC samples were collected from all locations; TOC samples were collected from each shallow and deep overburden monitoring well; and MNA samples were collected from three shallow and three deep overburden wells. Groundwater analysis for VOC, TOC, and MNA was performed by TestAmerica, Inc. located in Amherst, New York. Microbial analysis was performed by Microbial Insights, Inc. located in Knoxville, Tennessee.

3.2 April 2018 Groundwater Elevation and Flow Direction

In addition to groundwater elevation data recorded from the 20 wells sampled each quarter, a comprehensive round of groundwater levels was measured from all Site wells and piezometers during the April 2018 sampling event. **Table 3** provides a summary of groundwater elevations measured on April 9, 2018.

Two groundwater surface contour maps for April 2018 are provided; shallow overburden groundwater surface contours are presented in **Figure 10**, and deep overburden groundwater surface contours are presented in **Figure 11**; note that the groundwater elevation from MW-30 was not included in the groundwater surface contour figures as the well is screened through both shallow and deep groundwater overburden units. Groundwater elevations measured in April 2018 from the shallow overburden ranged from 688.61 ft above mean sea level (AMSL) at A1-GP14-S to 685.39 ft AMSL at A1-GP15-S. Groundwater elevations measured April 2018 from the deep overburden ranged from 681.86 ft AMSL at MW-35D to 686.51 ft AMSL at MW-40D. Based on these water level measurements, the groundwater beneath the Site indicates a northwest flow direction. This flow direction is most pronounced in the deep overburden, as the shallow overburden groundwater is influenced by Site features as described in Section 2.2.2.

3.3 April 2018 Groundwater Analytical Data

The April 2018 groundwater sampling event was the tenth comprehensive sampling event conducted at the Site since completion of the groundwater injection IRM in March 2015. VOCs detected in groundwater during the April 2018 sampling event are presented in **Table 4** and are compared to the Site RAOs or groundwater criteria presented in TOGS 1.1.1. The following table summarizes the VOCs detected, their respective concentration ranges, the number of detections, and the number of those detections that exceeded Site-specific groundwater RAOs or groundwater criteria presented in NYCRR.

Groundwater Contaminants of Concern Summary of Results
April 2018

VOCs Detected in Groundwater	Concentration Range (µg/L)	Number of Detections	RAO/NYCRR Exceedances
Chloroethane	14 – 9,400	6	6
Vinyl chloride*	0.95 – 4,200	5	4
1,1-Dichloroethane*	0.75 – 3,900	5	4
1,1,1-Trichloroethane*	20 - 390	4	4
cis-1,2-Dichloroethene	1.2 – 1,100	4	3
1,1,2-Trichloro-1,2,2-trifluoroethane	55 -740	3	3
1,1-Dichloroethene*	6.8 - 120	3	3
Xylenes, total	3.0 - 44	3	2
Toluene	2.2 - 670	2	1
Ethylbenzene	3.1 – 49	2	1
Methylene Chloride	3.1 – 9.4	2	1
1,2-Dichloroethane*	14	1	1
Trichloroethene*	7.2	1	1
2-Hexanone	2.7	1	0

Note: VOCs in the table above followed by an asterisk (*) are Site COCs.

A total of 14 VOCs were detected in groundwater from the monitoring wells (not including one on-Site stormwater catch basin and two temporary piezometers screened in the storm sewer pipe bedding) during the April 2018 sampling event. Thirteen of the 14 VOCs detected exceeded either the Site-specific RAOs or the NYCRR criteria for groundwater at one or more wells. Only five of the eight COCs were detected; all of which reflected a marked decrease in concentration of the parent VOCs (1,1,1-TCA, PCE, and TCE) following the IRMs. **Figures 12** through **19** illustrate April 2018 contours for individual COCs which were detected in shallow and/or deep overburden groundwater. **Figures 20** and **21** illustrate April 2018 contours for TVOCs in shallow and deep overburden groundwater respectively.

The highest concentrations of VOCs in shallow overburden groundwater were detected at A1-GP-10 and MW-42S. The highest concentrations of VOCs in deep overburden groundwater were detected at MW-40D. Chloroethane, 1,1-DCA, VC and cis-1,2-DCE exhibited the highest overall concentrations in groundwater, all of which are degradation products of 1,1,1-TCA, PCE, and/or TCE.

3.4 April 2018 Storm Sewer Catch Basin and Storm Sewer Pipe Bedding Analytical Data

VOC data collected from the on-Site catch basin CB-1 exhibited 10 compounds, with all parent VOCs (1,1,1-TCA, PCE, and TCE) showing a decrease in concentration following the IRMs. Five of the eight COCs were detected.

VOC data collected from the two temporary piezometers screened in the storm sewer pipe bedding (TP-05 and TP-06) were below the detection limits for RAO's, with the exception of one detection of 1,1,1-TCA and TCE at TP-05. These detections (4.0 µg/L and 1.2 µg/L, respectively) were below the RAO of 5 µg/L, and below historical concentrations of this compound at that location.

Attached **Figure 3** shows the locations of the catch basin and temporary piezometers. Analytical data are summarized in **Appendix A**.

3.5 Comparison of April 2018 COCs in Groundwater with Pre-IRM Groundwater Analytical Data

Trend plots illustrating concentrations of COCs (1,1,1-TCA, 1,1,2-TCA, 1,1-DCA, 1,1-DCE, 1,2-DCA, PCE, TCE, and VC) over time are provided in **Appendix B**. Because concentrations of TCE were historically the highest of the COCs detected at the Site, a discussion of historical and current TCE concentrations in groundwater at Site monitoring wells and piezometers is provided below.

In April 2018, TCE was detected at one well (A1-GP06-S) at 7.2 ug/l, down from 330 ug/L in January 2016. TCE was detected at the on-Site catch basin (CB-1) at 11 µg/L and at temporary piezometer TP-5 at 1.2 µg/L. Based on the substantial decrease in concentration of TCE at locations with historical detections of TCE, the injection of ABC+® appears to continually degrade TCE. This is most clearly demonstrated on the trend plots in **Appendix B** for monitoring wells A1-GP02-S (5,000 ug/L to almost zero), MW-42S (12,000 ug/L to almost zero), and MW-38D (11,000 ug/L to almost zero).

3.6 Groundwater MNA Data Summary

The use of the ERD amendment ABC+ was designed to provide needed nutrients, such as a soluble lactic acid carbon source, a phosphate buffer to control pH for optimum microbial growth, and zero valent iron which accelerates abiotic dechlorination of chlorinated ethenes and ethanes. The microbial analysis from "Bio-traps" placed on-Site indicated that the necessary concentrations microflora, such as DHC species producing the enzymes tceA reductase and vinyl chloride reductase, remain present in the subsurface. Stimulation of the bacteria by the presence of chlorinated solvents, combined with the extra nutrients supplied by injection, have dramatically reduced the concentrations of original parent CVOCs TCE and 1,1,1-TCA over time. The initial concentrations of known TCA degradation products (1,1-DCA and chloroethane), as well as of PCE/TCE degradation products (1,2-DCE isomers and VC), suggest that advanced decomposition of the chlorinated solvents has already enhanced microbial populations which would use CVOCs as substrates. Induction of reducing conditions can accelerate the reductive dechlorination of parent solvents and increase the relative accumulation of degradation intermediates such as VC before complete mineralization. As more aerobic conditions return after treatment, then VC oxidizing bacteria should increase and complete the dechlorination to ethene and co-metabolic oxidation followed by complete mineralization. In the event that continued monitoring indicates this process has plateaued, then additional amendments or subsurface microbial characterization could be performed to attempt to further enhance degradation (refer to Section 5.2 - Recommendations).

3.7 Dechlorinating Bacteria Analysis

Following the injection of ABC+®, AECOM deployed "Bio-traps" in both the shallow and deep overburden groundwater wells to monitor the concentration (i.e., cells/bead) of dechlorinating bacteria. The "Bio-traps" were submitted to Microbial Insights, Inc., in Knoxville, Tennessee for analysis. Per the April 2018 analysis, the shallow overburden groundwater shows a general increase of DHC, tceA Reductase, BAV1 VC Reductase, and VC Reductase bacteria, with concentration levels indicating that reductive dechlorination will yield a generally useful biodegradation rate (Lu et al., 2006). Deep overburden groundwater shows a general decrease of DHC, tceA Reductase, BAV1 VC Reductase, and VC Reductase bacteria, with concentration levels of vinyl chloride reductase genes indicating that reductive dechlorination may still occur while DHC populations indicate that other Site-specific data

should be evaluated to determine whether subsurface conditions may be limiting reductive dechlorination (Lu et al., 2006). Refer to the tables below and **Appendix A** for microflora data.

Shallow Overburden Dechlorinating Bacteria Data

Sample ID	MW-42S	MW-43S	MW-42S	MW-42S
Sample Date	7/27/15	7/12/16	4/12/17	4/12/18
Dechlorinating Bacteria (Cells/bead)				
DHC	$<2.50x10^{1}$	$1.77x10^{2}$	$3.98x10^{4}$	$4.04x10^{4}$
tceA Reductase	$<2.50x10^{1}$	$1.58x10^{1}$	$1.28x10^{4}$	$4.92x10^{4}$
BAV1 VC Reductase	$<2.50x10^{1}$	$<2.50x10^{1}$	$<2.50x10^{1}$	$3.3x10^{1}$
VC Reductase	$<2.50x10^{1}$	$<2.50x10^{1}$	$1.04x10^{3}$	$3.56x10^{3}$

Deep Overburden Dechlorinating Bacteria Data

Sample ID	MW-38D	MW-38D	MW-38D	MW-38D
Sample Date	7/27/15	7/12/16	4/12/17	4/12/18
Dechlorinating Bacteria (Cells/bead)				
DHC	$8.41x10^{2}$	$4.00x10^{4}$	$2.52x10^{4}$	$1.81x10^{2}$
tceA Reductase	$<2.50x10^{1}$	$1.78x10^{2}$	$7.24x10^{2}$	$6.36x10^{1}$
BAV1 VC Reductase	$1.20x10^{2}$	$2.22x10^{4}$	$2.20x10^{2}$	$1.25x10^{1}$
VC Reductase	$1.47x10^{1}$	$6.96x10^{2}$	$9.12x10^{2}$	$5.16x10^{1}$

3.8 Dechlorinating Chemical Analysis

In addition to the dechlorinating bacteria results, the presence and distribution of TCE degradation products (cis-1,2-DCE and VC) and 1,1,1-TCA degradation products (1,1-DCA and chloroethane) provide supportive evidence that the attenuation of TCE and 1,1,1-TCA and their degradation products, via reductive dechlorination, continues to occur in-situ at the Site. The occurrence and concentrations of these degradation products are directly related to the historic distribution of TCE and 1,1,1-TCA in the subsurface. A limited number of other VOCs were sporadically detected in groundwater at the Site, with the majority of these detections in groundwater located at wells A1-GP02-S, A1-GP06-S, A1-GP10-S, MW-42S, and MW-40D; refer to **Table 4**.

3.9 Total Organic Carbon

Samples were collected for TOC analysis to monitor the concentration of available carbon sources for the optimum microbial growth. Although TOC concentrations are decreasing over time in the areas targeted for injection (refer to **Figure 9**), locations with the highest concentrations of COCs (A1-GP02-S, A1-GP06-S, A1-GP10-S, MW-42S, and MW-40D) still have TOC concentrations above pre-injection levels. Refer to **Appendix A** for a summary of TOC concentrations and **Figure 22** and **Figure 23** for April 2018 TOC concentration contours in the shallow and deep overburden groundwater, respectively.

4.0 Site Inspection

This section describes quarterly Site inspections, O&M tasks completed, and recommendations for improvements.

4.1 Boiler Room

On November 4, 2014, AECOM and NYSDEC inspected the concrete floor of the boiler room and AECOM sealed visible floor cracks with concrete caulking. In addition, the annulus between a drain line effluent and the associated floor penetration foundation perforations was sealed with expanding foam. Two other foundation perforations (drains) were observed and temporarily plugged with modelling clay just prior to a sampling event, as the floor drains appeared to discharge to the bedding gravel beneath the concrete floor slab. The sealing of floor cracks and foundation perforations has decreased the concentrations in the indoor air samples and lowered the regulatory action level from 'mitigation' to 'monitoring' (AECOM, January 2015).

The improvements established in the boiler room (which is normally not occupied) as a result of the corrective actions completed to address soil vapor intrusion concerns consist of caulking in the boiler room floor and the seal around the annulus of a drain pipe in the boiler room. These improvements were inspected quarterly during groundwater sampling events. During the week of November 20, 2017, AECOM and subcontractor Matrix Environmental Technologies, Inc. (METI) performed preventive maintenance in the boiler room that consisted of removing and replacing all floor crack caulking and drain pipe annulus seals, and resealing all visible floor cracks and foundation perforations. Note, as stated in the SMP, if the boiler room becomes occupied or its usage changes, additional treatment and/or control measures will be evaluated.

4.2 Monitoring Wells

In Section 5.2 of the 2017 PRR, AECOM proposed to decommission 17 of the 36 monitoring wells and piezometers; i.e., wells that are not sampled quarterly as part of the SMP. On August 4, 2017 NYSDEC approved the decommissioning of 14 wells and piezometers; NYSDEC required that A1-GP09-S, A1-GP14-S and A1-GP16-S remain and be added to the quarterly groundwater sampling program.

During the week of October 23, 2017, AECOM and subcontractor METI decommissioned 14 wells in accordance with NYSDEC's November 3, 2009 Groundwater Monitoring Well Decommissioning Policy; refer to **Appendix C** for well decommissioning records. In addition, five wells were refurbished (i.e., repair of flush mount road boxes and concrete pads).

5.0 Conclusions and Recommendations

Based on results of the groundwater analytical data collected during the reporting period, conclusions, upcoming Site-related activities, and a proposed monitoring and reporting schedule are presented below.

5.1 Conclusions

1. Groundwater elevations measured in April 2018 from the shallow overburden ranged from 685.39 ft AMSL at A1-GP15-S to 688.61 ft AMSL at A1-GP14-S. Groundwater elevations measured April 2018 from the deep overburden ranged from 681.86 ft AMSL at MW-35D to 686.51 ft AMSL at MW-40D. Based on these water level measurements, the groundwater beneath the Site exhibits a northwest flow direction. This flow direction is most pronounced in the deep overburden, as the shallow overburden groundwater is influenced by Site features (e.g., storm sewer and utility systems).
2. The groundwater analytical data indicate that the IRMs were, and continue to be, successful in the attenuation of CVOCs.
3. The groundwater microbial analyses indicate that the necessary microflora, such as DHC, tceA reductase, BAV1 VC Reductase, and VC Reductase bacteria, are present in the shallow overburden at sufficient concentrations, whereas the deep overburden groundwater shows a general decrease of microflora.
4. VOC data collected from on-Site catch basin CB-1 in April 2018 exhibited a general decreasing trend in concentration of COCs following the IRMs, with the exception of VC which increased slightly.
5. Concentrations of VOCs in samples collected in April 2018 from the temporary piezometers screened in the storm sewer bedding were below the RAOs for COCs.
6. Periodic monitoring data demonstrate that TOC concentrations in the areas targeted for injections remain above pre-injection levels, maintaining conditions for microbial growth.
7. The boiler room floor crack caulking and drain pipe annulus seals (i.e., sub-slab mitigation controls) were replaced during the reporting period as a preventative measure.
8. With approval from NYSDEC, 14 wells were decommissioned and five wells were refurbished (i.e., repair of flush mount road boxes and concrete pads).

5.2 Recommendations

Based on information gathered during the current reporting period, the following recommendations are proposed for the Site:

1. Continue quarterly inspections of the boiler room sub-slab mitigation controls.
2. Continue quarterly inspections of the monitoring well network.
3. Perform four quarterly groundwater sampling events during the next reporting period.

4. Evaluate if additional targeted injections (at approximately 12 locations) would be beneficial, targeting localized areas adjacent to monitoring wells A1-GP02-S, A1-GP06-S, A1-GP10-S, MW-42S, and MW-40D.
5. Review and update the Site health and safety plan as needed.

5.3 Proposed Monitoring and Compliance Sampling Schedule

The proposed schedule for groundwater sampling at the Site during the next reporting period includes quarterly sampling of 20 wells, the on-Site catch basin, and two temporary piezometers screened in the storm sewer pipe bedding; refer to **Table 1** for a list of locations to be sampled and associated analyses.

It is anticipated that the next PRR will be prepared following receipt of laboratory analytical results for the April 2019 comprehensive groundwater sampling event, and will include the results from groundwater sampling events scheduled for July 2018, October 2018, January 2019, and April 2019.

6.0 Evaluate Remedy Performance, Effectiveness, and Protectiveness

6.1 Institutional Controls and Engineering Controls Certification

As a component of the PRR requirement, included in **Appendix D** is the completed IC/EC certification form.

Institutional controls include:

1. Groundwater Use Restrictions
2. Land Use Restrictions
3. Site Management Plan
4. Soils Monitoring Plan
5. Groundwater Monitoring Plan
6. IC/EC Plan

Engineering controls include:

1. None listed.

7.0 References

AECOM. August 2017. “Work Plan to Decommission Monitoring Wells and Piezometers”, Former Scott Aviation Facility Area 1 BCP Site, Lancaster, New York, Erie County.

AECOM. June 2017. “Periodic Review Report (December 29, 2015 through April 12, 2017)”, Former Scott Aviation Facility Area 1 BCP Site, Lancaster, New York, Erie County.

NYSDEC. December 2015. “Decision Document”, Former Scott Aviation Facility (Area 1) Brownfield Cleanup Program, Lancaster, Erie County, Site No. C915233.

AECOM. December 2015. “Site Management Plan”, Former Scott Aviation Facility Area 1 BCP Site, Lancaster, New York, Erie County.

AECOM. December 2015. “Final Alternatives Analysis Report - Former Scott Aviation Facility Area 1 BCP Site, NYSDEC Site Code No. C915233, Lancaster, New York”.

AECOM. March 2015. “2015 Interim Remedial Measures Construction Completion Report - Former Scott Aviation Facility Area 1 BCP Site, NYSDEC Site Code No. C915233, Lancaster, New York”.

AECOM. January 2015. “Sub-Slab Vapor Evaluation - Former Scott Aviation Facility Area 1 BCP Site, NYSDEC Site Code No. C915233, Lancaster, New York”.

AECOM. October 2014. “MIP/HPT and Baseline Sampling Work Plan – Former Scott Aviation Facility Area 1 BCP Site No. C915233, Lancaster, New York”.

AECOM, June 2014. “2014 Interim Remedial Measures Remedial Action Work Plan, Former Scott Aviation Facility Area 1, Lancaster New York”.

AECOM. March 2015. “2014 Interim Remedial Measures Construction Completion Report - Former Scott Aviation Facility Area 1 BCP Site, NYSDEC Site Code No. C915233, Lancaster, New York”.

AECOM. October 2013. “Soil Vapor Intrusion Evaluation: Supplemental Soil and Groundwater Data Report - Former Scott Aviation Facility Area 1 BCP Site, NYSDEC Site Code No. C915233, Lancaster, New York”.

AECOM. August 2013. “Soil Vapor Intrusion Evaluation - Former Scott Aviation Facility Area 1 BCP Site, NYSDEC Site Code No. C915233, Lancaster, New York”.

AECOM. April 2013. “Draft Alternatives Analysis Report - Former Scott Aviation Facility Area 1 BCP Site, NYSDEC Site Code No. C915233, Lancaster, New York”.

AECOM. April 2012. “Supplemental Remedial Investigation Report - Former Scott Aviation Facility Area 1 BCP Site, NYSDEC Site Code No. C915233, Lancaster, New York”.

AECOM. September 2011. “Remedial Investigation Report - Former Scott Aviation Facility Area 1 BCP Site, NYSDEC Site Code No. C915233, Lancaster, New York”.

AECOM. May 2010. “Addendum to the Remedial Investigation / Alternatives Analysis Work Plan - Former Scott Aviation Facility Area 1 BCP Site, NYSDEC Site Code No. C915233, Lancaster, New York”.

AECOM. February 2010. “Remedial Investigation / Alternatives Analysis Work Plan - Former Scott Aviation Facility Area 1 BCP Site, NYSDEC Site Code No. C915233, Lancaster, New York”.

Earth Tech. January 2008. “Preliminary Groundwater Assessment Report”, Former Scott Aviation Facility, Lancaster, New York.

Earth Tech. June 2004. “Phase II Environmental Site Investigation”, Tyco/Scott Aviation Facility, Lancaster, New York.

NYSDEC. May 2010. Program Policy DER-10, Technical Guidance for Site Investigation and Remediation.

NYDEC. November 2009. “CP-43: Groundwater Monitoring Well Decommissioning Policy.”

NYSDEC. December 2006. Rules and Regulations, NYCRR Part 375 Environmental Remediation Programs.

NYDEC. May 2004. “Draft Brownfield Cleanup Program Guide.”

Earth Tech. April 2004. “Phase I Environmental Site Assessment and Modified Compliance Assessment”, Tyco/Scott Aviation Facility, Lancaster, New York.

NYSDEC, 1998. Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations Division of Water Technical and Operational Guidance Series (TOGS) 1.1.1. June 1998 (June 2004 addendum).

NYSDEC, 1998. Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations Division of Water Technical and Operational Guidance Series (TOGS) 1.1.1. June 1998 (April 2000 addendum).

NYSDEC, 1998. Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations Division of Water Technical and Operational Guidance Series (TOGS) 1.1.1. June 1998 (January 1999 addendum).

NYSDEC, 1998. Ambient Water Quality Standards and Guidance Values and Groundwater Effluent Limitations Division of Water Technical and Operational Guidance Series (TOGS) 1.1.1. June 1998 (April 2000 addendum).

Figures



SOURCE:
1982 U.S. GEOLOGIC SURVEY 7.5 X 15 MINUTE TOPOGRAPHIC QUADRANGLE
LANCASTER, NEW YORK

LEGEND

AVOX PLANT 3 ADDED AFTER PUBLICATION OF LANCASTER, NEW YORK TOPOGRAPHIC QUADRANGLE.

0 1000 2000
SCALE IN FEET

AECOM

FIGURE 1
SITE LOCATION MAP

FORMER SCOTT AVIATION FACILITY
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_063 Site Loc Map.dwg, 2/5/2015 11:06:33 AM, Splawnm



AECOM

FIGURE 2
SITE LAYOUT MAP

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK



Location ID	Investigative Phase	Date Completed	Screen Interval (ft bgs)
MW-30	ESI Phase II	7/7/2005	10 - 20
A1-GP01S	PGA Phase I	2/27/2006	5 - 15
A1-GP02S		2/27/2006	5 - 15
A1-GP03S		2/27/2006	5 - 15
A1-GP04S		2/27/2006	5 - 15
A1-GP05S		2/27/2006	5 - 15
A1-GP06S		2/27/2006	5 - 15
A1-GP07S	PGA Phase II	5/16/2006	5 - 15
A1-GP08S		5/16/2006	5 - 15
A1-GP09S		5/16/2006	5 - 15
A1-GP10S		5/16/2006	5 - 15
A1-GP11S		5/15/2006	5 - 15
A1-GP12S[1]		5/16/2006	5 - 15
A1-GP13S	PGA Phase III	5/22/2007	5 - 15
A1-GP14S		5/22/2007	5 - 15
A1-GP15S		5/23/2007	5 - 15
A1-GP16S		5/23/2007	5 - 15
A1-GP17S		5/23/2007	5 - 15
A1-GP18S		5/24/2007	5 - 15
A1-GP12S[2]	RI	5/27/2010	5 - 15
MW-35S		5/26/2010	5 - 15
MW-35D		5/26/2010	21 - 26
MW-36S		6/4/2010	5 - 15
MW-36D		6/4/2010	16 - 21
MW-37S		5/28/2010	4.5 - 14.5
MW-37D		5/28/2010	15 - 20
MW-38D		6/3/2010	16 - 21
MW-39D		6/3/2010	15 - 20
MW-40D		6/2/2010	17.8 - 22.8
MW-40B		6/1/2010	24.8 - 34.8
TP-1		6/24/2010	2.9 - 5.4
TP-2		6/24/2010	1.5 - 4
TP-3		6/24/2010	1.4 - 3.9
TP-4		6/24/2010	1 - 3.5
MW-42S	SRI	3/28/2011	5 - 15
MW-43S		3/28/2011	5 - 15
MW-44S		5/19/2011	6 - 15
TP-5		5/19/2011	1 - 6
TP-6	2015 IRM	4/13/2015	4 - 9

Notes:
1. This well was damaged and subsequently replaced during the RI field activities.
2. This well is a replacement well for the well with the same identification that was installed during Phase II of the PGA.

ft bgs - feet below ground surface
ESI - Environmental Site Investigation
PGA - Preliminary Groundwater Assessment
RI - Remedial Investigation
SRI - Supplimental Remedial Investigation

AECOM

FIGURE 3
MONITORING WELL, PIEZOMETER AND CATCH BASIN LOCATIONS

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_166 MW PZ and CB Locs_May2018.dwg, 5/15/2018 1:09:34 PM, Splawnm

A
NORTH

A'
SOUTH

137.67'

45.88'

37.47'

MW-35D
EL. 688.9'

MW-38D
EL. 687.5'

MW-39D
EL. 687.4'

MW-37D
EL. 687.6'

FILL

SILT

CLAY

SILTY CLAY

SILT AND GRAVEL

0-6" TOPSOIL, brown (moist/dry)
6-9" tan SILT, trace f.sand (dry/moist)
9-20" reddish brown CLAY, trace silt, stiff (moist/dry)
0-15" reddish brown CLAY, trace silt, stiff (moist/dry)
0-20" reddish brown SILTY CLAY with 1mm silt layer (moist)
0-7" reddish brown SILTY CLAY, little SILT, (wet)
7-20" reddish brown CLAYEY SILT, thin silt layers interbedded (dry/moist)
0-24" reddish brown SILTY CLAY, mottled slightly (moist)
0-6" reddish brown SILTY CLAY, trace gravel
6-24" dark reddish/purple brown CLAY, trace silty clay, (moist) *color change
0-24" dark purple brown CLAY, (moist)
0-23" dark purple/brown CLAY, trace silty, trace gravel, slightly mottled, (moist)
0-24" dark purple-reddish brown CLAY, some silty layers, trace gravel, (moist)
0-24" purple/reddish brown CLAY trace silt, trace gravel, (moist)
0-24" purple/reddish brown CLAY trace silt, trace gravel, (moist), soft
0-20" reddish brown CLAY, little silty, trace gravel (moist-wet)
0-2" reddish brown CLAY, little silt, little gravel, (moist)
2-6" medium gray f-c SAND, some gravel, trace silt, (moist-wet), shale fragments in shoe

0-7" brown thick TOPSOIL (moist)
7-7" reddish brown SILT, little organics, trace clay, (moist)
0-22" reddish brown-tan-grey mottled SILT, little clay, trace f-m gravel (dry-moist)
0-24" reddish brown, tan-grey-olive mottled SILT, little clay (moist), wet silt layers 1" @24" (45ppm)
0-10" olive grey SILT (wet) (45ppm)
10-24" reddish brown - olive mottled SILT, trace clay, trace f. gravel (moist) PID - 0-243, 243@7" bgs
0-9" reddish brown-olive mottled SILT, little clay (moist) max PID = 45.2ppm
9-10" tan-grey f. sand, trace silt (wet), 110 ppm
10-24" reddish brown - purple SILT, some clay, trace gravel (moist-plastic), PID = 45 to 5ppm @ 24"
0-14" reddish brown-purple CLAY, trace silt, trace f-m gravel (moist) plastic
0-24" reddish brown-purple CLAY, trace silt, trace f-m gravel (moist), 4.5ppm @ 6" in silt
layer - 0 in remainder of sample
refusal - rock in shoe - auger to 16"
0-24" reddish brown-purple CLAY, trace silt, trace gravel (moist), 3.4ppm @ 17" in thin silt
layer (grey, moist) 0.0ppm in rest of core
0-10" reddish brown purple SILT and CLAY, little f-m gravel (moist)
10-15" dark grey SILT and rock chips (wet)
0-4" dark grey SILT and granite chips (moist)
refusal

0-7" dark brown TOPSOIL, moist
7-10" brown topsoil grading to CLAYEY SILT (moist)
10-12" reddish brown mottled with brown CLAYEY SiLT (moist)
0-24" reddish brown SILTY, little clay thin grey silt interbeds increases to bottom (moist)
0-24" reddish brown SILTY CLAY (moist) - more wet @ bottom, (18-20" grey
SiLT layer (moist-wet)) collect samples @ 5-6"
0-6" reddish brown - tan SILT, some clay (wet)
0-1.1 PID
6-12" reddish brown-tan mottled SILT, some clay, grey silt think interbeds (moist)
0-18" reddish brown CLAY, little silt, trace gravel (moist)
18-24" reddish brown to purple CLAY, some silt (grey interbeds), trace gravel (moist)
24-grey SILT (wet)
8-24" reddish brown, slightly purple CLAY, little silt, trace gravel (moist)
0-24" reddish brown to purple CLAY, little trace silt, trace gravel (moist), plastic
0-24" reddish brown - slightly purple CLAY, little grey silt interbeds (moist)
0-20" reddish brown-purple SILT and CLAY, trace grey silt layers (moist)
20-24" grey SILT and f-c GRAVEL, little f.sand (wet-moist)
bouncing spoon - shale

0-7" TOPSOIL
7-21" tan with reddish brown mottling, SILT, little clay, (moist)
0-19" reddish brown with grey/tan mottling, SILT, little clay, (dry-moist)
0-18" reddish brown with tan mottling, SILT and CLAY, (moist)
0-14" reddish brown with tan mottling SILT and CLAY, (moist)
14-16" tan SILT, trace clay, (wet)
16-21" reddish brown with tan mottling CLAY, some silt, thin grey silt layers,
(moist) sample 6-7"
0-24" reddish brown SILT, little clay light grey silt layers interbedded, (dry-moist)
0-24" reddish brown CLAY, little silt, trace f.gravel, (moist)
0-24" purple-reddish brown CLAY, trace silt, trace f.gravel, (moist), very plastic
0-24" purple-reddish brown with grey sile/f.sand layer, CLAY, trace silt, (moist)
0-24" reddish brown CLAY and SILT, f.sand and silt layers interbedded increasing to bottom - color change to grey to bottom, moist - wetter to bottom
0-22" medium grey CLAY and SILT (very moist), soft, trace f-c sand and gravel
22-24" medium grey f-c sand, trace silt, little rock chips (dry)

TD = 26'
TD = 21'
TD = 20'
TD = 20'

690
688
686
684
682
680
678
676
674
672
670
668
666
664
662

GROUND SURFACE ELEVATION (ft. AMSL)

LEGEND:

- FILL
- SILT
- CLAY
- SILTY CLAY
- SILT AND GRAVEL

TD = TOTAL DEPTH

GROUNDWATER ELEVATION (ft AMSL)

HORIZONTAL SCALE
0 10 20 40
SCALE IN FEET

VERTICAL SCALE
4x EXAGGERATION
0 2.5 5 10
SCALE IN FEET

AECOM
10 Patewood Drive, Building 6, Suite 500
Greenville, SC 29615
T: (864) 234-3000 F: (864) 234-3069
www.aecom.com

FIGURE 4
GEOLOGIC CROSS-SECTION

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK



AECOM

FIGURE 5
PRE-INJECTION SHALLOW OVERBURDEN GROUNDWATER TOTAL VOC CONTAMINANT PLUME

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60155991_130 Total VOC Contaminant Plume_Aug2010.dwg, 6/6/2017 11:53:39 AM, Splawnm



AECOM

FIGURE 6
PRE-INJECTION DEEP OVERBURDEN GROUNDWATER TOTAL VOC CONTAMINANT PLUME

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60155991_132 Total VOC Contaminant Plume_Deep Overburden GW Data_Aug2010.dwg, 6/6/2017 11:52:21 AM, Splawnm



AECOM

FIGURE 7
PRE-INJECTION SHALLOW OVERBURDEN GROUNDWATER TCE CONTAMINANT PLUME

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60155991_131 TCE Contaminant Plume_Aug2010.dwg, 6/6/2017 11:53:09 AM, Splawnm



AECOM

FIGURE 8
PRE-INJECTION DEEP OVERBURDEN GROUNDWATER TCE CONTAMINANT PLUME

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60155991_140 Pre-Injection Deep Overburden GW TCE Plume.dwg, 6/6/2017 11:54:02 AM, Splawnm



AECOM
10 Patewood Drive, Building 6, Suite 500
Greenville, SC 29615
T: (864) 234-3000 F: (864) 234-3069
www.aecom.com

FIGURE 9
INJECTION ZONE DETAILS

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK



AECOM

FIGURE 10
SHALLOW OVERBURDEN GROUNDWATER SURFACE ELEVATION CONTOURS APRIL 9, 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_167 Shallow Overburden GW Surface Conts_Apr2018.dwg, 5/14/2018 3:17:07 PM, Splawnm



AECOM

FIGURE 11
DEEP OVERBURDEN GROUNDWATER SURFACE ELEVATION CONTOURS APRIL 9, 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_168 Deep Overburden GW Surface Conts_April2018.dwg, 5/11/2018 2:28:07 PM, Splawnm



AECOM

FIGURE 12
POST-INJECTION SHALLOW OVERBURDEN MONITORING 1,1,1-TRICHLOROETHANE PLUME APRIL 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_169 1,1,1-TCA_Shallow Overburden Post-Inj Performance MW Locs_Apr2018.dwg, 5/14/2018 3:23:59 PM, Splawnm



AECOM

FIGURE 13
POST-INJECTION DEEP OVERBURDEN MONITORING 1,1,1-TRICHLOROETHANE PLUME APRIL 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK



AECOM

FIGURE 14
POST-INJECTION SHALLOW OVERBURDEN MONITORING 1,1-DICHLOROETHANE PLUME APRIL 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_171 1,1-DCA_Shallow Overburden Post-Inj Performance MW Locs_Apr2018.dwg, 5/21/2018 11:41:53 AM, Splawnm



AECOM

FIGURE 15
POST-INJECTION DEEP OVERBURDEN MONITORING 1,1-DICHLOROETHANE PLUME APRIL 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_172 1,1-DCA_Deep Overburden Post-Inj Performance MW Locs_Apr2018.dwg, 5/14/2018 12:56:56 PM, Splawnm



AECOM

FIGURE 16
POST-INJECTION SHALLOW OVERBURDEN MONITORING 1,1-DICHLOROETHENE PLUME APRIL 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_173 1,1-DCE_Shallow Overburden Post-Inj Performance MW Locs_Apr2018.dwg, 5/14/2018 3:28:32 PM, Splawnm



AECOM

FIGURE 17
POST-INJECTION SHALLOW OVERBURDEN MONITORING 1,2-DICHLOROETHANE PLUME APRIL 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK



AECOM

FIGURE 18
POST-INJECTION SHALLOW OVERBURDEN MONITORING VINYL CHLORIDE PLUME APRIL 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_176 VC_Shallow Overburden Post-Inj Performance MW Locs_Apr2018.dwg, 5/21/2018 1:10:17 PM, Splawnm



AECOM

FIGURE 19
POST-INJECTION SHALLOW OVERBURDEN MONITORING TOTAL VOCs PLUME APRIL 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_177 Total VOCs_Shallow Overburden Post-Inj Performance MW Locs_Apr2018.dwg, 5/21/2018 1:15:33 PM, Splawnm



AECOM

FIGURE 20
POST-INJECTION DEEP OVERBURDEN MONITORING TOTAL VOCs PLUME APRIL 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_178 Total VOCs_Deep Overburden Post-Inj Performance MW Locs_Apr2018.dwg, 5/21/2018 1:20:50 PM, Splawnm



AECOM

FIGURE 21
POST-INJECTION SHALLOW OVERBURDEN MONITORING TOTAL ORGANIC CARBON APRIL 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK



AECOM

FIGURE 22
POST-INJECTION DEEP OVERBURDEN MONITORING TOTAL ORGANIC CARBON APRIL 2018

FORMER SCOTT AVIATION FACILITY AREA 1
LANCASTER, NEW YORK

L:\work\60147012\CADD\60147012_180 Total Organic Carbon_Deep Overburden Post-Inj Performance MW Locs_Apr2018.dwg, 5/14/2018 1:00:01 PM, Splawnm

Tables

Table 1
Groundwater Monitoring Program
Former Scott Aviation Facility Area 1 (BCP Site #C915233)
Lancaster, New York

Location	Field Parameters	VOCs (8260B)	TOC (9060)	Iron Ferrous and Ferric (SM 3500 FE D)	Iron Ferric (SM 3500)	Nitrogen Nitrate (MCAWW 353.2)	Nitrogen Nitrate-Nitrate (MCAWW 353.2)	Nitrate (EPA 353.2)	Sulfate Turbidimetric (9038)	Manganese (6010C)	Sulfate (300.0)	Sulfide Total (SM 4500 S2 D)	Alkalinity (MCAWW 310.2)	Iron (200.7 Rev 4.4)	Carbon Dioxide (RSK-175)	COD (MCAWW 410.4)	BOD (SM 5210B)	Phosphorus (SM 4500 P E)	Nitrogen Ammonia (MCAWW 350.1)	Methane Ethane, Ethene (RSK-175)
Monitoring Well and Temporary Piezometer Groundwater Sampling																				
MW-30	✓	✓	✓																	
MW-35S	✓	✓	✓																	
MW-35D	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
MW-36S	✓	✓	✓																	
MW-36D	✓	✓	✓																	
MW-37D	✓	✓	✓																	
MW-38D	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
MW-39D	✓	✓	✓																	
MW-40D	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
MW-42S	✓	✓	✓																	
MW-43S	✓	✓	✓																	
MW-44S	✓	✓	✓																	
A1-GP02-S	✓	✓	✓																	
A1-GP06-S	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
A1-GP09-S	✓	✓	✓																	
A1-GP10-S	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
A1-GP14-S	✓	✓	✓																	
A1-GP15-S	✓	✓	✓																	
A1-GP16-S	✓	✓	✓																	
A1-GP18-S	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓	✓
Storm Sewer Water Sampling																				
CB-1		✓																		
TP-5		✓																		
TP-6		✓																		

Notes:
QA/QC samples will also be collected per QAPP.
Field Parameters include pH, temperature, turbidity, oxidation-reduction potential (ORP), dissolved oxygen (DO), and specific conductivity.
VOC - Volatile Organic Compound
TOC - Total Organic Carbon
COD - Chemical Oxygen Demand
BOD - Biochemical Oxygen Demand

Table 2
Monitoring Well, Piezometer, and Catch Basin Specifications
Former Scott Aviation Facility Area 1 (BCP Site #C915233)
Lancaster, New York

Well ID	Well Location	Coordinates (longitude/latitude)	Well Diameter (inches)	Elevation (feet above mean sea level)			
				Casing	Surface	Screen Top	Screen Bottom
A1-GP02-S	Plume	42.9047° N, 78.6593° W	0.75	689.82	687.3	682.3	672.3
A1-GP03-S*	Plume	42.9046° N, 78.6592° W	0.75	690.70	688.8	683.8	673.8
A1-GP04-S*	Plume	42.9046° N, 78.6594° W	0.75	690.46	687.7	682.7	672.7
A1-GP05-S*	Plume	42.9046° N, 78.6593° W	0.75	690.38	687.6	682.6	672.6
A1-GP06-S	Plume	42.9047° N, 78.6592° W	0.75	687.71	687.8	682.8	672.8
A1-GP07-S*	Plume	42.9047° N, 78.6593° W	0.75	690.47	687.5	682.5	672.5
A1-GP08-S*	Plume	42.9047° N, 78.6594° W	0.75	689.68	686.5	681.5	671.5
A1-GP09-S	Downgradient	42.9045° N, 78.6594° W	0.75	689.36	686.8	681.8	671.8
A1-GP10-S	Plume	42.9045° N, 78.6591° W	0.75	689.10	689.2	684.2	674.2
A1-GP12-S*	Plume	42.9047° N, 78.6591° W	0.75	689.5	689.4	684.4	674.4
A1-GP13-S*	Plume	42.9045° N, 78.6589° W	0.75	689.69	689.8	684.8	674.8
A1-GP14-S	Downgradient	42.9049° N, 78.6591° W	0.75	689.43	689.7	684.7	674.7
A1-GP15-S	Downgradient	42.9049° N, 78.6595° W	0.75	687.69	688.0	683.0	673.0
A1-GP16-S	Downgradient	42.9046° N, 78.6596° W	0.75	689.86	686.6	681.6	671.6
A1-GP17-S*	Downgradient	42.9045° N, 78.6596° W	0.75	690.11	687.0	682.0	672.0
A1-GP18-S	Upgradient	42.9044° N, 78.6592° W	0.75	690.37	687.5	682.5	672.5
MW-30	Upgradient	42.9045° N, 78.6585° W	2	689.69	689.8	679.8	669.8
MW-35D	Downgradient	42.9050° N, 78.6594° W	2	688.40	688.9	667.9	662.9
MW-35S	Downgradient	42.9050° N, 78.6594° W	2	688.56	689.1	684.1	674.1
MW-36D	Plume	42.9046° N, 78.6595° W	2	689.66	687.1	671.1	666.1
MW-36S	Upgradient	42.9046° N, 78.6595° W	2	689.82	687.1	683.1	672.1
MW-37D	Upgradient	42.9044° N, 78.6593° W	2	690.05	687.6	672.6	667.6
MW-37S*	Plume	42.9044° N, 78.6593° W	2	690.10	687.4	682.9	672.9
MW-38D	Plume	42.9047° N, 78.6593° W	2	689.66	687.5	671.5	666.5
MW-39D	Plume	42.9045° N, 78.6593° W	2	689.72	687.4	672.4	667.4
MW-40D	Plume	42.9045° N, 78.6591° W	2	689.19	689.5	671.7	666.7
MW-41B*	Bedrock	42.9046° N, 78.6592° W	2	689.78	687.8	663.0	653.0
MW-42S	Plume	42.9045° N, 78.6588° W	2	689.08	689.7	684.7	674.7
MW-43S	Plume	42.9047° N, 78.6590° W	2	689.14	689.6	684.6	674.6
MW-44S	Upgradient	42.9043° N, 78.6588° W	2	688.98	689.4	684.4	674.4
CB-1	Catch Basin	42.9044° N, 78.6600° W	na	na	689.5	na	683.2(1)
TP-5	Stormsewer	42.9051° N, 78.6592° W	0.75	690.53	689.5	685.5	682.5
TP-6	Stormsewer	42.9051° N, 78.6592° W	0.75	690.25	690.5	686.5	681.5

(1) Bottom elevation of catch basin.

Table 3
Groundwater Elevation Data
Former Scott Aviation Facility Area 1 (BCP Site #C915233)
Lancaster, New York

Monitoring Point Identification	Top of Casing Elevation	April 9, 2018	
		Depth to Groundwater (feet from TOC)	Groundwater Elevation (feet AMSL)
Monitoring Wells			
MW-30[1]	689.69	3.11	686.58
MW-35S	688.56	0.00	688.56
MW-35D	688.40	6.54	681.86
MW-36S	689.82	2.81	687.01
MW-36D	689.66	5.21	684.45
MW-37D	690.05	4.28	685.77
MW-38D	689.66	4.21	685.45
MW-39D	689.72	3.89	685.83
MW-40D	689.19	2.68	686.51
MW-42S	689.08	2.52	686.56
MW-43S	689.13	1.84	687.29
MW-44S	688.96	0.88	688.08
Piezometers			
A1-GP02-S	689.82	3.45	686.37
A1-GP06-S	687.71	1.65	686.06
A1-GP09-S	689.36	2.45	686.91
A1-GP10-S	689.10	1.64	687.46
A1-GP14-S	689.43	0.82	688.61
A1-GP15-S	687.69	2.30	685.39
A1-GP16-S	689.86	3.79	686.07
A1-GP18-S	690.37	3.50	686.87
Storm Sewer			
TP-5	690.53	7.76	682.77
TP-6	690.25	7.48	682.77
CB-1	690.70	6.28	684.42

Notes:
1 - Well is screened across both shallow and deep overburden units.
TOC - Top of Casing
AMSL - Above Mean Sea Level
NA - Not Available
S - well is screened in shallow overburden
D - well is screened in deep overburden

Table 4

Summary of Monitoring Well Analytical Data - April 2018
Former Scott Aviation Facility
NYSDEC Site Code No. C915233
Lancaster, New York

Sample ID	Groundwater	CB-1	TP-5	TP-6	A1-GP02-S	A1-GP06-S	A1-GP09-S	A1-GP10-S	A1-GP14-S
Date Collected	RAO/NYCRR	04/09/18	04/09/18	04/09/18	04/12/18	04/10/18	04/12/18	04/10/18	04/10/18
Lab Sample ID	Objective	480-133949-1	480-133949-2	480-133949-3	480-133949-5	480-133949-14	480-133949-5	480-133949-15	480-133949-12
Volatile Organic Compounds by Method 8260 (µg/L)									
1,1-Dichloroethane*	5	**47**	< 1.0 U	< 1.0 U	< 20 U	**360**	< 4.0 U	**3,900**	< 1.0 U
1,1-Dichloroethene*	5	**13**	< 1.0 U	< 1.0 U	< 20 U	**6.8 J**	< 4.0 U	**19 J**	< 1.0 U
1,1,1-Trichloroethane*	5	**180**	**4.0**	< 1.0 U	< 20 U	**110**	< 4.0 U	**140**	< 1.0 U
1,1,2-Trichloro-1,2,2-trifluoroethane	5	**130**	**7.6**	< 1.0 U	< 20 U	**92**	< 4.0 U	**55**	< 1.0 U
1,2-Dichloroethane*	0.6	< 4.0 U	< 1.0 U	< 1.0 U	< 20 U	< 10 U	< 4.0 U	**18 J**	< 1.0 U
2-Hexanone	50	< 20 U	< 5.0 U	< 5.0 U	< 100 U	< 50 U	< 20 U	< 250 U	< 5.0 U
Chloroethane	5	**11**	< 1.0 U	< 1.0 U	< 20 U	**940**	< 4.0 U	**9,400 F1**	< 1.0 U
cis-1,2-Dichloroethene	5	**260**	**8.5**	< 1.0 U	**730**	**8.2 J**	< 4.0 U	< 50 U	< 1.0 U
Ethylbenzene	5	< 4.0 U	< 1.0 U	< 1.0 U	**49**	< 10 U	< 4.0 U	< 50 U	< 1.0 U
Methylene Chloride	5	< 4.0 U	< 1.0 U	< 1.0 U	**9.4 J**	< 10 U	**3.1**	< 50 U	< 1.0 U
Toluene	5	**11**	< 1.0 U	< 1.0 U	< 20 U	< 10 U	< 4.0 U	< 50 U	< 1.0 U
trans-1,2-Dichloroethene	5	**4.0**	< 1.0 U	< 1.0 U	< 20 U	< 10 U	< 4.0 U	< 50 U	< 1.0 U
Trichloroethene*	5	**11**	**1.2**	< 1.0 U	< 20 U	**7.2 J**	< 4.0 U	< 50 U	< 1.0 U
Vinyl chloride*	2	**17**	< 1.0 U	< 1.0 U	**4,200**	**11**	< 4.0 U	**260**	< 1.0 U
Xylenes, Total	5	**5.5 J**	< 2.0 U	< 2.0 U	**44**	< 20 U	< 8.0 U	< 100 U	< 2.0 U
Total Volatile Organic Compounds	NL	689.5	21	0	5,032.4	1,528.0	3.1	13,792	0

Table 4

Summary of Monitoring Well Analytical Data - April 2018
Former Scott Aviation Facility
NYSDEC Site Code No. C915233
Lancaster, New York

Sample ID	Groundwater	A1-GP15-S	A1-GP16-S	A1-GP18-S	MW-30	MW-35S	MW-36S	MW-42S	MW-43S	MW-44S
Date Collected	RAO/NYCRR	04/09/18	04/09/18	04/10/18	04/11/18	04/09/18	04/09/18	04/11/18	04/11/18	04/11/18
Lab Sample ID	Objective	480-133949-11	480-133949-13	480-133949-16	480-133949-17	480-133949-18	480-133949-19	480-134235-3	480-133949-21	480-133949-10
Volatile Organic Compounds by Method 8260 (µg/L)										
1,1-Dichloroethane*	5	< 1.0 U	< 1.0 U	< 1.0 U	**0.75 J**	< 1.0 U	< 1.0 U	**2,000**	< 4.0 U	< 1.0 U
1,1-Dichloroethene*	5	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	**120 J**	< 4.0 U	< 1.0 U
1,1,1-Trichloroethane*	5	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	**390**	< 4.0 U	< 1.0 U
1,1,2-Trichloro-1,2,2-trifluoroethane	5	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	**740**	< 4.0 U	< 1.0 U
1,2-Dichloroethane*	0.6	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 200 U	< 4.0 U	< 1.0 U
2-Hexanone	50	< 5.0 U	< 5.0 U	< 5.0 U	< 5.0 U	< 5.0 U	< 5.0 U	< 1,000 U	< 20 U	< 5.0 U
Chloroethane	5	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	**8,400**	< 4.0 U	< 1.0 U
cis-1,2-Dichloroethene	5	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	**1.2**	**1,100**	< 4.0 U	< 1.0 U
Ethylbenzene	5	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 200 U	< 4.0 U	< 1.0 U
Methylene Chloride	5	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 200 U	< 4.0 U	< 1.0 U
Toluene	5	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	**670**	< 4.0 U	< 1.0 U
trans-1,2-Dichloroethene	5	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 200 U	< 4.0 U	< 1.0 U
Trichloroethene*	5	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 1.0 U	< 200 U	< 4.0 U	< 1.0 U
Vinyl chloride*	2	< 1.0 U	< 1.0 U	< 1.0 U	**0.95 J**	< 1.0 U	< 1.0 U	**2,800**	< 4.0 U	< 1.0 U
Xylenes, Total	5	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 2.0 U	< 400 U	**3.0 J**	< 2.0 U
Total Volatile Organic Compounds	NL	0	0	0	1.7	0	1.2	16,220	3.0	0

Table 4

Summary of Monitoring Well Analytical Data - April 2018
Former Scott Aviation Facility
NYSDEC Site Code No. C915233
Lancaster, New York

Sample ID	Groundwater	MW-35D	MW-36D	MW-37D	MW-38D	MW-39D	MW-40D
Date Collected	RAO/NYCRR	04/10/18	04/10/18	04/11/18	04/10/18	04/12/18	04/10/18
Lab Sample ID	Objective	480-133949-7	480-133949-20	480-134235-1	480-133949-8	480-134235-2	480-133949-9
Volatile Organic Compounds by Method 8260 (µg/L)							
1,1-Dichloroethane*	5	< 1.0 U	< 1.0 U	< 1.0 U	< 4.0 U	< 4.0 U	**400**
1,1-Dichloroethene*	5	< 1.0 U	< 1.0 U	< 1.0 U	< 4.0 U	< 4.0 U	< 10 U
1,1,1-Trichloroethane*	5	< 1.0 U	< 1.0 U	< 1.0 U	< 4.0 U	< 4.0 U	**20**
1,1,2-Trichloro-1,2,2-trifluoroethane	5	< 1.0 U	< 1.0 U	< 1.0 U	< 4.0 U	< 4.0 U	< 10 U
1,2-Dichloroethane*	0.6	< 1.0 U	< 1.0 U	< 1.0 U	< 4.0 U	< 4.0 U	< 10 U
2-Hexanone	50	< 5.0 U	**2.7 J**	< 5.0 U	< 20 U	< 20 U	< 50 U
Chloroethane	5	< 1.0 U	< 1.0 U	< 1.0 U	**14**	< 4.0 U	**970**
cis-1,2-Dichloroethene	5	< 1.0 U	< 1.0 U	< 1.0 U	< 4.0 U	< 4.0 U	< 10 U
Ethylbenzene	5	< 1.0 U	< 1.0 U	< 1.0 U	**3.1 J**	< 4.0 U	< 10 U
Methylene Chloride	5	< 1.0 U	< 1.0 U	< 1.0 U	< 4.0 U	< 4.0 U	< 10 U
Toluene	5	< 1.0 U	< 1.0 U	< 1.0 U	**2.2 J**	< 4.0 U	< 10 U
trans-1,2-Dichloroethene	5	< 1.0 U	< 1.0 U	< 1.0 U	< 4.0 U	< 4.0 U	< 10 U
Trichloroethene*	5	< 1.0 U	< 1.0 U	< 1.0 U	< 4.0 U	< 4.0 U	< 10 U
Vinyl chloride*	2	< 1.0 U	< 1.0 U	< 1.0 U	< 4.0 U	< 4.0 U	< 10 U
Xylenes, Total	5	< 2.0 U	< 2.0 U	< 2.0 U	**15**	< 8.0 U	< 20 U
Total Volatile Organic Compounds	NL	0	2.7	0	34.3	0	1,390

Notes:
Bold font indicates the analyte was detected.
Bold font and bold outline indicates the screening criteria was exceeded.
* Site-specific Contaminants of Concern per Decision Document December 2015).
Site-specific Contaminants of Concern, 1,1,2-trichloroethane and tetrachloroethane were not detected above the reporting limit.
J - Analyte detected at a level less than the reporting limit and greater than or equal to the method detection limit. Concentrations within this range are estimated.
U - Not detected at or above reporting limit.
NL - Not listed

Appendix A

Former Scott Aviation Area 1 Pre-Injection and Post-Injection Groundwater Quality Data

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
CB-1	Monitoring event	BL1	6/1/2011	-1434	6.34	NA	689.5	NA	NA (Grab Sample)						NS
	Monitoring event	BL2	6/16/2011	-1419	6.34	NA	689.5	NA							NS
	Monitoring event	BL3	10/7/2011	-1306	6.34	NA	689.5	NA							NS
	Monitoring event	P1	6/12/2015	38	6.34	NA	689.5	NA							NS
	Monitoring event	P2	1/6/2016	246	6.34	NA	689.5	NA							NS
	Monitoring event	P3	4/8/2016	339	6.34	7.64	689.5	681.9							NS
	Monitoring event	P4	7/11/2016	433	6.34	6.31	689.5	683.2							NS
	Monitoring event	P5	10/13/2016	527	6.34	6.25	689.5	683.3	8.04	7.62	122.3	0.296	5.98	14.97	NS
	Monitoring event	P6	1/20/2017	626	6.34	NA	689.5	NA	NA (Grab Sample)						NS
	Monitoring event	P7	4/7/2017	703	6.34	6.19	689.5	683.3	7.71	NA	25.9	0.305	17.9	NA	NS
	Monitoring event	P8	7/10/2017	797	6.34	6.3	690.5	684	7.82	0.63	6.7	0.63	4.95	17.8	NS
	Monitoring event	P9	10/18/2017	897	6.34	6.25	689.5	683.3	7.97	5.79	211.5	0.77	12.9	16.9	NS
	Monitoring event	P10	1/2/2018	973	6.34	NA	689.5	NA	NS (Grab Sample)						NS
	Monitoring event	P11	4/9/2018	1070	6.34	6.28	689.5	NA	7.48	14.76	14.9	0.379	NA	3.85	NS

(ug/L)

Event	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane
BL1	420	400 J	1.6	53	41	ND	ND	ND	ND	61	ND	ND	2.8
BL2	120	220	0.87 J	18	14	ND	ND	ND	ND	390 J	ND	ND	0.6 J
BL3	170	260	1.4	26	28	ND	ND	ND	ND	ND	ND	ND	ND
P1	27	19	ND	18	3.7	ND	ND	36	ND	340	ND	0.46 J	ND
P2	45	140	0.29 J	42	8.2	0.28 J	ND	ND	ND	73	ND	ND	37
P3	10	32	ND	4.4	3.2 J	ND	ND	ND	ND	110	ND	ND	2.5 J
P4	ND	1.6	ND	0.60 J	ND	ND	ND	ND	ND	4.7 J	ND	ND	0.38 J
P5	3.4	3.5	ND	3.2	0.81 J	ND	ND	ND	ND	ND	ND	ND	2.6
P6	21	45	ND	11	5.0	ND	ND	ND	ND	ND	ND	ND	5.6
P7	13	16	ND	5.1	1.8	ND	ND	ND	ND	ND	ND	ND	2.1
P8	ND	4.3	ND	3.8	ND	ND	ND	ND	ND	3.4	ND	ND	0.76
P9	45	23	0.31	28	3.0	ND	ND	ND	ND	ND	ND	ND	12.0
P10	83	270	ND	53	6.8	ND	ND	ND	ND	ND	ND	ND	22
P11	180	130	ND	47	13	ND	ND	ND	ND	ND	ND	ND	11

Event	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
BL1	ND	ND	140	ND	ND	ND	ND	ND	0.5 J	1.9	1.8	59	8.4	1 J
BL2	ND	ND	51	ND	ND	ND	ND	ND	ND	ND	1.5	18	1.4	ND
BL3	ND	ND	52	ND	ND	ND	ND	ND	0.73 J	ND	ND	22	ND	ND
P1	0.55 J	ND	44	ND	ND	0.41 J	ND	ND	ND	3.2	ND	1.5	1.6	7.4
P2	ND	ND	100	ND	0.75	0.18 J	ND	ND	ND	6.2	2.2	12	13	5.3
P3	ND	ND	18	ND	ND	ND	6.9	ND	ND	ND	ND	2.9 J	ND	ND
P4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P5	ND	ND	4.2	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.92	ND
P6	ND	ND	33	ND	ND	ND	ND	ND	ND	1.4	ND	3.2	4.1	2.0
P7	ND	ND	20	ND	ND	ND	ND	ND	ND	1.6	ND	0.97 J	1.8	1.8 J
P8	ND	ND	1.0	0.8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P9	ND	ND	99.0	ND	ND	ND	ND	ND	ND	0.42	1.0	0.67	6.0	ND
P10	ND	ND	82	ND	ND	ND	ND	ND	ND	ND	ND	19	18	ND
P11	ND	ND	260	ND	ND	ND	ND	ND	ND	11	4.0	11	17	5.5 J

Carbon Dioxide (ug/L)	Ethane (ug/L)	Ethene (ug/L)	Methane (ug/L)	Nitrate (mg/L)	Manganese (mg/L)	Ferric iron (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrite (mg/L)	Phosphorous (mg/L)	Ammonia (mg/L)	COD (mg/L)	BOD (mg/L)	Total Alkalinity (mg/L)	Ferrous Iron (mg/L)	Iron (mg/L)	Acetic Acid (mg/L)	Formic Acid (mg/L)	Lactic Acid (mg/L)	n-Butyric Acid (mg/L)	Propionic Acid (mg/L)	Pyruvic Acid (mg/L)	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1) (cells / mL)	BAV1 VC R-Dase (1) (cells / mL)	VC R-Dase (cells / mL)
Not Sampled For These Parameters																										

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
TP-05	Monitoring event	BL1	6/1/2011	-1434	7.0	NA	690.5	NA	NA (Grab Sample)						NS
TP-05	Monitoring event	P1	7/28/2015	84	7.0	7.75	690.5	682.8	7.07	3.62	-66.7	1.153	9.43	19.51	NS
TP-05	Monitoring event	P2	1/6/2016	246	7.0	NA	690.5	NA							NS
TP-05	Monitoring event	P3	4/8/2016	339	7.0	7.64	690.5	682.9	NA (Grab Sample)						NS
TP-05	Monitoring event	P4	7/11/2016	433	7.0	7.79	690.5	682.7							NS
TP-05	Monitoring event	P5	10/13/2016	527	7.0	7.56	690.5	683	7.48	5.94	116	0.549	11.4	15.35	NS
TP-05	Monitoring event	P6	1/20/2017	626	7.0	NA	690.5	NA	NA (Grab Sample)						NS
TP-05	Monitoring event	P7	4/7/2017	703	7.0	7.63	690.5	682.9	7.3	NA	26.6	1.197	70.1	NA	NS
TP-05	Monitoring event	P8	7/10/2017	797	7.0	7.8	690.5	683	7.14	4.06	26.5	0.67	40.3	19.1	NS
TP-05	Monitoring event	P9	10/18/2017	897	7.0	7.64	690.5	682.9	7.71	3.92	220.5	0.74	122	17.1	NS
TP-05	Monitoring event	P10	1/2/2018	973	7.0	NA	690.5	NA	NA (Grab Sample)						NS
TP-05	Monitoring event	P11	4/9/2018	1070	7.0	7.76	690.5	NA	7.42	14.1	71.3	0.689	NA	7.37	NS

(ug/L)

Event	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
BL1	83	60 J	ND	12	7.2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	23	ND	ND	ND	ND	ND	ND	ND	ND	8.8	1.6	ND
P1	2.5	23	ND	29	1.1	ND	ND	22	ND	28	ND	ND	2.3	ND	ND	17	ND	ND	ND	0.48 J	ND	ND	4.4	1.2	1.9	9.9	4.3
P2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.54 J	ND	ND
P3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P4	ND	2.7	ND	2.2	ND	ND	ND	ND	ND	3.3 J	ND	ND	0.49 J	ND	ND	1.4	2.1	ND	ND	ND	ND	ND	ND	ND	1.4	ND	ND
P5	0.82 J	ND	ND	3.2 J	ND	ND	ND	ND	ND	ND	ND	ND	0.92 J	ND	ND	2.7	ND	ND	ND	ND	ND	ND	ND	ND	0.87	ND	ND
P6	ND	0.54 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P8	ND	2.5	ND	5.0	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	2.3	ND	ND	ND	ND	ND	ND	ND	ND	1.1	ND	ND
P9	8.6	3.7	ND	7.5	0.64	ND	ND	ND	ND	ND	ND	ND	2.4	ND	ND	20.0	ND	ND	ND	ND	ND	ND	ND	ND	1.1	1.2	ND
P10	ND	0.52 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.64 J	ND	ND
P11	4.0	7.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	8.5	ND	ND	ND	ND	ND	ND	ND	ND	1.2	ND	ND

Event	Carbon Dioxide (ug/L)	Ethane (ug/L)	Ethene (ug/L)	Methane (ug/L)	Nitrate (mg/L)	Manganese (mg/L)	Ferric iron (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrite (mg/L)	Phosphorous (mg/L)	Ammonia (mg/L)	COD (mg/L)	BOD (mg/L)	Total Alkalinity (mg/L)	Ferrous Iron (mg/L)	Iron (mg/L)	Acetic Acid (mg/L)	Formic Acid (mg/L)	Lactic Acid (mg/L)	n-Butyric Acid (mg/L)	Propionic Acid (mg/L)	Pyruvic Acid (mg/L)	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1) (cells / mL)	BAV1 VC R-Dase (1) (cells / mL)	VC R-Dase (cells / mL)
BL1–P11	Not Sampled For These Parameters																										

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
TP-06	Monitoring event	P1	6/12/2015	38	9.0	NS	690.3	NS	NA (Grab Sample)						NS
TP-06	Monitoring event	P2	7/28/2015	84	9.0	7.75	690.3	682.5	7.13	1.54	54.5	3.082	2.82	19.35	NS
TP-06	Monitoring event	P3	1/6/2016	246	9.0	NA	690.3	NA	NA (Grab Sample)						NS
TP-06	Monitoring event	P4	4/8/2016	339	9.0	7.4	690.3	682.9							NS
TP-06	Monitoring event	P5	7/11/2016	433	9.0	7.52	690.3	682.7							NS
TP-06	Monitoring event	P6	10/13/2016	527	8.6	7.43	690.3	682.8	7.34	4.61	175.9	2.302	24.2	16.71	NS
TP-06	Monitoring event	P7	1/20/2017	626	9.0	NA	690.3	NA	NA (Grab Sample)						NS
TP-06	Monitoring event	P8	4/7/2017	703	9.0	7.33	690.3	682.9	9.51	NA	18.4	1.525	150	NA	NS
TP-06	Monitoring event	P9	7/10/2017	797	9.0	8.5	690.3	682	7.27	1.10	19.6	3.16	52.1	18.8	NS
TP-06	Monitoring event	P10	10/18/2017	897	9.0	7.45	690.3	682.9	7.71	5.21	207.2	2.44	27	17.7	NS
TP-06	Monitoring event	P11	1/2/2018	973	9.0	NA	690.3	NA	NA (Grab Sample)						NS
TP-06	Monitoring event	P12	4/19/2018	1080	9.0	7.48	690.3	NA	7.09	14.63	61.13	2.478	NA	6.34	NS

(ug/L)

Event	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
P1	1.8	0.31 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.1	ND	ND	ND	ND	ND	ND	ND	ND	0.49 J	ND	ND
P2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	2.8	ND	ND	ND	ND	ND	ND	ND	ND	0.83 J	ND	ND
P3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.0	ND	ND	0.21 J	ND	ND	ND	ND	ND	ND	ND	ND
P8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.95	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P9	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.67	ND	ND
P10	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.42	ND	ND	ND	ND	ND	ND	ND	ND	0.46	ND	ND
P11	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P12	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Event	Carbon Dioxide (ug/L)	Ethane (ug/L)	Ethene (ug/L)	Methane (ug/L)	Nitrate (mg/L)	Manganese	Ferric iron	Sulfate	Sulfide	Nitrite	Phosphorous	Ammonia	COD	BOD	Total Alkalinity	Ferrous Iron	Iron	Acetic Acid	Formic Acid	Lactic Acid	n-Butyric Acid	Propionic Acid	Pyruvic Acid	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1)	BAV1 VC R-Dase (1)	VC R-Dase
P1–P12	Not Sampled For These Parameters																										

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth	Water Level Measurement	Top of Casing Elevation	Head Elevation	pH	Dissolved Oxygen	Oxidation Reduction Potential	Specific Conductance	Turbidity	Temperature	Carbon, Total Organic	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
					(feet)	(ft. ATOC)	(ft. AMSL)	(ft. AMSL)	(SU)	(mg/L)	(mV)	(mS/cm)	(NTUs)	(°C)	(mg/L)	(ug/L)																										
A1-GP02-S	Monitoring event	BL1	6/22/2010	-1778	15	4.12	689.82	685.7	6.93	7.31	47.1	1.117	46.5	18.4	NS	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	6,400	ND	ND	ND	ND	ND	ND	ND	94 J	11,000	ND	ND
	Monitoring event	BL2	8/4/2010	-1735	15	4.9	689.82	684.92	6.82	4.37	-31.9	1.17	454	21.27	NS	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	10,000	ND	ND	ND	ND	ND	ND	ND	190 J	20,000	ND	ND
	Monitoring event	BL3	3/10/2015	-56	15	3.95	689.8	685.9	7.24	6.95	-0.9	0.85	52.7	6.86	3.3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	3,300	ND	ND	ND	ND	ND	ND	ND	ND	5,400	ND	ND
	Monitoring event	P1	7/28/2015	84	15	4.55	689.8	685.3	5.75	0.89	48.2	5.212	25	16.89	3,700	ND	ND	ND	ND	34 J	ND	ND	ND	ND	360 J	ND	ND	ND	ND	ND	23,000	ND	ND	ND	92	ND	ND	ND	120	8,000	140	ND
	Monitoring event	P2	1/7/2016	247	15	4.1	689.8	685.7	6.06	3.51	21.8	5.662	53.2	9.23	NS	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	29,000	ND	ND	ND	ND	ND	ND	ND	ND	330 J	770	ND
	Monitoring event	P3	4/8/2016	339	15	2.64	689.8	687.2	6.24	2.24	-5.3	2.794	69.3	6.85	1,280	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	22,000	ND	ND	ND	250 J	ND	ND	ND	ND	ND	2,400	ND
	Monitoring event	P4	7/11/2016	433	15	6.04	689.8	683.8	6.35	3.9	-40.7	4.406	43.7	18.39	1,570	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	32,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	10,000	ND
	Monitoring event	P5	10/10/2016	524	15	6.6	689.8	683.2	6.71	6.59	-61.4	3.404	43.5	18.42	1,180	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	6,400	ND	ND	ND	ND	ND	ND	ND	ND	ND	13,000	ND
	Monitoring event	P6	1/23/2017	629	15	3.15	689.8	686.7	6.68	3.1	-61.3	1.284	20.3	8.27	261	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	810	ND	ND	ND	ND	ND	ND	ND	50	ND	1,700	ND
	Monitoring event	P7	4/11/2017	707	15	2.75	689.8	687.1	6.52	4.88	-44.7	1.413	125	10.7	268	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	900	ND	ND	ND	ND	ND	ND	ND	93	ND	3,700	ND
	Monitoring event	P8	7/6/2017	793	15	5.7	689.8	684.1	6.79	2.4	-90.7	2.39	23.9	17.0	669	ND	ND	ND	ND	ND	ND	ND	ND	ND	120	ND	ND	ND	ND	ND	790	ND	65	ND	ND	ND	ND	ND	50	ND	4,300	54
	Monitoring event	P9	10/17/2017	896	15	4.4	689.8	685.4	6.84	2.44	-235.4	36.2	36.2	14.7	407	ND	ND	ND	ND	ND	ND	ND	ND	ND	190	ND	ND	ND	ND	ND	230	ND	33	ND	ND	ND	ND	ND	ND	ND	1,900	29
	Monitoring event	P10	1/5/2018	976	15	3.61	689.8	686.2	8.21	4.91	-112.1	1.06	NA	6.8	270	ND	ND	ND	ND	ND	ND	ND	64 J	ND	96 J	ND	ND	ND	ND	ND	680	ND	47	ND	ND	ND	ND	ND	ND	ND	6,700	43
	Monitoring event	P11	4/12/2018	1073	15	3.45	689.8	686.4	6.96	5.26	-74.5	1.109	NA	8.5	210	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	730	ND	49	9.4 J	ND	ND	ND	ND	ND	ND	4,200	44

Well ID	Carbon Dioxide	Ethane	Ethene	Methane	Nitrate	Manganese	Ferric iron	Sulfate	Sulfide	Nitrite	Phosphorous	Ammonia	COD	BOD	Total Alkalinity	Ferrous Iron	Iron	Acetic Acid	Formic Acid	Lactic Acid	n-Butyric Acid	Propionic Acid	Pyruvic Acid	Dehalococcoides spp (1)	TCE R-Dase (1)	BAV1 VC R-Dase (1)	VC R-Dase
	(ug/L)				(mg/L)																			(cells / mL)			
A1-GP02-S	Not Sampled For These Parameters																										

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
A1-GP06-S	Monitoring event	BL1	6/21/2010	-1779	15	3.4	687.7	684.3	6.88	3.45	83.7	0.752	64.1	16.99	NS
	Monitoring event	BL2	8/4/2010	-1735	15	3.24	687.7	684.5	7.1	4.32	13.2	0.793	4.1	19.3	NS
	Monitoring event	BL3	11/5/2014	-181	15	2.15	687.7	685.6	7.19	1.0	-57.4	0.759	NS	12.74	NS
	Monitoring event	BL4	3/11/2015	-55	15	2.0	687.7	685.7	5.8	9.8	257.3	0.616	8.54	4.86	5.5
	Monitoring event	P1	7/27/2015	83	15	2.75	687.7	685	6.8	0.63	-106.2	3.365	11.8	15.83	1,420
	Monitoring event	P2	1/7/2016	247	15	2.1	687.7	685.6	7.18	0.51	-115.7	2.024	17.0	10.28	415
	Monitoring event	P3	4/8/2016	339	15	1.76	687.7	686	7.11	0.7	-93.5	1.126	33.2	6.42	219
	Monitoring event	P4	7/12/2016	434	15	3.23	687.71	684.48	7.22	1.18	-137.2	1.964	47.9	17.81	588
	Monitoring event	P5	10/10/2016	524	15	3.55	687.71	684.16	7.28	1.92	-83.5	2.066	11.4	17.64	398
	Monitoring event	P6	1/24/2017	630	15	1.67	687.71	686.04	7.96	0.47	-106	1.177	19.5	10.65	47.7
	Monitoring event	P7	4/11/2017	707	15	0.35	687.7	687.4	7.17	0.58	-90.7	0.945	33	11.6	245
	Monitoring event	P6	7/6/2017	793	15	3.3	687.7	684.4	7.31	0.79	-75.3	1.3	15.8	15.7	210
	Monitoring event	P7	10/18/2017	897	15	3.95	687.7	683.8	7.59	5.56	-227	1.44	10.1	15.0	288
	Monitoring event	P8	1/5/2018	976	15	2.00	687.71	685.71	11.05	0.75	-196.2	0.843	NA	11.22	4.6
	Monitoring event	P9	4/10/2018	1071	15	1.65	687.71	686.06	7.26	1.31	-108.3	0.553	NA	7.3	53.0

(ug/L)

Event	Date	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform
BL1	6/21/2010	620	660	ND	890	63 J	ND	ND	ND	ND	ND	ND	ND	ND	ND
BL2	8/4/2010	1,700	1,900	16 J	3,200	270	ND	ND	ND	ND	ND	ND	ND	ND	ND
BL3	11/5/2014	Not Sampled For These Parameters													
BL4	3/11/2015	ND	7.4	ND	21	0.89 J	ND	ND	ND	ND	ND	ND	ND	ND	ND
P1	7/27/2015	110	300	4.1	3,300	60	3.1	ND	140	ND	50	ND	0.34 J	36	0.68 J
P2	1/7/2016	ND	ND	ND	340	ND	ND	ND	95 J	ND	41 J	ND	ND	310	ND
P3	4/8/2016	73	63	ND	450	7.8 J	ND	ND	28 J	ND	ND	ND	ND	790	ND
P4	7/12/2016	35	110	ND	680	ND	ND	ND	69 J	ND	31 J	ND	ND	1,300	ND
P5	10/10/2016	ND	26	ND	270	ND	ND	ND	ND	ND	ND	ND	ND	670	ND
P6	1/24/2017	24	31	ND	300	ND	ND	ND	ND	ND	ND	ND	ND	1,300	ND
P7	4/11/2017	34	52	ND	210	6.2 J	ND	ND	32 J	ND	ND	ND	ND	730	ND
P6	7/6/2017	63	68	490	13	ND	ND	ND	ND	ND	ND	ND	ND	1,400	ND
P7	10/18/2017	ND	ND	ND	200	ND	ND	ND	42	ND	73	ND	ND	1,800	ND
P8	1/5/2018	44	1.6 J	84	400	3.7 J	2.1 J	ND	16 J	ND	ND	ND	ND	ND	ND
P9	4/10/2018	110	92	ND	360	6.8 J	ND	ND	ND	ND	ND	ND	ND	940	ND

(ug/L)

Event	Date	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
BL1	6/21/2010	ND	32 J	ND	ND	ND	ND	ND	ND	ND	ND	46 J	ND	ND
BL2	8/4/2010	ND	130	33 J	ND	ND	ND	ND	ND	ND	ND	200	20 J	ND
BL3	11/5/2014													
BL4	3/11/2015	ND	ND	ND	ND	ND	1.4 B	ND	ND	ND	ND	0.81 J	ND	ND
P1	7/27/2015	ND	270	190	ND	ND	ND	16	ND	15	3.2	18	16	ND
P2	1/7/2016	ND	25	ND	ND	ND	5.5 J	ND	ND	ND	ND	ND	16	ND
P3	4/8/2016	ND	ND	ND	ND	ND	5.1 J	ND	ND	6.1 J	ND	5.4 J	33	ND
P4	7/12/2016	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	44	ND
P5	10/10/2016	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P6	1/24/2017	ND	ND	ND	ND	ND	16 J	ND	ND	ND	ND	ND	29	ND
P7	4/11/2017	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P6	7/6/2017	ND	16	ND	ND	ND	ND	ND	ND	ND	ND	ND	50	ND
P7	10/18/2017	ND	ND	ND	ND	ND	ND	ND	ND	4.4	ND	ND	14	ND
P8	1/5/2018	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P9	4/10/2018	ND	8.2 J	ND	ND	ND	ND	ND	ND	ND	ND	7.2 J	11	ND

Event	Date	Carbon Dioxide (ug/L)	Ethane (ug/L)	Ethene (ug/L)	Methane (ug/L)	Nitrate (mg/L)	Manganese (mg/L)	Ferric iron (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrite (mg/L)	Phosphorous (mg/L)	Ammonia (mg/L)
BL1	6/21/2010	Not Sampled For These Parameters											
BL2	8/4/2010												
BL3	11/5/2014	9,500	NS	NS	44	ND	0.047	0.27	22	NS	ND	ND	0.23
BL4	3/11/2015	Not Sampled For These Parameters											
P1	7/27/2015	10,000	ND	ND	660	ND	1.6 B	45.5	ND	NS	ND	0.42	0.19
P2	1/7/2016	4,000	ND	ND	2,900	0.029 J	0.37	21	22.3	ND	ND	0.54	0.023
P3	4/8/2016	6,000	ND	ND	2,200	ND	0.46	15.8	9.2	ND	ND	0.059	0.019 J
P4	7/12/2016	49,000	ND	ND	410	ND	0.25 B	7.4	ND	ND	ND	0.16	0.13
P5	10/10/2016	36,000	ND	ND	2,600	ND	0.23 B	4.9	ND	0.80 J	0.020 J	0.14	0.16
P6	1/24/2017	44,000	ND	ND	1,800	0.024 J	0.23	13.6	33.9	ND	ND	0.060 F1	ND
P7	4/11/2017	23,000	ND	ND	2,500	ND	0.12	2.9	12	ND	ND	0.05	0.065
P6	7/6/2017	#####	ND	ND	710	ND	0.26	9.1	7.3	1.2	ND	0.14	0.039
P7	10/18/2017	#####	ND	ND	#####	0.048	0.13	8.6	62.1	ND	ND	0.068	0.084
P8	1/5/2018	46,000	ND	ND	2,600	ND	0.33	10.3	15.6	ND	ND	0.25	0.040
P9	4/10/2018	38,000	ND	ND	16,000		0.59	18.0	3.1 J			0.24	

Event	Date	COD (mg/L)	BOD (mg/L)	Total Alkalinity (mg/L)	Ferrous Iron (mg/L)	Iron (mg/L)	Acetic Acid (mg/L)	Formic Acid (mg/L)	Lactic Acid (mg/L)	n-Butyric Acid (mg/L)	Propionic Acid (mg/L)	Pyruvic Acid (mg/L)	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1) (cells / mL)	BAV1 VC R-Dase (1) (cells / mL)	VC R-Dase (cells / mL)
BL1	6/21/2010	Not Sampled For These Parameters														
BL2	8/4/2010															
BL3	11/5/2014	19.6	ND	376	ND	0.27	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
BL4	3/11/2015	Not Sampled For These Parameters														
P1	7/27/2015	3220	3410	2430	27.6	73.1	1730	14.4	ND	137	836	ND	Not Sampled For These Parameters			
P2	1/7/2016	443	942	787 B	ND	21	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
P3	4/8/2016	453	552 b	701	ND	15.8	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
P4	7/12/2016	2030 B	>1295.73 H b	1360	1.2 H F	8.6	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
P5	10/10/2016	1,750	ND	1,080	ND	4.9	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P6	1/24/2017	211	744 H b	456	0.080 J H F	13.7	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P7	4/11/2017	574	418 Hb	697	ND	ND	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P6	7/6/2017	531	498	663	ND	9.1	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P7	10/18/2017	677	608	757	ND	8.6	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P8	1/5/2018	261	283 H b	515	ND	10.3	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P9	4/10/2018	110	274 H b	565 B	ND	18.0	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			

1

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
A1-GP10-S	Monitoring event	BL1	6/21/2010	-1779	15	2.7	689.1	686.4	6.57	5.08	1.9	1.171	473	17.45	NS
A1-GP10-S	Monitoring event	BL2	8/3/2010	-1736	15	3.8	689.1	685.3	6.64	2.61	-58.6	1.036	115.7	20.32	NS
A1-GP10-S	Monitoring event	BL3	11/5/2014	-181	15	4.3	689.1	684.8	6.9	2.15	-68.2	1.007	NA	12.65	NS
A1-GP10-S	Monitoring event	BL4	3/11/2015	-55	15	1.8	689.1	687.3	6.87	1.84	-49.8	1.096	32	7.56	2.7
A1-GP10-S	Monitoring event	P1	6/12/2015	38	NS (Grab Sample)										NS
A1-GP10-S	Monitoring event	P2	7/27/2015	83	15	2.29	689.1	686.8	6.33	4.31	13.4	3.454	22.6	15.9	1570
A1-GP10-S	Monitoring event	P3	1/7/2016	247	15	1.85	689.1	687.3	7.12	5.28	-50.8	1.33	22.1	9.97	37.7 B
A1-GP10-S	Monitoring event	P4	4/8/2016	339	15	1.05	689.1	688.05	7.01	3.54	-42.2	0.979	20.0	7.43	35
A1-GP10-S	Monitoring event	P5	7/11/2016	433	15	3.65	689.1	685.45	6.75	7.22	-33.6	1.791	22.6	19.36	303
A1-GP10-S	Monitoring event	P6	10/7/2016	521	15	2.1	689.1	687	6.93	5.01	160	1.556	7.12	17.47	96.7
A1-GP10-S	Monitoring event	P7	1/23/2017	629	15	1.75	689.1	687.35	7.82	13.49	-62.2	0.493	10	11.09	39.9
A1-GP10-S	Monitoring event	P8	4/10/2017	706	15	0.81	689.1	688.29	7.01	6.12	-26.1	0.653	6.2	14.5	48.9
A1-GP10-S	Monitoring event	P9	7/6/2017	793	15	2.65	689.1	686.5	6.66	3.67	-79	1.52	11.3	15.7	185
A1-GP10-S	Monitoring event	P10	10/17/2017	896	15	2.1	689.1	687	6.95	5.1	#####	0.74	2.55	14.1	7.1
A1-GP10-S	Monitoring event	P11	1/4/2018	975	15	2.16	689.1	686.9	9.6	5.42	-124.5	0.459	NA	9.75	16.5
A1-GP10-S	Monitoring event	P12	4/10/2018	1071	15	1.64	689.1	687.5	6.8	5.64	-53.6	0.808	NA	7.36	5.9 B

Event	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
	(ug/L)																										
BL1	55,000	1400 J	84	43,000	1,300 J	77	ND	96	2.6 J	ND	ND	0.87 J	ND	7.3	0.46 J	ND	1.2 J	2 J	ND	17	ND	1.2 J	8	1.3 J	92	41	16
BL2	84,000	1,900 J	ND	48,000	2,000 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
BL3	Not Sampled For These Parameters																										
BL4	1,500	85	1.2 J	440	65	1.6 J	ND	ND	ND	ND	ND	ND	3	ND	ND	7.4	ND	ND	ND	4.2 J	ND	ND	ND	ND	6.6	ND	ND
P1	28,000	790	ND	15,000	1,000	40 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	190	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P2	12,000	430	ND	2,900	1,600	9.6 J	ND	380	ND	950	ND	ND	ND	16 J	ND	45	ND	ND	ND	20 J	ND	ND	ND	ND	36	ND	ND
P3	4,900	290	ND	4,300	470	ND	ND	ND	ND	ND	ND	ND	520	ND	ND	51	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P4	1,700	180	ND	4,800	220	ND	ND	ND	ND	ND	ND	ND	640	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P5	6,600	140	ND	29,000	500	72	ND	ND	ND	ND	ND	ND	6,700	ND	ND	270	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P6	360	ND	ND	7,200	190 J	47 J	ND	ND	ND	ND	ND	ND	12,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P7	ND	ND	ND	580	ND	ND	ND	ND	ND	ND	ND	ND	4,100	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P8	240	110 J	ND	4,100	45 J	ND	ND	ND	ND	ND	ND	ND	32,000	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	690	ND
P9	2,400	ND	ND	9,600	380	ND	ND	ND	ND	ND	ND	ND	#####	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P10	23	6.0	ND	240	4.0	1.4	ND	ND	ND	7.3	ND	ND	320	ND	ND	0.51	ND	0.2	ND	ND	ND	ND	0.77	0.74	0.47	45	1.2
P11	44 J	30 J	ND	600	ND	11 J	ND	ND	ND	ND	ND	ND	3,300	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	85	ND
P12	140	55	ND	3,900	19 J	18 J	ND	ND	ND	ND	ND	ND	9,400	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	260	ND

Event	Carbon Dioxide	Ethane	Ethene	Methane	Nitrate	Manganese	Ferric iron	Sulfate	Sulfide	Nitrite	Phosphorous	Ammonia	COD	BOD	Total Alkalinity	Ferrous Iron	Iron	Acetic Acid	Formic Acid	Lactic Acid	n-Butyric Acid	Propionic Acid	Pyruvic Acid	Dehalococcoides spp (1)	TCE R-Dase (1)	BAV1 VC R-Dase (1)	VC R-Dase
	(ug/L)				(mg/L)																			(cells / mL)			
BL1	Not Sampled For These Parameters																										
BL2	Not Sampled For These Parameters																										
BL3	9,800	NS	NS	91	ND	0.042	0.63	8.3	NS	ND	ND	0.033	27.4	3	388	0.17	0.8	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
BL4	Not Sampled For These Parameters																										
P1	Not Sampled For These Parameters																										
P2	39,000	ND	ND	91	ND	22	2.3	ND	ND	ND	0.044	0.039	4,400	>3,531.	2650	2.3	4.6	1270	15.2	ND	131	1,510	ND	Not Sampled For These Parameters			
P3	6,600	ND	ND	2,000	ND	2.4	6.6	5.2 J	ND	ND	0.14	0.082	258	154	734 B	ND	6.6	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
P4	11,000	ND	ND	860	ND	2.1	7.4	ND	ND	ND	0.061	ND	442	150	557	0.29 HF	7.7	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
P5	180,000	ND	ND	150	ND	1.6 B	4.1	0.66 J	ND	ND	0.034	ND	761	NS	1040	0.35 HF	4.4	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
P6	120,000	ND	ND	620	ND	1.4 B	6	24.8	ND	ND	0.18	0.082	265	>82.08 b	592	ND	6	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P7	74,000	ND	ND	ND	0.044 J	1.5	2.6	11.5	ND	ND	0.036	ND	252	111 H b	468	ND	2.6	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P8	81,000	ND	ND	2,200	ND	1.3	4.7	ND	ND	ND	0.074	ND	239	22.9 B	470	ND	4.7	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P9	180	ND	ND	530	ND	1.3	ND	ND	ND	ND	0.077	ND	218	ND	676	ND	6.2	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P10	110	ND	ND	1,100	ND	0.29	0.86	29.7	ND	ND	0.045	ND	50.7	40.8	400	ND	0.86	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P11	52,000	ND	ND	2,300	ND	0.60	3.3	12.7	ND	ND	0.39	0.62	275	13.6	432	ND	3.3	25.0	ND	ND	ND	15.3	ND	Not Sampled For These Parameters			
P12	80,000	ND	ND	4,900	ND	0.88	3.5	7.7	ND	ND	0.10	ND	503 B	7.5 b	432 B	ND	3.5	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth	Water Level Measurement	Top of Casing Elevation	Head Elevation	pH	Dissolved Oxygen	Oxidation Reduction Potential	Specific Conductance	Turbidity	Temperature	Carbon, Total Organic	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
					(feet)	(ft. ATOC)	(ft. AMSL)	(ft. AMSL)	(SU)	(mg/L)	(mV)	(mS/cm)	(NTUs)	(°C)	(mg/L)	(ug/L)																										
A1-GP15-S	Monitoring event	BL1	6/17/2010	-1783	15	0.54	687.7	687.2	6.88	3.94	1.1	0.657	18.5	12.88	NS	ND	ND	ND	ND	ND	ND	ND	ND	9.3 J	23 J	ND	0.52 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	BL3	8/2/2010	-1737	15	4.2	687.7	683.5	6.97	1.71	-21.2	0.725	6.1	20.69	NS	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	BL4	3/11/2015	-55	15	1.2	687.7	686.5	6.85	1.4	42	0.801	59.8	6.37	2.2	Not Sampled For These Parameters																										
	Monitoring event	P1	7/29/2015	85	15	3.2	687.7	684.5	7.61	5.79	42.1	0.725	50.2	22.04	3.6 B	3	ND	ND	ND	ND	ND	ND	ND	ND	11	ND	ND	ND	ND	ND	6.5	ND	ND	ND	ND	ND	ND	ND	ND	4	ND	ND
	Monitoring event	P2	4/8/2016	339	15	0.1	687.7	687.6	7.14	6.13	3.5	0.647	99	8.46	2.9	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P3	7/11/2016	433	15	6.11	687.7	681.6	7.3	5.96	14.2	0.73	53	18.69	3.4	0.99 J	ND	ND	4.5	ND	ND	ND	ND	ND	4.0 J	ND	ND	0.47 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P4	10/7/2016	521	15	11	687.7	676.7	7.52	3.2	138.7	0.675	86.7	15.46	2.7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P5	1/23/2017	629	15	NA	687.7	NA	6.66	1.49	75.2	0.687	50	9.6	5.2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P6	4/12/2017	708	15	0.35	687.7	687.3	7.48	11.4	50.6	0.494	47.6	11.4	3.2	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P7	7/6/2017	793	15	4.35	687.7	683.3	7.64	5.77	-61	0.66	17.2	17.5	2.2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P8	10/17/2017	896	15	6.4	687.7	681.3	7.5	3.95	-220	0.71	21.8	13.3	3.4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.29	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P9	1/2/2018	973	15	NA	687.7	NA	Not Sampled (well could not be located under snow)																																	
	Monitoring event	P10	4/10/2018	1071	15	2.3	687.7	685.4	7.2	15.55	51.8	0.318	NA	7.77	4.7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Well ID	Event	Carbon Dioxide	Ethane	Ethene	Methane	Nitrate	Manganese	Ferric iron	Sulfate	Sulfide	Nitrite	Phosphorous	Ammonia	COD	BOD	Total Alkalinity	Ferrous Iron	Iron	Acetic Acid	Formic Acid	Lactic Acid	n-Butyric Acid	Propionic Acid	Pyruvic Acid	Dehalococcoides spp (1)	TCE R-Dase (1)	BAV1 VC R-Dase (1)	VC R-Dase
		(ug/L)				(mg/L)																			(cells / mL)			
A1-GP15-S	BL1																											
	BL3																											
	BL4																											
	P1																											
	P2																											
	P3																											
	P4	Not Sampled For These Parameters																										
	P5																											
	P6																											
	P7																											
	P8																											
	P9																											
	P10																											

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth	Water Level Measurement	Top of Casing Elevation	Head Elevation	pH	Dissolved Oxygen	Oxidation Reduction Potential	Specific Conductance	Turbidity	Temperature	Carbon, Total Organic
					(feet)	(ft. ATOC)	(ft. AMSL)	(ft. AMSL)	(SU)	(mg/L)	(mV)	(mS/cm)	(NTUs)	(°C)	(mg/L)
A1-GP18-S	Monitoring event	BL1	6/18/2010	-1782	18	4.12	690.4	686.3	6.95	6.28	36.3	0.737	30	13.31	NS
	Monitoring event	BL2	8/2/2010	-1737	15	5.25	690.4	685.1	7.12	3.36	-66.8	0.677	5.1	16.29	NS
	Monitoring event	BL3	11/5/2014	-181	18	4.5	690.4	685.9	7.3	3.11	-69.7	0.587	NS	12.36	NS
	Monitoring event	BL4	3/11/2015	-55	18	5.25	690.4	685.1	7.38	1.93	50	0.699	11	8.35	1
	Monitoring event	P1	7/27/2015	83	18	5.35	690.4	685	6.08	0.89	-40.5	3.265	22.9	14.3	829 B
	Monitoring event	P2	1/7/2016	247	18	4.65	690.4	685.7	7.01	NA	-48.2	1.726	NA	8.24	178
	Monitoring event	P3	4/8/2016	339	18	3.2	690.4	687.2	6.94	1.41	-94.3	1.186	893	7.65	89.1
	Monitoring event	P4	7/8/2016	430	18	7.1	690.37	683.27	NA	1.47	-5.2	1.059	>1000	14.21	20.5
	Monitoring event	P5	10/7/2016	521	18	9.1	690.4	681.3	7.05	6.46	46.1	1.414	69	16.75	8.9
	Monitoring event	P6	1/23/2017	629	18	NA	690.37	NA	7.14	0.45	-117.3	0.758	50	10.38	5.1
	Monitoring event	P7	4/10/2017	706	18	3.72	690.4	686.7	7.04	NA	-70.1	763	333	6.5	4.9
	Monitoring event	P8	7/6/2017	793	18	5.95	690.4	684.4	7.21	0.51	-148	0.79	3308	15.1	4.8
	Monitoring event	P9	10/16/2017	895	18	6.9	690.4	683.5	7.09	3.02	-299	0.9	1474	13.4	3.5
	Monitoring event	P10	1/5/2018	976	18	NA	690.37	NA	NA	1.2	-149.9	0.58	72.6	9.26	72.4
	Monitoring event	P11	4/9/2018	1070	18	3.5	690.37	686.87	7.16	19.7	-80.4	0.481	NA	8.12	3.8

Event	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
	(ug/L)																										
BL1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
BL2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
BL3	Not Sampled For These Parameters																										
BL4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P1	ND	ND	ND	ND	ND	ND	ND	130	ND	140	ND	ND	ND	ND	ND	3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P2	ND	ND	ND	ND	ND	ND	ND	50	ND	16 J	ND	ND	ND	ND	ND	2.4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P3	ND	ND	ND	ND	ND	ND	ND	36	ND	18 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P4	ND	ND	ND	ND	ND	ND	ND	20	ND	11	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P5	ND	ND	ND	ND	ND	ND	ND	4.2 J	ND	5.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.16 J	ND	ND	ND	ND	ND	ND	ND	ND
P7	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P9	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P10	44	84	1.6 J	400	3.7 J	2.1 J	ND	16 J	ND	22 J	ND	ND	ND	ND	1,300	8.2	ND	ND	ND	ND	ND	ND	3.2 J	ND	2.4 J	22	ND
P11	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Event	Carbon Dioxide	Ethane	Ethene	Methane	Nitrate	Manganese	Ferric iron	Sulfate	Sulfide	Nitrite	Phosphorous	Ammonia	COD	BOD	Total Alkalinity	Ferrous Iron	Iron	Acetic Acid	Formic Acid	Lactic Acid	n-Butyric Acid	Propionic Acid	Pyruvic Acid	Dehalococcoides spp (1)	TCE R-Dase (1)	BAV1 VC R-Dase (1)	VC R-Dase
	(ug/L)				(mg/L)																			(cells / mL)			
BL1	Not Sampled For These Parameters																										
BL2																											
BL3	8,200	NS	NS	260	ND	2.3	121	27.8	NS	ND	0.65	0.18 B	ND	ND	359 B	ND HF	121	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
BL4	Not Sampled For These Parameters																										
P1	17,000	ND	ND	520	ND	0.83	17.8	ND	NS	ND	1.2	0.24	2440	1140	1100	2.1	19.9	329	ND	ND	111	446	ND	Not Sampled For These Parameters			
P2	6,100	ND	ND	1,800	ND	0.23	2	ND	ND	ND	0.5	0.16	596	ND	775 B	ND	2	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
P3	6,700	ND	ND	1,100	ND	0.76	34	ND	ND	ND	0.41	ND	147	101 H	660	ND	34	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
P4	69,000	ND	ND	910	ND	0.39 B	19.3	ND	ND	ND	2.0 B	0.05	41.7 B	14.2 b	489	0.12 H F	19.4	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
P5	80,000	ND	ND	2,400	ND	0.73 B	32.7	1.8 J	2.8	ND	1.7	0.1	54.7	5.8 B	442	ND	32.7	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P6	53,000	ND	ND	1,000	ND	0.63	8.2	21.3	ND	ND	0.72	0.015 J	6.5 JF1	54.7 H b	415	ND	8.2	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P7	68,000	ND	ND	1,900	ND	0.65	8.1	16.4	ND	ND	0.5	ND	ND	5.1	435	ND	8.1	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P8	######	ND	ND	350	ND	0.42	7.5	7.3	ND	ND	0.45	0.078	10.8	5.7	451	ND	7.5	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P9	######	ND	ND	3,900	ND	0.32	4.9	6.9	ND	ND	0.14	0.073	ND	2.3	513	ND	4.9	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P10	52,000	ND	ND	14,000	ND	2.2	99.8	32.1	ND	ND	3.2	0.1 F1	5.7 J B	5.7	415	ND	99.8	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
P11	59,000	ND	ND	3,600	ND	0.54	7.9	34.7	ND	ND	0.18	ND	20.2	4.9 b	377	ND	7.9	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
MW-30	Monitoring event	BL1	6/18/2010	-1782	18.85	3.09	689.7	686.6	7.08	3.16	-90.7	0.922	16.44	17.84	NS
	Monitoring event	BL2	8/3/2010	-1736	18.85	3.9	689.7	685.8	7.7	1.0	-123	0.917	2.22	19.27	NS
	Monitoring event	P1	7/29/2015	85	18.85	3.95	689.7	685.7	7.34	0.39	-120	0.846	1.49	18.73	3.7
	Monitoring event	P2	4/8/2016	339	18.85	2.95	689.7	686.7	7.47	0.27	-72	0.626	10.94	10.41	2.5 B
	Monitoring event	P3	7/14/2016	436	18.85	10.9	689.7	678.8	7.37	0.09	-123	0.734	5.59	17.56	3.4
	Monitoring event	P4	10/11/2016	525	18.85	10.4	689.7	679.3	7.50	0.56	-112	0.829	5.34	18.11	3.3
	Monitoring event	P5	1/25/2017	631	18.85	3.96	689.7	685.7	7.41	0.45	-59	0.785	11.5	11.71	3.2
	Monitoring event	P6	4/12/2017	708	18.85	12.35	689.7	677.3	7.43	0.26	-114	0.759	14.6	11.2	2.9
	Monitoring event	P7	7/7/2017	794	18.85	4.1	689.7	685.6	7.56	0.18	-102	0.73	1.82	17.4	1.6
	Monitoring event	P8	10/19/2017	898	18.85	4.86	689.7	684.8	7.45	0.26	-310	0.93	2.18	17.4	3.1
	Monitoring event	P9	1/2/2018	973	18.85	3.47	689.7	686.2	7.57	1.96	-33.4	0.346	NA	7.6	2.2
	Monitoring event	P10	4/11/2018	1072	18.85	3.11	689.7	686.6	7.32	0.3	-97.5	0.187	NA	10.94	2.2 B

(ug/L)

Well ID	Event	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
MW-30	BL1	ND	ND	ND	2.1 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	6.4	ND	ND	ND	ND	ND	ND	ND	ND	1.4 J	4.9J	ND
	BL2	ND	ND	ND	2.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	7.7	ND	ND	ND	ND	ND	ND	ND	ND	1.6 J	5.9	ND
	P1	ND	ND	ND	1.4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	5.2	ND	ND	ND	ND	ND	ND	ND	ND	1.1	1.4	ND
	P2	ND	ND	ND	1.8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	7.2	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.8	ND
	P3	ND	ND	ND	3.4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	16	ND	ND	ND	ND	ND	ND	ND	ND	2.4	ND	ND
	P4	ND	ND	ND	2.1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	11	ND	ND	ND	ND	ND	ND	ND	ND	0.56 J	1.3	ND
	P5	ND	ND	ND	1.1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.5	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.8	ND
	P6	ND	ND	ND	1.2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.8	ND	ND	ND	ND	ND	ND	ND	ND	ND	2.1	ND
	P7	ND	ND	ND	0.54	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	2.0	ND
	P8	ND	ND	ND	1.2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.58	ND	ND	ND	ND	ND	ND	ND	ND	ND	2.5	ND
	P9	ND	ND	ND	1.1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.3	ND
	P10	ND	ND	ND	0.75	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.95	ND

Well ID	Carbon Dioxide (ug/L)	Ethane (ug/L)	Ethene (ug/L)	Methane (ug/L)	Nitrate (mg/L)	Manganese (mg/L)	Ferric iron (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrite (mg/L)	Phosphorous (mg/L)	Ammonia (mg/L)	COD (mg/L)	BOD (mg/L)	Total Alkalinity (mg/L)	Ferrous Iron (mg/L)	Iron (mg/L)	Acetic Acid (mg/L)	Formic Acid (mg/L)	Lactic Acid (mg/L)	n-Butyric Acid (mg/L)	Propionic Acid (mg/L)	Pyruvic Acid (mg/L)	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1) (cells / mL)	BAV1 VC R-Dase (1) (cells / mL)	VC R-Dase (cells / mL)
MW-30	Not Sampled For These Parameters																										

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)	1,1,1-Trichloroethane (ug/L)	1,1,2-Trichloro-1,2,2-trifluoroethane (ug/L)	1,1,2-Trichloroethane (ug/L)	1,1-Dichloroethane (ug/L)	1,1-Dichloroethene (ug/L)	1,2-Dichloroethane (ug/L)	2-Hexanone (ug/L)	2-Butanone (MEK) (ug/L)	4-Methyl-2-pentanone (ug/L)	Acetone (ug/L)	Benzene (ug/L)	Carbon Disulfide (ug/L)	Chloroethane (ug/L)	Chloroform (ug/L)	Chloromethane (ug/L)	cis-1,2-Dichloroethene (ug/L)	Dichlorodifluoromethane (ug/L)	Ethylbenzene (ug/L)	Methylcyclohexane (ug/L)	Methylene chloride (ug/L)	Methyl Acetate (ug/L)	Tetrachloroethene (ug/L)	Toluene (ug/L)	trans-1,2-Dichloroethene (ug/L)	Trichloroethene (ug/L)	Vinyl chloride (ug/L)	Xylenes, Total (ug/L)
MW-35S	Monitoring event	BL1	6/17/2010	-1783	14.5	1.58	688.6	687	6.49	9.72	145.5	0.955	1.6	13.17	NS	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	BL2	8/2/2010	-1737	14.5	5.71	688.6	682.9	6.33	1.38	-3.9	0.955	0.89	17.63	NS	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.8 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	BL3	3/11/2015	-55	15	3.6	688.6	685	7.07	3.9	82.4	0.873	5.65	7.03	2.4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P1	7/28/2015	84	15	4.95	688.6	683.6	7.15	4.43	105.8	0.865	2.51	17.26	2 B	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P2	4/8/2016	339	15	0.56	688.6	688	7.3	5.51	29.2	0.54	11.2	7.4	5.4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P3	7/13/2016	435	15	7.95	688.6	680.6	7.07	0.49	-13.3	0.874	5.24	16.53	2.1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P4	10/11/2016	525	15	13.15	688.6	675.4	7.24	1.66	17.6	0.811	5.47	15.11	3	ND	ND	ND	ND	ND	ND	ND	5.1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P5	1/23/2017	629	15	1.25	688.6	687.3	7.16	6.73	32.2	0.825	2.96	8.79	2.1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P6	4/10/2017	706	15	0.6	688.6	688	6.96	4.65	119.1	0.815	3.21	10.7	2.3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P7	7/7/2017	794	15	6.1	688.6	682.5	7.18	3.03	-67	0.89	8.57	14.7	2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P8	10/17/2017	896	15	9.5	688.6	679.1	7.15	0.35	-348	1.0	1.06	14.4	2.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P9	1/4/2018	975	15	0.83	688.6	687.7	8.6	7.8	-57.3	0.585	NA	8.63	2.4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P10	4/9/2018	1070	15	0	688.6	688.6	7.28	4.79	37.1	0.4	NA	7.68	2.6 B	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Well ID	Carbon Dioxide (ug/L)	Ethane (ug/L)	Ethene (ug/L)	Methane (ug/L)	Nitrate (mg/L)	Manganese (mg/L)	Ferric iron (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrite (mg/L)	Phosphorous (mg/L)	Ammonia (mg/L)	COD (mg/L)	BOD (mg/L)	Total Alkalinity (mg/L)	Ferrous Iron (mg/L)	Iron (mg/L)	Acetic Acid (mg/L)	Formic Acid (mg/L)	Lactic Acid (mg/L)	n-Butyric Acid (mg/L)	Propionic Acid (mg/L)	Pyruvic Acid (mg/L)	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1) (cells / mL)	BAV1 VC R-Dase (1) (cells / mL)	VC R-Dase (cells / mL)
MW-35S	Not Sampled For These Parameters																										

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
MW-36S	Monitoring event	BL1	6/17/2010	-1783	15	2.98	689.8	686.8	6.82	13.05	135.3	1.227	3.31	14.41	NS
MW-36S	Monitoring event	BL2	8/3/2010	-1736	15	5.4	689.8	684.4	6.85	1.6	-85.7	1.139	2.7	16.28	NS
MW-36S	Monitoring event	BL3	3/10/2015	-56	15	3.21	689.8	686.6	6.95	2.87	214.7	1.064	2.43	6.03	2
MW-36S	Monitoring event	P1	7/29/2015	85	15	3.85	689.8	686	6.12	0.18	-142.1	2.958	3.81	17.43	1130 B
MW-36S	Monitoring event	P2	4/8/2016	339	15	3.1	689.8	686.7	6.87	0.83	-107.2	1.552	1.2	8.21	76.5
MW-36S	Monitoring event	P3	7/11/2016	433	15	7.54	689.8	682.2	6.86	0.45	-71.6	1.613	10.4	14.47	21.5
MW-36S	Monitoring event	P4	10/12/2016	526	15	5.9	689.8	683.9	5.79	0.3	-145	10.07	19.7	17.16	15.1
MW-36S	Monitoring event	P5	1/24/2017	630	15	2.9	689.8	686.9	7.05	0.2	-241	1.268	7.44	6.84	6.1
MW-36S	Monitoring event	P6	4/12/2017	708	15	5.15	689.8	684.6	6.8	0.07	-187	1.189	4.61	7.6	4.5
MW-36S	Monitoring event	P7	7/6/2017	793	15	6.1	689.8	683.7	7.1	0.07	-73.5	1.24	4.35	16.2	5
MW-36S	Monitoring event	P8	10/17/2017	896	15	7.5	689.8	682.3	7.09	0.16	-329	1.36	3.82	14.9	5
MW-36S	Monitoring event	P9	1/4/2018	975	15	3.06	689.8	686.7	9.12	1.17	-33.7	0.812	NA	7.52	4.2
MW-36S	Monitoring event	P10	4/9/2018	1070	15	2.81	689.8	687	7.16	1.16	-66.9	0.781	NA	7.02	3.7

(ug/L)

Event	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
BL1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.2 J	ND	ND	ND	2.6 J	ND	ND	ND	ND	ND	ND	ND	ND	7.2	ND	ND
BL2	ND	ND	ND	0.38 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.5 J	ND	ND	ND	ND	ND	ND	ND	ND	0.58 J	ND	ND
BL3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P1	ND	ND	ND	0.52 J	ND	ND	28	170	ND	400	ND	2.1	ND	ND	ND	1.4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P2	ND	ND	ND	ND	ND	ND	ND	42	ND	22	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P3	ND	ND	ND	ND	ND	ND	ND	22	ND	18	ND	ND	ND	ND	ND	1.1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P4	ND	ND	ND	ND	ND	ND	ND	3.2	ND	ND	ND	ND	ND	ND	ND	1.8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.20 J	ND	ND	ND	1.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P6	ND	ND	ND	ND	ND	ND	ND	ND	ND	4.0 J	ND	0.27 J	ND	ND	ND	1.5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P9	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P10	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	1.2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Well ID	Carbon Dioxide (ug/L)	Ethane (ug/L)	Ethene (ug/L)	Methane (ug/L)	Nitrate (mg/L)	Manganese (mg/L)	Ferric iron (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrite (mg/L)	Phosphorous (mg/L)	Ammonia (mg/L)	COD (mg/L)	BOD (mg/L)	Total Alkalinity (mg/L)	Ferrous Iron (mg/L)	Iron (mg/L)	Acetic Acid (mg/L)	Formic Acid (mg/L)	Lactic Acid (mg/L)	n-Butyric Acid (mg/L)	Propionic Acid (mg/L)	Pyruvic Acid (mg/L)	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1) (cells / mL)	BAV1 VC R-Dase (1) (cells / mL)	VC R-Dase (cells / mL)
MW-36S	Not Sampled For These Parameters																										

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
MW-42S	Monitoring event	BL1	4/7/2011	-1489	14.3	10.9	689.1	678.2	6.92	1.89	70.8	1.692	2.3	11.52	NS
MW-42S	Monitoring event	BL2	3/12/2015	-54	14.3	1.8	689.1	687.3	6.94	0.91	-101.3	1.855	8.04	7.55	15.7
MW-42S	Monitoring event	P1	6/12/2015	38	NA (Grab Sample)										ND
MW-42S	Monitoring event	P2	7/27/2015	83	14.3	2.7	689.08	686.38	6.28	0.3	-92.7	2.521	2.85	19.35	1560
MW-42S	Monitoring event	P3	4/8/2016	339	14.3	3	689.1	686.1	6.67	0.36	-111.7	1.96	7.48	9.49	620
MW-42S	Monitoring event	P4	7/14/2016	436	14.3	5.38	689.1	683.7	6.47	0.27	-81.4	2.784	5.54	18.7	796
MW-42S	Monitoring event	P5	10/13/2016	527	14.3	2.3	689.1	686.8	6.83	0.21	-86.4	1.358	3.76	18.7	287
MW-42S	Monitoring event	P6	1/25/2017	631	14.3	3.06	689.1	686	6.84	0.78	-95.7	1.643	3.12	8.83	238
MW-42S	Monitoring event	P7	4/12/2017	708	14.3	1.68	689.08	687.4	7.02	0.12	-115.3	1.094	4.89	9.1	136
MW-42S	Monitoring event	P8	7/10/2017	797	14.3	2.1	689.1	687	6.8	0.21	-67.8	1.39	4.68	17.4	238
MW-42S	Monitoring event	P9	10/19/2017	898	14.3	6.35	689.1	682.7	6.56	0.14	-344.2	2.66	3.77	18.8	395
MW-42S	Monitoring event	P10	1/2/2018	973	14.3	3.6	689.1	685.5	7.98	2.39	-28.2	0.914	NA	5.34	162
MW-42S	Monitoring event	P11	4/11/2018	1072	14.3	2.57	689.08	686.51	6.91	0.72	-78.4	1.011	NA	8.42	625

Event	1,1,1-Trichloroethane (ug/L)	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
BL1	25,000	1,700	240 J	8,550	6,100	76	11	510 J	3.5 J	400	1.9	9	100 J	4.8	ND	1,000	ND	ND	ND	11	ND	6	1,100	31	13,000	27	ND
BL2	19,000	14,000	240	12,000	6,300	ND	ND	ND	ND	ND	ND	ND	160 J	ND	ND	5,700	ND	ND	ND	ND	ND	ND	1,200	ND	12,000	ND	ND
P1	3,700	1,600	100	7,600	2,300	44 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	6,400	ND	ND	ND	ND	ND	ND	520	ND	2,700	ND	ND
P2	1,700	660	71 J	9,700	2,400	44 J	ND	ND	ND	ND	ND	ND	170 J	ND	ND	6,700	ND	ND	ND	ND	ND	ND	590	ND	280	ND	ND
P3	3,600	5,000	ND	7,100	5,000	ND	ND	ND	ND	ND	ND	ND	15,000	ND	ND	13,000	ND	ND	ND	140 J	ND	ND	1,000	ND	ND	610	ND
P4	12,000	8,300	120 J	11,000	7,800	110 J	ND	ND	ND	ND	ND	ND	10,000	ND	ND	29,000	890	ND	ND	120 J	ND	ND	2,100	ND	100 J	530	ND
P5	440	640	ND	2,000	520	ND	ND	ND	ND	ND	ND	ND	14,000	ND	ND	2,700	ND	ND	ND	ND	ND	ND	340	ND	ND	ND	ND
P6	1,200	1,600	ND	2,900	790	130 J	ND	ND	ND	ND	ND	ND	21,000	ND	ND	3,800	ND	ND	ND	230 J	ND	ND	1,000	ND	ND	2,400	ND
P7	230	440	ND	1,700	220	74 J	ND	ND	ND	ND	ND	ND	10,000 F	ND	ND	1,100	ND	ND	ND	ND	ND	ND	360	ND	ND	1,400	ND
P8	ND	1,200	ND	1,800	150	ND	ND	ND	ND	ND	ND	ND	24,000	ND	ND	690	ND	ND	ND	ND	ND	ND	1,100	ND	ND	3,600	ND
P9	4,100	7,500	48	8,900	1,700	170	ND	ND	ND	ND	ND	1,100	19,000	ND	ND	28,000	ND	ND	ND	ND	ND	ND	1,900	280	54	12,000	ND
P10	740	850	ND	2,500	ND	ND	ND	ND	ND	ND	ND	ND	21,000	ND	ND	1,200	ND	ND	ND	ND	ND	ND	950	ND	ND	4,700	ND
P11	390	740	ND	2,000	120 J	ND	ND	ND	ND	ND	ND	ND	8,400	ND	ND	1,100	ND	ND	ND	ND	ND	ND	670	ND	ND	2,800	ND

Event	Carbon Dioxide (ug/L)	Ethane	Ethene	Methane	Nitrate (mg/L)	Manganese	Ferric iron	Sulfate	Sulfide	Nitrite	Phosphorous	Ammonia	COD	BOD	Total Alkalinity	Ferrous Iron	Iron	Acetic Acid	Formic Acid	Lactic Acid	n-Butyric Acid	Propionic Acid	Pyruvic Acid	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1)	BAV1 VC R-Dase (1)	VC R-Dase
BL1	Not Sampled For These Parameters																										
BL2	Not Sampled For These Parameters																										
P1	Not Sampled For These Parameters																										
P2	Not Sampled For These Parameters																							<2.5E+01	<2.5E+01	<2.5E+01	<2.5E+01
P3	Not Sampled For These Parameters																										
P4	Not Sampled For These Parameters																										
P5	Not Sampled For These Parameters																										
P6	Not Sampled For These Parameters																										
P7	Not Sampled For These Parameters																							3.98E+04	1.28E+04	<2.50E+01	1.04E+03
P8	Not Sampled For These Parameters																										
P9	Not Sampled For These Parameters																										
P10	Not Sampled For These Parameters																										
P11	Not Sampled For These Parameters																							4.04E+04	4.29E+04	3.33E+01	3.56E+03

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
MW-43S	Monitoring event	BL1	4/7/2011	-1489	14.5	2.57	689.1	686.6	7.04	5.68	47.2	0.794	3.62	11.93	NS
	Monitoring event	BL2	3/12/2015	-54	14.5	2.68	689.1	686.5	7.45	1.0	-140	0.615	2.58	9.48	2.1
	Monitoring event	P1	7/29/2015	85	14.5	2.35	689.14	686.79	5.63	0.31	-23.2	4.348	10.82	21.25	2,060 B
	Monitoring event	P2	4/8/2016	339	14.5	2.3	689.1	686.8	6.89	0.28	-122	2.139	15.9	11.08	22.8
	Monitoring event	P3	7/13/2016	435	14.5	2.15	689.14	686.99	6.82	0.07	-101.6	2.23	23.4	22.29	21
	Monitoring event	P4	10/13/2016	527	14.5	3.27	689.1	685.9	6.88	0.22	-80.7	1.87	54.5	18.93	22.2
	Monitoring event	P5	1/25/2017	631	14.5	2.00	689.1	687.1	6.81	0.78	-100	1.698	11.9	9.41	17
	Monitoring event	P6	4/11/2017	707	14.5	2.94	689.1	686.2	6.77	0.15	-93.5	1.536	21.5	13.7	12.6
	Monitoring event	P7	7/10/2017	797	14.5	3.35	689.1	685.8	7.02	0.24	-77.3	1.42	13.6	18.4	11.9
	Monitoring event	P8	10/19/2017	898	14.5	2.62	689.1	686.5	6.88	0.2	-189	1.53	9.91	18	12.3
	Monitoring event	P9	1/2/2018	973	14.5	3.35	689.1	685.8	8.48	1.92	-83.7	0.894	NA	6.65	11.9
	Monitoring event	P10	4/11/2018	1072	14.5	1.84	689.1	687.3	6.9	0.95	-83.7	0.717	NA	10.95	4.8

(ug/L)

Event	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform
BL1	15	7.4	ND	13	3.5 J	ND	ND	3.3 J	ND	13	ND	1.1	12	ND
BL2	ND	ND	ND	1.8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P1	ND	ND	ND	29	ND	ND	3.1 J	250	ND	980	1.3	ND	13	ND
P2	ND	ND	ND	ND	ND	ND	ND	57	ND	33 J	ND	ND	9.8	ND
P3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	7.5	ND
P4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	10	ND
P5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	11	ND
P6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	8.1	ND
P7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	6.5	ND
P8	ND	ND	ND	0.48	ND	ND	ND	ND	ND	ND	0.98	ND	ND	ND
P9	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	6.4	ND
P10	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Event	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
BL1	ND	34	ND	ND	0.69 J	ND	ND	ND	1.5	ND	15	19	1.7 J
BL2	ND	3.7	ND	ND	0.82 J	ND	ND	ND	ND	ND	ND	1.7	0.73
P1	ND	46	ND	ND	ND	ND	ND	ND	0.97 J	ND	0.60 J	7	1.7 J
P2	ND	ND	ND	ND	ND	5.4	ND	ND	ND	ND	ND	ND	ND
P3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.8	ND
P5	ND	ND	ND	ND	ND	3.0 J	ND	ND	ND	ND	ND	ND	ND
P6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P8	ND	0.64	ND	0.54	0.12	ND	ND	ND	1.7	0.8	ND	ND	2.9
P9	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P10	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	3.0 J

Event	Carbon Dioxide, Ethane, Ethene, Methane (ug/L); Nitrate, Manganese, Ferric iron, Sulfate, Sulfide, Nitrite, Phosphorous, Ammonia, COD, BOD, Total Alkalinity, Ferrous Iron, Iron, Acetic Acid, Formic Acid, Lactic Acid, n-Butyric Acid, Propionic Acid, Pyruvic Acid (mg/L)	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1) (cells / mL)	BAV1 VC R-Dase (1) (cells / mL)	VC R-Dase (cells / mL)
BL1	Not Sampled For These Parameters				
BL2					
P1					
P2					
P3	Not Sampled For These Parameters	1.77E+02	1.58E+01J	<2.5E+01	<2.5E+01
P4	Not Sampled For These Parameters				
P5					
P6					
P7					
P8					
P9					
P10					

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
MW-44S	Monitoring event	BL	6/1/2011	-1434	15	8.55	689	680.4	7	7.45	324	0.66	45.1	15.98	NS
MW-44S	Monitoring event	P1	7/29/2015	85	15	1.6	689	687.4	7.08	0.41	-140	1.004	3.04	15.84	31.6 B
MW-44S	Monitoring event	P2	4/8/2016	339	15	1.55	689	687.5	7.23	0.43	-81	0.897	4.1	8.56	3.1
MW-44S	Monitoring event	P3	7/14/2016	436	15	4	689	685	7.18	0.4	-99.5	0.954	3.99	15.47	2.1
MW-44S	Monitoring event	P4	10/11/2016	525	15	2.55	689	686.5	7.21	1.28	-92.5	0.947	6.9	15.33	2.3
MW-44S	Monitoring event	P5	1/25/2017	631	15	1.09	689	688	7.22	0.4	-82.6	0.915	7.86	8.32	2.4
MW-44S	Monitoring event	P6	4/7/2017	703	15	0.89	689	688.2	7.12	0.32	-94.1	0.831	10.1	7.4	2.2
MW-44S	Monitoring event	P7	7/10/2017	797	15	2.45	689	686.6	7.32	0.43	-66.7	0.88	4.62	15	1.5
MW-44S	Monitoring event	P8	10/16/2017	895	15	2.15	689	686.9	7.29	0.77	-286	0.93	2.36	13.8	1.3
MW-44S	Monitoring event	P9	1/2/2018	973	15	1.32	689	687.7	8.01	1.36	-60.4	0.588	NA	7.5	1.5
MW-44S	Monitoring event	P10	4/11/2018	1072	15	0.88	689	688.2	7.32	2.28	-111	0.58	NA	6.75	2.4

(ug/L)

Well ID	Event	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
MW-44S	BL	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-44S	P1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.96	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-44S	P2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-44S	P3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-44S	P4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-44S	P5	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-44S	P6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-44S	P7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-44S	P8	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-44S	P9	ND	0.64 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-44S	P10	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Carbon Dioxide (ug/L)	Ethane	Ethene	Methane
Not Sampled For These Parameters			

Nitrate (mg/L)	Manganese	Ferric iron	Sulfate	Sulfide	Nitrite	Phosphorous	Ammonia	COD	BOD	Total Alkalinity	Ferrous Iron	Iron	Acetic Acid	Formic Acid	Lactic Acid	n-Butyric Acid	Propionic Acid	Pyruvic Acid	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1)	BAV1 VC R-Dase (1)	VC R-Dase
Not Sampled For These Parameters																						

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
MW-35D	Monitoring event	BL1	6/17/2010	-1783	26	8.14	698.7	690.5	8.32	2.27	61.4	0.492	24.8	11.57	NS
MW-35D	Monitoring event	BL2	8/2/2010	-1737	26	7.83	698.7	690.8	7.06	0.68	58.7	0.499	7.23	18.46	NS
MW-35D	Monitoring event	BL3	11/5/2014	-181	NS	8	698.7	690.7	7.47	0.87	-56.6	0.399	NS	12.98	NS
MW-35D	Monitoring event	BL4	3/12/2015	-54	29	6.65	698.7	692	7.23	1.08	-64	0.511	10.01	8.41	4.7
MW-35D	Monitoring event	P1	7/28/2015	84	26	6.8	698.66	691.86	7.71	0.9	-104.4	0.454	4.18	13.97	3.3 B
MW-35D	Monitoring event	P2	1/8/2016	248	26	7.6	698.7	691.1	7.73	0.84	-91.9	0.494	9.95	10.21	2.0 B
MW-35D	Monitoring event	P3	4/8/2016	339	26	6.96	698.7	691.7	7.76	0.38	-28.5	0.407	7.11	9.53	1.9
MW-35D	Monitoring event	P4	7/12/2016	434	26	7.42	698.66	691.24	7.58	0.13	-98.6	0.466	83.7	15.93	1.5
MW-35D	Monitoring event	P5	10/11/2016	525	26	8.65	698.66	690.01	7.76	0.78	-115	0.455	26	14.3	1.9
MW-35D	Monitoring event	P6	1/24/2017	630	26	8.07	698.66	690.59	7.61	0.35	-117.8	0.294	84	10.28	3.6 B
MW-35D	Monitoring event	P7	4/10/2017	706	26	7.44	698.7	691.2	7.81	0.16	-153.8	0.39	15	13.4	2.9
MW-35D	Monitoring event	P8	7/7/2017	794	26	8.25	698.66	690.41	7.81	0.22	-77.2	0.438	20.8	14.9	1.6
MW-35D	Monitoring event	P9	10/17/2017	896	26	8.9	698.7	689.8	7.87	0.23	-321	0.491	11.8	13.4	2.2
MW-35D	Monitoring event	P10	1/3/2018	974	26	7.29	698.7	691.4	9.9	1.46	-145	0.319	NA	9.88	2.6
MW-35D	Monitoring event	P11	4/10/2018	1071	26	6.54	698.7	692.1	7.46	0.78	-108.8	0.311	NA	9.77	7.3

(ug/L)

Event	Date	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
BL1	6/17/2010	ND	ND	ND	ND	ND	ND	ND	ND	ND	4.1 J	ND	0.71 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
BL2	8/2/2010	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.69 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
BL3	11/5/2014	Not Sampled For These Parameters																										
BL4	3/12/2015	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P1	7/28/2015	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P2	1/8/2016	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P3	4/8/2016	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P4	7/12/2016	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P5	10/11/2016	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P6	1/24/2017	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P7	4/10/2017	ND	ND	ND	ND	ND	ND	ND	ND	ND	5.4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P8	7/7/2017	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P9	10/17/2017	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P10	1/3/2018	ND	ND	ND	ND	ND	ND	ND	ND	ND	12	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P11	4/10/2018	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Event	Date	Carbon Dioxide (ug/L)	Ethane (ug/L)	Ethene (ug/L)	Methane (ug/L)	Nitrate (mg/L)	Manganese (mg/L)	Ferric iron (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrite (mg/L)	Phosphorous (mg/L)	Ammonia (mg/L)	COD (mg/L)	BOD (mg/L)	Total Alkalinity (mg/L)	Ferrous Iron (mg/L)	Iron (mg/L)	Acetic Acid (mg/L)	Formic Acid (mg/L)	Lactic Acid (mg/L)	n-Butyric Acid (mg/L)	Propionic Acid (mg/L)	Pyruvic Acid (mg/L)	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1) (cells / mL)	BAV1 VC R-Dase (1) (cells / mL)	VC R-Dase (cells / mL)
BL1	6/17/2010	Not Sampled For These Parameters																										
BL2	8/2/2010																											
BL3	11/5/2014	3,200	NS	NS	3,900	ND	0.05	2.3	9.1	NS	ND	0.009	0.37	18.7	5.2	260	0.12	2.4	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
BL4	3/12/2015	Not Sampled For These Parameters																										
P1	7/28/2015	1,600	0.0015 J	ND	2,900	ND	0.021	ND	4.4	NS	ND	ND	0.32	ND	5.6	256	4.8	0.49	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
P2	1/8/2016	610 J	ND	ND	1,200	ND	0.031	1.3	5	ND	ND	0.094	0.31	ND	6.3 b	269 B	ND	1.3	NS	NS	NS	NS	NS	NS				
P3	4/8/2016	ND	ND	ND	1,600	ND	0.12	5.1	6.8	ND	ND	0.056	0.23	12.4	2.4	221	0.094 J HF F1	5.2	NS	NS	NS	NS	NS	NS				
P4	7/12/2016	10,000	ND	ND	660	ND	0.051 B	2.6	3.4 J B	ND	ND	0.034	0.26	ND	2.8 b	253	0.10 H F	2.7	NS	NS	NS	NS	NS	NS				
P5	10/11/2016	11,000	ND	ND	1,300	ND	0.21 B	11.5	3.3	0.8 J	ND	0.66	12.2	ND	5	257	0.12	11.6	ND	ND	ND	ND	ND	ND				
P6	1/24/2017	8,900	ND	ND	1,400	ND	0.083 B	3.7	5.6	ND	ND	0.12	0.13 F1	10.1	3.3 b	157	ND	3.7	ND	ND	ND	ND	ND	ND				
P7	4/10/2017	9,200	ND	ND	2,500	ND	0.073	2.2	2.7	ND	ND	0.059	0.26	ND	3.7	238	ND	2.2	ND	ND	ND	ND	ND	ND				
P8	7/7/2017	14,000	ND	ND	3,000	ND	0.041	1.8	4.1	ND	ND	1.8	0.26	ND	4.2	263	ND	1.8	ND	ND	ND	ND	ND	ND				
P9	10/17/2017	######	ND	ND	######	ND	0.027	1.3	2.7	ND	ND	0.033	0.29	ND	2.7	275	ND	1.3	ND	ND	ND	ND	ND	ND				
P10	1/3/2018	######	ND	ND	9,800	ND	0.049	2.4	2.0	ND	ND	1.5	0.29	ND	4.6	267	ND	2.4	ND	ND	ND	ND	ND	ND				
P11	4/10/2018	19,000	ND	ND	8100	0.037 J	0.60	5.7	2.4 J	ND	ND	0.042	0.070	ND	10.3 b	228	ND	5.7	NS	NS	NS	NS	NS	NS				

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
MW-36D	Monitoring event	BL1	6/17/2010	-1783	21	5.4	689.7	684.3	7.02	5.75	111	0.652	2.04	11.44	NS
MW-36D	Monitoring event	BL2	8/2/2010	-1737	21	6.3	689.7	683.4	6.92	1.41	-118.3	0.711	13.2	29.2	NS
MW-36D	Monitoring event	BL3	3/10/2015	-56	23.5	5.9	689.7	683.8	7.8	2.84	46.3	0.647	15.2	8.59	1.2
MW-36D	Monitoring event	P1	7/29/2015	85	23.5	6.25	689.66	683.41	5.75	0.3	-64.1	5.357	54.5	15	4,880 B
MW-36D	Monitoring event	P2	4/8/2016	339	23.5	5.4	689.7	684.3	5.55	0.49	3.5	4.533	2.3	9.03	4,530 B
MW-36D	Monitoring event	P3	7/11/2016	433	23.5	7.65	689.74	682.09	5.81	1.38	-36.4	7.885	19.9	13.82	4,210
MW-36D	Monitoring event	P4	10/12/2016	526	23.5	9.1	689.74	680.64	5.79	0.3	-145.2	10.07	19.7	17.16	5,930
MW-36D	Monitoring event	P5	1/24/2017	630	23.5	5.88	689.7	683.9	6.76	0.31	-146	4.677	34.3	8.07	1,590
MW-36D	Monitoring event	P6	4/12/2017	708	23.5	5.15	689.7	684.6	6.4	0.12	-116	4.997	26.1	9.3	2,970
MW-36D	Monitoring event	P7	7/6/2017	793	23.5	6.95	689.7	682.8	7.11	0.23	-57.5	3.04	18.1	15.7	870
MW-36D	Monitoring event	P8	10/18/2017	897	23.5	7.5	689.7	682.2	7.15	0.22	-317	2.52	16	14.9	152
MW-36D	Monitoring event	P9	1/4/2018	975	23.5	5.12	689.7	684.6	9.52	2.17	-91	1.444	NA	8.23	31.9
MW-36D	Monitoring event	P10	4/9/2018	1070	23.5	5.21	689.7	684.5	7.35	0.75	-108	1.334	NA	8.17	21.3

Well ID	Event	Date	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
			(ug/L)																								
MW-36D	BL1	6/17/2010	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	2.1	ND	ND
MW-36D	BL2	8/2/2010	ND	ND	ND	ND	ND	ND	ND	200	ND	21 J	ND	0.93 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.74 J	ND	ND
MW-36D	BL3	3/10/2015	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-36D	P1	7/29/2015	ND	ND	ND	0.57 J	ND	ND	ND	130	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.67 J	ND	ND	ND	ND	ND	ND	ND
MW-36D	P2	4/8/2016	ND	ND	ND	ND	ND	ND	ND	600	ND	580	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-36D	P3	7/11/2016	ND	ND	ND	ND	ND	ND	ND	910	ND	330	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-36D	P4	10/12/2016	ND	ND	ND	ND	ND	ND	ND	1,100	ND	650	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-36D	P5	1/24/2017	ND	ND	ND	ND	ND	ND	ND	660	ND	260	ND	0.96 J	ND	ND	ND	ND	ND	ND	ND	6.0	ND	ND	ND	ND	ND	ND	ND
MW-36D	P6	4/12/2017	ND	ND	ND	ND	ND	ND	ND	930	ND	480	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-36D	P7	7/6/2017	ND	ND	ND	ND	ND	ND	27	500	ND	160	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-36D	P8	10/18/2017	ND	ND	ND	ND	ND	ND	15	260	ND	110	ND	0.53	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
MW-36D	P9	1/4/2018	ND	ND	ND	ND	ND	ND	6.6	170	ND	78	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.88 J	ND	ND	ND	ND
MW-36D	P10	4/9/2018	ND	ND	ND	ND	ND	ND	2.7 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Well ID	Carbon Dioxide (ug/L)	Ethane (ug/L)	Ethene (ug/L)	Methane (ug/L)	Nitrate (mg/L)	Manganese (mg/L)	Ferric iron (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrite (mg/L)	Phosphorous (mg/L)	Ammonia (mg/L)	COD (mg/L)	BOD (mg/L)	Total Alkalinity (mg/L)	Ferrous Iron (mg/L)	Iron (mg/L)	Acetic Acid (mg/L)	Formic Acid (mg/L)	Lactic Acid (mg/L)	n-Butyric Acid (mg/L)	Propionic Acid (mg/L)	Pyruvic Acid (mg/L)	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1) (cells / mL)	BAV1 VC R-Dase (1) (cells / mL)	VC R-Dase (cells / mL)
MW-36D	Not Sampled For These Parameters																										

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)	1,1,1-Trichloroethane (ug/L)	1,1,2-Trichloro-1,2,2-trifluoroethane (ug/L)	1,1,2-Trichloroethane (ug/L)	1,1-Dichloroethane (ug/L)	1,1-Dichloroethene (ug/L)	1,2-Dichloroethane (ug/L)	2-Hexanone (ug/L)	2-Butanone (MEK) (ug/L)	4-Methyl-2-pentanone (ug/L)	Acetone (ug/L)	Benzene (ug/L)	Carbon Disulfide (ug/L)	Chloroethane (ug/L)	Chloroform (ug/L)	Chloromethane (ug/L)	cis-1,2-Dichloroethene (ug/L)	Dichlorodifluoromethane (ug/L)	Ethylbenzene (ug/L)	Methylcyclohexane (ug/L)	Methylene chloride (ug/L)	Methyl Acetate (ug/L)	Tetrachloroethene (ug/L)	Toluene (ug/L)	trans-1,2-Dichloroethene (ug/L)	Trichloroethene (ug/L)	Vinyl chloride (ug/L)	Xylenes, Total (ug/L)
MW-37D	Monitoring event	BL1	6/18/2010	-1782	20	4.35	690.1	685.7	7.23	5.14	-79	0.802	8.9	11.45	NS	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	BL2	8/3/2010	-1736	20	5.30	690.1	684.8	7.15	1.08	-139	0.786	2.98	15.21	NS	ND	ND	ND	ND	ND	ND	ND	ND	ND	7.7 J	ND	1.1 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	BL3	3/10/2015	-56	22.5	4.98	690.1	685.1	8	0.59	-80.3	0.662	0.073	9.2	0.65 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P1	7/29/2015	85	22.5	5.4	690.05	684.65	6.42	0.52	-84.5	2.371	29.6	13.94	1,060 B	ND	ND	ND	ND	ND	ND	ND	280	ND	50	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P2	4/8/2016	339	22.5	4.28	690.1	685.8	6.89	0.15	-107	1.999	20	8.28	294	ND	ND	ND	ND	ND	ND	ND	390 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P3	7/12/2016	434	22.5	7.00	690.1	683.1	9.95	0.35	-105	1.411	7.34	13.28	60.9	ND	ND	ND	ND	ND	ND	1.6 J	130	ND	24	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P4	10/12/2016	526	22.5	8.35	690.1	681.7	6.98	0.35	-89.9	0.969	10.77	12.87	22.8	ND	ND	ND	ND	ND	ND	ND	6	ND	4.6	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P5	1/24/2017	630	22.5	4.86	690.1	685.2	6.93	0.25	-87.7	1.003	11.1	9.52	18.3	ND	ND	ND	ND	ND	ND	ND	1.9 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P6	4/11/2017	707	22.5	4.12	690.1	685.9	7	0.03	-110	0.852	11.4	10.7	6.3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P7	7/10/2017	797	22.5	5.95	690.1	684.1	7.08	13.3	-87	1.02	13.3	13.3	4.4	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P8	10/18/2017	897	22.5	6.55	690.1	683.5	7.13	0.1	-315	0.94	6.8	12.3	5.3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P9	1/5/2018	976	22.5	4.72	690.1	685.3	10.22	1.09	-87.5	0.764	NA	8.4		ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P10	4/11/2018	1072	22.5	4.28	690.1	685.8	7.86	0.54	-83.9	0.639	NA	7.87	4.3	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Well ID	Carbon Dioxide (ug/L)	Ethane (ug/L)	Ethene (ug/L)	Methane (ug/L)	Nitrate (mg/L)	Manganese (mg/L)	Ferric iron (mg/L)	Sulfate (mg/L)	Sulfide (mg/L)	Nitrite (mg/L)	Phosphorous (mg/L)	Ammonia (mg/L)	COD (mg/L)	BOD (mg/L)	Total Alkalinity (mg/L)	Ferrous Iron (mg/L)	Iron (mg/L)	Acetic Acid (mg/L)	Formic Acid (mg/L)	Lactic Acid (mg/L)	n-Butyric Acid (mg/L)	Propionic Acid (mg/L)	Pyruvic Acid (mg/L)	Dehalococcoides spp (1) (cells / mL)	TCE R-Dase (1) (cells / mL)	BAV1 VC R-Dase (1) (cells / mL)	VC R-Dase (cells / mL)
MW-37D	Not Sampled For These Parameters																										

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth (feet)	Water Level Measurement (ft. ATOC)	Top of Casing Elevation (ft. AMSL)	Head Elevation (ft. AMSL)	pH (SU)	Dissolved Oxygen (mg/L)	Oxidation Reduction Potential (mV)	Specific Conductance (mS/cm)	Turbidity (NTUs)	Temperature (°C)	Carbon, Total Organic (mg/L)
MW-38D	Monitoring event	BL	6/22/2010	-1778	21	15.21	689.7	674.5	7.05	1.1	20.5	0.716	2.1	14.23	NS
	Monitoring event	BL2	8/4/2010	-1735	21	6.25	689.7	683.4	6.92	0.79	-46.9	0.718	1.43	18.1	NS
	Monitoring event	BL3	11/5/2014	-181	24	5.51	689.7	684.2	7.7	0.21	-114.6	0.658	NS	12.85	NS
	Monitoring event	BL4	3/10/2015	-56	24	5.32	689.7	684.3	7.78	0.62	-2.3	0.778	25.7	7.89	2.5
	Monitoring event	P1	6/12/2015	38	NS (Grab Sample)										
	Monitoring event	P2	7/27/2015	83	24	5.65	689.66	684.01	5.67	0.36	-57.6	5.771	739	17.39	7,240
	Monitoring event	P3	1/7/2016	247	24	5.2	689.66	684.46	5.39	0.51	22.2	6.189	27.7	9.7	4,650
	Monitoring event	P4	4/8/2016	339	24	4.69	689.66	684.97	6.31	0.65	-75	4.248	21.6	8.83	2,540
	Monitoring event	P5	7/12/2016	434	24	6.3	689.66	683.36	6.89	0.07	-159	5.553	51.6	18.55	2,270
	Monitoring event	P6	10/12/2016	526	24	7.35	689.66	682.31	7.33	1.6	-149.4	3.317	51.9	14.3	1,310 B
	Monitoring event	P7	1/23/2017	629	24	5.22	689.66	684.44	7.33	1.08	-138.8	2.997	38	10.38	650
	Monitoring event	P8	4/12/2017	708	24	4.4	689.66	685.26	7.32	0.01	-163.5	2.526	17.9	8.4	459 B
	Monitoring event	P9	7/7/2017	794	24	5.7	689.66	683.96	7.61	0.07	-115.7	2.59	19.5	18.4	370

Well ID	Event / Description		Date	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
				(ug/L)																										
MW-38D	Monitoring event	BL	6/22/2010	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	4,400	ND	270	ND	ND	ND	230 J	300	ND	11,000	ND	730 J
	Monitoring event	BL2	8/4/2010	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	13,000	ND	ND	ND	ND	ND	130	ND	ND	2,100	ND	260 J
	Monitoring event	BL3	11/5/2014	Not Sampled For These Parameters																										
	Monitoring event	BL4	3/10/2015	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	290	ND	ND	ND	ND	ND	ND	ND	ND	1.9	260	ND
	Monitoring event	P1	6/12/2015	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	190	ND	ND	ND	ND	ND	ND	ND	ND	18 J	50	ND
	Monitoring event	P2	7/27/2015	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	390	ND	3.8 J	ND	ND	ND	ND	ND	ND	6.8	60	4.8 J
	Monitoring event	P3	1/7/2016	ND	ND	ND	ND	ND	ND	ND	610	ND	880	ND	ND	ND	ND	ND	560	ND	ND	ND	ND	ND	ND	ND	ND	ND	44	ND
	Monitoring event	P4	4/8/2016	ND	ND	ND	3.8 J	1.3 J	ND	6.9 J	1,000	ND	120	ND	ND	ND	ND	ND	850	ND	7.3	ND	9.1	ND	ND	ND	ND	ND	240	15
	Monitoring event	P5	7/12/2016	ND	ND	ND	ND	ND	ND	ND	1,100	ND	130	ND	ND	ND	ND	ND	80	ND	ND	ND	ND	ND	ND	ND	ND	ND	59	ND
	Monitoring event	P6	10/12/2016	ND	ND	ND	5.1 J	ND	ND	ND	860	ND	110	ND	ND	15	ND	ND	ND	ND	ND	ND	ND	ND	ND	7.7 J	ND	ND	58	8.2 J
	Monitoring event	P7	1/23/2017	ND	ND	ND	ND	ND	ND	ND	520	ND	87 J	ND	ND	16	ND	ND	ND	ND	ND	ND	ND	ND	ND	6.7 J	ND	ND	14	9.3 J
	Monitoring event	P8	4/12/2017	ND	ND	ND	2.1 J	ND	ND	ND	660	ND	86	ND	ND	17	ND	ND	ND	ND	5.7	ND	2.0 J	ND	ND	7.5	ND	ND	6.7	13
	Monitoring event	P9	7/7/2017	ND	ND	ND	ND	ND	ND	ND	720	ND	74	ND	0.81 J	19	ND	ND	ND	ND	3.9 J	ND	ND	ND	ND	5.9	ND	ND	5.1	11

Well ID	Event / Description		Date	Carbon Dioxide	Ethane	Ethene	Methane	Nitrate	Manganese	Ferric iron	Sulfate	Sulfide	Nitrite	Phosphorous	Ammonia	COD	BOD	Total Alkalinity	Ferrous Iron	Iron	Acetic Acid	Formic Acid	Lactic Acid	n-Butyric Acid	Propionic Acid	Pyruvic Acid	Dehalococcoides spp (1)	TCE R-Dase (1)	BAV1 VC R-Dase (1)	VC R-Dase
				(ug/L)				(mg/L)																			(cells / mL)			
MW-38D	Monitoring event	BL	6/22/2010	Not Sampled For These Parameters																										
	Monitoring event	BL2	8/4/2010																											
	Monitoring event	BL3	11/5/2014	5,500	NS	NS	1,200	ND	0.025	0.98	4.8	NS	ND	0.27	0.14	229	68.2	489	ND	0.98	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
	Monitoring event	BL4	3/10/2015	Not Sampled For These Parameters																										
	Monitoring event	P1	6/12/2015																											
	Monitoring event	P2	7/27/2015	79,000	ND	ND	6,000	ND	2	397	ND	ND	ND	2.3	0.49	33600	18900	5150	105	502	2420	693	746	1860	966	ND	8.41E+02	<2.50E+01	1.20E+02	1.47E+01J
	Monitoring event	P3	1/7/2016	20,000	ND	ND	570	ND	3	ND	2.0 J	ND	ND	1.8	0.57	14,300	ND	5860	664 HF	477	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
	Monitoring event	P4	4/8/2016	9,700	ND	ND	1,300	ND	2.4	102	ND	ND	ND	1.1	4.4	8,670	>1499.20 H	4220	347 HF	449	NS	NS	NS	NS	NS	NS				
	Monitoring event	P5	7/12/2016	140,000	ND	ND	5,400	ND	1.0 B	108	ND	0.064 J	ND	2	3.5	37600	>1477.73 H b	3910	119 HF	227	NS	NS	NS	NS	NS	NS	4.00E+04	1.78E+02	2.22E+04	6.96E+02
	Monitoring event	P6	10/12/2016	100,000	ND	ND	1,900	ND	0.042 B	32.8	ND	ND	ND	0.36	0.52	3,860	>89.20B	3,020	0.41 HF	33.2	ND	ND	ND	ND	ND	ND	Not Sampled For These Parameters			
	Monitoring event	P7	1/23/2017	6,000	ND	ND	200	ND	0.022	18.2	20.9 J	ND	ND	0.69	0.87	2,050	2,040 H b	2,290	15.3 HF	33.5	ND	ND	ND	ND	ND	ND				
	Monitoring event	P8	4/12/2017	120,000	ND	ND	4,300	ND	0.017	24	ND	ND	ND	0.59	ND	1,300	667 Hb	2,290 B	0.096 JHF	24.1	ND	ND	ND	ND	ND	ND	2.52E+04	7.24E+02	2.20E+02	9.12E+02
	Monitoring event	P9	7/7/2017	92,000	ND	ND	5,300	ND	0.008	11.2	ND	ND	ND	0.43	ND	1,240	708 H b	1,840	ND	11.2	ND	ND	ND	ND	ND	ND				

Well ID		MW-38D		
Event / Description		Monitoring event	Monitoring event	Monitoring event
Date		P10	P11	P12
Elapsed Time (Days)		10/18/2017	1/4/2018	4/10/2018
		897	975	1071
(feet)	Total Depth	24	24	24
(ft. ATOC)	Water Level Measurement	6.5	NA	4.21
(ft. AMSL)	Top of Casing Elevation	689.66	689.66	689.66
(ft. AMSL)	Head Elevation	685.26	NA	NA
(SU)	pH	8.1	NA	7.51
(mg/L)	Dissolved Oxygen	0.49	NA	1.09
(mV)	Oxidation Reduction Potential	-278.7	NA	-51.3
(mS/cm)	Specific Conductance	2.06	NA	1.381
(NTUs)	Turbidity	16.9	NA	NA
(°C)	Temperature	13.6	NA	9.16
(mg/L)	Carbon, Total Organic	113	77.1	19.2
(ug/L)	1,1,1-Trichloroethane	ND	ND	ND
	1,1,2-Trichloro-1,2,2-trifluoroethane	ND	ND	ND
	1,1,2-Trichloroethane	ND	ND	ND
	1,1-Dichloroethane	19 J	ND	ND
	1,1-Dichloroethene	1.1	ND	ND
	1,2-Dichloroethane	ND	ND	ND
	2-Hexanone	ND	ND	ND
	2-Butanone (MEK)	110	130	ND
	4-Methyl-2-pentanone	ND	ND	ND
	Acetone	33	45	ND
	Benzene	1.7	ND	ND
	Carbon Disulfide	ND	0.81 J	ND
	Chloroethane	75	23	14
	Chloroform	ND	ND	ND
	Chloromethane	ND	ND	ND
	cis-1,2-Dichloroethene	27	ND	ND
	Dichlorodifluoromethane	ND	ND	ND
	Ethylbenzene	9.6	4.1	3.1 J
	Methylcyclohexane	ND	ND	ND
	Methylene chloride	ND	ND	ND
	Methyl Acetate	ND	ND	ND
	Tetrachloroethene	ND	ND	ND
	Toluene	39	14	2.2 J
	trans-1,2-Dichloroethene	5.1	ND	ND
	Trichloroethene	ND	ND	ND
	Vinyl chloride	47	5.1	ND
	Xylenes, Total	30	15	15
(ug/L)	Carbon Dioxide	40,000	81,000	84,000
	Ethane	ND	ND	ND
	Ethene	ND	ND	ND
	Methane	15,000	22,000	20,000
(mg/L)	Nitrate	ND	ND	ND
	Manganese	0.0062	0.0059	0.0067
	Ferric iron	1.3	6.8	3.6
	Sulfate	ND	ND	ND
	Sulfide	ND	ND	ND
	Nitrite	ND	ND	ND
	Phosphorous	0.85	0.56	0.45
	Ammonia	0.4	0.095 F1	1.8
	COD	323	245	79.8
	BOD	133 Hb	147 H b	25.7 b
	Total Alkalinity	1,300 B	1,680	1440 B
	Ferrous Iron	1.0 JHF	ND	ND
	Iron	2.3	ND	3.6
	Acetic Acid	ND	ND	NS
	Formic Acid	ND	ND	NS
	Lactic Acid	ND	ND	NS
	n-Butyric Acid	ND	ND	NS
	Propionic Acid	ND	ND	NS
	Pyruvic Acid	ND	ND	NS
(cells / mL)	Dehalococcoides spp (1)	1.81E+02	Not Sampled For These Parameters	
	TCE R-Dase (1)	6.36E+01		
	BAV1 VC R-Dase (1)	1.25E+01		
	VC R-Dase	5.16E+01		

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth	Water Level Measurement	Top of Casing Elevation	Head Elevation	pH	Dissolved Oxygen	Oxidation Reduction Potential	Specific Conductance	Turbidity	Temperature	Carbon, Total Organic	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
					(feet)	(ft. ATOC)	(ft. AMSL)	(ft. AMSL)	(SU)	(mg/L)	(mV)	(mS/cm)	(NTUs)	(°C)	(mg/L)	(ug/L)																										
MW-39D	Monitoring event	BL1	6/18/2010	-1782	20	4	689.7	685.7	7.1	4.93	-49.6	0.724	12.09	11.89	NS	17	ND	ND	4.7 J	2.3 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	BL2	8/3/2010	-1736	20	5	689.7	684.7	7.1	1.57	-138	0.724	18	15.89	NS	13	ND	ND	5.8	3.1 J	ND	ND	ND	ND	4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	BL3	3/10/2015	-56	22.5	4.7	689.7	685	7.81	0.77	-47.4	0.655	1.75	8.85	0.55 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P1	7/29/2015	85	22.5	5.2	689.7	684.5	5.76	0.4	-63	5.088	767	17.12	3340 B	ND	ND	ND	0.80 J	ND	ND	ND	420	ND	18	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	21	ND	ND	ND	ND	ND	ND
	Monitoring event	P2	4/8/2016	339	22.5	4.08	689.7	685.6	6.77	0.43	-144	3.505	120	7.17	2250	ND	ND	ND	ND	ND	ND	ND	910	ND	250 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P3	7/12/2016	434	22.5	6.7	689.7	683	6.77	0.45	-119	2.287	44.4	14.8	436	ND	ND	ND	ND	ND	ND	2.7 J	340	ND	83	ND	0.27 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P4	10/13/2016	527	22.5	7.8	689.7	681.9	6.85	0.41	-91.2	1.807	35.7	12.21	127	ND	ND	ND	ND	ND	ND	1.3 J	170	ND	48	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P5	1/24/2017	630	22.5	4.65	689.7	685.1	6.85	0.29	-117	1.613	27.1	9.12	57.4	ND	ND	ND	ND	ND	ND	2.6 J	180	ND	43	ND	0.24 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
	Monitoring event	P6	4/11/2017	707	22.5	3.84	689.7	685.9	6.78	0.03	-120	1.35	25	11	30.7	ND	ND	ND	ND	ND	ND	1.3 J	28	ND	10	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.73 J	ND	ND	ND	ND
	Monitoring event	P7	7/6/2017	793	22.5	5.55	689.7	684.2	7.03	0.13	-90.9	1.25	24.2	13.2	NS	ND	ND	ND	ND	ND	ND	ND	3.7	ND	3.2	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.93	ND	ND	ND	ND
	Monitoring event	P8	10/18/2017	897	22.5	6.27	689.7	683.5	7.05	0.13	-314	1.37	22.2	12.6	11	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.86	ND	ND	ND	ND
	Monitoring event	P9	1/9/2018	980	22.5	3.7	689.7	686	9.33	1.08	-53.8	0.855	NA	8.84	10	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.74	ND	ND	ND	ND
	Monitoring event	P10	4/12/2018	1073	22.5	3.89	689.7	685.8	7.15	0.77	-85.2	0.834	NA	8.75	11.7	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Well ID	Carbon Dioxide	Ethane	Ethene	Methane	Nitrate	Manganese	Ferric iron	Sulfate	Sulfide	Nitrite	Phosphorous	Ammonia	COD	BOD	Total Alkalinity	Ferrous Iron	Iron	Acetic Acid	Formic Acid	Lactic Acid	n-Butyric Acid	Propionic Acid	Pyruvic Acid	Dehalococcoides spp (1)	TCE R-Dase (1)	BAV1 VC R-Dase (1)	VC R-Dase
	(ug/L)				(mg/L)																			(cells / mL)			
MW-39D	Not Sampled For These Parameters																										

Well ID	Event / Description		Date	Elapsed Time (Days)	Total Depth	Water Level Measurement	Top of Casing Elevation	Head Elevation	pH	Dissolved Oxygen	Oxidation Reduction Potential	Specific Conductance	Turbidity	Temperature	Carbon, Total Organic
					(feet)	(ft. ATOC)	(ft. AMSL)	(ft. AMSL)	(SU)	(mg/L)	(mV)	(mS/cm)	(NTUs)	(°C)	(mg/L)
MW-40D	Monitoring event	BL1	6/21/2010	-1779	22.8	3.53	689.2	685.7	6.91	1.01	69	0.719	3.74	13.22	NS
	Monitoring event	BL2	8/3/2010	-1736	22.8	4.3	689.2	684.9	7.2	1.95	-202	0.693	3.5	17.37	NS
	Monitoring event	BL3	11/6/2014	-180	NA	NA	NA	NA	8.31	NA	-14	0.624	Na	12.18	NS
	Monitoring event	BL4	3/11/2015	-55	22.5	3.95	689.2	685.2	9.01	0.75	-15.1	0.669	2.09	8.81	1.8
	Monitoring event	P1	6/12/2015	38	NS (Grab Sample)										ND
	Monitoring event	P2	7/27/2015	83	22.5	4.25	689.19	684.94	6.54	0.56	-108.9	2.82	21.6	15.85	1260
	Monitoring event	P3	1/7/2016	247	22.5	3.25	689.19	685.94	7.47	0.37	-163.4	1.497	9.17	11.39	313
	Monitoring event	P4	4/8/2016	339	22.5	2.892	689.19	686.298	7.59	0.12	-161	1.092	18.2	7.16	202
	Monitoring event	P5	7/11/2016	433	22.5	4.95	689.19	684.24	7.12	1.2	-135	2.045	19	18.53	614
	Monitoring event	P6	10/11/2016	525	22.5	5.77	689.19	683.42	7.13	1.64	-94.9	1.788	18.8	15.42	267
	Monitoring event	P7	1/25/2017	631	22.5	3.64	689.19	685.55	7.08	0.37	-118.3	1.228	13.9	9.5	146
	Monitoring event	P8	4/10/2017	706	22.5	2.88	689.19	686.31	7.05	0.17	-136.3	1.115	15	13.9	172
	Monitoring event	P9	7/10/2017	797	22.5	4.1	689.2	685.1	7.85	0.35	-145	1.18	22.5	14.2	NS
	Monitoring event	P10	10/16/2017	895	22.5	4.55	689.2	684.6	7.09	0.41	-329.9	0.96	10.17	12.5	131
	Monitoring event	P11	1/4/2018	975	22.5	3.39	689.2	685.8	NA	NA	NA	NA	NA	NA	168 B
	Monitoring event	P12	4/10/2018	1071	22.5	2.68	689.19	686.51	7.96	0.36	-105.1	0.47	NA	10.13	48.5

Event	1,1,1-Trichloroethane	1,1,2-Trichloro-1,2,2-trifluoroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	2-Hexanone	2-Butanone (MEK)	4-Methyl-2-pentanone	Acetone	Benzene	Carbon Disulfide	Chloroethane	Chloroform	Chloromethane	cis-1,2-Dichloroethene	Dichlorodifluoromethane	Ethylbenzene	Methylcyclohexane	Methylene chloride	Methyl Acetate	Tetrachloroethene	Toluene	trans-1,2-Dichloroethene	Trichloroethene	Vinyl chloride	Xylenes, Total
	(ug/L)																										
BL1	23	ND	ND	260	1.8 J	ND	ND	ND	ND	3.4 J	ND	ND	1.4 J	ND	ND	1.2 J	ND	ND	ND	ND	ND	ND	ND	ND	2.8 J	ND	1.1 J
BL2	25	ND	ND	550	6 J	ND	ND	ND	ND	ND	ND	4 J	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
BL3	Not Sampled For These Parameters																										
BL4	2,800	110	ND	5,400	200	ND	ND	ND	ND	ND	ND	ND	1,100	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	67	ND
P1	ND	ND	ND	1,800	ND	ND	ND	ND	ND	ND	ND	ND	380	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P2	ND	ND	ND	12,000	64 J	ND	ND	260 J	ND	ND	ND	ND	1,100	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P3	ND	ND	ND	190	ND	ND	ND	ND	ND	ND	ND	ND	4900 F1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P4	ND	ND	ND	220	ND	ND	ND	ND	ND	ND	ND	ND	2,500	ND	ND	ND	ND	ND	ND	46 J	ND	ND	ND	ND	ND	ND	ND
P5	ND	ND	ND	12 J	ND	ND	ND	380	ND	ND	ND	ND	950 F1	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P6	ND	ND	ND	71	ND	5.2 J	ND	140 J	ND	ND	ND	ND	1,800	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P7	ND	ND	ND	180	ND	4.8 J	ND	130 J	ND	ND	ND	ND	1,200 F1	ND	ND	ND	ND	ND	ND	14 J	ND	ND	ND	ND	ND	ND	ND
P8	43	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	2,200	ND	ND	ND	ND	ND	ND	39 J	ND	ND	ND	ND	ND	ND	ND
P9	ND	ND	ND	150	ND	ND	ND	190	ND	ND	ND	ND	850	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P10	ND	ND	ND	51	ND	1.3	ND	63	ND	13	ND	ND	410	ND	ND	ND	ND	ND	ND	ND	ND	ND	0.69	ND	ND	0.9	ND
P11	ND	ND	ND	32	ND	ND	ND	160	ND	ND	ND	ND	380	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND
P12	20	ND	ND	400	ND	ND	ND	ND	ND	ND	ND	ND	970	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND	ND

Event	Carbon Dioxide	Ethane	Ethene	Methane	Nitrate	Manganese	Ferric iron	Sulfate	Sulfide	Nitrite	Phosphorous	Ammonia	COD	BOD	Total Alkalinity	Ferrous Iron	Iron	Acetic Acid	Formic Acid	Lactic Acid	n-Butyric Acid	Propionic Acid	Pyruvic Acid	Dehalococcoides spp (1)	TCE R-Dase (1)	BAV1 VC R-Dase (1)	VC R-Dase
	(ug/L)				(mg/L)																			(cells / mL)			
BL1	Not Sampled For These Parameters																										
BL2																											
BL3	1,400	NS	NS	1,400	ND	0.002	0.24	ND	NS	ND	ND	0.61	12.9	2.7	291	ND	0.24	NS	NS	NS	NS	NS	NS	Not Sampled For These Parameters			
BL4	Not Sampled For These Parameters																										
P1																											
P2	7,600	ND	ND	1,800	ND	0.44	59.7	ND	NS	ND	0.92	0.2	4220	2890	1900	44.3	104	1300	ND	ND	95	672	ND	Not Sampled For These Parameters			
P3	3,300	ND	ND	2,500	ND	0.23	24.4	2.1 J	0.090 J	ND	0.41	0.27 F1	2600 B	738 H	966	ND	24.4	NS	NS	NS	NS	NS	NS				
P4	3,100	ND	ND	1,200	ND	0.077	19.7	ND	0.13	ND	0.32	0.25	623	557	771	0.078 J HF	19.8	NS	NS	NS	NS	NS	NS				
P5	46,000	ND	ND	1,200	ND	0.064 B	17.1	ND	ND	ND	0.41	0.29	2080 B	>1374.27 H b	1330	0.77 HF	17.9	NS	NS	NS	NS	NS	NS				
P6	81,000	ND	ND	1,500	ND	0.025 B	16.6	ND	ND	ND	0.35	0.32	817	254 HB	9,066	0.21 HF	16.8	ND	ND	ND	ND	ND	ND				
P7	54,000	ND	ND	1,100	ND	0.011	6.4	ND	ND	ND	0.24	0.43	466	222 b	697	0.13 HF	6.5	ND	ND	ND	ND	ND	ND				
P8	43,000	ND	ND	3,200	ND	0.0052	4	ND	ND	ND	0.2	0.44	649	331	620	ND	4	ND	ND	ND	ND	ND	ND				
P9	9	ND	ND	2,600	ND	0.011	6.6	1.9	ND	ND	0.099	0.27	713	978	695	ND	6.6	ND	ND	ND	ND	ND	ND				
P10	39	ND	ND	11,000	ND	0.013	5.7	ND	0.029	ND	0.18	0.43	393	175	518	ND	5.7	ND	ND	ND	ND	ND	ND				
P11	27,000	ND	ND	16,000	0.086	0.026	19.1	ND	ND	0.034	0.050	0.014 J	78	ND	579	ND	19.1	282	ND	ND	ND	117	ND				
P12	32,000	ND	ND	15,000	ND	0.0074	3.1	ND	ND	ND	0.13	0.33 F1	139	95.1 b	325	0.38 HF	3.5	NS	NS	NS	NS	NS	NS				

Appendix B

Former Scott Aviation Area 1 Summary of VOCs in Groundwater

MONITORING WELL A1-GP02S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

Sample Date	Analytical Results (µg/L)							
	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/22/2010	ND	ND	ND	ND	ND	ND	11,000	ND
8/4/2010	ND	ND	ND	ND	ND	ND	20,000	ND
3/10/2015	ND	ND	ND	ND	ND	ND	5,400	ND
7/28/2015	ND	ND	ND	34	ND	ND	8,000	140
1/7/2016	ND	ND	ND	ND	ND	ND	330	770
4/8/2016	ND	ND	ND	ND	ND	ND	ND	2,400
7/11/2016	ND	ND	ND	ND	ND	ND	ND	10,000
10/10/2016	ND	ND	ND	ND	ND	ND	ND	13,000
1/23/2017	ND	ND	ND	ND	ND	ND	ND	1,700
4/11/2017	ND	ND	ND	ND	ND	ND	ND	3,700
7/6/2017	ND	ND	ND	ND	ND	ND	ND	4,300
10/17/2017	ND	ND	ND	ND	ND	ND	ND	1,900
1/5/2018	ND	ND	ND	ND	ND	ND	ND	6,700
4/12/2018	ND	ND	ND	ND	ND	ND	ND	4,200

MONITORING WELL A1-GP02S

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



MONITORING WELL A1-GP06S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/21/2010	620	ND	890	63	ND	ND	46	ND
8/4/2010	1,700	16	3,200	270	ND	ND	200	20
3/11/2015	110	ND	21	ND	ND	ND	0.81	ND
7/27/2015	110	4.1	3,300	0.89	3.1	ND	18	16
1/7/2016	ND	ND	340	60	ND	ND	330	16
4/8/2016	73	ND	450	ND	ND	ND	5.4	33
7/12/2016	35	ND	680	7.8	ND	ND	ND	44
10/10/2016	ND	ND	270	ND	ND	ND	ND	ND
1/24/2017	24	ND	300	ND	ND	ND	ND	29
4/11/2017	34	ND	210	6.2	ND	ND	ND	ND
7/6/2017	63	490	13	ND	ND	ND	ND	50
10/18/2017	ND	ND	200	ND	ND	ND	ND	14
1/5/2018	44	84	400	3.7	2.1	ND	ND	ND
4/10/2018	110	ND	360	6.8	ND	ND	7.2	11

MONITORING WELL A1-GP06S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York



MONITORING WELL A1-GP10S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

Sample Date	Analytical Results (µg/L)							
	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/21/2010	55,000	84	43,000	1,300	77	1.2	92	41
8/3/2010	84,000	ND	48,000	2,000	ND	ND	ND	ND
3/11/2015	1,500	1.2	440	65	1.6	ND	6.6	ND
6/12/2015	28,000	ND	15,000	1,000	40	ND	ND	ND
7/27/2015	12,000	ND	2,900	1,600	9.6	ND	36	ND
1/7/2016	4,900	ND	4,300	470	ND	ND	ND	ND
4/8/2016	1,700	ND	4,800	220	ND	ND	ND	ND
7/11/2016	6,600	ND	29,000	500	72	ND	ND	ND
10/7/2016	360	ND	7,200	190	47	ND	ND	ND
1/23/2017	ND	ND	580	ND	ND	ND	ND	ND
4/10/2017	240	ND	4,100	45	ND	ND	ND	690
7/6/2017	2,400	ND	9,600	380	ND	ND	ND	ND
10/17/2017	23	ND	240	4	1.4	ND	0.47	45
1/4/2018	44	ND	600	ND	11	ND	ND	85
4/10/2018	140	ND	3,900	19	18	ND	ND	260

MONITORING WELL A1-GP10S

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



MONITORING WELL A1-GP15S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/17/2010	ND	ND	ND	ND	ND	ND	ND	ND
8/2/2010	ND	ND	ND	ND	ND	ND	ND	ND
3/11/2015	ND	ND	ND	ND	ND	ND	ND	ND
7/29/2015	3	ND	ND	ND	ND	ND	4	ND
4/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
7/11/2016	0.99	4.5	ND	ND	ND	ND	ND	ND
10/7/2016	ND	ND	ND	ND	ND	ND	ND	ND
1/23/2017	ND	ND	ND	ND	ND	ND	ND	ND
4/12/2017	ND	ND	ND	ND	ND	ND	ND	ND
7/6/2017	ND	ND	ND	ND	ND	ND	ND	ND
10/17/2017	ND	ND	ND	ND	ND	ND	ND	ND
1/2/2018	NS	NS	NS	NS	NS	NS	NS	NS
4/10/2018	ND	ND	ND	ND	ND	ND	ND	ND

MONITORING WELL A1-GP15S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York



MONITORING WELL A1-GP18S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/18/2010	ND	ND	ND	ND	ND	ND	ND	ND
8/2/2010	ND	ND	ND	ND	ND	ND	ND	ND
3/11/2015	ND	ND	ND	ND	ND	ND	ND	ND
7/27/2015	ND	ND	ND	ND	ND	ND	ND	ND
1/7/2016	ND	ND	ND	ND	ND	ND	ND	ND
4/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
7/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
10/7/2016	ND	ND	ND	ND	ND	ND	ND	ND
1/23/2017	ND	ND	ND	ND	ND	ND	ND	ND
4/10/2017	ND	ND	ND	ND	ND	ND	ND	ND
7/6/2017	ND	ND	ND	ND	ND	ND	ND	ND
10/16/2017	ND	ND	ND	ND	ND	ND	ND	ND
1/5/2018	44	84	2.1	3.7	2.1	ND	2.4	22
4/9/2018	ND	ND	ND	ND	ND	ND	ND	ND

MONITORING WELL A1-GP18S

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



MONITORING WELL MW-30
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/18/2010	ND	ND	2.1	ND	ND	ND	1.4	4.9
8/3/2010	ND	ND	2.4	ND	ND	ND	1.6	5.9
7/29/2015	ND	ND	1.4	ND	ND	ND	1.1	1.4
4/8/2016	ND	ND	1.8	ND	ND	ND	ND	1.8
7/14/2016	ND	ND	3.4	ND	ND	ND	2.4	ND
10/11/2016	ND	ND	2.1	ND	ND	ND	0.56	1.3
1/25/2017	ND	ND	1.1	ND	ND	ND	ND	1.8
4/12/2017	ND	ND	1.2	ND	ND	ND	ND	2.1
7/7/2017	ND	ND	0.54	ND	ND	ND	ND	2.0
10/19/2017	ND	ND	1.2	ND	ND	ND	ND	2.5
1/2/2018	ND	ND	1.1	ND	ND	ND	ND	1.3
4/11/2018	ND	ND	0.75	ND	ND	ND	ND	0.95

MONITORING WELL MW-30
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York



MONITORING WELL MW-35S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/17/2010	ND	ND	ND	ND	ND	ND	ND	ND
8/2/2010	ND	ND	ND	ND	ND	ND	ND	ND
3/11/2015	ND	ND	ND	ND	ND	ND	ND	ND
7/28/2015	ND	ND	ND	ND	ND	ND	ND	ND
4/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
7/13/2016	ND	ND	ND	ND	ND	ND	ND	ND
10/11/2016	ND	ND	ND	ND	ND	ND	ND	ND
1/23/2017	ND	ND	ND	ND	ND	ND	ND	ND
4/10/2017	ND	ND	ND	ND	ND	ND	ND	ND
7/7/2017	ND	ND	ND	ND	ND	ND	ND	ND
10/17/2017	ND	ND	ND	ND	ND	ND	ND	ND
1/4/2018	ND	ND	ND	ND	ND	ND	ND	ND
4/9/2018	ND	ND	ND	ND	ND	ND	ND	ND

MONITORING WELL MW-35S

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



MONITORING WELL MW-36S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/17/2010	ND	ND	ND	ND	ND	ND	7.2	ND
8/3/2010	ND	ND	0.38	ND	ND	ND	0.58	ND
3/10/2015	ND	ND	ND	ND	ND	ND	ND	ND
7/29/2015	ND	ND	0.52	ND	ND	ND	ND	ND
4/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
7/11/2016	ND	ND	ND	ND	ND	ND	ND	ND
10/12/2016	ND	ND	ND	ND	ND	ND	ND	ND
1/24/2017	ND	ND	ND	ND	ND	ND	ND	ND
4/12/2017	ND	ND	ND	ND	ND	ND	ND	ND
7/6/2017	ND	ND	ND	ND	ND	ND	ND	ND
10/17/2017	ND	ND	ND	ND	ND	ND	ND	ND
1/4/2018	ND	ND	ND	ND	ND	ND	ND	ND
4/9/2018	ND	ND	ND	ND	ND	ND	ND	ND

MONITORING WELL MW-36S

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



MONITORING WELL MW-42S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
4/7/2011	25,000	240	8,550	6,100	76	6	13,000	27
3/12/2015	19,000	240	12,000	6,300	ND	ND	12,000	ND
6/12/2015	3,700	100	7,600	2,300	44	ND	2,700	ND
7/27/2015	1,700	71	9,700	2,400	44	ND	280	ND
4/8/2016	3,600	ND	7,100	5,000	ND	ND	ND	610
7/14/2016	12,000	120	11,000	7,800	110	ND	100	530
10/13/2016	440	ND	2,000	520	ND	ND	ND	ND
1/25/2017	1,200	ND	2,900	790	130	ND	ND	2,400
4/12/2017	230	ND	1,700	220	74	ND	ND	1,400
7/10/2017	ND	ND	1,800	150	ND	ND	ND	3,600
10/19/2017	4,100	48	8,900	1,700	170	ND	54	12,000
1/2/2018	740	ND	2,500	ND	ND	ND	ND	4,700
4/11/2018	390	ND	2,000	120	ND	ND	ND	2,800

MONITORING WELL MW-42S

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



MONITORING WELL MW-43S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
4/7/2011	15	ND	13	3.5	ND	ND	15	19
3/12/2015	ND	ND	1.8	ND	ND	ND	ND	1.7
7/29/2015	ND	ND	29	ND	ND	ND	0.60	7
4/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
7/13/2016	ND	ND	ND	ND	ND	ND	ND	ND
10/13/2016	ND	ND	ND	ND	ND	ND	ND	3.8
1/25/2017	ND	ND	ND	ND	ND	ND	ND	ND
4/11/2017	ND	ND	ND	ND	ND	ND	ND	ND
7/10/2017	ND	ND	ND	ND	ND	ND	ND	ND
10/19/2017	ND	ND	0.48	ND	ND	ND	ND	ND
1/2/2018	ND	ND	ND	ND	ND	ND	ND	ND
4/11/2018	ND	ND	ND	ND	ND	ND	ND	ND

MONITORING WELL MW-43S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York



MONITORING WELL MW-44S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/1/2011	ND	ND	ND	ND	ND	ND	ND	ND
7/29/2015	ND	ND	ND	ND	ND	ND	ND	ND
4/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
7/14/2016	ND	ND	ND	ND	ND	ND	ND	ND
10/11/2016	ND	ND	ND	ND	ND	ND	ND	ND
1/25/2017	ND	ND	ND	ND	ND	ND	ND	ND
4/7/2017	ND	ND	ND	ND	ND	ND	ND	ND
7/10/2017	ND	ND	ND	ND	ND	ND	ND	ND
10/16/2017	ND	ND	ND	ND	ND	ND	ND	ND
1/2/2018	ND	ND	ND	ND	ND	ND	ND	ND
4/11/2018	ND	ND	ND	ND	ND	ND	ND	ND

MONITORING WELL MW-44S
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York



MONITORING WELL MW-35D
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/17/2010	ND	ND	ND	ND	ND	ND	ND	ND
8/2/2010	ND	ND	ND	ND	ND	ND	ND	ND
3/12/2015	ND	ND	ND	ND	ND	ND	ND	ND
7/28/2015	ND	ND	ND	ND	ND	ND	ND	ND
1/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
4/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
7/12/2016	ND	ND	ND	ND	ND	ND	ND	ND
10/11/2016	ND	ND	ND	ND	ND	ND	ND	ND
1/24/2017	ND	ND	ND	ND	ND	ND	ND	ND
4/10/2017	ND	ND	ND	ND	ND	ND	ND	ND
7/7/2017	ND	ND	ND	ND	ND	ND	ND	ND
10/17/2017	ND	ND	ND	ND	ND	ND	ND	ND
1/3/2018	ND	ND	ND	ND	ND	ND	ND	ND
4/10/2018	ND	ND	ND	ND	ND	ND	ND	ND

MONITORING WELL MW-35D

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



MONITORING WELL MW-36D
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/17/2010	ND	ND	ND	ND	ND	ND	2.1	ND
8/2/2010	ND	ND	ND	ND	ND	ND	0.74	ND
3/10/2015	ND	ND	ND	ND	ND	ND	ND	ND
7/29/2015	ND	ND	0.57	ND	ND	ND	ND	ND
4/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
7/11/2016	ND	ND	ND	ND	ND	ND	ND	ND
10/12/2016	ND	ND	ND	ND	ND	ND	ND	ND
1/24/2017	ND	ND	ND	ND	ND	ND	ND	ND
4/12/2017	ND	ND	ND	ND	ND	ND	ND	ND
7/6/2017	ND	ND	ND	ND	ND	ND	ND	ND
10/18/2017	ND	ND	ND	ND	ND	ND	ND	ND
1/4/2018	ND	ND	ND	ND	ND	ND	ND	ND
4/9/2018	ND	ND	ND	ND	ND	ND	ND	ND

MONITORING WELL MW-36D

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



MONITORING WELL MW-37D
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/18/2010	ND	ND	ND	ND	ND	ND	ND	ND
8/3/2010	ND	ND	ND	ND	ND	ND	ND	ND
3/10/2015	ND	ND	ND	ND	ND	ND	ND	ND
7/29/2015	ND	ND	ND	ND	ND	ND	ND	ND
4/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
7/12/2016	ND	ND	ND	ND	ND	ND	ND	ND
10/12/2016	ND	ND	ND	ND	ND	ND	ND	ND
1/24/2017	ND	ND	ND	ND	ND	ND	ND	ND
4/11/2017	ND	ND	ND	ND	ND	ND	ND	ND
7/10/2017	ND	ND	ND	ND	ND	ND	ND	ND
10/18/2017	ND	ND	ND	ND	ND	ND	ND	ND
1/5/2018	ND	ND	ND	ND	ND	ND	ND	ND
4/11/2018	ND	ND	ND	ND	ND	ND	ND	ND

MONITORING WELL MW-37D

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



MONITORING WELL MW-38D
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/22/2010	ND	ND	ND	ND	ND	230	11,000	ND
8/4/2010	ND	ND	ND	ND	ND	130	2,100	ND
3/10/2015	ND	ND	ND	ND	ND	ND	1.9	260
6/12/2015	ND	ND	ND	ND	ND	ND	18	50
7/27/2015	ND	ND	ND	ND	ND	ND	6.8	60
1/7/2016	ND	ND	ND	ND	ND	ND	ND	44
4/8/2016	ND	ND	3.8	1.3	ND	ND	ND	240
7/12/2016	ND	ND	ND	ND	ND	ND	ND	59
10/12/2016	ND	ND	5.1	ND	ND	ND	ND	58
1/23/2017	ND	ND	ND	ND	ND	ND	ND	14
4/12/2017	ND	ND	2.1	ND	ND	ND	ND	6.7
7/7/2017	ND	ND	ND	ND	ND	ND	ND	5.1
10/18/2017	ND	ND	19	1.1	ND	ND	ND	47
1/4/2018	ND	ND	ND	ND	ND	ND	ND	5.1
4/10/2018	ND	ND	ND	ND	ND	ND	ND	ND

MONITORING WELL MW-38D

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



MONITORING WELL MW-39D
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/18/2010	17	ND	4.7	2.3	ND	ND	ND	ND
8/3/2010	13	ND	5.8	3.1	ND	ND	ND	ND
3/10/2015	ND	ND	ND	ND	ND	ND	ND	ND
7/29/2015	ND	ND	0.80	ND	ND	ND	ND	ND
4/8/2016	ND	ND	ND	ND	ND	ND	ND	ND
7/12/2016	ND	ND	ND	ND	ND	ND	ND	ND
10/13/2016	ND	ND	ND	ND	ND	ND	ND	ND
1/24/2017	ND	ND	ND	ND	ND	ND	ND	ND
4/11/2017	ND	ND	ND	ND	ND	ND	ND	ND
7/6/2017	ND	ND	ND	ND	ND	ND	ND	ND
10/18/2017	ND	ND	ND	ND	ND	ND	ND	ND
1/9/2018	ND	ND	ND	ND	ND	ND	ND	ND
4/12/2018	ND	ND	ND	ND	ND	ND	ND	ND

MONITORING WELL MW-39D

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



MONITORING WELL MW-40D
SUMMARY OF VOCs IN GROUNDWATER
Former Scott Aviation Site
Lancaster, New York

	Analytical Results (µg/L)							
Sample Date	1,1,1-Trichloroethane	1,1,2-Trichloroethane	1,1-Dichloroethane	1,1-Dichloroethene	1,2-Dichloroethane	Tetrachlorothene	Trichloroethene	Vinyl chloride
6/21/2010	23	ND	260	1.8	ND	ND	2.8	ND
8/3/2010	25	ND	550	6	ND	ND	ND	ND
3/11/2015	2,800	ND	5,400	200	ND	ND	ND	67
6/12/2015	ND	ND	1,800	ND	ND	ND	ND	ND
7/27/2015	ND	ND	12,000	64	ND	ND	ND	ND
1/7/2016	ND	ND	190	ND	ND	ND	ND	ND
4/8/2016	ND	ND	220	ND	ND	ND	ND	ND
7/11/2016	ND	ND	12	ND	ND	ND	ND	ND
10/11/2016	ND	ND	71	ND	5.2	ND	ND	ND
1/25/2017	ND	ND	180	ND	4.8	ND	ND	ND
4/10/2017	43	ND	ND	ND	ND	ND	ND	ND
7/10/2017	ND	ND	150	ND	ND	ND	ND	ND
10/16/2017	ND	ND	51	ND	1.3	ND	ND	0.9
1/4/2018	ND	ND	32	ND	ND	ND	ND	ND
4/10/2018	20	ND	400	ND	ND	ND	ND	ND

MONITORING WELL MW-40D

SUMMARY OF VOCs IN GROUNDWATER

Former Scott Aviation Site

Lancaster, New York



Appendix C

Well Decommissioning Logs

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D.: A1-GP03
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	15.0
Casing type/dia. (in)	0.75
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-15.0'
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	
Cement type	
Quantity of bentonite used (lbs.)	
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	1.0

WELL SCHEMATIC*



COMMENTS:

* Sketch in all relevant decommissioning data, including: interval overdrilled, interval grouted, casing left in hole, well stickup, etc.

Drilling Contractor

Department Representative

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D.: A1-GP04
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	15.0
Casing type/dia. (in)	0.75
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-15.0'
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	
Cement type	
Quantity of bentonite used (lbs.)	
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	1.0

WELL SCHEMATIC*



COMMENTS:

* Sketch in all relevant decommissioning data, including: interval overdrilled, interval grouted, casing left in hole, well stickup, etc.

Drilling Contractor

Department Representative

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D.: A1-GP05
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	15.0
Casing type/dia. (in)	0.75
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-15.0'
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	
Cement type	
Quantity of bentonite used (lbs.)	
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	2.0

WELL SCHEMATIC*



COMMENTS:

* Sketch in all relevant decommissioning data, including: interval overdrilled, interval grouted, casing left in hole, well stickup, etc.

Drilling Contractor

Department Representative

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D.: A1-GP07
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	15.0
Casing type/dia. (in)	0.75
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-15.0'
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	
Cement type	
Quantity of bentonite used (lbs.)	
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	1.0

WELL SCHEMATIC*



COMMENTS:

* Sketch in all relevant decommissioning data, including: interval overdrilled, interval grouted, casing left in hole, well stickup, etc.

Drilling Contractor

Department Representative

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D.: A1-GP08
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	15.0
Casing type/dia. (in)	0.75
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-15.0'
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	
Cement type	
Quantity of bentonite used (lbs.)	
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	1.0

WELL SCHEMATIC*



COMMENTS:

* Sketch in all relevant decommissioning data, including: interval overdrilled, interval grouted, casing left in hole, well stickup, etc.

Drilling Contractor

Department Representative

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D.: A1-GP12
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	15.0
Casing type/dia. (in)	0.75
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-15.0'
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	90.0
Cement type	
Quantity of bentonite used (lbs.)	5.0
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	

WELL SCHEMATIC*



COMMENTS:

* Sketch in all relevant decommissioning data, including: interval overdrilled, interval grouted, casing left in hole, well stickup, etc.

Drilling Contractor

Department Representative

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D.: A1-GP13
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	15.0'
Casing type/dia. (in)	0.75
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-15.0'
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	
Cement type	
Quantity of bentonite used (lbs.)	
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	2.0

WELL SCHEMATIC*



COMMENTS:

* Sketch in all relevant decommissioning data, including: interval overdrilled, interval grouted, casing left in hole, well stickup, etc.

Drilling Contractor

Department Representative

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D.: MW-37S
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	18.0'
Casing type/dia. (in)	
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-15.0'
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	90.0
Cement type	
Quantity of bentonite used (lbs.)	5.0
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	

WELL SCHEMATIC*



COMMENTS:

* Sketch in all relevant decommissioning data, including: interval overdrilled, interval grouted, casing left in hole, well stickup, etc.

Drilling Contractor

Department Representative

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D.: MW-41B
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	0.0'
Casing type/dia. (in)	
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-34.0'
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	180.0
Cement type	
Quantity of bentonite used (lbs.)	10.0
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	

WELL SCHEMATIC*



COMMENTS:

Drilling Contractor

Department Representative

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D. TP 1:
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	5.75
Casing type/dia. (in)	
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-5.4'
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	
Cement type	
Quantity of bentonite used (lbs.)	
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	0.5

WELL SCHEMATIC*



COMMENTS:

Drilling Contractor

Department Representative

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D. TP 2:
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	5.52
Casing type/dia. (in)	0.75
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-4.0'
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	
Cement type	
Quantity of bentonite used (lbs.)	
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	0.5

WELL SCHEMATIC*



COMMENTS:

Drilling Contractor

Department Representative

WELL DECOMMISSIONING RECORD

Site Name: Former Scott Aviation Site (60538931-1)	Well I.D. TP 3:
Site Location: 225 Erie St. Lancaster NY	Driller: Rob Gin; Pat Bliek; Steve Marchetti
Drilling Co.: Matrix	Inspector: Sean P. Connelly
	Date: 10/23/17

DECOMMISSIONING DATA
(Fill in all that apply)

OVERDRILLING	
Interval Drilled	
Drilling Method(s)	
Borehole Dia. (in.)	
Temporary Casing Installed? (y/n)	
Depth temporary casing installed	
Casing type/dia. (in.)	
Method of installing	
CASING PULLING	
Method employed	
Casing retrieved (feet)	4.3
Casing type/dia. (in)	0.25
CASING PERFORATING	
Equipment used	
Number of perforations/foot	
Size of perforations	
Interval perforated	
GROUTING	
Interval grouted (FBLS)	0.0-3.9
# of batches prepared	
For each batch record:	
Quantity of water used (gal.)	
Quantity of cement used (lbs.)	
Cement type	
Quantity of bentonite used (lbs.)	
Quantity of calcium chloride used (lbs.)	
Volume of grout prepared (gal.)	
Volume of grout used (gal.)	0.5

WELL SCHEMATIC*



COMMENTS:

Drilling Contractor

Department Representative

Appendix D

Institutional Controls and Engineering Controls Certification Form

Enclosure 2
NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION
Site Management Periodic Review Report Notice
Institutional and Engineering Controls Certification Form

Site Details **Box 1**

Site No. C915233

Site Name Former Scott Aviation Facility (Area 1)

Site Address: 215 and 221 Erie Street Zip Code: 14086
City/Town: Lancaster
County: Erie
Site Acreage: ~~1.3~~ 1.25 Acres

Reporting Period: ~~July 01, 2017 to July 01, 2018~~ April 12, 2017 to April 12, 2018

		YES	NO
1.	Is the information above correct?	❑	X
	If NO, include handwritten above or on a separate sheet.		
2.	Has some or all of the site property been sold, subdivided, merged, or undergone a tax map amendment during this Reporting Period?	❑	X
3.	Has there been any change of use at the site during this Reporting Period (see 6NYCRR 375-1.11(d))?	❑	X
4.	Have any federal, state, and/or local permits (e.g., building, discharge) been issued for or at the property during this Reporting Period?	❑	X
	If you answered YES to questions 2 thru 4, include documentation or evidence that documentation has been previously submitted with this certification form.		
5.	Is the site currently undergoing development?	❑	X

Box 2

		YES	NO
6.	Is the current site use consistent with the use(s) listed below? Commercial and Industrial	X	❑
7.	Are all ICs/ECs in place and functioning as designed?	X	❑

IF THE ANSWER TO EITHER QUESTION 6 OR 7 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.

A Corrective Measures Work Plan must be submitted along with this form to address these issues.

_____ _____
Signature of Owner, Remedial Party or Designated Representative Date

		YES	NO
8.	Has any new information revealed that assumptions made in the Qualitative Exposure Assessment regarding offsite contamination are no longer valid?	❑	X

If you answered YES to question 8, include documentation or evidence that documentation has been previously submitted with this certification form.

9.	Are the assumptions in the Qualitative Exposure Assessment still valid? (The Qualitative Exposure Assessment must be certified every five years)	X	❑

If you answered NO to question 9, the Periodic Review Report must include an updated Qualitative Exposure Assessment based on the new assumptions.

SITE NO. C915233

Description of Institutional Controls

Parcel	Owner	Institutional Control
104.16-5-8	AVOX Systems, Inc.	Ground Water Use Restriction Landuse Restriction Site Management Plan Soil Management Plan Monitoring Plan IC/EC Plan

An Environmental Easement was filed with the Erie County Clerk's Office on November 19, 2015. The Controlled Property may be used for commercial and industrial use as long as the following long-term institutional controls are employed: (1) restrict the use of site groundwater as a source of potable or process water without necessary water quality treatment as determined by the NYSDOH or Erie County Department of Health; (2) all future activities on the property that will disturb remaining contaminated material must be conducted in accordance with the Site Management Plan; and (3) monitoring to assess the performance and effectiveness of the remedy must be conducted as defined in the Site management Plan.

104.16-5-9	AVOX Systems, Inc.	Soil Management Plan Monitoring Plan IC/EC Plan Ground Water Use Restriction Landuse Restriction Site Management Plan

An Environmental Easement was filed with the Erie County Clerk's Office on November 19, 2015. The Controlled Property may be used for commercial and industrial use as long as the following long-term institutional controls are employed: (1) restrict the use of site groundwater as a source of potable or process water without necessary water quality treatment as determined by the NYSDOH or Erie County Department of Health; (2) all future activities on the property that will disturb remaining contaminated material must be conducted in accordance with the Site Management Plan; and (3) monitoring to assess the performance and effectiveness of the remedy must be conducted as defined in the Site management Plan.

Description of Engineering Controls

None Required

Not Applicable/No EC's

Periodic Review Report (PRR) Certification Statements

1. I certify by checking "YES" below that:

a) the Periodic Review report and all attachments were prepared under the direction of, and reviewed by, the party making the certification;

b) to the best of my knowledge and belief, the work and conclusions described in this certification are in accordance with the requirements of the site remedial program, and generally accepted e

YES	NO
X	❑

2. If this site has an IC/EC Plan (or equivalent as required in the Decision Document), for each Institutional or Engineering control listed in Boxes 3 and/or 4, I certify by checking "YES" below that all of the following statements are true:

(a) the Institutional Control and/or Engineering Control(s) employed at this site is unchanged since the date that the Control was put in-place, or was last approved by the Department;

(b) nothing has occurred that would impair the ability of such Control, to protect public health and the environment;

(c) access to the site will continue to be provided to the Department, to evaluate the remedy, including access to evaluate the continued maintenance of this Control;

(d) nothing has occurred that would constitute a violation or failure to comply with the Site Management Plan for this Control; and

(e) if a financial assurance mechanism is required by the oversight document for the site, the mechanism remains valid and sufficient for its intended purpose established in the document.

YES	NO
X	❑

IF THE ANSWER TO QUESTION 2 IS NO, sign and date below and DO NOT COMPLETE THE REST OF THIS FORM. Otherwise continue.

A Corrective Measures Work Plan must be submitted along with this form to address these issues.

_____ _____

Signature of Owner, Remedial Party or Designated Representative Date

IC CERTIFICATIONS
SITE NO. C915233

Box 6

SITE OWNER OR DESIGNATED REPRESENTATIVE SIGNATURE

I certify that all information and statements in Boxes 1,2, and 3 are true. I understand that a false statement made herein is punishable as a Class "A" misdemeanor, pursuant to Section 210.45 of the Penal Law.

I Dino Zack, P.G. at AECOM, 257 West Genesee St., Buffalo, NY 14202,
print name print business address

am certifying on behalf of Scott Figgie LLC (Owner or Remedial Party)

for the Site named in the Site Details Section of this form.

Dino D. Zack

Signature of Owner, Remedial Party, or Designated Representative Rendering Certification

June 30, 2018
Date